

CATALOG

# **Electronic relays and controls**

Offer overview and technical data



ABB has the industry's most comprehensive range of time relays measuring and monitoring relays, interface relays and power supplies – helping you to source all critical components from a single global supplier.

Increase the reliability of process equipment with control devices that provide intelligent signals and smart adjustments that help you achieve maximum system availability.

# Electronic relays and controls

Table of contents

4	Overview
13	Time relays
73	Measuring and monitoring relays
267	Power supplies
401	Interface relays and optocouplers
501	Index

## Overview

## Interface relays and optocouplers


## A proven technology used worldwide


Relays are universally applicable and are utilized in a diverse array of applications. They are a significant element in contemporary industrial processes and are used in applications where galvanic isolation, signal separation, voltage coupling and signal amplification are required.



Optocouplers are predominantly used in applications where a high switching frequency is necessary. Furthermore, optocouplers do not contain any moving parts and are therefore bounce-free, immune to vibrations and possess a long electrical life. This wide selection of relays adheres to the highest global standards and satisfies the requirements for a diverse number of applications and needs.

ABB offers a complete range of interface relays and optocouplers for increased flexibility and choice. This portfolio includes pluggable relays for easy interchangeability and optocouplers for an extended electrical life. The portfolio includes electromechanical relays and optocouplers - the electromechanical relays operate using an electromagnetic field, whereas optocouplers use light.





## Time relays

## Have the perfect timing- everywhere

Available in three different ranges to cover every application, the CT range time relays are used to provide reliable timing functions worldwide. In both industrial and building applications, the time relays of the CT range have proven their excellent functionality in daily use under the toughest conditions.

Choose ABB as the partner for all your low voltage timing control needs to leverage our wide variety of product options. From economic to high-end solutions – the range offers maximum value. Time relays are found everywhere, for example in air conditioning systems, heaters and fans in industrial and in residential buildings. On-delay, off-delay and a range of other functions cover all requirements.



Shock and vibration resistant CT-S relays are perfect for use in rolling stock

- · Control panels
- Pump controls
- Star-delta motor starting
- Movable equipment like cranes
- Machine tools
- Automatic doors
- Car park barriers
- Assembly machines
- HVAC

- Compressor controls
- Transportation
- Industrial refrigeration
- · Packaging machines
- Backing ovens
- · Water and wastewater
- Wind
- Industrial cleaning processes



# Primary switch mode power supplies

Excellent reliability in harsh environments

Available in five different ranges to cover every application requirement, ABB's CP range power supplies are used to power valuable assets worldwide.









Emergency lighting



LED lighting







Printing industry



Packaging industry







Choose ABB as your power supply partner and leverage our wide variety of product options. From economic to high-end solutions, the CP range offers maximum value. Their excellent reliability in daily use is well proven even under the toughest of conditions.









# Measuring and monitoring relays

Increase process availability and take action

The relays inform users about abnormal conditions and allow them to take necessary corrective actions before severe and costly failures can occur.



Measuring and monitoring relays monitor and detect operating conditions with regard to phase, current, voltage, frequency, temperature, liquid level or insulation faults. The relays inform users about abnormal conditions and allow them to take necessary corrective actions before severe and costly failures can occur.

ABB offers the broadest range of measuring and monitoring relays in the industry - so you can source your critical components from a global supplier. Increase the reliability of your process equipment with controllers that deliver intelligent signals and settings to ensure maximum availability. Ensure continuous operation, engineer time savings and benefit from ABB's global support for measuring and monitoring relays.









## **Electronic relays and controls websites**

Your one-stop shop for product information

On our web site you will also find the products in this catalog together with the current life cycle status, data sheets, certificates and tools.



3D data



Life cycle information




Coordination tables (SOC)



**E-configure** 



Certificates






## Online data sheets

For detailed product information, use the order code to access the online data sheets as in the following example:

new.abb.com/products/1SVR750740R0120







## **ABB Connect**

Your digital assistant

Connect to your electrification solutions with your digital assistant, access the latest news, and create your own digital workspace; search 'ABB Connect' on the Apple App Store, Google Play Store or Microsoft Store and download today.



Find the latest product details



Make your phone or tablet your workspace



Tap and stay connected to all the latest information

new.abb.com/low-voltage/service/abb-connect



# **Time relays**Table of contents

15	applications
21	CT-C range
33	CT-S range
51	Time relays for building
<b>31</b>	applications
54	•



# Time relays for industrial applications Table of contents

16	Offer	overview

## Time relays for industrial applications

## Offer overview



#### CT-C: the compact range

The CT-C range combines lower cost with higher value and performance by offering essential functions in a space-saving 17.5 mm housing. The range offers a choice of 11 devices, including single and multifunctional types, with timing functions that range from 0.05 seconds to 100 hours. Equipped with a wide voltage range, the CT-C range is suitable for a huge variety of applications worldwide.



#### CT-S: the high-performance range

The advanced CT-S range is ABB's universal range of electronic timers. It includes 22 single-function devices and 16 multifunction time relays, offering flexibility in operation with up to 13 functions. The devices feature seven or ten time ranges, adjustable from 0.05 seconds to 300 hours. Additionally, every device is available in two different connection technologies: familiar double-chamber cage connection terminals (screw terminals) and ABB's vibration-resistant Easy Connect technology (push-in terminals).

# Time relays for industrial applications

# Type selection

		multi-functional	single-functional	multi-functional	single-functional			
Timing function		ст-с		CT-S				
$\boxtimes$	ON-delay	CT-MFC, CT-MKC	CT-ERC	CT-MVS, CT-MFS, CT-MBS, CT-WBS	CT-ERS			
	OFF-delay	CT-MFC, CT-MKC, CT-ARC	CT-AHC	CT-MVS, CT-MFS, CT-MBS	CT-APS, CT-AHS, CT-ARS			
	ON- and OFF-delay			CT-MVS, CT-MXS, CT-MFS, CT-MBS				
1/\	Impulse-ON	CT-MFC, CT-MKC	CT-VWC	CT-MVS, CT-MFS, CT-MBS, CT-WBS				
1/1	Impulse-OFF	CT-MFC, CT-MKC, CT-ARC		CT-MVS, CT-MFS, CT-MBS				
1Л≌	Impulse-ON and OFF			CT-MXS				
ЛМ	Flasher starting with ON	CT-MFC, CT-MKC	CT-EBC	CT-MFS, CT-MBS, CT-WBS				
	Flasher staring with OFF	CT-MFC, CT-MKC	CT-EBC	CT-MFS, CT-MBS, CT-WBS				
Л≌	Flasher starting with ON or OFF			CT-MVS				
ĭ	Pulse generator starting with ON or OFF		CT-TGC	CT-MXS				
1	Pulse former	CT-MFC, CT-MKC		CT-MVS, CT-MFS, CT-MBS				
<u>A</u>	Star-delta change-over		CT-SDC, CT-SAC		CT-SDS			
<u></u> 1∏	Star-delta change-over with impulse			CT-MVS.2x, CT-MFS, CT-MBS				
+	☐1☐ ☐1☐ ☐ further functions (depending on device)			CT-MVS, CT-MXS, CT-MFS, CT-MBS, CT-WBS				
Alterna	ting without time delay		CT-PAC					

 $\label{lem:condition} A \ detailed \ explanation \ of the \ different timing \ functions \ can \ be found \ in \ the \ chapter \ "Timing \ functions".$ 

### Synonyms

5y11011y1115				
Used expression	Alternative expression(s)			
1 c/o contact	SPDT			
2 c/o contacts	DPDT			
voltage-related	wet / non-floating			
volt-free	dry / floating			













## Time relays for industrial applications

## **Applications**

ABB offers a wide selection of time relays – from economic to high-end – to suit every application for businesses worldwide. ABB time relays provide simple, reliable and economical control solutions in all types of panel. They are typically used in industrial applications and OEM equipment, providing time-delayed switching to start a motor, control a load or manage a process.



Remote control of time delays with a remote potentiometer.



Cyclic switching of machinery, for example the weekly startup of a fan to prevent them sticking or the flushing of pipes to keep them clear.



Lighting control, for example the delayed switching of multiple rows of lamps in production facilities or greenhouses.



Time controlled start up or shut down of machinery equipment, for example the delayed switch off of conveyor belts or the successive shut down of a plant.



Alarm triggering in case of fault detection, for example to allow the flashing of a lamp in industrial applications or rolling stock.



Star-delta motor starting to reduce starting current with changeover delay to prevent interphase short-circuits.

Have the perfect timing everywhere with ABB's time relays:

- Control panels
- Pump controls
- · Star-delta motor starting
- Movable equipment e.g. cranes
- · Machine tools
- · Automatic doors

- Car park barriers
- Assembly machines
- HVAC
- Compressor controls
- Transportation
- Industrial refrigeration

- · Packaging machines
- Backing ovens
- · Water and wastewater
- Wind
- Industrial cleaning processes



# **CT-C range**Table of contents

22	benefits and advantages
23	Operating controls
24	Selection table
25	Ordering details
26	Technical data
30	Technical diagrams

## Benefits and advantages



The CT-C range combines lower cost with higher value and performance by offering essential functions in a 17.5 mm housing, freeing up room in any control cabinet. The range includes 11 devices, offering both single and multifunctional types, with a time range from 0.05 seconds to 100 hours. Equipped with wide voltage ranges, CT-C time relays allow for use across a huge variety of applications worldwide.



With a width of just 17.5 mm, the CT-C range is 22% smaller than standard industrial housings for time relays. Its reduced overall footprint saves space in control cabinets. For more flexibility both  $1\,\text{c/o}$  and  $2\,\text{c/o}$  output versions are offered in the compact housing.




The CT-C range is an economical range that combines lower cost with higher value and performance. It suits basic applications where a time relay is needed, while offering improved functionality in each device.



By combining more functions into each device, the CT-C range makes it possible to reduce stock by up to 75% compared to other ranges. All devices in the CT-C range offer a wide supply voltage range as well as a wide time setting range from 0.05 seconds to 100 hours. This significantly reduces order code variance, making the range more compact with just 15 order codes covering every requirement.

# **CT-C range**Operating controls



# **CT-C range** Selection table

			_			_								_	_	_
	Order number	1SVR508010R1300	1SVR508020R0000	1SVR508020R1100	1SVR508120R0000	1SVR508100R0000	1SVR508100R0100	1SVR508110R0000	1SVR508110R0100	1SVR508130R0000	1SVR508150R0000	1SVR508160R0000	1SVR508160R0100	1SVR508210R0100	1SVR508211R0100	1SVR508180R0100
	Type	CT-MKC.31	CT-MFC.12	CT-MFC.21	CT-ARC.12	CT-ERC.12	CT-ERC.22	CT-AHC.12	CT-AHC.22	CT-VWC.12	CT-EBC.12	CT-TGC.12	CT-TGC.22	CT-SAC.22	CT-SDC.22	CT-PAC.22
Timing function															_	_
ON-delay	$\boxtimes$	-	•			•	•									
OFF-delay with aux. voltage		-	-	•				•								
OFF-delay w/o aux. voltage		_														
Impulse-ON	1/□⊠	_	_	-						-						
Impulse-OFF with aux. voltage	1	-	-	•												
Impulse-OFF w/o aux. voltage	1.	_	_	_							_					
Flasher starting with ON		-	-	-							-					
Flasher starting with OFF	Л	-	-	•							•	_	_			
Pulse generator starting with ON or OFF		_	_	_								•				
Pulse former	111	-	-											_	_	
Star-delta change-over														•		_
Alternating w/o time delay																
Features									_				_		_	_
Control input, voltage-related triggering		•														
Time range						_						_	_	_	_	_
0.05 s - 100 h		-	•	•	_	•	•	•		•	•	2	2	_	_	
0.05 s - 10 min																
Supply voltage		_		_		_								_	_	_
12-240 V AC/DC		-	_		_	_	_	_	_	_	_	_	_	_		_
24-48 V DC			-		•	•	-	-	-	-	-	-	-	•	•	-
24-240 V AC														_		
Output															_	
Solid state		-		_	-	_	2	_	2	-		_	2			
c/o contact			1	2	1	1	2	1	2	1	1	1	2	2	1	2
n/o contact														2	2	2

## Ordering details



CT-MFC.12



CT-ERC.22

- Control input with voltage-related triggering
- No triggering

### Description

The CT-C range combines lower cost with higher value and performance in a slim 17.5 mm-wide housing. All relays have a wide time setting range from 0.05 seconds up to 100 hours. Combined with a wide voltage range they are the perfect choice for applications worldwide.

#### Ordering details

Timing function	Rated control supply voltage	Time ranges	Control input	Output	Туре	Order code	Weight (1 pc)
							kg (lb)
Multi <sup>1)</sup>	12-240 V AC/DC	7 (0.05 s - 100 h)		Solid state	CT-MKC.31	1SVR508010R1300	0.060 (0.132)
Multi <sup>1)</sup>	24-240 V AC 24-48 V DC			1 c/o	CT-MFC.12	1SVR508020R0000	0.060 (0.132)
Multi <sup>1)</sup>	12-240 V AC/DC			2 c/o	CT-MFC.21	1SVR508020R1100	0.065 (0.143)
Dual <sup>2)</sup>	24-48 V DC 24-240 V AC	4 (0.05 s - 10 min)	-	1 c/o	CT-ARC.12	1SVR508120R0000	0.060 (0.132)
ON-delay	24-240 V AC 24-48 V DC	7 (0.05 s - 100 h)	-	1 c/o	CT-ERC.12	1SVR508100R0000	0.060 (0.132)
			-	2 c/o	CT-ERC.22	1SVR508100R0100	0.065 (0.143)
OFF-delay				1 c/o	CT-AHC.12	1SVR508110R0000	0.060 (0.132)
				2 c/o	CT-AHC.22	1SVR508110R0100	0.065 (0.143)
Impulse- ON			-	1 c/o	CT-VWC.12	1SVR508130R0000	0.060 (0.132)
Flasher <sup>3)</sup>			-		CT-EBC.12	1SVR508150R0000	0.060 (0.132)
Pulse generator		2×7 (0.05 s - 100 h)			CT-TGC.12 <sup>4)</sup>	1SVR508160R0000	0.060 (0.132)
				2 c/o	CT-TGC.22 <sup>4)</sup>	1SVR508160R0100	0.065 (0.143)
Star-delta change-		4 (0.05 s - 10 min)	-	2 n/o	CT-SDC.22 <sup>5)</sup>	1SVR508211R0100	0.065 (0.143)
over			-		CT-SAC.22 <sup>6)</sup>	1SVR508210R0100	
Alternating without time delay	24-240 V AC 24-48 V DC	-	-	2 n/o	CT-PAC.22	1SVR508180R0100	0.059 (0.130)

 $<sup>^{1)}</sup>$  Functions: ON-delay, OFF-delay with auxiliary voltage, Impulse-ON, Impulse-OFF with  $auxiliary\ voltage, Flasher\ starting\ with\ ON,\ Flasher\ starting\ with\ OFF,\ Pulse\ former$ 

<sup>&</sup>lt;sup>2)</sup> OFF-delay without aux. voltage (True OFF-delay), True Impulse-OFF
<sup>3)</sup> Flasher starting with ON, Flasher starting with OFF
<sup>4)</sup> ON and OFF times adjustable independently: 2 x 7 time ranges 0.05 s - 100 h

<sup>5)</sup> Transition time 50 ms fixed

 $<sup>^{6)}</sup>$  Transition time adjustable

## Technical data

Data at  $T_a$  = 25 °C and rated values, unless otherwise indicated

		CT-C with 1 c/o contact	CT-C with 2 c/o contacts	CT-MFC.21	CT-MKC.31	CT-PAC.22
Input circuit - Supply circuit		ļ.				
Rated control supply voltage U <sub>s</sub>		24-240 V AC / 2	24-48 V DC	12-240 V AC/I	С	24-240 V AC/ 24-48 V DC
Rated control supply voltage U <sub>s</sub> tolerance		-15+10 %				
Rated frequency		DC or 50/60 Hz	z			
Frequency range AC		47-63 Hz				
Typical power consumption		max. 3.5 VA				
Power failure buffering time		min. 20 ms				
Release voltage		> 10 % of the m	ninimum rated co	ontrol supply vo	ltage U₅	
Minimum energizing time	CT-ARC	100 ms				
Formatting time <sup>1)</sup>	CT-ARC	5 min				
Input circuit - Control circuit						
Control input, control function	A1-Y1/B1	start timing ex	ternal			-
Kind of triggering		voltage-related	d triggering			-
Resistance to reverse polarity		yes				-
Parallel load / polarized		yes / yes				-
Maximum cable length to the control inputs		50 m - 100 pF/ı	m			-
Minimum control pulse length		20 ms	-			
Control voltage potential		see rated conti	-			
Timing circuit						
Time ranges 7 time ranges	s 0.05 s - 100 h		) 0.5-10 s 3.) 5- 5.) 5-100 min			-
		1.) 0.05-1 s 2. 3.) 5-100 s 4.	-			
Recovery time		< 50 ms	-			
Accuracy within the rated control supply voltage toler	ance	∆ t < 0.005 % /	-			
Accuracy within the temperature range		Δt < 0.06 % / °	-			
Repeat accuracy (constant parameters)		∆t < ± 0.5 %	-			
Setting accuracy of time delay		± 10% of full-so	-			
Star-delta transition time CT	-SDC / CT-SAC	fixed 50 ms / adjustable: 20 ms, 30 ms, 40 ms, 50 ms, 60 ms, 80 ms or 100 ms				-
Star-delta transition time tolerance CT	-SDC / CT-SAC	±3 ms	-			
Indication of operational states						,
Control supply voltage / timing	U: green LED	: contro	ol supply voltage g	e applied		control supply
Relay energized R, R1,	R2: yellow LED	☐ : outpu	ıt relay energized	d		
Operating elements and controls						
Adjustment of the time range		front-face rota	ry switch, direct	reading scales	,	-
Fine adjustment of the time value		front-face pote	-			
Preselection of the timing function at multifunction d	evices	front-face rota	-			
Adjustment of the transition time	CT-SAC	front-face pote	-			
Selection of alternating relay function <sup>2)</sup>	CT-PAC	-				front-face rotary switch

<sup>1)</sup> Prior to first commissioning and after a six month stop of operation.

<sup>&</sup>lt;sup>2)</sup> Besides three marked rotary switch positions, CT-PAC has a fourth unmarked position after R2 in a clockwise direction. This position corresponds to the function R2.

## Technical data


			CT-C with 1 c/o contact	CT-C with 2 c/o contacts	CT-MFC.21	CT-MKC.31	CT-PAC.22
Output circut							
Kind of output		15-16/18	Relay, 1 c/o contact	-			
		15-16/18; 25-26/28	-	Relay, 2 c/o co	ntacts	-	
		17-18	-	, ,		Solid state, 1 n/o contact	-
		17-18; 17-28	-	Relay 2 n/o (CT SDC, CT-SAC)	-	1	1
		13-14; 13-24	-				Relay, 2 n/o contacts
Contact material			Cd free			-	-
Rated operational vol	tage U <sub>e</sub>		250 V			,	
Minimum switching v	oltage / minimum s	witching current	12 V / 100 mA			5 V / 1 mA	12 V / 100 mA
Maximum switching v	oltage / maximum	switching current	see load limit o	curves		250 V AC/ 1 A (resistive)	see load limit curve
Rated operational cur	rent I <sub>e</sub>	AC-12 (resistive) at 230 V	4 A	4 A	4 A	1 A	4 A
		AC-15 (inductive) at 230 V	3 A	3 A	n/o: 3 A n/c: 0.75 A	0.2 A	3 A
		DC-12 (resistive) at 24 V	4 A	4 A	4 A	1 A	4 A
		DC-13 (inductive) at 24 V	2 A (CT-ARC: 1.5 A)	2 A	1 A	1 A	2 A
AC rating (UL 508) (except CT-MKC)			В 300	В 300	n/o: B 300 n/c: C 300	-	B300
	max	x. rated operational voltage	300 V AC	300 V AC	300 V AC	-	300 V AC
	maximum	continuous thermal current at B300	5 A	5 A	n/o: 5 A	-	5 A
	maximum	continuous thermal current at C300	-	-	n/c: 2.5 A	-	-
	max. making	g/breaking apparent power at B300	3600 VA / 360 VA	3600 VA / 360 VA	n/o: 3600/360 VA	-	3600 VA / 360 VA
	max. making	g/breaking apparent power at C300	-	-	n/c: 1800/180 VA	-	-
Rating (UL 60947-5-1) (CT-MKC)	Rating (UL 60947-5-1) utilization (CT-MKC) category		-	-	-	AC-15: 0.2 A / 230 V DC-13: 1 A / 24 V	-
		max. rated operational voltage	-	-	-	250 V	-
		max. continuous thermal curren	-	-	-	1 A	-
Mechanical lifetime		30 x 10° switching cycles			-	30 x 10 <sup>6</sup> switching cycles	
Electrical lifetime		0.1 x 10 <sup>6</sup> switching cycles 10 x 10 <sup>6</sup> switching cycles cycles			switching	0.1 x 10 <sup>6</sup> switching cycles	
Max. fuse rating to ac	hieve short-circuit	n/c contact	6 A fast-acting				
protection		n/o contact	10 A fast-actin	g	6 A fast-acting	1 A FF	10 A fast- acting

## Technical data


		CT-C with 1 c/o contact	CT-C with 2 c/o contacts	CT-MFC.21	CT-MKC.31	CT-PAC.22	
General data							
Mean time between failures (MTBF)		on request					
Duty cycle		100%					
Dimensions		see 'Dimension	nal drawings'				
Mounting			N 60715), snap-r	nounting witho	out any tool		
Mounting position		any	1 001 13), 31140 1	mountaing within	at any tool		
Minimum distance to other units	horizontal / vertical	-	mm if switching	Current >2 A)	/ no		
Material of housing	nonzontary verticar	UL 94 V-2	Tilli i switching	current >2 A) /	110		
	housing / terminals						
Degree of protection	nousing / terminais	1P30 / 1P20					
Electrical connection	fine strongled with (c.u.t)	2 0 5 1 5	2 (2 20 16 A)4/6				
Connecting capacity	fine-stranded with(out) wire and ferrule rigid		<sup>2</sup> (1 x 20-14 AWG <sup>2</sup> (2 x 20-16 AWG	)			
Stripping length		7 mm (0.28 in)					
Tightening torque		0.5-0.8 Nm (4.4	3-7.08 lb.in)				
Environmental data							
Ambient temperature range	operation / storage	-20 +60 °C /	-40 +85 °C				
Climatic class	IEC/EN 60721-3-3	3k22					
Relative humidity range		25-85%					
Vibration, sinusoidal	IEC/EN 60068-2-6	20 m/s²; 10 cyc	les, 1015010	Hz			
Shock (half-sine)	IEC/EN 60068-2-27	_					
Isolation data		, , ,					
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	300 V					
	output circuit 1 / output circuit 2	300 V					
Rated impulse withstand voltage U <sub>imp</sub>	between all isolated circuits	4 kV; 1.2/50 μs					
Power-frequency withstand voltage test (test voltage)	between all isolated circuits	· ·	0 s				
Basic insulation (IEC/EN 60664-1)	input circuit / output circuit	300 V					
Protective separation (IEC/EN 60664-1)	input circuit / output circuit	250 V at polluti	ion degree 2 / ov	vervoltage cate	gory II	250 V at pollution degree 3 / overvoltage category III	
Pollution degree (IEC/EN 60664-1)		3					
Overvoltage category (IEC/EN 60664-	1)	III					
Standards / Directives			1				
Standards		IEC/EN 61812-	1			IEC/EN 60947-5-1	
Low Voltage Directive		2014/35/EU					
EMC Directive		2014/30/EU					
RoHS Directive		2011/65/EU incl. 2015/863/EU					
Electromagnetic compatibility			,		,		
Interference immunity to		IEC/EN 61000-	6-2, IEC/EN 610	00-6-1			
electrostatic discharge	IEC/EN 61000-4-2						
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3						
electrical fast transient / burst	IEC/EN 61000-4-4	level 3 (2 kV / 5	kHz)				
surge	IEC/EN 61000-4-5	level 4 (2 kV L-L	.)				
conducted disturbances, induced b radio-frequency fields	•						
Interference emission		IEC/EN 61000-	6-3, IEC/EN 610	00-6-4			
high-frequency radiated	IEC/CISPR 22, EN 55022						
high-frequency conducted	IEC/CISPR 22, EN 55022						

## Technical diagrams

### Example of application - Star-delta changeover




Control circuit diagram



Power circuit diagram


### **Connection diagrams**

### CT-MFC.21




A1-A2	Supply: 12-240 V AC/DC				
A1-Y1/B1	Control input				
15-16/18	1st c/o contact				
25-26/28	2nd c/o contact				

### CT-MFC.12




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

#### **⊠CT-ERC.22**



A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

### ⊠CT-ERC.12



A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact

## Technical diagrams

#### \_


#### **Connection diagrams**

#### CT-AHC.22

A1	15	25	
Y1/ B1 A1 	15 	25  	
18	16	Y1/B1	
28	26	A2	


A1-A2	Supply: 24-48 V DC or 24- 240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

### CT-AHC.12




A1-A2	Supply: 24-48 V DC or 24- 240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

#### 1**□⊠ CT-VWC.12**




A1-A2	Supply: 24-48 V DC or 24- 240 V AC
15-16/18	1st c/o contact

#### □ CT-EBC.12




A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact

#### ≅⊓ CT-TGC.22




A1-A2	Supply:
	24-48 V DC or
	24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

#### ≅⊓ CT-TGC.12




A1-A2	Supply: 24-48 V DC or 24- 240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

#### △ CT-SDC.22




A1-A2	Supply: 24-48 V DC or 24-240 V AC
17-18	1st n/o contact (star contactor)
17-28	2nd n/o contact (delta contactor)

#### △ CT-SAC.22




A1-A2	Supply: 24-48 V DC or 24-240 V AC
17-18	1st n/o contact (star contactor)
17-28	2nd n/o contact (delta contactor)

### CT-PAC.22




A1-A2	Supply:
	24-48 V DC or
	24-240 V AC
13-14	1st n/o contact
	(relay R1)
13-24	2nd n/o contact (relay R2)

### CT-ARC.12



A1-A2	Supply: 12-240 V AC/DC
15-16/18	1st c/o contact

### CT-MKC.31




A1-A2	Supply: 12-240 V AC/DC
15-16/18	1st c/o contact


## Technical diagrams

#### **Load limit curves**


### AC load (resistive)




### DC load (resistive)



# Derating factor F for inductive AC load




#### **Contact lifetime**




# Wiring notes for devices with control input

# A parallel load to the control input is possible




### Dimensional drawings


in **mm** and inches



CT-C devices with 1 c/o contact or 2 n/o contacts



CT-C devices with 2 c/o contacts



# **CT-S range**Table of contents

34	Deficites and davantages
38	Selection table
39	Ordering details - multifunctional devices
40	Ordering details - singlefunctional devices
41	Ordering details - Accessories
42	Technical data
46	Technical diagrams

## **CT-S** range

## Benefits and advantages



The advanced CT-S range includes 22 single-function devices and 16 multifunction timers with up to 13 functions. The devices feature seven or ten time ranges, which are adjustable from 0.05 seconds to 300 hours. Every device is available in two different connection technologies: double-chamber cage connection terminals or ABB's vibration-resistant Push-in Technology.



Improve installation efficiency

The CT-S range allows simple tool free mounting and demounting on the DIN rail. Thanks to the easy connect and the double-chamber cage connection technology simplified wiring with or without wire end ferrules is no problem. Both allow simple and easy installation, even in case of different cable diameters.



Reliable in harsh conditions

The CT-S range's extended features make it especially suited for harsh environments. The housing material has the highest UL fire protection classification. All functions are available with Push-in terminals, making operations in environments with high vibrations possible without retightening. Additionally, the CT-S range offers devices with an extended temperature range, running operations in temperatures as low as -40 °C effortlessly. Specific types are tested according to the latest rail industry standards, making them a perfect solution for rolling stock and other rail applications




Global availability

Every device in the CT-S range is designed to provide a wide supply voltage range, making global differences irrelevant. Additionally, the CT-S range meets a broad range of standards and requirements. Together with ABB's global support and sales network, using CT-S gives customers the confidence of worldwide sourcing – no matter where they build, install or operate their equipment.


## **CT-S range**

## Operating controls




# **CT-S** range

## Benefits and advantages



01 Tool-free mounting of wires



O2 Wiring of double-cage chamber connection terminals with screw driver

#### **Easy Connect Technology**

Tool-free wiring and excellent vibration resistance. Easy Connect (Push-in terminals) provide connection of wires up to  $2 \times 0.5 - 1.5 \text{ mm}^2$  ( $2 \times 20 - 16 \text{ AWG}$ ), rigid or fine-strand with or without wire end ferrules. The extended type designators for products with push-in terminals are indicated by a **P** following the extended type designator e.g. CT-xxS.xx**P**.


#### Double-chamber cage connection terminals

According to IEC/EN 60947-1 double-chamber cage connection terminals provide connection of wires up to 2 x 0.5-2.5 mm $^\circ$  (2 x 20-14 AWG) rigid or fine-strand, with or without wire end ferrules. Thanks to the technology, using different cable diameters in one terminal is easy and simple to install. Potential distribution does not require additional terminals. The extended type designators for products with double-chamber cage connection terminals (screw terminals) are indicated by an **S** following the extended type designator, e.g. CT-xxS.xx**S**.



# Made for extreme conditions

Selected products of the CT-S range comply to the latest rail standards like EN50155. Designed for harsh environments, not only are standard screw type terminals offered – push-in terminals with excellent vibration resistance are also available. Perfect for use in rolling stock.





# Electronic relays for railway solutions brochure

For more information about time relays in rolling stock applications visit:

new.abb.com/low-voltage/products/electronicrelays

or scan the QR code



# Selection table

Order number and type
All devices are available
either with push-in terminals (P-type) or doublechamber cage connection
terminals (S-type).

Terminal	Туре	Order number
Push-in	● = P	■ = 4
Screw	• = S	<b>■</b> = 3

		_	_	_	_		_	_	_	_	_	_			_		_	_	_	_
		8	000	8	8	000	00	8	300	00	00	8	00	00	00	8	00	8	8	00
	*_	1SVR7=0020R0200	1SVR7=0020R3300	1SVR7=0021R2300	1SVR7=0020R3100	1SVR7=0030R3300	1SVR7=0010R0200	1SVR7=0010R3200	1SVR7=0040R3300	1SVR7=0100R0300	1SVR7=0100R3300	1SVR7=0100R3100	1SVR7=0180R0300	1SVR7=0180R3300	1SVR7=0180R3100	1SVR7=0110R3300	1SVR7=0120R3100	1SVR7=0120R3300	1SVR7=0210R3300	1SVR7=0211R2300
	μ	020	020	)21	020	330	010	010	040	001	001	8	180	180	180	110	120	120	210	2111
	Ē		ĕ						0	0	0		9		9		0		0	Õ
	Order number*	VR7																		
	ö	15	15	13	13	15	13	15	15	15	15	13	15	15	13	13	15	15	15	13
		•	•		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
		CT-MVS.21	CT-MVS.22•	CT-MVS.23	CT-MVS.12•	CT-MXS.22•	CT-MFS.21●	CT-MBS.22•	CT-WBS.22•	CT-ERS.21	CT-ERS.22•	CT-ERS.12•	CT-APS.21	CT-APS.22	CT-APS.12	CT-AHS.22●	CT-ARS.110	CT-ARS.21•	CT-SDS.22•	CT-SDS.23•
	, *u	≥	Σ	Σ	≥	×Σ	Α	ΜB	WB	ER	ER	ER	AP	AP	AP	Ä	AR	AR	SD	SD
	Type,	片	C,	Ċ.	占	Ċ.	C.	片	CT-	CT-	CT-	Ċ.	C.	Ċ.	C,	Ċ.	CT-	C,	Ċ.	CŢ.
Timing function				_	_			_											_	_
ON-delay	$\boxtimes$																			_
ON-delay, accumulative	<b>⊠</b> (+)		•	•	-		-												$\Box$	
OFF-delay w. aux. voltage			•	•	-		-	•					•	•	•	-			$\exists$	
OFF-delay w. aux. voltage, accumulative																				
OFF-delay w/o aux. voltage																				
ON- and OFF-delay, symmetrical			•	•	-		-	•											$\Box$	
ON- and OFF-delay, symmetrical, accumulative							-												T	
ON- and OFF-delay, asymmetrical																				
ON/OFF function		•	•	-	-	•	•	•	•										T	
Impulse-ON	1Л⊠	•	•	-	•		•	•	•											_
Impulse-ON, accumulative	1Л⊠						-												T	
Impulse-OFF w. aux. voltage	1/		•	•	-		-	•												
Impulse-OFF w. aux. voltage, accumulative	1/1						-												T	
Impulse-ON and OFF	1Л≧					•														_
Fixed impulse with adjustable time delay	⊠iΠ																		$\Box$	
Adjustable impulse with fixed time delay	⊠iΠ																		$\Box$	
Flasher starting with ON	Л⊠	ĺ					•	•	•										T	
Flasher with reset, starting with ON	Л⊠						-	•											$\Box$	_
Flasher starting with OFF	Л						-	•	•											
Flasher with reset, starting with OFF	Л						-	•												
Flasher starting with ON or OFF	л≌	-	•	-	-															
Pulse generator starting with ON or OFF	ĭ																			
Single pulse generator	ĭ∏					•														
Pulse former	1, 1	•	•	•	-		-	•												
Star-delta change-over	Δ																			
Star-delta change-over with impulse	∆1∏																			
Features																				
Control input, voltage-related triggering															•					
Control input, volt-free triggering							2	1												
Remote potentiometer connection		-				2	=													
2nd c/o contact selectable as instantaneous contact		-					-	•												
Extended temperature range (-40+60 °C)																				
Time range								_	_	_	_				_		_			
0.05 s - 10 min																			-	
0.05 s - 300 h						2														
Supply voltage								_	_	_	_				_					
24-48 V DC			•		=	•					•	-		•	•	-			-	
24-240 V AC			•		•						•	•			•	•				
24-240 V AC/DC		•					•											•		
380-440 V AC																				_
Output		_	_					_	_	_					_		_			
c/o contact		2	2	2	1	2	2	2	2	2	2	1	2	2	1	2	1	2		
n/o contact																			2	2

# Ordering details - multifunctional devices



CT-MVS.21P



CT-MBS.22P

- Control input with voltage-related triggering
- ☐ Control input with volt-free triggering
- □/□ Two control inputs with volt-free triggering
- No triggering

# Description

The high-performance CT-S range is ideally suited for universal use and is available with two different connection technologies:

- Double-chamber cage connection terminals (Screw terminals)
- Easy Connect Technology (Push-in terminals)

# Ordering details

Timing function 5)	Rated control supply voltage	Time ranges	Control input	Output	Туре	Order code	Weight (1 pc) kg (lb)	
Multi	24- 240 V AC/DC	10 (0.05 s - 300 h)		2 c/o	CT-MVS.21S 1) 2) 3)	1SVR730020R0200	0.148 (0.326)	
					CT-MVS.21P 1) 2) 3)	1SVR740020R0200	0.136 (0.30)	
	24-48 V DC, 24-240 V AC	-			CT-MVS.22S	1SVR730020R3300	0.142 (0.313)	
					CT-MVS.22P	1SVR740020R3300	0.131 (0.289)	
	380-440 V AC				CT-MVS.23S	1SVR730021R2300	0.144 (0.317)	
					CT-MVS.23P	1SVR740021R2300	0.133 (0.293)	
Multi	24-48 V DC, 24-240 V AC	10 (0.05 s - 300 h)	■ 1 c/d		1 c/o	CT-MVS.12S	1SVR730020R3100	0.107 (0.236)
					CT-MVS.12P	1SVR740020R3100	0.102 (0.225)	
Multi	24-48 V DC, 24-240 V AC	2×10 (0.05 s - 300 h)	-	2 c/o	CT- MXS.22S <sup>4)</sup>	1SVR730030R3300	0.142 (0.313)	
					CT-MXS.22P 4)	1SVR740030R3300	0.131 (0.289)	
Multi	24- 240 V AC/DC	10 (0.05 s - 300 h)	0/0	2 c/o	CT-MFS.21S 1) 2) 3)	1SVR730010R0200	0.145 (0.32)	
					CT-MFS.21P 1) 2) 3)	1SVR740010R0200	0.133 (0.293)	
	24-48 V DC, 24-240 V AC	10 (0.05 s - 300 h)		2 c/o	CT-MBS.22S <sup>2) 3)</sup>	1SVR730010R3200	0.14 (0.309)	
					CT-MBS.22P <sup>2) 3)</sup>	1SVR740010R3200	0.129 (0.284)	
Multi	24-48 V DC, 24-240 V AC	10 (0.05 s - 300 h)	-	2 c/o	CT-WBS.22S	1SVR730040R3300	0.123 (0.271)	
					CT-WBS.22P	1SVR740040R3300	0.115 (0.254)	

 $<sup>^{1)}</sup>$  Extended temperature range -40 °C

 $<sup>^{\</sup>rm 2)}$  Remote potentiometer connection

 $<sup>^{\</sup>rm 3)}$  2nd c/o contact selectable as instantaneous contact

<sup>&</sup>lt;sup>4)</sup> 2 remote potentiometer connections

 $<sup>^{5)}</sup>$  See selection table on previous page

S: Screw connection

P: Push-in / easy connect

# Ordering details - singlefunctional devices



CT-ERS.21P



CT-AHS.22P



CT-SDS.23P

- Control input with voltage-related triggering
- ☐ Control input with volt-free triggering
- □/□ Two control inputs with volt-free triggering
- No triggering

# Ordering details

Timing function	Rated control supply voltage	Time ranges	Control input	Output	Туре	Order code	Weight (1 pc) kg (lb)	
ON-delay	24-240 V AC/ DC	10 (0.05 s - 300 h)	-	2 c/o	CT-ERS.21S <sup>1)</sup>	1SVR730100R0300	0.13 (0.287)	
					CT-ERS.21P <sup>1)</sup>	1SVR740100R0300	0.121 (0.267)	
	24-48 V DC, 24-240 V AC	-			CT-ERS.22S	1SVR730100R3300	0.121 (0.267)	
					CT-ERS.22P	1SVR740100R3300	0.113 (0.249)	
	24-48 V DC, 24-240 V AC		-	1 c/o	CT-ERS.12S	1SVR730100R3100	0.106 (0.234)	
					CT-ERS.12P	1SVR740100R3100	0.101 (0.222)	
OFF- delay	24-240 V AC/ DC	10 (0.05 s - 300 h)		2 c/o	CT-APS.21S <sup>1)</sup>	1SVR730180R0300	0.146 (0.322)	
					CT-APS.21P <sup>1)</sup>	1SVR740180R0300	0.125 (0.276)	
	24-48 V DC, 24-240 V AC					CT-APS.22S	1SVR730180R3300	0.138 (0.304)
			•		CT-APS.22P	1SVR740180R3300	0.127 (0.28)	
					1 c/o	CT-APS.12S	1SVR730180R3100	0.109 (0.24)
					CT-APS.12P	1SVR740180R3100	0.103 (0.227)	
	24-48 V DC, 24-240 V AC	10 (0.05 s - 300 h)		2 c/o	CT-AHS.22S	1SVR730110R3300	0.136 (0.30)	
					CT-AHS.22P	1SVR740110R3300	0.125 (0.276)	
OFF- delay <sup>2)</sup>	24-240 V AC/DC	7 (0.05 s - 10 min)	-	1 c/o	CT-ARS.11S	1SVR730120R3100	0.106 (0.234)	
					CT-ARS.11P	1SVR740120R3100	0.10 (0.22)	
			-	2 c/o	CT-ARS.21S	1SVR730120R3300	0.124 (0.273)	
					CT-ARS.21P	1SVR740120R3300	0.115 (0.254)	
Star- delta	24-48 V DC, 24-240 V AC	7 (0.05 s - 10 min)	-	2 n/o	CT-SDS.22S	1SVR730210R3300	0.114 (0.251)	
change- over <sup>3)</sup>					CT-SDS.22P	1SVR740210R3300	0.108 (0.238)	
	380-440 V AC				CT-SDS.23S	1SVR730211R2300	0.118 (0.26)	
					CT-SDS.23P	1SVR740211R2300	0.112 (0.247)	

 $<sup>^{1)}</sup>$  Extended temperature range -40  $^{\circ}$ C

<sup>2)</sup> Without auxiliary voltage

<sup>3) 50</sup> ms transition time

S: Screw connection

P: Push-in / easy connect

# Ordering details - Accessories



MT-x50B

The CT-S range offers the possibility of using accessories such as a remote potentiometer to adjust the time delay or a sealable, transparent cover to protect against unauthorized changes of time and threshold values.

# Remote potentiometer

 $50~k\Omega$  ±20 % - 0.2  $\Omega,$  degree of protection IP66



30 mm adapters

Material	Diameter in mm	Type	Order code	Pack unit pieces	Weight 1 piece g / oz
Plastic, black	22.5	MT-150B	1SFA611410R1506	1	0.040
Plastic, chrome	22.5	MT-250B	1SFA611410R2506	1	0.040
Metal, chrome	22.5	MT-350B	1SFA611410R3506	1	0.048

# 30 mm adapter for attaching the potentiometer 22 mm in 30 mm mounting hole



Marker label 29.6 x 44.5 mm

Material	Туре	Order code	Pack unit pieces	Weight 1 piece g / oz
Plastic, black	KA1-8029	1SFA616920R8029	1	
Metal, chrome	KA1-8030	1SFA616920R8030	1	

# Marker label



Marker label with scale 0-10 48.5 x 44.5 mm

Caption	Туре	Order code	Pack unit pieces	Weight 1 piece g / oz
Symbol (see illustration)	SK 615 562-87	GJD6155620R0087	1	0.002
Scale 0 - 10	SK 615 562-88	GJD6155620R0088	1	0.002
Scale 0 - 30	MA16-1060	1SFA611940R1060	1	0.002

# Accessories for CT-S



Sealable transparent cover for CT-S in new housing

Description	Type	Order code	Pack unit pieces	Weight 1 piece g / oz
Adapter for screw mounting	ADP.01	1SVR430029R0100	1	0.018 (0.040)
Sealable transparent cover	COV.11	1SVR730005R0100	1	0.004 (0.009)
Marker label for devices w/o DIP switches	MAR.01	1SVR366017R0100	10	0.001 (0.002)
Marker label for devices with DIP switches	MAR.12	1SVR730006R0000	10	0.001 (0.002)

Data at  $T_a$  = 25 °C and rated values, unless otherwise indicated

		CT-S
Input circuit - Supply circuit		101-3
	CT yyy v1	24.240 V AC /DC
Rated control supply voltage U <sub>s</sub>		24-240 V AC/DC 24-48 V DC, 24-240 V AC
_		380-440 V AC
Pated control cumply voltage II, telerance	C1-xxx.x3	-15+10 %
Rated control supply voltage U <sub>s</sub> tolerance		
Rated frequency		DC or 50/60 Hz
Frequency range AC		47-63 Hz
Typical power consumption	24.4.00	max. 16 VA
Power failure buffering time		min. 15 ms
	230/400 V AC	
Release voltage		> 10 % of the minimum rated control supply voltage U <sub>s</sub>
Minimum energizing time		100 ms (CT-ARS)
Formatting time 1)		5 min (CT-ARS)
Input circuit - Control circuit		
Kind of triggering		voltage-related triggering
Control input, Control function	A1-Y1/B1	start timing external
Parallel load / polarized		yes / no
Maximum cable length to the control input		50 m - 100 pF/m
Minimum control pulse length		20 ms
Control voltage potential		see rated control supply voltage
Current consumption of the control input	24 V DC	1.2 mA
	230 V AC	8 mA
	400 V AC	6 mA
Kind of triggering	CT-MFS, CT-MBS, CT-AHS	volt-free triggering
Control input, Control function	Y1-Z2	start timing external
	X1-Z2	pause timing / accumulative functions (CT-MFS)
Maximum switching current in the control	circuit	1 mA
Maximum cable length to the control input		50 m - 100 pF/m
Minimum control pulse length		20 ms
No-load voltage at the control inputs		10-40 V DC
Remote potentiometer		
Remote potentiometer connections, resistant	e value Z1-Z2	50 kΩ (CT-MFS, CT-MBS, CT-MVS.21, CT-MXS)
	Z3-Z2	50 kΩ (CT-MXS)
Maximum cable length to remote potentiomet	er	2 x 25 m, shielded with 100 pF/m
Shield connection		Z2
Timing circuit		
Time ranges	10 time ranges 0.05 s - 300 h	1.) 0.05-1 s 2.) 0.15-3 s 3.) 0.5-10 s 4.) 1.5-30 s 5.) 5-100 s 6.) 15-300 s 7.) 1.5-30 min 8.) 15-300 min 9.) 1.5-30 h 10.) 15-300 h
7 time ra		1.) 0.05-1 s 2.) 0.15-3 s 3.) 0.5-10 s 4.) 1.5-30 s 5.) 5-100 s 6.) 15-300 s 7.) 0.5-10 min
Recovery time	24-240 V AC/DC	< 50 ms
_	24-48 V DC, 24-240 V AC	< 80 ms
_	380-440 V AC	< 60 ms
Accuracy within the rated control supply volta	ge tolerance	Δt < 0.004 % / V
Accuracy within the temperature range		Δt < 0.03 % / °C
Repeat accuracy (constant parameters)		< ±0.2 %
Setting accuracy of time delay		±6 % of full-scale value
Star-delta transition time		fixed 50 ms (CT-SDS, CT-MBS, CT-MFS, CT-MVS.2x)
Star-delta transition time tolerance		±2 ms


 $<sup>^{\</sup>mbox{\tiny 1)}}\mbox{Prior}$  to first commissioning and after a six-month stop in operation

Indication of operational sta	ates						
Control supply voltage / timi	ng	U/T: green LED	ि: control supply voltage ap	plied / \tau_: timing			
Control supply voltage		U: green LED		·			
Relay state		R, R1, R2: yellow LED	1111	•			
Output circuit	,		a cosperation of grade				
Kind of output		15-16/18	relay, 1 c/o contact	,			
			relay, 2 c/o contacts				
			relay, 2 c/o contacts, 2nd c/o contacts	act selectable as inst. contact			
			relay, 2 n/o contacts (CT-SDS)				
Contact material			Cd-free, on request				
Rated operational voltage U <sub>e</sub>		IEC/EN 60947-1	250 V				
Minimum switching voltage	/ minimum swit	tching current	12 V / 100 mA				
Maximum switching voltage	/ maximum sw	itching current	see load limit curves				
Rated operational current I <sub>e</sub>		AC-12 (resistive) at 230 V	4 A				
		AC-15 (inductive) at 230 V	3 A				
		DC-12 (resistive) at 24 V	4 A				
		DC-13 (inductive) at 24 V	2 A (CT-ARS; 1.5 A)				
AC rating (UL 508)	utilization cat	tegory (Control Circuit Rating Code)	B 300				
		max. rated operational voltage	300 V AC				
	maximum	continuous thermal current at B300	5 A				
	max. making	g/breaking apparent power at B300	3600 VA / 360 VA				
Mechanical lifetime			30 x 10 <sup>6</sup> switching cycles				
Electrical lifetime		at AC-12, 230 V, 4 A	0.1 x 10 <sup>6</sup> switching cycles				
Frequency of operation		with/without load	360/72000 h <sup>-1</sup> CT-ARS: 1200/18000 h <sup>-1</sup>				
Max. fuse rating to achieve sl	nort-circuit pro	tection n/c contact	6 A fast-acting				
		n/o contact	10 A fast-acting				
General data							
MTBF			on request				
Duty cycle			100%				
Dimensions			see 'Dimensional drawings'				
Mounting			DIN rail (IEC/EN 60715), snap-on n	nounting without any tool			
Mounting position			any				
Minimum distance to other u	nits	vertical / horizontal	* : *				
Material of housing			UL 94 V-0				
Degree of protection		housing / terminals	IP50 / IP20				
Electrical connection							
			Screw connection technology	Easy Connect Technology (Push-in)			
Connecting capacity			1 x 0.5-2.5 mm² (1 x 18-14 AWG)	2 x 0.5-1.5 mm² (2 x 18-16 AWG			
		ferrule	2 x 0.5-1.5 mm <sup>2</sup> (2 x 18-16 AWG)				
		rigid	1 x 0.5-4 mm <sup>2</sup> (1 x 20-12 AWG) 2 x 0.5-2.5 mm <sup>2</sup> (2 x 20-14 AWG)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG			
Stripping length			8 mm (0.32 in)				
Tightening torque			0.6-0.8 Nm (7.08 lb.in)	-			

Environmental data			
Ambient temperature ranges	operation / storage	-25+60 °C / -40+85 °C, -40+60 °C / -40+85 °C for CT-M CT-APS.21	VS.21, CT-MFS.21, CT-ERS.21,
Relative humidity range		25 % to 85 %	
Vibration, sinusoidal (IEC/EN 60068-2-6)	functioning	40 m/s², 10-58/60-150 Hz	
	resistance	60 m/s², 10-58/60-150 Hz, 20 cycle	es
Vibration, seismic (IEC/EN 60068-3-3)	functioning	20 m/s <sup>2</sup>	
Shock, half-sine (IEC/EN 60068-2-27)	functioning	150 m/s², 11 ms, 3 shocks/direction	n
	resistance	300 m/s², 11 ms, 3 shocks/direction	on
Isolation data		CT-S with 1 c/o	CT-S with 2 c/o
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	500 V	, and the second
	output circuit 1 / output circuit 2	not available	300 V
Rated impulse withstand voltage $U_{imp}$	between all isolated circuits	4 kV; 1.2/50 μs except devices CT-xxx.23: input / output: 6 kV; 1.2/50 μs output 1 / output 2: 4 kV; 1.2/50 μs	s
Power-frequency withstand voltage (test voltage)	between all isolated circuits	2.0 kV; 50 Hz; 60 s	
Basic insulation (IEC/EN 60664-1)	input circuit / output circuit	500 V	
Protective separation (IEC/EN 60664-1)	input circuit / output circuit	250 V	
Pollution degree (IEC/EN 60664-1)		3	
Overvoltage category (IEC/EN 60664-1)		III	
Standards / Directives			
Standards		IEC/EN 61812-1	
Low Voltage Directive		2014/35/EU	
EMC Directive		2014/30/EU	
RoHS Directive		2011/65/EU	
Electromagnetic compatibility			
Interference immunity to		IEC/EN 61000-6-2, IEC/EN 61000-	6-1
electrostatic discharge	IEC/EN 61000-4-2	Level 3, 6 kV / 8 kV	
radiated, radio-frequency electromagnetic field	IEC/EN 61000-4-3	Level 3, 10 V/m (1 GHz) 3 V/m (2 GH	Hz) 1 V/m (2.7 GHz)
electrical fast transient / burst	IEC/EN 61000-4-4	Level 3, 2 kV / 5 kHz	
surge	IEC/EN 61000-4-5	Level 4, 2 kV A1-A2	
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	Level 3, 10 V	
harmonics and interharmonics	IEC/EN 61000-4-13	Class 3	
Interference emission		IEC/EN 61000-6-3, IEC/EN 61000-	6-4
high-frequency radiated	IEC/CISPR 22, EN 55022	Class B	
high-frequency conducted	IEC/CISPR 22, EN 55022	Class B	


# Technical diagrams

# DIP switch configuration CT-MXS.22x




Default setting: all DIP switches in position OFF

# Example of application - Star-delta changeover



Control circuit diagram



Power circuit diagram

# Technical diagrams

#### \_

#### **Connection diagrams**

### CT-MVS.21

A1	15	25 21	
Y1/B1	Z2	Z1	
iY1/ B1 A1         	15 	25 21 	900
A2		26 28 22 24	2CDC252002F0b06
28 24	26 22		52
18	16	A2	O.

A1-A2 Supply: 24-240 V AC/DC

A1-Y1/B1 Control input 15-16/18 1st c/o contact

25-26/28 2nd c/o contact

21-22/24 2nd c/o contact as instantaneous contact

Z1-Z2 Remote potentiometer connection


# CT-MVS.22

A1	15	25	
Y1/B1			
Y1/ B1 A1 		25              26 28	2CDC252003F0 b06
28	26		C252
18	16	A2	SCD

A1-A2 Supply: 224-48 V DC or 24-240 V AC

A1-Y1/B1 Control input 15-16/18 1st c/o contact 25-26/28 2nd c/o contact

# CT-MVS.23




A1-A2 Supply: 380-440V AC

A1-Y1/B1 Control input

15-16/18 1st c/o contact

25-26/28 2nd c/o contact


#### CT-MVS.12



A1-A2 Supply: 24-48 V DC or 24-240 V AC

A1-Y1/B1 Control input 15-16/18 1st c/o contact

#### CT-MXS.22



A1-A2 Supply: 24-48 V DC or 24-240 V AC


A1-Y1/B1 Control input 15-16/18 1st c/o contact

25-26/28 2nd c/o contact
Z1-Z2 Remote potentiometer

connection
73-72 Remote potentiometer

Z3-Z2 Remote potentiometer connection

#### CT-MFS.21



A1-A2 Supply: 24-240 V AC/DC

15-16/18 1st c/o contact 25-26/28 2nd c/o contact

21-22/24 2nd c/o contact as instantaneous contact

Y1-Z2 Control input X1-Z2 Control input

Z1-Z2 Remote potentiometer connection

#### CT-MBS.22

A1	15	25 21
	Z2	Z1
A1       A2 1	15          6   18	25 21 26 28 22 24
28 24	26 22	Y1
18	16	A2


A1-A2 Supply: 24-48 V DC or 24-240 V AC

15-16/18 1st c/o contact 25-26/28 2nd c/o contact

21-22/24 2nd c/o contact as instantaneous contact

Y1-Z2 Control input
Z1-Z2 Remote potentiometer connection

#### CT-WBS.22




A1-A2 Supply: 24-48 V DC or 24-240 V AC

15-16/18 1st c/o contact 25-26/28 2nd c/o contact

# Technical diagrams

### **Connection diagrams**


#### **⊠CT-ERS.21**



A1-A2 Supply: 24-240 V AC/DC

15-16/18 1st c/o contact 25-26/28 2nd c/o contact


#### ⊠CT-ERS.22



A1-A2 Supply: 24-48 V DC or 24-240 V AC

15-16/18 1st c/o contact 25-26/28 2nd c/o contact


#### **⊠CT-ERS.12**



A1-A2 Supply: 24-48 V DC or 24-240 V AC

15-16/18 1st c/o contact

#### CT-APS.21



A1-A2 Supply: 24-240 V AC/DC

A1-Y1/B1 Control input 15-16/18 1st c/o contact 25-26/28 2nd c/o contact


#### CT-APS.22

A1	15	25	
Y1/B1			
Y1/ B1 A1 I I I A2	15           	25 	3CDC252011F0b06
28	26		C252
18	16	A2	ő

A1-A2 Supply: 24-48 V DC or 24-240 V AC

A1-Y1/B1 Control input 15-16/18 1st c/o contact 25-26/28 2nd c/o contact


#### CT-APS.12



A1-A2 Supply: 24-48 V DC or 24-240 V AC

A1-Y1/B1 Control input 15-16/18 1st c/o contact

#### CT-AHS.22




A1-A2 Supply: 24-48 V DC or 24-240 V AC

Y1-Z2 Control input

15-16/18 1st c/o contact

25-26/28 2nd c/o contact


### CT-ARS.11



A1-A2 Supply: 24-240 V AC/DC


15-16/18 1st c/o contact

### CT-ARS.21



A1-A2 Supply: 24-240 V AC/DC 15-16/18 1st c/o contact 25-26/28 2nd c/o contact

# △ CT-SDS.22




A1-A2 Supply: 24-48 V DC or 24-240 V AC

17-18 1st n/o contact

17-28 2nd n/o contact

#### △ CT-SDS.23




A1-A2 Supply: 380-440 V AC
17-18 1st n/o contact
17-28 2nd n/o contact


# Technical diagrams

# Load limit curves


# AC load (resistive)




# DC load (resistive)



# Derating factor F for inductive AC load




### **Contact lifetime**




# Wiring notes

# Control inputs (volt-free triggering)




# Triggering of the control inputs (volt-free) with a proximity switch (3 wire)<sup>1)</sup>




# Technical diagrams


# Wiring notes

# Control inputs (voltage-related triggering)






# Remote potentiometer





The control input Y1/B1 is triggered with electric potential against A2. It is possible to use the control supply voltage from terminal A1 or any other voltage within the rated control supply voltage range.


# **Dimensional drawings**

in **mm** and inches












# Time relays for building applications Table of contents

33	Applications
54	Benefits and advantages
56	Selection table
57	Ordering details
58	Technical data
62	Technical diagrams













# Time relays for building applications

# **Applications**

The CT-D range is designed in a modular housing, making it well suited for building and residential applications. In just 12 order codes the CT-D range covers all the main timing functions needed for building automation, safely and reliably.




A typical application for timers is delayed switching. Switching several rows of lamps on and off in corridors, stairwells, staircases, etc, is a widespread application in which the excellent functionality of the CT-D timers is undisputed.



Air conditioning systems, heaters and fans can be found everywhere in buildings - just like the CT-D timers long used to switch them. On-delay, off-delay and a range of other functions cover all requirements.



Elevators, escalators, gates, compressors and doors - here too ABB timers ensure optimum and time-delayed opening as required. ABB's CT-D timers cover most functions with just 12 order codes.



# Benefits and advantages



The CT-D range is ideal for building applications and installation panels, due to its compact modular housing. For maximum flexibility in operation, nine single-function as well as two multifunction devices with seven timing functions are available. The devices offer four or seven time ranges from 0.05 seconds up to 100 hours. Their wide supply voltage range allows their use in applications worldwide.



Space savings

The CT-D range is ideal for installation panels thanks to its compact modular housing. The housing's design helps make the status and configuration more clearly visible. The CT-D range also offers a higher output current than standard industrial types. As well as the 1 c/o contacts, ABB offers devices with 2 c/o contacts for maximum flexibility.




Easy to install

Direct reading scales help make time setting quick and easy. A pre-selection for the time range together with an additional scale for fine adjustments help improve installation efficiency. For more flexibility, the delay time can even be changed when processes are running, making optimization to fit the application even simpler. All devices can be mounted and demounted tool-free.



The CT-D range fulfills various global standards and approvals, supporting business worldwide. Additionally, all devices from the CT-D range have a wide supply voltage from 24-48 V DC and 24-240 V AC, making it ideal for the use in installation panels around the world.

# Operating controls



# **CT-D range**Selection table

	Order number	1SVR500020R0000	1SVR500020R1100	1SVR500100R0000	1SVR500100R0100	1SVR500110R0000	1SVR500110R0100	1SVR500130R0000	1SVR500150R0000	1SVR500160R0000	1SVR500160R0100	1SVR500210R0100	1SVR500211R0100
	Туре	CT-MFD.12	CT-MFD.21	CT-ERD.12	CT-ERD.22	CT-AHD.12	CT-AHD.22	CT-VWD.12	CT-EBD.12	CT-TGD.12	CT-TGD.22	CT-SAD.22	CT-SDD,22
Timing function													
ON-delay	$\boxtimes$												
OFF-delay with aux. voltage						•							
Impulse-ON	1Л⊠	=	-					•					
Impulse-OFF with aux. voltage	1/1	•	-										
Flasher starting with ON	Л⊠								-				
Flasher starting with OFF	Л	•											
Pulse generator starting with ON or OFF	<b>≅</b> ∏									•			
Pulse former	1.												
Star-delta change-over	$\triangle$											•	
Features													
Control input, voltage-related triggering													
Time range													
0.05 s - 100 h										2	2		
0.05 s - 10 min													
Supply voltage													
12-240 V AC/DC													
24-48 V DC				•				•					-
24-240 V AC				•	•	•	•	•	•	•	•		•
Output													
c/o contact		1	2	1	2	1	2	1	1	1	2		
- /												_	_

# Ordering details



CT-MFD.12



CT-ERD.22

- Control input with voltage-related triggering
- No triggering

# Description

The CT-D range with its modular design is a perfect solution for installation panels. For maximum flexibility in operation, 10 single-function as well as two multifunction devices with seven timing functions are available. The devices offer four or seven time ranges from 0.05 seconds up to 100 hours. Their wide input range allows their use in applications worldwide.

#### Ordering details

Timing function	Rated control supply voltage	Time ranges	Control input	Output	Туре	Order code	Weight (1 pc)
	voitage						kg (lb)
Multi <sup>1)</sup>	24-240 V AC 24-48 V DC	7 (0.05 s - 100 h)		1 c/o	CT-MFD.12	1SVR500020R0000	0.060 (0.132)
Multi <sup>1)</sup>	12-240 V AC/DC	7 (0.05 s - 100 h)		2 c/o	CT-MFD.21	1SVR500020R1100	0.065 (0.143)
ON-delay	24-240 V AC 24-48 V DC	7 (0.05 s - 100 h)	-	1 c/o	CT-ERD.12	1SVR500100R0000	0.060 (0.132)
			-	2 c/o	CT-ERD.22	1SVR500100R0100	0.065 (0.143)
OFF-delay				1 c/o	CT-AHD.12	1SVR500110R0000	0.060 (0.132)
				2 c/o	CT-AHD.22	1SVR500110R0100	0.065 (0.143)
Impulse- ON			-	1 c/o	CT-VWD.12	1SVR500130R0000	0.060 (0.132)
Flasher starting with ON					CT-EBD.12	1SVR500150R0000	
Pulse generator	_	2×7 (0.05 s - 100 h)			CT-TGD.12 <sup>2)</sup>	1SVR500160R0000	0.060 (0.132)
				2 c/o	CT-TGD.22 <sup>2)</sup>	1SVR500160R0100	0.065 (0.143)
Star-delta change-		4 (0.05 s - 10 min)	-	2 n/o	CT-SDD.22 <sup>3)</sup>	1SVR500211R0100	0.065 (0.143)
over			-		CT-SAD.22 <sup>4)</sup>	1SVR500210R0100	

 $<sup>^{1)}</sup>$  Functions: ON-delay, OFF-delay with auxiliary voltage, Impulse-ON, Impulse-OFF with auxiliary voltage, Flasher starting with ON, Flasher starting with OFF, Pulse former

 $<sup>^{2)}</sup>$  ON and OFF times adjustable independently: 2 x 7 time ranges 0.05 s - 100 h

 $<sup>^{\</sup>scriptscriptstyle{3)}}$  Transition time 50 ms fixed

<sup>4)</sup> Transition time adjustable

Data at Ta = 25 °C and rated values, unless otherwise indicated


Data at $T_a = 25$ °C and rated values, unle	ss otherwise indicated					
	,	CT-D with 1 c/o contact	CT-D with 2 c/o contacts	CT-MFD.21		
Input circuit - Supply circuit			·	`		
Rated control supply voltage U <sub>s</sub>		24-240 V AC / 24-48 V	DC	12-240 V AC/DC		
Rated control supply voltage U <sub>s</sub> tolerance		-15+10 %		·		
Rated frequency		DC or 50/60 Hz				
Frequency range AC		47-63 Hz				
Typical power consumption		max. 3.5 VA				
Power failure buffering time		min. 20 ms				
Release voltage		> 10 % of the minimun	n rated control supply v	oltage U <sub>s</sub>		
Input circuit - Control circuit	'					
Control input, control function	A1-Y1/B1	start timing external				
Kind of triggering		voltage-related trigge	ring			
Resistance to reverse polarity		yes				
Parallel load / polarized		yes / yes				
Maximum cable length to the control input	S	50 m - 100 pF/m				
Minimum control pulse length		20 ms				
Control voltage potential		see rated control supp	ly voltage			
Current consumption of the control input	24 V DC	3.8 mA (CT-AHD.12) 3.9 mA (CT-MFD.12) 1.0 mA (CT-TGD.12)	0.9 mA (CT-AHD.22, CT-TGD.22)	0.4 mA		
	115 V AC	23.9 mA (CT-AHD.12) 23.0 mA (CT-MFD.12) 1.3 mA (CT-TGD.12)	3.2 mA (CT-AHD.22, CT-TGD.22)	0.3 mA		
	230 V AC	26.9 mA (CT-AHD.12) 26.0 mA (CT-MFD.12) 1.6 mA (CT-TGD.12)	6.4 mA (CT-AHD.22, CT-TGD.22)	0.7 mA		
Timing circuit	1	l.		· ·		
Time ranges	7 time ranges 0.05 s - 100 h	1.) 0.05-1 s 2.) 0.5-10 5.) 5-100 min 6.) 0.5-		10 min		
4 time ranges 0.0	5 s - 10 min (CT-SDD, CT-SAD)	1.) 0.05-1 s 2.) 0.5-10	s 3.) 5-100 s 4.) 0.5-	10 min		
Recovery time		< 50 ms				
Accuracy within the rated control supply voltag	e tolerance	Δt < 0.005 % / V				
Accuracy within the temperature range		Δt < 0.06 % / °C				
Repeat accuracy (constant parameters)		Δt < ± 0.5 %				
Setting accuracy of time delay		± 10% of full-scale value				
Star-delta transition time	CT-SDD/ CT-SAD	•	ms, 40 ms, 50 ms, 60 m	s, 80 ms or 100 ms		
Star-delta transition time tolerance	CT-SDD / CT-SAD	±3 ms				
Indication of operational states	,	4		,		
Control supply voltage / timing	U: green LED	l: control suppl	y voltage applied			
Relay energized	R, R1, R2: yellow LED	l: output relay	energized			
Operating elements and controls		<u> </u>				
Adjustment of the time range		front-face rotary swite	ch, direct reading scale	 S		
Fine adjustment of the time value		front-face potentiome	· · · · · · · · · · · · · · · · · · ·			
Preselection of the timing function at multifund	ction devices		ch, direct reading scale	S		
Adjustment of the transition time		front-face potentiome	· <u> </u>			
3	2: 0/10					

			CT-D with 1 c/o contact	CT-D with 2 c/o contacts	CT-MFD.21	
Output circuit			l .	ļ	ļ.	
Kind of output		15-16/18	Relay, 1 c/o contact	-		
		15-16/18; 25-26/28	-	Relay, 2 c/o contact	S	
		17-18; 17-28		Relay, 2 n/o contacts (CT-SDC, CT-SAC)		
Contact material			AgNi alloy, Cd free	'		
Rated operational volta	age U <sub>e</sub>		250 V			
Minimum switching vo	ltage / minimum switc	hing current	12 V / 100 mA			
Maximum switching vo	ltage / maximum swit	ching current	250 V AC / 6 A	250 V AC / 5 A		
Rated operational curr	ent I <sub>e</sub>	AC-12 (resistive) at 230 V	6 A	5 A		
		AC-15 (inductive) at 230 V	3 A	3 A	n/o: 3 A n/c: 0.75 A	
		DC-12 (resistive) at 24 V	6 A	5 A	'	
		DC-13 (inductive) at 24 V	2 A	2 A	1 A	
AC rating (UL 508)	utilization catego	ry (Control Circuit Rating Code)	B 300		n/o: B 300 n/c: C 300	
_		max. rated operational voltage	300 V AC			
_	maximum cont	inuous thermal current at B300	5 A		n/o: 5 A	
_	maximum cont	inuous thermal current at C300	-		n/c: 2.5 A	
_	max. making/bro	eaking apparent power at B300			n/o: 3600/360 VA	
max. making/breaking apparent power at C300				n/c: 1800/180 VA		
Mechanical lifetime			30 x 10 <sup>6</sup> switching cycles			
Electrical lifetime			0.1 x 10 <sup>6</sup> switching cycles			
Max. fuse rating to ach	ieve short-circuit	n/c contact	6 A fast-acting			
protection		· ·	10 A fast-acting 6 A fast-acting			
General data		· · · · · · · · · · · · · · · · · · ·				
Mean time between fai	lures (MTBF)		on request	,	"	
Duty cycle			100%			
Dimensions			see 'Dimensional dra	wings'		
Mounting			DIN rail (IEC/EN 60715), snap-mounting without any tool			
Mounting position			any			
Minimum distance to o	ther units	horizontal / vertical	no / no			
Material of housing			UL 94 V-2			
Degree of protection		housing / terminals				
Electrical connection	,	<del>-</del>		,	1	
Connecting capacity		fine-stranded with(out)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 2	0-16 AWG)		
- · ·		wire and ferrule	1 x 0.5-2.5 mm <sup>2</sup> (1 x 2	0-14 AWG)		
		rigid	2 x 0.5-1.5 mm <sup>2</sup> (2 x 2			
			1 x 0.5-4 mm <sup>2</sup> (1 x 20	-12 AWG)		
Stripping length			7 mm (0.28 in)			
Tightening torque			0.5-0.8 Nm (4.43-7.08	3 lb.in)		
Environmental data						
Ambient temperature	ange	operation / storage	-20 +60 °C / -40	+85 °C		
Climatic class		EC/EN 60721-3-3	3k22			
Relative humidity rang	e		25-85%			
Vibration, sinusoidal		IEC/EN 60068-2-6	20 m/s²; 10 cycles, 10	)15010 Hz		
Shock (half-sine)		IEC/EN 60068-2-27	150 m/s <sup>2</sup> , 11 ms			


			CT-D with 1 c/o contact	CT-D with 2 c/o contacts	CT-MFD.21
Isolation data	1			1	,
Rated insulation voltage U <sub>i</sub>	inpu	t circuit / output circuit	300 V		
	output ci	cuit 1 / output circuit 2	not available	300 V	300 V
Rated impulse withstand voltage U <sub>imp</sub>	betv	een all isolated circuits	4 kV; 1.2/50 μs		
Power-frequency withstand voltage test (test voltage)	betv	veen all isolated circuits	2.5 kV; 50 Hz; 60 s		
Basic insulation (IEC/EN 60664-1)	inpu	t circuit / output circuit	300 V		
Protective separation (IEC/EN 60664-1)	inpu	t circuit / output circuit	250 V at pollution of	degree 2 / overvoltage ca	ategory II
Pollution degree (IEC/EN 60664-1)			3		
Overvoltage category (IEC/EN 60664-1)			Ш		
Standards / Directives					
Standards			IEC/EN 61812-1		
Low Voltage Directive			2014/35/EU		
EMC Directive			2014/30/EU		
RoHS Directive			2011/65/EU		
Electromagnetic compatibility					
Interference immunity to			IEC/EN 61000-6-2,	IEC/EN 61000-6-1	
electrostatic discharge		IEC/EN 61000-4-2	Level 3 (6 kV / 8 kV)		
radiated, radio-frequency, electromag	netic field	IEC/EN 61000-4-3	Level 3 (10 V / m)		
electrical fast transient / burst		IEC/EN 61000-4-4	Level 3 (2 kV / 5 kH	z)	
surge		IEC/EN 61000-4-5	Level 4 (2 kV L-L)		
conducted disturbances, induced by radio-frequency fields		IEC/EN 61000-4-6	Level 3 (10 V)		
Interference emission			IEC/EN 61000-6-3,	IEC/EN 61000-6-4	
high-frequency radiated		EC/CISPR 22, EN 55022	Class B		
high-frequency conducted		EC/CISPR 22, EN 55022	Class B		

# Technical diagrams

# Example of application - Star-delta changeover



Control circuit diagram




Power circuit diagram

# Technical diagrams

\_


# **Connection diagrams**

# CT-MFD.21




A1-A2	Supply: 12-240 V AC/DC
A1-Y1/B1	Control input
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

# CT-MFD.12




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

# **⊠CT-ERD.22**




A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

# **⊠CT-ERD.12**




A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact

# CT-AHD.22




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

# CT-AHD.12




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

# 1**□** CT-VWD.12




A1-A2	Supply:
	24-48 V DC or
	24-240 V AC
15-16/18	1st c/o contact

# **□⊠ CT-EBD.12**




A1-A2	Supply: 24-48 V DC or 24-240 V AC
15-16/18	1st c/o contact

# ≅⊓ CT-TGD.22




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact
25-26/28	2nd c/o contact

# ≅⊓ CT-TGD.12




A1-A2	Supply: 24-48 V DC or 24-240 V AC
A1-Y1/B1	Control input
15-16/18	1st c/o contact

# △ CT-SDD.22



A1-A2	Supply:
	24-48 V DC or
	24-240 V AC
17-18	1st n/o contact
	(star contactor)
17-28	2nd n/o contact
	(delta contactor)

# △ CT-SAD.22




A1-A2	Supply:
	24-48 V DC or
	24-240 V AC
17-18	1st n/o contact
	(star contactor)
17-28	2nd n/o contact
	(delta contactor)

# Technical diagrams

### **Load limit curves**


# AC load (resistive)

### CT-D.1x




# DC load (resistive)


### CT-D.1x




Derating factor F for inductive AC load




CT-D.2x



CT-D.2x




**Contact lifetime** 




# Wiring notes for devices with control input

# A parallel load to the control input is possible




# **Dimensional drawings**

in mm and inches



CT-D devices with 1 c/o contact or 2 n/o contacts



CT-D devices with 2 c/o contacts



# CT-C, CT-S, CT-D


# On delay functions (Delay on make) igttimes

#### On-delay



This function requires a continuous control supply voltage for timing. Timing begins when a control supply voltage is applied. When the selected time delay is complete, the output relay energizes. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

#### ON-delay accumulative



This function requires a continuous control supply voltage for timing. Timing begins when a control supply voltage is applied. When the selected time delay is complete, the output relay energizes. Timing can be paused by closing the control input.

The elapsed time t1 is stored and continues from this time value when the control input is re-opened. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

# OFF delay functions (Delay on break, retriggerable Watchdog) ■


# OFF-delay with auxiliary voltage



This function requires a continuous control supply voltage for timing. If the control input is closed, the output relay energizes immediately. If the control input is opened, the time delay starts. When the selected time delay is complete, the output relay de-energizes.

If control input re-closes before the time delay is complete, the time delay is reset and the output relay does not change state. Timing starts again when the control input re-opens. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

### OFF-delay without auxiliary voltage




The OFF-delay function without auxiliary voltage does not require a continuous control supply voltage for timing. Applying a control supply voltage energizes the output relay. If the control supply voltage is interrupted, the OFF-delay starts. When timing is complete, the output relay de-energizes.

If a control supply voltage is re-applied before the time delay is complete, the time delay is reset and the output relay remains energized. A control supply voltage must be applied for the minimum energizing time (200 ms), for correct operation.

# CT-C, CT-S, CT-D

### OFF-delay with auxiliary voltage, accumulative



This function requires a continuous control supply voltage for timing. If the control input is closed, the output relay energizes immediately. If the control input is opened, the time delay starts. When the selected time delay is complete, the output relay de-energizes. If the control input closes before the time delay is complete, the time delay is reset and the output relay does not change state. Timing starts again when the control input reopens.

Pause timing / Accumulative OFF-delay: Timing can be paused by closing control 2. The elapsed time t1 is stored and continues from this time value when control input 2 is re-opened. This can be repeated as often as required. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

#### Impulse-ON functions 1☐⊠

#### Impulse-ON (interval)



This function requires a continuous control supply voltage for timing. The output relay energizes immediately when the control supply voltage is applied and de-energizes after the set pulse time is complete. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

### Impulse-ON, accumulative



This function requires a continuous control supply voltage for timing. The output relay energizes immediately when the control supply voltage is applied and de-energizes after the set pulse time is complete. If control input 1 is open, timing begins when a control supply voltage is applied. Or, if control a supply voltage is already applied, opening control input 1 starts timing. When the selected pulse time is complete, the output relay de-energizes. Closing control input 1, before the pulse time is complete, de-energizes the output relay and resets the pulse time.

#### Pause timing / Accumulative impulse-ON:

Timing can be paused by closing control input 2. The elapsed time t1 is stored and continues from this time value when control input 2 is re-opened. This can be repeated as often as required. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

# CT-C, CT-S, CT-D


### Impulse-OFF functions 1☐

Impulse-OFF with auxiliary voltage



This function requires a continuous control supply voltage for timing. The output relay energizes immediately when the control input is de-energized and the output de-energizes after the set pulse time is complete. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.


Impulse-OFF without auxiliary voltage



This function does not require a continuous control supply voltage for timing.

If the control supply voltage is interrupted, the output relay energizes and the OFF time starts. When timing is complete, the output relay de-energizes. If a control supply voltage is re-applied before the time delay is complete, the time delay is reset and the output relay de-energizes. A control supply voltage must be applied for the minimum energizing time (200 ms), for proper operation.

# Impulse-OFF with auxiliary voltage (Trailing edge interval) accumulative



This function requires a continuous control supply voltage for timing. If a control supply voltage is applied, opening control input 1 energizes the output relay immediately and starts timing. When the selected pulse time is complete, the output relay de-energizes. Closing control input 1, before the pulse time is complete, de-energizes the output relay and resets the pulse time.

Pause timing / Accumulative impulse-OFF:

Timing can be paused by closing control input 2. The elapsed time t1 is stored and continues from this time value when control input 2 is re-opened. This can be repeated as often as required. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

### Impulse-ON and Impulse-OFF functions 1☐

Impulse-ON and impulse-OFF



This function requires a continuous control supply voltage for timing. If a control supply voltage is applied, closing the control input energizes the output relay immediately and starts the pulse time t1. When t1 is complete, the output relay de-energizes. Re-opening the control input energizes the output relay immediately and starts the pulse time t2. When t2 is complete, the output relay de-energizes. t1 and t2 are independently adjustable. If the control input changes state before the pulse time is complete, the output relay de-energizes and the pulse time is reset. If the control input changes state again, the interrupted pulse time restarts. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

CT-C, CT-S, CT-D

# Flasher starting with ON functions $\square \boxtimes$

#### Flasher starting with ON



Applying a control supply voltage starts timing with symmetrical ON & OFF times. The cycle starts with an ON time first. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

#### Flasher with reset starting with ON



Applying a control supply voltage starts timing with symmetrical ON & OFF times. The cycle starts with an ON time first. The time delay can be reset by closing the control input. Opening the control input starts the timer pulsing again with symmetrical ON & OFF times. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.


### Flasher starting with OFF functions □

### Flasher starting with OFF



Applying a control supply voltage starts timing with symmetrical ON & OFF times. The cycle starts with an OFF time first. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.


#### Flasher with reset starting with OFF



Applying a control supply voltage starts timing with symmetrical ON & OFF times. The cycle starts with an OFF time first. The time delay can be reset by closing the control input. Opening the control input starts the timer pulsing again with symmetrical ON & OFF times. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

# Flasher starting with ON or OFF functions $\square$

### Flasher starting with ON or OFF



Applying a control supply voltage starts timing with symmetrical ON / OFF times. If the control input is open while supply voltage is connected the cycle starts with an ON time first. If the control input is closed while supply voltage is connected the cycle starts with an OFF time first.

# CT-C, CT-S, CT-D

#### Pulse former III

#### Puls former (single shot)



This function requires a continuous control supply voltage for timing. Closing the control input energizes the output relay immediately and starts timing. Operating the control input during the time delay has no effect. When the selected ON time is complete, the output relay de-energizes. After the ON time is complete, it can be restarted by closing the control input. If control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

# Single-pulse generator $\blacksquare 1 \square$

#### Single-pulse generator, starting with OFF



This function requires a continuous control supply voltage for timing. Applying a control supply voltage while the control input is open energizes the output relay after the OFF time t1 is complete. When the following ON time t2 is complete, the output relay de-energizes. Alternatively, when a control supply voltage is already applied, the timing process can be started by opening control input. Closing the control input with a control supply voltage applied, de-energizes the output relay and re- sets the time delay. The ON & OFF times are independently adjustable.

### Pulse generator **≅**□


# Starting with the ON or OFF time (Recycling unequal times, ON or OFF first)



This function requires a continuous control supply voltage for timing. Applying a control supply voltage, with closed control input, starts timing with an OFF time first. Applying a control supply voltage, with open control input, starts timing with an ON time first. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

### Impulse with delay ⊠1Л

#### Fixed impulse with adjustable time delay



This function requires a continuous control supply voltage for timing. The time delay t1 starts when a control supply voltage is applied. When t1 is complete, the output relay energizes for the fixed impulse time t2 of 500 ms. If the control supply voltage is interrupted, the time delay is re- set. The output relay does not change state.

### Adjustable impulse with fixed time delay




This function requires a continuous control supply voltage for timing. As soon as the control supply voltage is applied, the time delay t2 (fixed 500 ms) starts. When t2 is complete, the output relay energizes and the selected pulse time t1 starts. When t1 is complete, the output relay de-energizes. If the control supply voltage is interrupted, the pulse time is reset and the output relay de-energizes.

# CT-C, CT-S, CT-D

### ON- and OFF-delay 🖂 🖿

Symmetrical ON- and OFF-delay 1)



This function requires a continuous control supply voltage for timing. Closing the control input starts the ON-delay time t1. When timing is complete, the output relay energizes. Opening the control input starts the OFF-delay time t2. When the OFF-delay t2 is complete, the output relay de-energizes. If the control input opens before the ON-delay (<t1) is complete, the time delay is reset and the output relay remains de-energized. If control input closes before the OFF-delay time (<t2) is complete, the time delay is reset and the output relay remains energized.

1) Variant with 2nd control input for pause timing is available too.


#### Asymmetrical ON- and OFF-delay



This function requires a continuous control supply voltage for timing. Closing the control input starts the ON-delay t1. When timing is complete, the output relay energizes. Opening the control input starts the OFF-delay t2. When the OFF-delay is complete, the output relay de-energizes. The ON-delay and OFF-delay are independently adjustable.

If the control input opens before the ON-delay is complete (<t1), the time delay is reset and the output relay remains de-energized. If the control input closes before the OFF-delay is complete (<t2), the time delay is reset and the output relay remains energized. If the control supply voltage is interrupted, the output relay de-energizes and the time delay is reset.

#### Star-Delta changeover (with impulse) △ △1 □



This function requires a continuous control supply voltage for timing. Applying a control supply voltage, energizes the star contactor connected to output 1 and begins the set starting time t1. When the starting time is complete, the first output contact de-energizes the star contactor. When the transition time t2 is complete, the second output contact energizes the delta contactor. The delta contactor remains energized as long as the control supply voltage is applied. t2 is fixed to 50 ms or in some variants adjustable.

#### **Further functions**

### ON/OFF function $\square$



This function is used for test purposes during commissioning and troubleshooting. If the selected maximum value of the time range is smaller than 300 hours (front-face potentiometer "Time sector" ≠ 300 h), applying a control supply voltage energizes the output relay immediately. Interrupting the control supply voltage, de-energizes the output relay. If the selected maximum value of the time range is 300 hours (front-face potentiometer "Time sector" = 300 h) and a control supply voltage is applied the output relay does not energize.

### Alternating without time delay



The alternating function is designed to evenly use the electromechanical resource of a twin pump, compressors and generators. The alternating relay has two normally open contacts, which are closed alternately each time the control supply voltage is applied.



# Measuring and monitoring relays Table of contents

74	Benefits and advantages
76	Offer overview
79	Applications
81	Single-phase monitoring relays
105	Three-phase monitoring relays
137	Grid feeding monitoring relays
151	Insulation monitoring relays fo unearthed supply systems
181	Thermistor motor protection relays
203	Temperature monitoring relays with potentiometer
219	Smart temperature monitoring relays
239	Liquid level monitoring relays
261	Accessories

# Benefits and advantages



#### Sealable transparent cover

Protection against unauthorized changes of time and threshold values.

# Benefits and advantages



### **Easy Connect technology**

- $\bullet \ \ Tool-free \ wiring \ and \ excellent \ vibration \ resistance.$
- Push-in terminals provide connection of wires up to  $2 \times 0.5 1.5 \text{ mm}^2$  (2 x 20 -16 AWG), rigid or fine-strand with or without wire end ferrules.
- Excellent vibration resistance the right solution for harsh environments.



#### Double-chamber cage connection terminals

Double-chamber cage connection terminals provide connection of wires up to  $2 \times 0.5$ - $2.5 \text{ mm}^2$  ( $2 \times 20$ -14 AWG) rigid or fine-strand, with or without wire end ferrules.



### LEDs for status indication

All actual operational states are displayed by front-face LEDs, simplifying commissioning and troubleshooting.




### Integrated marker label

Integrated marker labels allow the product to be marked quickly and simply. No additional marker labels are required.

### Offer overview

Measuring and monitoring relays monitor and detect operating conditions with regard to phase, current, voltage, frequency, temperature, liquid level or insulation faults. The relays inform users about abnormal conditions and allow them to take necessary corrective actions before severe and costly failures can occur. Depending on the product model, measuring and monitoring relays are categorized into seven product families.




### Single-phase current monitoring relays

- Monitoring of motor current consumption
- Monitoring of lighting installations and heating circuits
- Monitoring of transportation equipment overload
- Monitoring of locking devices, electromechanical brake gear and locked rotors


#### Single-phase voltage monitoring relays

- · Speed monitoring of DC motors
- · Monitoring of battery voltages and other supply networks



### Three-phase monitoring relays

- Voltage monitoring of mobile three-phase equipment
- Protection of personnel and installations against phase reversal
- Monitoring of the supply voltage of machines and installations
- Protection of equipment against damage caused by unstable supply voltage
- · Switching to emergency or auxiliary supply
- Protection of motors against damage caused by unbalanced phase voltages and phase loss
- · Suitable for HVAC applications




#### Grid feeding monitoring relays

The CM-UFD.M\* range monitors all voltage and frequency parameters in a grid and ensures the safe feeding of decentrally produced electrical energy into the grid.


- Monitoring of the voltage with up to 2 thresholds for over- and undervoltage
- Monitoring of the frequency with up to 2 thresholds for over- and underfrequency
- ROCOF (rate of change of frequency) and vector shift detection
- · In compliance with several local standards

### Offer overview



#### Insulation monitoring relays


- Monitoring of electrically isolated supply mains for insulation resistance failure
- Detection of initial faults
- · Protection against earth faults



#### Temperature monitoring relays

Acquisition, messaging and regulation of temperatures of solid, liquid and gaseous media in processes and machines


- · Motor and system protection
- Control panel temperature monitoring
- Frost monitoring
- Temperature limits for process variables, e.g. in the packing or electroplating industry
- Control of systems and machines like heating, air-conditioning and ventilation systems, solar collectors, heat pumps or hot water supply systems
- · Bearing, gear oil and coolant monitoring



### Thermistor motor protection

CM-MSE and CM-MSS provide full protection of motors with integrated PTC resistor sensors.


Protection of motors against thermal overload, e. g. caused by insufficient cooling, heavy load starting conditions, undersized motors, etc.



### Liquid level monitoring relays


- Protection of pumps against dry running
- Protection against container overflow
- · Control of liquid levels
- Detection of leaks
- Control of mixing ratios

### Offer overview



#### CM-N range: Multifunctional range

- 45 mm wide housing
- Output contacts: 2 c/o (SPDT) contacts
- Continuous voltage range (24-240 V AC/DC) or single-supply
- Setting and operation via front-face operating controls
- Adjustment of threshold values and switching hysteresis via direct reading scale
- · Adjustable time delays
- Integrated and snap-fitted front-face marker label
- Sealable transparent cover (accessory)



### CM-S range: Universal and multifunctional range

- Only 22.5 mm wide housing
- Output contacts: 1 or 2 c/o (SPDT) contacts
- One supply voltage range or supplied by measuring circuit
- Setting and operation via front-face operating controls
- Adjustment of threshold values and switching hysteresis via direct reading scale
- Integrated and snap-fitted front-face marker
- Snap-on housing: The relays can be placed on a DIN rail tool-free just snap it on or remove it tool-free
- Sealable transparent cover (accessory)



### CM-E range: Economy range

- Only 22.5 mm wide housing
- Output contacts: 1 c/o contact or 1 n/o contact
- One supply voltage range
- One monitoring function
- Cost-efficient solution for OEM applications
- Preset monitoring ranges



#### CM-TCN range: Smart temperature monitoring relays

- 45 mm wide housing
- Output contacts: 3 c/o contact
- Wide supply voltage range (24-240 V AC/DC)
- · A wide range of settings, that can be adjusted flexibly
- NFC parametrization via smartphone app
- Back-lit LCD for easy reading and parametrization
- Embedded Modbus RTU communication interface

### **Applications**

ABB offers a wide selection of measuring and monitoring relays to suit a wide range of applications for businesses worldwide. Excellent vibration resistance with the Easy Connect terminal technology and railway certifications for selected products ensure the operability, even in harsh environments.



#### **Automation panels**

- Textile industry measuring and monitoring of motor voltage and current overload of, for example, looms.
- Packaging industry measuring and monitoring of motor voltage and current overload of, for example, conveyor belts.



#### Infrastructure

- Water and wastewater applications monitoring the liquid level of water tanks and wastewater recycling plants.
- Lifts status monitoring of the three phase mains of, for example, construction lifts, passenger lifts and escalators.
- Hoisting applications construction cranes, harbor cranes.
- · Railway.



#### Renewable energy

- Solar monitoring of the insulation resistance and the frequency and voltage of the public grid to keep electrical grids stable and meet local requirements.
- Wind temperature, current and voltage supervision of automation panels and electrical motors.



#### **Buildings**

- Lifts status monitoring of the three phase mains of, for example, construction lifts, passenger lifts and escalators.
- HVAC monitoring of grid parameters, control and protection of loads.











# Single-phase monitoring relays Table of contents

82	Benefits and advantages						
84	Operating controls						
86	Single-phase current monitoring relays						
86	Selection table						
87	Ordering details						
88	Single-phase voltage monitoring relays						
88	Selection table						
89	Ordering details						
90	Technical data						
96	Technical diagrams						
98	Function diagrams						

### Benefits and advantages



For the monitoring of currents and voltages in single-phase AC/DC systems, ABB's CM-range contains a wide selection of powerful and compact devices, all in an only 22.5 mm wide housing. This product range includes current and voltage monitoring relays for over- and undercurrent and voltage protection – from 3 mA to 15 A, and from 3 V to 600 V.



Read the status of the relay at a glance: clear visualization of the device status via LEDs. Easy to adjust with rotary wheels and variants with push-in terminals make a quick and easy installation and setting possible.



Reliable in harsh conditions

All relays work reliably in environments with low temperatures down to -25 °C. Additionally, the housing fulfills the UL 94 V-0 flammability standard requirements. Together with the vibration resistant push-in terminals, the relay is not only reliable, no matter the environment temperature, but is also durable to shock and vibration. Save time as retightening is no longer needed, and enhance the reliability and safety of the equipment.



Easy installation

Like all devices from the measuring and monitoring portfolio, the single-phase monitoring relays are easily configurable via front facing potentiometers. Easy threshold configuration without calculation is accomplished by direct reading scales. For further configuration options, additional settings can be made via dip-switches, offering the flexibility to configure, for example, the working principle of the relays and the output configuration. The device can be set up before installation in the application and easy adjustments during the process are possible.

### Benefits and advantages



#### Characteristics current and voltage monitoring relays<sup>1)</sup>

- Monitoring of DC and AC currents: 3 mA to 15 A
- Monitoring of DC and AC voltages from 3-600 V
- TRMS measuring principle
- · One device includes 3 current measuring ranges
- One device includes 4 voltage measuring ranges: 3-30 V; 6-60 V; 30-300 V; 60-600 V
- · Over- and undercurrent monitoring
- · Over- and undervoltage monitoring
- · ON or OFF-delay configurable
- · Open- or closed-circuit principle configurable
- Threshold values for >U and/or <U adjustable
- · Latching function configurable

- Thresholds for >I and/or <I adjustable
- Fixed hysteresis of 5 %
- Start-up delay T<sub>v</sub> adjustable 0; 0.1-30 s
- Tripping delay T<sub>v</sub> adjustable 0; 0.1-30 s
- 1 x 2 c/o contacts (common signal) or 2 x 1 c/o contact (separate signals for >I and <I) configurable</li>
- 1 x 2 c/o contacts (common signal) or 2 x 1 c/o contact (separate signals for >U and <U) configurable</li>
- 22.5 mm width
- 3 LEDs for the indication of operational states
- · Various approvals and marks
- 1) depending on device



### **Applications**

- Protection of electronic or electromechanical devices against over- and under voltage or over- and under current
- DC motor speed control

- · Battery monitoring
- · Monitoring of AC or DC supplies
- · Monitoring of heating or lighting circuits



### Current monitoring, single-phase

The ABB current monitoring relays CM-SRS.xx reliably monitor the occurrence of currents that exceed or fall below the selected threshold value. The functions overcurrent or undercurrent monitoring can be preselected. Single- and multifunction devices for the monitoring of direct or alternating currents from 3 mA to 15 A are available.

### Current window monitoring ( $I_{min}$ , $I_{max}$ )

The window monitoring relay CM-SFS.2x is available if the application requires the simultaneous monitoring of overand undercurrents.

#### Voltage monitoring, single-phase


The ABB voltage monitoring relays CM-SRS.xx are used to monitor direct and alternating voltages within a range of 3-600 V. Over- or undervoltage detection can be preselected.

### Voltage window monitoring $(U_{min}, U_{max})$

For the simultaneous detection of over- and undervoltages, the window monitoring relay CM-EFS.2 can be used.


# Operating controls

### **Current monitoring relays**



# Operating controls

### Voltage monitoring relays



#### \_

### Single-phase current monitoring relays

Selection table

																									_
		200	500	500	500	000	000	300	300	300	400	400	100	100	001	001	200	200	009	900	900	200	400	100	200
	er	1SVR730840R0200	1SVR740840R0200	1SVR730841R0200	1SVR740841R0200	1SVR730841R1200	1SVR740841R1200	1SVR730840R0300	1SVR730841R0300	1SVR730841R1300	1SVR730840R0400	1SVR740840R0400	1SVR730841R0400	1SVR740841R0400	1SVR730841R1400	1SVR740841R1400	1SVR730840R0500	1SVR730841R0500	1SVR730841R1500	1SVR730840R0600	1SVR740840R0600	1SVR730840R0700	1SVR730760R0400	1SVR740760R0400	1SVR730760R0500
	Order number	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	084	920	920	920
	ern	R73	R74	R73	R74	R73	R74	R73	R73	R73	R73	R74	R73	R74	R73	R74	R73	R73	R73	R73	R74	R73	R73	R74	R73
	ord.	15V																							
	Ť																				Δ.				
		.115	11.	118	11.	115	11.	125	125	125	.215	.21F	.215	.21F	218	.21F	.225	.225	.225	Σ̈́	Σ̈	Μ.	215	21P	225
		SRS	SFS	SFS	SFS																				
	Туре	CM-SRS.11	CM-SRS.11P	CM-SRS.11S	CM-SRS.11P	CM-SRS.11S	CM-SRS.11P	CM-SRS.12S	CM-SRS.12S	CM-SRS.12S	CM-SRS.21S	CM-SRS.21P	CM-SRS.21S	CM-SRS.21P	CM-SRS.21S	CM-SRS.21P	CM-SRS.22S	CM-SRS.22S	CM-SRS.22S	CM-SRS.M1S	CM-SRS.M1P	CM-SRS.M2S	CM-SFS.	CM-SFS.21P	CM-SFS.22S
Rated control supply voltage U <sub>s</sub>	<u></u>																								
24 - 240 V AC/DC											•	•								•				•	•
110 - 130 V AC													•												
220 - 240 V AC										•									•						
Measuring ranges AC/DC																									
3 - 30 mA			•								•				•										
10 - 100 mA		-																							
0.1 - 1 A			•								•	•								•					
0.3 - 1.5 A																									
1 - 5 A									•													•			
3 - 15 A																	•								
Monitoring function																									
Over- or undercurrent																									
Window current monitoring																									-
Latching																				sel	sel	sel	sel	sel	se
Open-circuit or closed-circuit principle																				sel	sel	sel	sel	sel	se
Timing functions for tripping delay																									
ON-delay, 0.1 - 30 s											adj														
ON- or OFF-delay, 0.1 - 30 s																							sel	sel	se
Output																									
c/o contact		1	1	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Connection type																									
Push-in terminals																									
Double-chamber cage connection terminal	ls																								

adj: adjustable sel: selectable

### Ordering details



CM-SRS.22S



CM-SFS.22P

### Description

The CM range current monitoring relays protect single-phase mains (DC or AC) from over- and undercurrent from 3 mA to 15 A.

### Ordering details

Description	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-SRS.11S	1SVR730840R0200	0.145 (0.320)
		1SVR730841R0200	0.161 (0.355)
		1SVR730841R1200	0.161 (0.355)
	CM-SRS.11P	1SVR740840R0200	0.137 (0.302)
		1SVR740841R0200	0.153 (0.337)
		1SVR740841R1200	0.153 (0.337)
	CM-SRS.12S	1SVR730840R0300	0.137 (0.302)
		1SVR730841R0300	0.168 (0.370)
		1SVR730841R1300	0.168 (0.370)
	CM-SRS.21S	1SVR730840R0400	0.152 (0.335)
		1SVR730841R0400	0.179 (0.395)
		1SVR730841R1400	0.179 (0.395)
	CM-SRS.21P	1SVR740840R0400	0.141 (0.311)
		1SVR740841R0400	0.168 (0.370)
		1SVR740841R1400	0.168 (0.370)
	CM-SRS.22S	1SVR730840R0500	0.144 (0.399)
		1SVR730841R0500	0.181 (0.399)
		1SVR730841R1500	0.181 (0.399)
	CM-SRS.M1S	1SVR730840R0600	0.153 (0.337)
	CM-SRS.M1P	1SVR740840R0600	0.142 (0.313)
	CM-SRS.M2S	1SVR730840R0700	0.155 (0.342)
	CM-SFS.21S	1SVR730760R0400	0.150 (0.331)
	CM-SFS.21P	1SVR740760R0400	0.139 (0.306)
	CM-SFS.22S	1SVR730760R0500	0.158 (0.348)

S: screw connection

P: push-in connection

### Single-phase voltage monitoring relays

Selection table

		_															_
	Order number	1SVR730830R0300	1SVR740830R0300	1SVR730831R0300	1SVR740831R0300	1SVR730831R1300	1SVR740831R1300	1SVR730830R0400	1SVR740830R0400	1SVR730831R0400	1SVR740831R0400	1SVR730831R1400	1SVR740831R1400	1SVR730830R0500	1SVR740830R0500	1SVR730750R0400	1SVR740750R0400
	Туре	CM-ESS.1S	CM-ESS.1P	CM-ESS.1S	CM-ESS.1P	CM-ESS.1S	CM-ESS.1P	CM-ESS.2S	CM-ESS.2P	CM-ESS.2S	CM-ESS.2P	CM-ESS.2S	CM-ESS.2P	CM-ESS.MS	CM-ESS.MP	CM-EFS.2S	CM-EFS.2P
Rated control supply voltage U <sub>s</sub>																	
24 - 240 V AC/DC																	
110 - 130 V AC				•	•						•						
220 - 240 V AC							•										
Measuring ranges AC/DC					,												
3 - 30 V			•	•			•				•					•	
6 - 60 V			•	•	•	•	•				•		•		•	•	
30 - 300 V			•	•	•	•	•				•		•		•	•	
60 - 600 V			•	•	•		•				•					•	
Monitoring function																	
Over- or undervoltage			•	•							•						
Windows voltage monitoring																•	-
Latching														sel	sel	sel	sel
Open-circuit or closed-circuit principle														sel	sel	sel	sel
Timing functions for tripping delay																	
ON-delay, 0.1 - 30 s								adj									
ON- or OFF-delay, 0.1 - 30 s																sel	sel
Output																	
c/o contact		1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2
Connection type																	
Push-in terminals																	
Double-chamber cage connection terminal	s			•		•								•		•	

adj: adjustable sel: selectable

### Single-phase voltage monitoring relays

### Ordering details



CM-ESS.MP



CM-EFS.2

### Description

The CM range voltage monitoring relays provide reliable monitoring of voltages, as well as the detection of phase loss in single-phase mains.

### Ordering details

Description	Туре	Order code	Weight (1 pc)
			kg (lb)
See selection table	CM-ESS.1S	1SVR730830R0300	0.135 (0.298)
		1SVR730831R0300	0.164 (0.362)
		1SVR730831R1300	0.164 (0.362)
	CM-ESS.1P	1SVR740830R0300	0.126 (0.278)
		1SVR740831R0300	0.155 (0.342)
		1SVR740831R1300	0.155 (0.342)
	CM-ESS.2S	1SVR730830R0400	0.153 (0.337)
		1SVR730831R0400	0.181 (0.399)
		1SVR730831R1400	0.181 (0.399)
	CM-ESS.2P	1SVR740830R0400	0.142 (0.313)
		1SVR740831R0400	0.170 (0.375)
		1SVR740831R1400	0.170 (0.375)
	CM-ESS.MS	1SVR730830R0500	0.154 (0.340)
	CM-ESS.MP	1SVR740830R0500	0.143 (0.320)
	CM-EFS.2S	1SVR730750R0400	0.157 (0.346)
	CM-EFS.2P	1SVR740750R0400	0.146 (0.322)

S: screw connection P: push-in connection

Туре		CM-SRS.1		CM-SRS	.2	CM-SRS.M		CM-SFS.2			
Input circuit - Supply circuit		A1-A2				·					
Rated control supply	A1-A2	110-130 V AC									
voltage U₅	A1-A2	220-240 V AC									
	A1-A2	24-240 V AC/DC									
Rated control supply voltage U <sub>s</sub>	tolerance	-15+10 %									
Rated frequency	50/60 Hz										
	50/60 Hz or I	DC									
Current / power consumption	see data she	ets									
Power failure buffering time	20 ms										
Transient overvoltage protection	Varistors										
Input circuit - Measuring circui	B1/B2/B3-C										
Monitoring function		over- or unde	ercurrent m	nonitori	ng configu	ırable		over- and under- current monitoring			
Measuring method		True RMS me	asuring pr	rinciple							
Measuring inputs		CM-SxS.x1				CM-SxS.x2					
	Terminal connection	B1-C	B2-C		33-C	B1-C	B2-C	В3-С			
	Measuring ranges AC/DC	3-30 mA	10-100 r	mA (	0.1-1 A	0.3-1.5 A	1-5 A	3-15 A <sup>1)</sup>			
	Input resistance	3.3 Ω	1 Ω	(	0.1 Ω	0.05 Ω	0.01 Ω	0.0025 Ω			
	Pulse overload capacity t< 1 s	500 mA	1 A		10 A	15 A	50 A	100 A			
	Continuous capacity	50 mA	150 mA		1.5 A	2 A	7 A	17 A			
Threshold value(s)		adjustable within the indicated measuring range									
Setting accuracy of threshold va	alue	6 % of full-scale value									
Hysteresis related to the thresh	old value	3-30 % adjustable 5 % fixed									
Measuring signal frequency ran	ge	DC / 15 Hz - 2 kHz									
Rated measuring signal frequer	ncy range	DC / 50-60 Hz									
Maximum response time		AC: 80 ms / DC: 120 ms									
Accuracy within the control sup	ply voltage tolerance	ΔU ≤ 0.5 %									
Accuracy within the temperatur	e range	ΔU ≤ 0.06 % / °C									
Timing circuit											
Start-up delay T <sub>s</sub>		none				0 or 0.1-30 s	adjustab	ole			
Tripping delay T <sub>v</sub>		none	C	0 or 0.1-	30 s adjust	table					
Repeat accuracy (constant para	meters)	±0.07 % of fu	ull scale								
Accuracy within the control sup	ply voltage tolerance	-		∆t ≤ 0.5	%						
Accuracy within the temperatur	-		Δt ≤ 0.06	5 % / °C							
Indication of operational state	s										
Control supply voltage	U/T: green LED	$\begin{array}{c} \square \square \square \text{: start-up delay } T_s \text{ active,} \\ \square \square \square \text{: tripping delay } T_v \text{ active} \end{array}$									
Measured value	: overcurrent,										
Relay status	R: yellow LED	☐☐: relay ☐☐☐: relay ☐☐☐: relay	-	l, active	latching fu	ınction					

Туре			CM-SRS.1	CM-SRS.2	CM-SRS.M	CM-SFS.2				
Output circuit	ts		11(15)-12(16)/14(18	11(15)-12(16)/14(18), 21(25)-22(26)/24(28) - Relays						
Kind of output	t		1 c/o contact	2 c/o contacts		1x2 c/o contacts or 2x1 c/o contact configurable				
Operating principle		open-circuit principle	e <sup>2)</sup>	open- or closed- configurable <sup>2)</sup>	-circuit principle					
Contact mater	rial		AgNi							
Minimum swit	ching voltage / m	inimum switching current	24 V / 10 mA							
Maximum swi	tching voltage / m	naximum switching current	250 V AC / 4 A AC							
•	onal voltage U <sub>e</sub>	AC-12 (resistive) at 230 V	4 A							
and rated ope	rational	AC-15 (inductive) at 230 V	3 A							
current I <sub>e</sub>		DC-12 (resistive) at 24 V	4 A							
		DC-13 (inductive) at 24 V	2 A							
AC rating (UL 508)	((	Utilization category Control Circuit Rating Code)	В 300							
	ma	x. rated operational voltage	300 V AC							
	max. continuo	ous thermal current at B 300	5 A							
	max. makin	g/breaking apparent power (Make/Break) at B 300	3600/360 VA							
Mechanical life	etime		30x10 <sup>6</sup> switching cyc	les						
Electrical lifet	ime (AC-12, 230 V,	, 4 A)	0.1x10 <sup>6</sup> switching cyc	cles						
Max. fuse ratin	g to achieve short	-circuit n/c contact	6 A fast-acting	10 A fast-acting		6 A fast-acting				
protection		n/o contact	10 A fast-acting	·						

<sup>(</sup>i) In case of measured currents > 10 A, lateral spacing has to be min. 10 mm
(ii) Open-circuit principle: output relay energizes if the measured value exceeds ☑ / falls below ☒ the adjusted threshold value Closed-circuit principle: output relay de-energizes if measured value exceeds ☑ / falls below ☒ the adjusted threshold value

Туре		CM-SRS.1	CM-SRS.2	CM-SRS.M	CM-SFS.2
General data			,	,	'
MTBF		on request			
Duty cycle		100 %			
Dimensions		see dimensiona	l drawings		
Mounting		DIN rail (IEC/EN	60715), snap-on mour	nting without any tool	
Mounting position		any			
Minimum distance to other un	its	-	at measured current >	10 A	
Material of housing		UL 94 V-0			
Degree of protection	housing / terminals	IP50 / IP20			
Electrical connection					
Connecting		Screw connecti	on technology	Easy Connect Te	chnology (Push-in)
capacity	fine-strand with(out) wire end ferrule		(1 x 20-14 AWG)	2 x 0.5-1.5 mm² (	
		1 x 0.5-4 mm <sup>2</sup> (1 2 x 0.5-2.5 mm <sup>2</sup>	x 20-12 AWG)	2 x 0.5-1.5 mm² (	2 x 20-16 AWG)
Stripping length		8 mm (0.32 in)	•	I	
Tightening torque		0.6-0.8 Nm (7.08	3 lb.in)	-	
Environmental data				1	
Ambient temperature range	operation /	-20+60 °C /			
	storage	-40+85 °C			
Damp heat (IEC 60068-2-30)		55 °C, 6 cycles			
Vibration (sinusoidal)		class 2			
Shock		class 2			
Isolation data					
Rated insulation voltage	supply /	600 V			
	measuring circuit / output				
	supply / output 1/2				
Rated impulse withstand voltage U <sub>imp</sub>	supply /measuring circuit / output				
	supply / output 1/2				
Pollution degree		3			
Overvoltage category		Ш			
Standards / Directives					
Standards		IEC/EN 60255-2	27, IEC/EN 60947-5-1		
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
Electromagnetic compatibility	t <u>y</u>				
Interference immunity to		IEC/EN 61000-6	5-2		
electrostatic discharge	IEC/EN 61000-4-2				
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3			
electrical fast transient / bu	urst IEC/EN 61000-4-4	level 3			
surge	IEC/EN 61000-4-5	level 3			
conducted disturbances, in radio-frequency fields	duced by IEC/EN 61000-4-6	level 3			
Interference emission		IEC/EN 61000-6	5-3		
high-frequency radiated	IEC/CISPR 22; EN 55022	Class B			
high-frequency conducted	IEC/CISPR 22; EN 55022	Class B			

### Single-phase voltage monitoring relays

Туре		CM-ESS.1	CM-ESS.2	CM-ESS.M	CM-EFS.2			
Input circuit - Supply circuit		A1-A2	'	<u>'</u>	'			
Rated control supply voltage U <sub>s</sub>	A1-A2	110-130 V AC	,					
	A1-A2	220-240 V AC						
	A1-A2	24-240 V AC/DC						
Rated control supply voltage U <sub>s</sub> t	olerance	-15+10 %						
Rated frequency	AC versions	50/60 Hz						
	50/60 Hz or DC							
Current / power consumption		see data sheet						
Power failure buffering time		20 ms						
Transient overvoltage protection	1	varistors						
Input circuit - Measuring circuit		B-C						
Monitoring function		over- or undervol configurable	tage monitoring		over- and under- voltage monitoring configurable			
Measuring method		True RMS measur	ring principle					
Measuring		CM-ExS						
inputs	Terminal connection	B-C	B-C	B-C	B-C			
	Measuring range AC/DC	3-30 V	6-60 V	30-300 V	60-600 V			
	Input resistance	600 kΩ	600 kΩ	600 kΩ	600 kΩ			
•	Pulse overload capacity t < 1 s	800 V	800 V	800 V	800 V			
	Continuous capacity	660 V	660 V	660 V	660 V			
Threshold value(s)		adjustable withir	the indicated meas	uring range				
Tolerance of the adjusted thresh	old value	6 % of full-scale value						
Hysteresis related to the thresho	old value	3-30 % adjustabl	e		5 % fixed			
Measuring signal frequency rang	e	DC / 15 Hz - 2 kHz						
Rated measuring signal frequenc	cy range	DC / 50-60 Hz						
Maximum response time		AC: 80 ms / DC: 1	.20 ms					
Accuracy within the control supp	ly voltage tolerance	$\Delta U \le 0.5 \%$						
Accuracy within the temperature	range	$\Delta U \leq 0.06 \% / ^{\circ}C$						
Transient overvoltage protection	1	Varistors						
Timing circuit								
Delay time T <sub>V</sub>		none	0 or 0.1-30 s ad	ljustable	'			
Repeat accuracy (constant paran	neters)	±0.07 % of full so	ale value					
Accuracy within the control supp	ly voltage tolerance	-	$\Delta t \leq 0.5 \%$					
Accuracy within the temperature	range	-	$\Delta t \leq 0.06 \% / ^{\circ}$	С				
Indication of operational states	i							
Control supply voltage	U/T: green LED	: control s	upply voltage applied delay T <sub>V</sub> active	d				
Measured value	U: red LED	covervoltage,						
Relay status	☐ : relay energized, no latching function ☐☐☐ : relay energized, active latching function ☐☐☐ : relay de-energized, active latching function							

#### \_

### Single-phase voltage monitoring relays

Туре			CM-ESS.1	CM-ESS.2	CM-ESS.M	CM-EFS.2
Output circuit	ts				,	'
Kind of output	t		1 c/o contact	2 c/o contacts		1x2 c/o contacts or 2x1 c/o contact configurable
Operating principle			open-circuit principle	e <sup>1)</sup>	open- or closed-circo configurable <sup>1)</sup>	uit principle
Contact mater	rial		AgNi			
Minimum swit	ching voltage / m	inimum switching current	24 V / 10 mA			
Maximum swi	tching voltage / n	naximum switching current	250 V AC / 4 A AC			
Rated operation		AC-12 (resistive) at 230 V	4 A			
U <sub>e</sub> and rated o current I <sub>e</sub>	perational	AC-15 (inductive) at 230 V	3 A			
current I <sub>e</sub>		DC-12 (resistive) at 24 V	4 A			
		DC-13 (inductive) at 24 V	2 A			
AC rating (UL 508)	(	Utilization category Control Circuit Rating Code)	В 300			
	ma	ax. rated operational voltage	300 V AC			
	max. continu	ous thermal current at B 300	5 A			
	max. makin	ig/breaking apparent power (Make/Break) at B 300	3600/360 VA			
Mechanical life	etime		30x10 <sup>6</sup> switching cyc	les		
Electrical lifet	ime	AC-12, 230 V, 4 A	0.1x10 <sup>6</sup> switching cyc	cles		
Max. fuse ratir	5	n/c contact	6 A fast-acting	10 A fast-acting		6 A fast-acting
short-circuit p	protection	n/o contact	10 A fast-acting			

### Single-phase voltage monitoring relays

Туре		CM-ESS.1	CM-ESS.2	CM-ESS.M	CM-EFS.2
General data			·	· · · · · · · · · · · · · · · · · · ·	·
MTBF		on request			,
Duty cycle		100%			
Dimensions		see dimensional	drawings		
Mounting		DIN rail (IEC/EN 6	50715), snap-on mou	unting without any tool	
Mounting position		any			
Minimum distance to other units	vertical / horizontal	not necessary / n	ot necessary		
Material of housing		UL 94 V-0	<del>-</del>		
Degree of protection	housing / terminals	IP50 / IP20			
Environmental data					
Ambient temperature ranges	operation	-20+60 °C			
· -	storage	-40+85 °C			
Damp heat, cyclic (IEC/EN 60068-2-30	<u> </u>	55 °C, 6 cycle			
Vibration, sinusoidal		class 2			
Shock		class 2			
Electrical connection					
Wire size		Screw connectio	n technology	Easy Connect Te	chnology (Push-in)
fine-strand with	(out) wire end ferrule		1 x 18-14 AWG)	2 x 0.5-1.5 mm² (i	
	rigid	1 x 0.5-4 mm <sup>2</sup> (1 x 0.5-2.5 mm <sup>2</sup> (2	(20-12 AWG)	2 x 0.5-1.5 mm² (i	2 x 20-16 AWG)
Stripping length		8 mm (0.32 in)			
Tightening torque		0.6-0.8 Nm (7.08	lb.in)	-	
Isolation data			1		
Rated insulation voltage	supply / measuring circuit / output	600 V			
	supply / output 1/2	250 V			
Rated impulse withstand voltage U <sub>imp</sub>	supply / measuring circuit / output	6 kV 1.2/50 μs			
	supply / output 1/2	4 kV 1.2/50 μs			
Pollution degree		3			
Overvoltage category		III			
Standards / Directives		•		,	
Product standard		IEC/EN 60255-27	, IEC/EN 60947-5-1		
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
Electromagnetic compatibility					
Interference immunity to		IEC/EN 61000-6-	2		
electrostatic discharge	IEC/EN 61000-4-2	level 3			
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3			
electrical fast transient / burst	IEC/EN 61000-4-4	level 3			
surge	IEC/EN 61000-4-5	level 3			
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3			
Interference emission		IEC/EN 61000-6-	3		
high-frequency radiated IEC	C/CISPR 22; EN 55022	class B			
high-frequency conducted IEC	C/CISPR 22; EN 55022	class B			

<sup>1)</sup> Open-circuit principle: output relay energizes if the measured value exceeds 🗷 / falls below 🖎 the adjusted threshold value Closed-circuit principle: output relay de-energizes if measured value exceeds 🗷 / falls below 🖎 the adjusted threshold value

### Technical diagrams

#### \_

### Connection diagram

### CM-SRS.1x, CM-SRS.2x

A1	11 <sub>15</sub>	С	
B1	B2	B3	
B1 B2 E	33 1	1 <sub>15</sub>	
C			
14 <sub>18</sub>	12 <sub>16</sub>	A2	300036330460006

A1	11 <sub>15</sub>	21 <sub>25</sub>		
B1	B2	B3		
B1 B2 E	33 11 <sub>15</sub>	21 <sub>25</sub>		
لللرإ	, J	J		
¹ <u>₩</u>	}-/- <sub> </sub> -	7/		
A1 A2 12 <sub>16</sub> 14 <sub>18</sub> 22 <sub>26</sub> 24 <sub>28</sub>				
14 <sub>18</sub>	12 <sub>16</sub>	С		
24 <sub>28</sub>	2226	A2		


A1-A2	Control supply voltage
B1-C	Measuring range 1: 3-30 mA or 0.3-1.5 A
B2-C	Measuring range 2: 10-100 mA or 1-5 A
B3-C	Measuring range 3: 0.1-1 A or 3-15 A
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open-circuit principle

#### CM-SRS.Mx

A1	11 <sub>15</sub>	21 <sub>25</sub>		
B1	B2	B3		
B1 B2 E	33 11 <sub>15</sub>	21 <sub>25</sub>		
A1 A2 12 <sub>16</sub> 14 <sub>18</sub> 22 <sub>26</sub> 24 <sub>28</sub>				
14 <sub>18</sub>	12 <sub>16</sub>	С		
24 <sub>28</sub>	2226	A2		

A1-A2	Control supply voltage
B1-C	Measuring range 1: 3-30 mA or 0.3-1.5 A
B2-C	Measuring range 2: 10-100 mA or 1-5 A
B3-C	Measuring range 3: 0.1-1 A or 3-15 A
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open- or closed circuit principle

### CM-SFS.2x



A1-A2	Control supply voltage
B1-C	Measuring range 1: 3-30 mA or 0.3-1.5 A
B2-C	Measuring range 2: 10-100 mA or 1-5 A
В3-С	Measuring range 3: 0.1-1 A or 3-15 A
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open- or closed circuit principle

### CM-SRS.2x

A1	11 <sub>15</sub>	21 <sub>25</sub>			
B1	B2	B3			
B1 B2 E	33 11 <sub>15</sub>	21 <sub>25</sub>			
		22 <sub>26</sub> 24 <sub>28</sub>	CPC3E330EE000E		
14 <sub>18</sub>	12 <sub>16</sub>	С	1		
14 <sub>18</sub> 24 <sub>28</sub>	22 <sub>26</sub>	A2	1		

A1-A2	Control supply voltage
B1-C	Measuring range 1: 3-30 mA or 0.3-1.5 A
B2-C	Measuring range 2: 10-100 mA or 1-5 A
B3-C	Measuring range 3: 0.1-1 A or 3-15 A
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open- or closed circuit principle

### **DIP switch functions**

### CM-SRS.1x, CM-SRS.2x

Position	2 1		١.,
ON †		4	52272F0005
OFF		<del>/-</del>	CDC252

1 ON Undercurrent monitoring OFF Overcurrent monitoring

OFF = Default

### CM-SRS.Mx

Position	4	3	2	1	2
ON †			closed	4	2252273F0005
OFF		M	open	1	2CDC252

1	ON	Undercurrent
	OFF	monitoring
	OFF	Overcurrent
		monitoring
2	ON	Closed-circuit
		principle
	OFF	Open-circuit
		principle
_		principle
3	ON	Latching function
		activated
	OFF	Latching function
		•
0	E - Defa	not activated
OF	F = Defa	ult

### CM-SFS.2x

Position	4	3	2	1	r2
ON †	2x1 c/o		closed		52274F0005
OFF	1x2 c/o		open	$\boxtimes$	2CDC252

1	ON OFF	OFF-delay ON-delay
	OFF	ON-delay
2	ON	Closed-circuit
		principle
	OFF	Open-circuit
		principle
3	ON	Latching function
		activated
	OFF	Latching function
		not activated
4	ON	2x1 c/o contact
	OFF	1x2 c/o contacts
OF	F = Defa	ault

### CM-SRS.2x

Position	4	3	2	1	١,,
ON †			closed	+	273 F0005
OFF			open	+	2CDC252

1	ON OFF	Undercurrent monitoring Overcurrent monitoring
2	ON OFF	Closed-circuit principle Open-circuit principle
3	ON	Latching function activated
	OFF	Latching function not activated
OFF = Default		

\_


### Single-phase voltage monitoring relays

### Technical diagrams

\_

### **Connection diagram**

### CM-ESS.1, CM-ESS.2



A1	11 <sub>15</sub>	21 <sub>25</sub>	
В			
В	11 <sub>15</sub>	21 <sub>25</sub>	
¢- <del></del>			١.
	12 <sub>16</sub> 14 <sub>18</sub>	$22_{26}  24_{28}$	
14 <sub>18</sub>	12 <sub>16</sub>	С	
24 <sub>28</sub>	2226	A2	1

A1-A2	Control supply voltage
B-C	Measuring ranges AC/DC: 3-30 V; 6-60 V; 30-300 V; 60-600 V
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open-circuit principle

### CM-EFS.2

A1	11 <sub>15</sub>	21 <sub>25</sub>	
В			
В	11 <sub>15</sub>	21 <sub>25</sub>	
1 1	- 1		
C-	} <i>_/</i>	- <i>-</i> / .	
			0005
A1 A2	12 <sub>16</sub> 14 <sub>18</sub>	$22_{26}  24_{28}$	2CDC252207F0005
14 <sub>18</sub>	12 <sub>16</sub>	С	2252
24 <sub>28</sub>	22 <sub>26</sub>	A2	2CD

A1-A2	voltage
B-C	Measuring ranges AC/DC: 3-30 V; 6-60 V; 30-300 V; 60-600 V
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open- or closed

### CM-ESS.M

A1	11 <sub>15</sub>	21 <sub>25</sub>	
В			
В	11 <sub>15</sub>	21 <sub>25</sub>	
	1		
C-	} <i>_/</i>	- <i>-</i> / .	
			3000
		$22_{26} 24_{28}$	SCIPCSESSOZEDODE
14 <sub>18</sub>	12 <sub>16</sub>	С	6367
24 <sub>28</sub>	22 <sub>26</sub>	A2	2

A1-A2	Control supply voltage
B-C	Measuring ranges AC/DC: 3-30 V; 6-60 V 30-300 V; 60-600 V
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub> 21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	Output contacts - open- or closed circuit principle

### **DIP** switch functions

### CM-ESS.1, CM-ESS.2

Position	2	1	2
ON †		$\rightarrow$	2252275F0005
OFF		<del>/</del>	2CDC252

1 ON Undervoltage monitoring
OFF Overvoltage monitoring

OFF = Default

### CM-EFS.2

Position	4	3	2	1	۱
ON †	2x1 c/o		closed		20000
OFF	1x2 c/o		open	X	70000000

1	ON OFF	ON-delay OFF-delay
2	ON	Closed-circuit principle
	OFF	Open-circuit principle
3	ON	Latching function
	OFF	Latching function not activated
4	ON	2x1 c/o contact
	OFF	1x2 c/o contacts
OFF = Default		

### CM-ESS.M

Position	4	3	2	1	2
ON †			closed	$\rightarrow$	52276F0005
OFF		M	open	<b>✓</b> √	2CDC252


1	ON	Undervoltage monitoring
	OFF	Overvoltage monitoring
2	ON	Closed-circuit principle
	OFF	Open-circuit principle
3	ON	Latching function activated
	OFF	Latching function not activated
^-	r - D-4	


### Function diagrams

#### CM-SRS.1x and CM-SRS.2x


If the measured value exceeds resp. drops below the adjusted threshold value, the output relay(s) energize(s): on the CM-SRS.1x - immediately, on the CM-SRS.2x - after the set tripping delay  $T_{V}$ . If the measured value exceeds resp. drops below the threshold value plus resp. minus the adjusted hysteresis, the output relay(s) de-energize(s). The hysteresis is adjustable within a range of 3-30 % of the threshold value.

CM-SRS.1x






#### Undercurrent monitoring →




#### CM-SRS.2x

#### Overcurrent monitoring 🗲



### Undercurrent monitoring $\overline{\succeq}$



\_

### Single-phase monitoring relays


### Function diagrams

#### CM-SRS.Mx


If the measured value exceeds resp. drops below the adjusted threshold value before the set start-up delay  $T_s$  is complete, the output relays do not change their actual state. If the measured value exceeds resp. drops below the adjusted threshold value when  $T_s$  is complete, the tripping delay  $T_v$  starts. If  $T_v$  is complete and the measured value is still exceeding resp. below the threshold value plus resp. minus the set hysteresis, the output relays energize  $\Box$  / de-energize  $\Box$ .

If the measured value exceeds resp. drops below the threshold value minus resp. plus the set hysteresis and the latching function is not activated [A], the output relays de-energize [A] / energize [A]. With activated latching function [A] the output relays remain energized [A] and de-energize only when the supply voltage is interrupted / the output relays remain de-energized [A] and energize only when the supply voltage is switched off and then again switched on = Reset. The hysteresis is adjustable within a range of 3-30 % of the threshold value.


### Overcurrent monitoring 🖅 with latching 🗔




### Overcurrent monitoring 🗹 without latching 🔀



### 



### 




### Function diagrams

CM-SFS.2x

Current window monitoring 1x2 c/o contact □□□□

ON-delayed ⋈ without latching ⋈




### ON-delayed current window monitoring with parallel switching c/o contacts ::

If the measured value exceeds resp. drops below the adjusted threshold value before the set start-up delay  $T_{\text{S}}$  is complete, the output relays do not change their actual state.

If the measured value exceeds resp. drops below the adjusted threshold value when  $T_s$  is complete, the tripping delay  $T_v$  starts when  $\boxtimes$  is configured. If  $T_v$  is complete and the measured value is still exceeding resp. below the threshold value minus resp. plus the fixed hysteresis (5%), the output relays energize  $\boxtimes$  /de-energize  $\boxtimes$ . If the measured value exceeds resp. drops below the threshold value plus resp. minus the hysteresis and the latching function is not activated  $\boxtimes$ , the output relays de-energize  $\boxtimes$  / energize  $\boxtimes$ . With activated latching function  $\boxtimes$  the output relays remain energized  $\boxtimes$  and de-energize only when the supply voltage is interrupted / the output relays remain de-energized  $\boxtimes$  and energize only when the supply voltage is switched off and then again switched on = Reset.

# Current window monitoring 1x2 c/o contact □ OFF-delayed ■ without latching ☒



## OFF-delayed **c** current window monitoring with parallel switching c/o contacts [250]:

If the measured value exceeds resp. drops below the adjusted threshold value when the set start-up delay Ts is complete, the output relays energize / de-energize , when is configured, and remain in this position during the set tripping delay  $T_{\nu}$ . If the measured value exceeds resp. drops below the threshold value plus resp. minus the fixed hysteresis (5%) and the latching function is not activated  $\boxtimes$ , the tripping delay  $T_{\nu}$ starts. After completion of T<sub>v</sub>, the output relays de-energize / energize , provided that the latching function is not activated . With activated latching function . the output relays remain energized and de-energize only when the supply voltage is interrupted / the output relays remain de-energized and energize only when the supply voltage is switched off and then again switched on = Reset. When again is adjusted on the device, the functionality is equivalent to the one described above. In this case, instead of both output relays, only one output relay each will be switched.


">|" =  $11_{15}$ - $12_{16}$ / $14_{18}$ ; "<|" =  $21_{25}$ - $22_{26}$ / $24_{28}$ 


### Function diagrams

#### CM-ESS.1x and CM-ESS.2x


Depending on the configuration, the voltage monitoring relays CM-ESS.1 and CM-ESS.2 can be used for over-  $\Box$  or undervoltage monitoring  $\Box$  in single-phase AC and/or DC systems. The voltage to be monitored (measured value) is applied to terminals B-C. The devices work according to the open-circuit principle. If the measured value exceeds resp. drops below the adjusted threshold value, the output relay(s) energize(s): on the CM-ESS.1 - immediately, on the CM-ESS.2 - after the set tripping delay  $T_v$ . If the measured value exceeds resp. drops below the threshold value plus resp. minus the adjusted hysteresis, the output relay(s) de-energize(s). The hysteresis is adjustable within a range of 3-30 % of the threshold value.

CM-ESS.1x






#### Undervoltage monitoring →




#### CM-ESS.2x

#### Overvoltage monitoring 🗲



### Undervoltage monitoring **→**




### Function diagrams

#### CM-ESS.Mx


If the measured value exceeds resp. drops below the adjusted threshold value, the tripping delay  $T_v$  starts. If  $T_v$  is complete and the measured value is still exceeding resp. below the threshold value plus resp. minus the set hysteresis, the output relays energize  $\boxed{}$  / de-energize  $\boxed{}$ .

If the measured value exceeds resp. drops below the threshold value plus resp. minus the set hysteresis and the latching function is not activated [A], the output relays de-energize [A] / energize [A]. With activated latching function [A] the output relays remain energized [A] and de-energize only when the supply voltage is interrupted / the output relays remain de-energized [A] and energize only when the supply voltage is switched off and then again switched on = Reset. The hysteresis is adjustable within a range of 3-30 % of the threshold value.


### Overvoltage monitoring 🗺 without latching 🔀




### Overvoltage monitoring 🔀 with latching 🗀



### Undervoltage monitoring → without latching ►



### Undervoltage monitoring → with latching □




\_

### Single-phase monitoring relays


### Function diagrams

CM-EFS.2x

Voltage window monitoring 1x2 c/o contact □□□□□
ON-delayed ⋈ without latching ⋈



Voltage window monitoring 1x2 c/o contact ☑ ○ OFF-delayed ■ without latching ☒



# ON-delayed ⊠ voltage window monitoring with parallel switching c/o contacts :

If the measured value exceeds resp. drops below the adjusted threshold value, the tripping delay  $T_v$  starts, when  $\bowtie$  is configured. If  $T_v$  is complete and the measured value is still exceeding resp. below the threshold value minus resp. plus the fixed hysteresis (5%), the output relays energize  $\bowtie$  / de-energize  $\bowtie$ .

If the measured value exceeds resp. drops below the threshold value plus resp. minus the hysteresis and the latching function is not activated , the output relays de-energize , energize . With activated latching function the output relays remain energized and de-energize only when the supply voltage is interrupted / the output relays remain de-energized and energize only when the supply voltage is switched off and then again switched on = Reset.

## OFF-delayed **■■** voltage window monitoring with parallel switching c/o contacts **□** :

If the measured value exceeds resp. drops below the adjusted threshold value, the output relays energize  $\boxed{\phantom{a}}$  / de-energize  $\boxed{\phantom{a}}$ , when  $\boxed{\phantom{a}}$  is configured, and remain in this position during the set tripping delay  $T_v$ .

If the measured value exceeds resp. drops below the threshold value plus resp. minus the fixed hysteresis (5%) and the latching function is not activated  $\bowtie$ , the tripping delay  $T_v$  starts.

After completion of T<sub>v</sub>, the output relays de-energize / energize /, provided that the latching function is not activated ... With activated latching function the output relays remain energized and de-energize only when the supply voltage is interrupted / the output relays remain de-energized and energize only when the supply voltage is switched off and then again switched on = Reset. When is adjusted on the device, the functionality is equivalent to the one described above. In this case, instead of both output relays, only one output relay each will be switched.

">U" =  $11_{15}$ - $12_{16}$ / $14_{18}$ ; "<U" =  $21_{25}$ - $22_{26}$ / $24_{28}$ 



# Three-phase monitoring relays Table of contents

106	Benefits and advantages
109	Function
110	Operating controls
112	Selection table - singlefunctional
113	Ordering details - singlefunctional
114	Selection table - multifunctional
115	Ordering details - multifunctional
116	Technical data
127	Technical diagrams
129	Function diagrams

# Three-phase monitoring relays

### Benefits and advantages



For the monitoring of voltages in a three-phase system or network, ABB's CM range contains a wide selection of powerful and compact devices. This product range includes voltage monitoring relays for phase sequence, phase loss, unbalance and monitoring of over- and under voltage from 160 V to 820 V.



Read the status of the relay at a glance: clear visualization of the device status via LEDs. Easy to adjust with rotary wheels and variants with push-in terminals make a quick and easy installation and setting possible.



All relays work reliably in environments with low temperatures down to -25°C. Additionally, the housing fulfills the UL 94 V-0 flammability standard requirements. Together with the vibration resistant push-in terminals, the relay is not only reliable no matter the environment temperature but is also durable to shock and vibration. Save time as retightening is no longer needed and enhance the reliability and safety not only for the equipment.



Like all devices from the measuring and monitoring portfolio, the three-phase monitoring relays are easily configurable via front facing potentiometers. Easy threshold configuration without calculation is accomplished by direct reading scales. For further configuration options, additional settings can be made via dip-switches, offering the flexibility to configure, for example, the working principle of the relays and the output configuration. The device can be set up before installation in the application and easy adjustments during the process are possible.

### Three-phase monitoring relays

## Benefits and advantages



#### Characteristics

- True RMS (TRMS) measuring principle
- Device for the use in mains with a frequency of 45-440 Hz and where harmonics are to be expected<sup>1)</sup>
- · Adjustable phase unbalance threshold value
- · Adjustable ON-delay/OFF-delay time
- · Powered by the measuring circuit
- 1 n/o contact, 1 or 2 c/o contacts
- LEDs for the indication of operational states

- Multifunctional and singlefunctional devices
- · Phase failure detection
- · Phase sequence monitoring
- Over- and undervoltage monitoring (fixed or adjustable)
- Wide-range operating voltage guarantees world-wide operation
- · Various approvals and marks

(1) devices CM-MPS.23 and CM-MPS.43



#### **Applications**

- Control for connection of moving equipment (e.g. air conditioning compressors, refrigerated trucks and containers, and cranes)
- Control against reverse motor operation (lifting, handling, elevators, escalators, etc.)
- Control of sensitive three-phase supplies
- Overheating of the motor due to asymmetrical voltage
- Protection of a plant against destruction due to overvoltage
- Direction of rotation of the drive









## **Function**

#### Phase unbalance monitoring

If the supply by the three-phase system is unbalanced due to an uneven distribution of the load, the motor will convert a part of the energy into reactive power. This energy gets lost unexploited; also the motor is exposed to higher thermal stress. Other thermal protection devices fail to detect continuing unbalances, which can lead to damage or destruction of the motor. The CM range three-phase monitors with phase unbalance monitoring can reliably detect this critical situation.

#### Phase sequence

Changing the phase sequence during operation or a wrong phase sequence prior to startup causes a change of the rotational direction of the connected device. Generators, pumps or fans rotate in the wrong direction and the installation is no longer working properly. In particular, for moveable equipment, such as construction machinery, phase sequence detection prior to the startup process is highly reasonable.

#### Phase loss

In case of phase loss, undefined stats of the installation are likely to occur; e.g. the startup process of motors is disturbed. All three-phase monitors of the ABB CM range detect a phase loss as soon as the voltage of one phase drops below 60 % of its nominal value.

#### Voltage monitoring


All electric devices can be damaged when operated continuously in a network with out-of-range voltages. For example, safe starting is not ensured in case of undervoltage. Also, the switching state of a contactor is not clearly defined when operated in a "forbidden" voltage range. This can lead to undefined states of the installation and cause damage or destruction of valuable parts.

#### Selectable phase sequence monitoring

The phase sequence monitoring can be switched off by means of a rotary switch or a DIP switch. This enables monitoring of three-phase mains where phase sequence is not relevant for the application, for example in case of motors with forward and reverse rotation, heating applications, etc.


#### Automatic phase sequence correction

The automatic phase sequence correction is activated by means of a DIP switch. With activated phase sequence correction, it is ensured that for any non-fixed or portable equipment, e.g. construction machinery, the correct phase sequence is always applied to the input terminals of the load. For details regarding the wiring, please see function description / diagrams.




# Operating controls

## S-range housing



# Operating controls

## N-range housing



Selection table - singlefunctional

														_			_					
	Order number 1SVR550881R9400	1SVR550882R9500	1SVR550870R9400	1SVR550871R9500	1SVR550824R9100	1SVR550826R9100	1SVR730824R9300	1SVR740824R9300	1SVR730784R2300	1SVR740784R2300	1SVR730784R3300	1SVR740784R3300	1SVR730794R1300	1SVR740794R1300	1SVR730794R3300	1SVR740794R3300	1SVR730794R2300	1SVR740794R2300	1SVR730774R1300	1SVR740774R1300	1SVR730774R3300	1SVR740774R3300
	1R9	2R9	OR9	1R9	4R9	6R9	4R9	4R9	4R2	4R2	4R3	4R3	4R1	4R1	4R3	4R3	4R2	4R2	4R1	4R1	4R3	4R3
	88	988	)87	780	382	382	382	385	078,	787	078	787	079,	729	079,	729	979,	7670	717	77.70	7770	77.70
	55(	55(	55(	55(	250	550	730	740	730	740	730	740	730	740	730	740	730	740	730	740	730	740
<del>-</del>	Urder number 1SVR550881R	SVR																				
	>  ∺	7	H	H	H	ä	H	H														
						N	S	_	CM-PSS.31S	CM-PSS.31P	CM-PSS.41S	CM-PSS.41P	CM-PVS.31S	CM-PVS.31P	CM-PVS.41S	CM-PVS.41P	CM-PVS.81S	CM-PVS.81P	CM-PAS.31S	CM-PAS.31P	CM-PAS.41S	CM-PAS.41P
	BE	BE	\ K	NE NE	표	CM-PFE.2	CM-PFS.S	CM-PFS.P	SS.	SS.	SS.	SS.	VS.	VS.	VS.	VS.	VS.	VS.	AS.	AS.	AS.	AS.
	Iype CM-PBE	CM-PBE	CM-PVE	CM-PVE	CM-PFE	7- P	4-P	7-	7- P	7- P	7-	7-P	4- P	4-P	<u>γ</u>	7- P	4-P	4-P	7- P	<u>γ</u>	<u>γ</u>	4-P
	<u> </u>	້ ວົ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ	ΰ
Rated control supply voltage U <sub>s</sub>																						
Phase to phase																						
160-300 V AC													•	•						•		
200-400 V AC																						
200-500 V AC							-	•														
208-440 V AC					•																	
300-500 V AC															•	•						
320-460 V AC			-																			
380 V AC																						
380-440 V AC	=																					
400 V AC																						
Phase to neutral																						
185-265 V AC																						
220-240 V AC																						
Rated frequency																						
50/60 Hz	┰																					
Suitable for monitoring																						
Single-phase mains																						
Three-phase mains	-	-		•	•	•	•	•	•		•			•	•	•	•	•		•	•	
Monitoring function																						
Phase failure								•														
Phase sequence							•	•	sel			•										
Overvoltage	İ			•					•		•		•	•	•	•	•					
Undervoltage				•					•		•			•	•	•	•					
Unbalance																				•		
Neutral <sup>1)</sup>																						
Thresholds	•																					
adjustable (adj) or fixed (fix)	fix	fix	fix	fix	fix	fix	fix	fix	fix	fix	fix	fix	adj									
Timing functions for tripping delay																						_
ON delay							fix	fix											sel	sel	sel	sel
On and OFF delay	fix	fix	fix	fix	fix	fix			adj													
Connection type																						_
Push-in terminals	Т													•				•				
Double-chamber cage connection terminals																					•	
2 2 2 2 2 3 2 2 2 2 2 2 2 2 2 2 2 2 2 2			_	_				_	_		_		_	_	<u> </u>		_		_			

<sup>(1)</sup> The external conductor voltage towards the neutral conductor is measured.

adj: adjustable sel: selectable fix: fixed

#### \_\_\_\_

## Three-phase monitoring relays

## Ordering details - singlefunctional



CM-PBE



CM-PSS.41P



CM-PAS.31P

#### Description

The three-phase monitoring relays are designed for use in three-phase mains for monitoring the phase parameters like phase sequence, phase failure, over- and undervoltage, as well as phase unbalance.

#### Ordering details

Characteristics	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-PBE	1SVR550881R9400	0.08 (0.17)
	CM-PBE	1SVR550882R9500	0.08 (0.17)
	CM-PVE	1SVR550870R9400	0.08 (0.17)
	CM-PVE	1SVR550871R9500	0.08 (0.17)
	CM-PFE	1SVR550824R9100	0.08 (0.17)
	CM-PFE.2	1SVR550826R9100	0.067 (0.147)

Characteristics	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-PFS.S	1SVR730824R9300	0.127 (0.280)
	CM-PFS.P	1SVR740824R9300	0.119 (0.262)
	CM-PSS.31S	1SVR730784R2300	0.132 (0.291)
	CM-PSS.31P	1SVR740784R2300	0.123 (0.271)
	CM-PSS.41S	1SVR730784R3300	0.132 (0.291)
	CM-PSS.41P	1SVR740784R3300	0.123 (0.271)
	CM-PVS.31S	1SVR730794R1300	0.141 (0.311)
	CM-PVS.31P	1SVR740794R1300	0.132 (0.291)
	CM-PVS.41S	1SVR730794R3300	0.139 (0.306)
	CM-PVS.41P	1SVR740794R3300	0.131 (0.289)
	CM-PVS.81S	1SVR730794R2300	0.136 (0.300)
	CM-PVS.81P	1SVR740794R2300	0.128 (0.282)
	CM-PAS.31S	1SVR730774R1300	0.133 (0.293)
	CM-PAS.31P	1SVR740774R1300	0.124 (0.273)
	CM-PAS.41S	1SVR730774R3300	0.132 (0.291)
	CM-PAS.41P	1SVR740774R3300	0.123 (0.271)

S: screw connection P: push-in connection

Selection table - multifunctional

					_													
Order number	1SVR730885R1300	1SVR740885R1300	1SVR730885R3300	1SVR740885R3300	1SVR730884R1300	1SVR740884R1300	1SVR730884R3300	1SVR740884R3300	1SVR730885R4300	1SVR740885R4300	1SVR730884R4300	1SVR740884R4300	1SVR750487R8300	1SVR760487R8300	1SVR750488R8300	1SVR760488R8300	1SVR750489R8300	1SVR760489R8300
	1PS.11S	CM-MPS.11P 1	CM-MPS.21S 1	CM-MPS.21P 1	CM-MPS.31S 1	CM-MPS.31P 1	CM-MPS.41S 1	CM-MPS.41P 1	CM-MPS.23S 1	CM-MPS.23P 1	CM-MPS.43S 1	CM-MPS.43P 1	CM-MPN.52S 1	CM-MPN.52P 1	CM-MPN.62S 1	CM-MPN.62P 1	CM-MPN.72S 1	CM-MPN.72P 1
9 2	Ϋ́	Ω̈́	Ϋ́	Ω̈́	Ϋ́	Ϋ́	Ϋ́	Ϋ́	Ω	Ϋ́	Ϋ́	Ϋ́	Ω̈́	Ω̈́	Ϋ́	Ω̈́	Ω̈́	Ω
Rated control supply voltage U <sub>s</sub>																		
Phase to phase																		
160-300 V AC																		
300-500 V AC							•	•				•						
350-580 V AC													•	•				
450-720 V AC																•		
530-820 V AC																	•	•
Phase to neutral	•																	
90-170 V AC																		
180-280 V AC																		
Rated frequency																		
50/60 Hz																		
50/60/400 Hz																		
Suitable for monitoring																		
Mains with harmonic content																		
Single-phase mains	•		•						=									
Three-phase mains	-								-	-	•			•		•	•	=
Monitoring function																		
Phase failure	•	•			-	-	-			•	•	•	•	•	•	•	•	-
Phase sequence	sel	adj																
Automatic phase sequence correction									adj									
Overvoltage	-		•		•	•	•	•	-	•	•	•	•	•	•	•	•	-
Undervoltage	-	•	•	-	•	•	•	-	-	•	•	•	•	•	•	•	-	-
Unbalance		-			-	-	-		-	-	•	-	•	•	•	-	-	-
Interrupted neutral monitoring 1)																		
Thresholds																		
Adjustable (adj)	adj																	
Timing functions for tripping delay																		
On- or OFF delay	adj																	
Connection type	_											1						
Push-in terminals	_		-			-		-	_			•		-		-		-
Double-chamber cage connection terminals																		

<sup>1)</sup> The relay detects by means of a phase unbalance the interruption of the neutral conductor. The external conductor voltage towards the neutral conductor is measured too.

adj: adjustable sel: selectable

## Ordering details - multifunctional



CM-MPS.23P



CM-MPN.52P

#### Description

The three-phase monitoring relays are designed for use in three-phase mains for monitoring the phase parameters, such as phase sequence, phase failure, over- and undervoltage, as well as phase unbalance.

#### Ordering details

Characteristics	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-MPS.11S	1SVR730885R1300	0.148 (0.326)
	CM-MPS.11P	1SVR740885R1300	0.137 (0.302)
	CM-MPS.21S	1SVR730885R3300	0.146 (0.322)
	CM-MPS.21P	1SVR740885R3300	0.135 (0.298)
	CM-MPS.31S	1SVR730884R1300	0.142 (0.313)
	CM-MPS.31P	1SVR740884R1300	0.133 (0.293)
	CM-MPS.41S	1SVR730884R3300	0.140 (0.309)
	CM-MPS.41P	1SVR740884R3300	0.132 (0.291)
	CM-MPS.23S	1SVR730885R4300	0.149 (0.328)
	CM-MPS.23P	1SVR740885R4300	0.138 (0.304)
	CM-MPS.43S	1SVR730884R4300	0.148 (0.327)
	CM-MPS.43P	1SVR740884R4300	0.137 (0.302)
	CM-MPN.52S	1SVR750487R8300	0.230 (0.507)
	CM-MPN.52P	1SVR760487R8300	0.226 (0.498)
	CM-MPN.62S	1SVR750488R8300	0.229 (0.505)
	CM-MPN.62P	1SVR760488R8300	0.225 (0.496)
	CM-MPN.72S	1SVR750489R8300	0.224 (0.494)
	CM-MPN.72P	1SVR760489R8300	0.220 (0.485)

 $<sup>\</sup>mathbf{S} : \mathsf{screw} \ \mathsf{connection}$ 

P: push-in connection

Туре		CM-PBE <sup>1)</sup>	CM-PBE	CM-PVE1)	CM-PVE	CM-PFE	CM-PFE.2	CM-PFS			
Input circuit - supply circuit		L1-L2-L3-N	L1-L2-L3	L1-L2-L3-N	L1-L2-L3	•		•			
Rated control supply voltage U	l <sub>s</sub> = measuring voltage	3x380- 440 V AC, 220-240 V AC	3x380- 440 V AC	3x320- 460 V AC, 185-265 V AC	3x320- 460 V AC	3x208- 440 V AC	3x200- 500 V AC				
Power consumption							13 mA / 9 VA	approx. 15 VA			
Rated control supply voltage U	I <sub>s</sub> tolerance	-15+15 % -15+10 %									
Rated frequency		50/60 Hz 50/60 Hz (-10+10 %) 50/60 Hz									
Duty time		100 %									
Input circuit - measuring circu	uit	L1-L2-L3-N	L1-L2-L3	L1-L2-L3-N	L1-L2-L3						
Monitoring functions	phase failure										
	phase sequence	-	-	-	-						
	over- / undervoltage	-	-			-	-	-			
	neutral		-		-	-	-	-			
Measuring ranges	easuring ranges		3x380- 440 V AC	3x320- 460 V AC, 185-265 V AC	3x320- 460 V AC	3x208- 440 V AC	3x200- 500 V AC				
Thresholds	$U_{min}$	0.6 x U <sub>N</sub>		fixed 185 V / 320 V	fixed 320 V	0.6 x U <sub>N</sub>					
	U <sub>max</sub>	-		fixed 265 V / 460 V	fixed 460 V	-					
Hysteresis related to the thres	hold value	fixed 5 % (release valu	e = 0.65 x U <sub>N</sub> )	fixed 5 %		-					
Measuring voltage frequency		50/60 Hz (-1	0 %+10 %)			50/60 Hz					
Response time		40 ms		80 ms		500 ms					
Accuracy within the temperatu	ire range	-		ΔU ≤ 0.06 %	/ °C						
Timing circuit											
Start-up delay t <sub>s</sub>		fixed 500 ms	s (±20 %)		_	fixed 500 r	ns				
Tripping t <sub>v</sub>	fixed 150 ms (±20 %)	5	at over-/ undervoltage fixed 500 ms ( $\pm$ 20 %)		fixed 500 r	ns	-				
Indication of operational stat	es										
Relay status	R: yellow LED	□ outp	ut relay energ	ized							
Fault message	F: red LED	LED Only CM-PFS: phase failure / phase sequence error									

Туре		·	CM-PBE <sup>1)</sup>	CM-PBE	CM-PVE <sup>1)</sup>	CM-PVE	CM-PFE	CM-PFE.2	CM-PFS			
Output circuit	:s		13-14				11-12/14		11 <sub>15</sub> -12 <sub>16</sub> / 14 <sub>18</sub> , 21 <sub>25</sub> -22 <sub>26</sub> / 24 <sub>28</sub>			
Kind of output			1 n/o conta	act			1 c/o contact		2 c/o contacts			
Operating pri	nciple		closed-circ	uit principle²	)							
Minimum swit Minimum swit	ching voltage / ching current		24 V / 10 m	ıA								
Maximum swi maximum swi	tching voltage / tching voltage		see data sh	neets								
•	onal voltage U <sub>e</sub>	AC-12 (resistive) 230 V	V 4 A									
•	ated operational AC-15 (inductive) 230		3 A									
current l <sub>e</sub>		DC-12 (resistive) 24 V	4 A									
		DC-13 (inductive) 24 V	2 A									
AC rating (UL 508)	Utilization	category (Control Circuit Rating Code)	B 300 pilot	duty, genera	l purpose 250	V, 4 A, cos ph	i 0.75					
	max.	rated operational voltage	300 V AC									
	max. continuo	us thermal current at B 300	5 A									
	max. m	aking/breaking apparent power at B 300	3600/360	VA								
Mechanical life	etime		30 x 10 <sup>6</sup> sw	itching cycle	s							
Electrical lifet	ime (AC-12, 230	V, 4 A)	0.1 x 10 <sup>6</sup> sw	vitching cycle	:S							
Max. fuse ratii	ng to achieve	n/c contact	10 A fast-a	cting			6 A fast-act	ing				
short-circuit p	rotection	n/o contact	10 A fast-a	cting								
Conventional	hermal current I	th					4 A					

Device with neutral monitoring: The external conductor voltage towards the neutral conductor is measured.
 Closed-circuit principle: Output relay is de-energized if the measured value exceeds/drops below the adjusted threshold.

Туре		CM-PBE <sup>1)</sup>	CM-PBE	CM-PVE <sup>1)</sup>	CM-PVE	CM-PFE	CM-PFE.2	CM-PFS
General data	,						,	
Duty cycle		100 %						
Dimensions		see dimens	sional drawin	gs				
Mounting			C/EN 60715)					
Mounting position		any	-,,					
Minimum distance to other unites	horizontal		rry			≥ 10 mm if temperatu rated oper currents >	re > 50 °C and ational	≥ 10 mm in case of continuous measuring voltage > 440 V
Degree of protection	housing / terminals	IP50 / IP20	)					
Electrical connection								
Connecting capacity	fine-strand with wire end ferrule fine-strand without wire end ferrule							Same as CM-PSS.31
	rigid	2 x 0.75-1.5	5 mm² (2 x 18	-16 AWG)				-
Stripping length	-	10 mm (0.3						Same as CM-PSS.31
Tightening torque		0.6-0.8 Nm						
Environmental data					,	1	1	
Ambient temperature range	operation / storage	-20+60 °C	/ -40+85 °C	2			1	
Climatic class		-				3K3		
Damp heat	IEC/EN 60068-2-30	40 °C, 93 %	RH, 4 days			-		
Damp heat, cyclic	IEC/EN 60068-2-30					6 x 24 h cy	cle, 55 °C, 95 %	RH
Vibration withstand	IEC/EN 60068-2-6	10-57 Hz: 0	).075 mm; 57-	150 Hz: 1 g		-		
Vibration, sinusoidal		-				class 2		
Shock		-				class 2		
Isolation data	I Maria de la companya della companya della companya de la companya de la companya della company						18	
Rated insulation voltage U <sub>i</sub>	between input, measuring and output circuits	400 V				-		
	input circuit / output circuit	-				600 V		
	output circuit 1 / output circuit 2	-						300 V
Rated impulse withstand voltage $U_{\text{imp}}$	between input, measuring and output circuits	4 kV / 1.2 -	50 μs			-		
	input circuit / output circuit	-				6 kV		
	output circuit 1 / output circuit 2	-						4 kV
Basic insulation	supply circuit / output circuit	-						600 V AC
Pollution degree		3						
Overvoltage category		III						
Standards / Directives								
Standards		IEC/EN 609	947-5-1			IEC/EN 60	255-27, IEC/EN	60947-5-1
Low Voltage Directive		2014/35/E	U					
EMC Directive		2014/30/E	:U					
RoHS Directive		2011/65/E	U					

Туре	<u> </u>	CM-PBE1)	CM-PBE	CM-PVE <sup>1)</sup>	CM-PVE	CM-PFE	CM-PFE.2	CM-PFS					
Electromagnetic compatibility				·		·	·	`					
Interference immunity to		IEC/EN 610	IEC/EN 61000-6-2										
electrostatic discharge	IEC/EN 61000-4-2	level 3 - 6 k	// 8 kV										
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 - 10 \	//m					level 3 - 10 V/m (1 GHz) 3 V/m (2 GHz) 1 V/m (2.7 GHz)					
electrical fast transient / burst	IEC/EN 61000-4-4	level 3 - 2 k	/ / 5 kHz										
surge	IEC/EN 61000-4-5	level 4 - 2 k\	/ L-L										
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3 - 10 \	J .										
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	-						class 3					
harmonics and interharmonics	IEC/EN 61000-4-13	-						class 3					
Interference emission		IEC/EN 610	00-6-3										
high-frequency radiated	IEC/CISPR 22, EN 55022	Class B											
high-frequency conducted	IEC/CISPR 22, EN 55022	Class B											

<sup>(1)</sup> Device with neutral monitoring: The external conductor voltage towards the neutral conductor is measured.

Туре	·	CM-PSS.31	CM-PSS.41	CM-PVS.31	CM-PVS.41	CM-PVS.81	CM-PAS.31	CM-PAS.41		
Input circuit = Measurin	g circuit	L1, L2, L3				-				
<del></del>	tage U <sub>s</sub> = measuring voltage		3x400 V AC	3x160- 300 V AC	3x300- 500 V AC	3x200- 400 V AC	3x160- 300 V AC	3x300- 500 V AC		
Rated control supply volt	tage U₅ tolerance	-15+10 %								
Rated frequency		50/60 Hz								
Frequency range		45-65 Hz								
Typical current / power o	consumption	25 mA / 18 VA (380 V AC)	25 mA / 18 VA (400 V AC)	25 mA / 10 VA (230 V AC)	25 mA / 18 VA (400 V AC)	19 mA / 10 VA (300 V AC)	25 mA / 10 VA (230 V AC)	25 mA /18 VA (400 V AC)		
Measuring circuit		L1, L2, L3								
Monitoring functions	Phase failure									
	Phase sequence	can be swite		_	_	_	_			
	Automatic phase sequence correction		-	-	-	-	-	-		
	Over- / undervoltage						-	-		
	Phase unbalance	-	-	-	-	-				
	Neutral	_	-	-	-	-	-	-		
Measuring range	Overvoltage	3x418 V AC	3x440 V AC	3x220- 300 V AC	3x420- 500 V AC	3x300- 400 V AC	-	-		
	Undervoltage	3x342 V AC	3x360 V AC	3x160- 230 V AC	3x300- 380 V AC	3x210- 300 V AC	-	-		
	Phase unbalance	-	-	-	-	-	2-25 % of av	-		
Thresholds	Overvoltage	fixed		adjustable v	within measu	ring range	-	-		
	Undervoltage	fixed		adjustable v	within measu	ring range	-	-		
	Phase unbalance (switch-off value)	-	-	-	-	-	adjust. with			
Tolerance of the adjusted	d threshold value	6 % of full-s	cale value							
Hysteresis related to	Over- / undervoltage	fixed 5 %					-			
the threshold value	Phase unbalance	-	-	-	-	-	fixed 20 %			
Maximum measuring cyc	cle time	100 ms								
Accuracy within the temp	perature range	ΔU ≤ 0.06 %	/ °C							
Measuring method		true RMS								
Timing circuit										
Start-up delay ts		fixed 200 m	S							
Tripping delay t <sub>v</sub>		ON- or OFF- 0; 0.1-30 s a	-				ON- delay 0; 0.1-30 s a	djustable		
Repeat accuracy (consta	nt parameters)	-	-	-	-	< ± 0.2 %	-	-		
Accuracy within the rate	d control supply voltage tolerance	Δt ≤ 0.5 %								
Accuracy within the temp	perature range	Δt ≤ 0.06 %	/ °C							
Indication of operations	al states									
				1 yellow LEI	D, 2 red LEDs					
		details see f	unction /-diagrams		operating mo		details see t	function /-diagrams		
Output circuits		15-16/18, 2								
Kind of output		relay, 2 x 1 c								
Operating principle		-	it principle <sup>1)</sup>							
Contact material	AgNi alloy, C	· · ·								
Minimum switching pow	er	24 V / 10 mA								
Maximum switching volt	age	see "Load limit curves"								

<sup>1)</sup> Closed-circuit principle: Output relay(s) de-energize(s) if measured value exceeds or falls below the adjusted threshold value

Туре	·	CM-PSS.31 CM-PSS.41 CM-PVS.31 C	CM-PVS.41 CM-PVS.81 CM-PAS.31 CM-PAS.41
Rated operational voltage U <sub>e</sub> and	AC-12 (resistive) 230 V	4 A	
rated operational current I <sub>e</sub>	AC-15 (inductive) 230 V	3 A	
	DC-12 (resistive) 24 V	4 A	
	DC-13 (inductive) 24 V	2 A	
AC rating (UL 508) (C	Utilization category ontrol Circuit Rating Code)	B 300	
max.	rated operational voltage	300 V AC	
max. continuou	is thermal current at B 300	5 A	
	max. making/breaking apparent power at B 300	3600/360 VA	
Mechanical lifetime		30 x 10 <sup>6</sup> switching cycles	
Electrical lifetime (AC-12, 230 V, 4	A)	0.1 x 10 <sup>6</sup> switching cycles	
Max. fuse rating to achieve	n/c contact	6 A fast-acting	
short-circuit protection	n/o contact	10 A fast-acting	
General data			
MTBF		on request	
Duty cycle		100%	
Dimensions		see dimensional drawings	
Mounting		DIN rail (IEC/EN 60715), snap-on mount	ting without any tool
Mounting position		any	
Minimum distance to other units	horizontal	10 mm (0.39 in) in case of continuous m	easuring voltages
		> 400 V	> 400 V - > 220 V > 400 V
Material of housing		UL 94 V-0	
Degree of protection	housing / terminals	IP50 / IP20	
Electrical connection			
Wire size		Screw connection technology	Easy Connect Technology (Push-in)
		1 x 0.5-2.5 mm <sup>2</sup> (1 x 18-14 AWG) 2 x 0.5-1.5 mm <sup>2</sup> (2 x 18-16 AWG)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 18-16 AWG)
	rigid	1 x 0.5-4 mm <sup>2</sup> (1 x 20-12 AWG) 2 x 0.5-2.5 mm <sup>2</sup> (2 x 20-14 AWG)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG)
Stripping length		8 mm (0.32 in)	
Tightening torque		0.6-0.8 Nm (7.08 lb.in)	-
Environmental data			
Ambient temperature ranges	operation / storage	-25+60 °C / -40+85 °C	
Damp heat, cyclic (IEC 60068-2-3	0)	6 x 24 h cycle, 55 °C, 95 % RH	
Climatic class		3K3	
Vibration (sinusoidal)		class 2	
Shock			
Indiation data		class 2	
Isolation data		class 2	
Rated insulation in	out circuit / output circuit		
Rated insulation in	out circuit / output circuit circuit 1 / output circuit 2	600 V	
Rated insulation input voltage U <sub>i</sub> output Rated impulse withstand	circuit 1 / output circuit 2	600 V	
$ \begin{array}{c} \text{Rated insulation} & \text{in} \\ \text{voltage U}_i & \text{output} \\ \text{Rated impulse withstand} \\ \text{voltage U}_{imp} \\ \end{array} $	circuit 1 / output circuit 2 input circuit output circuit	600 V 300 V 6 kV; 1.2/50 μs 4 kV; 1.2/50 μs	
$ \begin{array}{c c} \text{Rated insulation} & \text{inj} \\ \text{voltage } \text{U}_i & \text{output} \\ \text{Rated impulse withstand} \\ \text{voltage } \text{U}_{\text{imp}} \\ \\ \text{Basic insulation} & \text{inj} \end{array} $	circuit 1 / output circuit 2 input circuit output circuit out circuit / output circuit	600 V 300 V 6 kV; 1.2/50 μs 4 kV; 1.2/50 μs	
$ \begin{array}{c} \text{Rated insulation} & \text{in} \\ \text{voltage U}_i & \text{output} \\ \text{Rated impulse withstand} \\ \text{voltage U}_{imp} \\ \end{array} $	circuit 1 / output circuit 2 input circuit output circuit	600 V 300 V 6 kV; 1.2/50 μs 4 kV; 1.2/50 μs	
$ \begin{array}{c c} \text{Rated insulation} & \text{inj} \\ \text{voltage } \text{U}_i & \text{output} \\ \text{Rated impulse withstand} \\ \text{voltage } \text{U}_{\text{imp}} \\ \\ \text{Basic insulation} & \text{inj} \end{array} $	circuit 1 / output circuit 2 input circuit output circuit out circuit / output circuit input circuit /	600 V 300 V 6 kV; 1.2/50 μs 4 kV; 1.2/50 μs	

Туре		CM-PSS.31	CM-PSS.41	CM-PVS.31	CM-PVS.41	CM-PVS.81	CM-PAS.31	CM-PAS.41
Standards / Directives								
Standards		IEC/EN 602	55-27, IEC/EI	N 60947-5-1				
Low Voltage Directive		2014/35/EU	J					
EMC directive		2014/30/EU	J					
RoHS directive		2011/65/EU	J					
Electromagnetic compatibility		1						
Interference immunity to		EN 61000-6	-1					
electrostatic discharge	IEC/EN 61000-4-2	Level 3 (6 k\	/ / 8 kV)					
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	Level 3 (10 \	//m)					
electrical fast transient / burst	IEC/EN 61000-4-4	Level 3 (2 k\	/ / 2 kHz)					
surge	IEC/EN 61000-4-5	Level 4 (2 k)	/ L-L)					
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	Level 3 (10 \	/)					
Interference emission		IEC/EN 610	00-6-3					
high-frequency radiated	IEC/CISPR 22, EN 55022	class B						
high-frequency conducted	IEC/CISPR 22, EN 55022	class B						

Туре			CM-MPS.11	CM-MPS.21	CM-MPS.31	CM-MPS.41	
Input circuit = Measuri	ng circuit	,	L1, L2, L3, N	,	L1, L2, L3		
Rated control supply vo	Itage U <sub>s</sub> = me	asuring voltage	3x90-170 V AC	3x180-280 V AC	3x160-300 V AC	3x300-500 V AC	
Rated control supply vo			-15+10 %				
Rated frequency		50/60 Hz					
Frequency range		45-65 Hz					
Typical current / power	consumption	1	25 mA / 10 VA (115 V AC)	25 mA / 18 VA (230 V AC)	25 mA / 10 VA (230 V AC)	25 mA / 18 VA (400 V AC)	
Measuring circuit			L1, L2, L3, N	`	L1, L2, L3	`	
Monitoring functions		Phase failure					
		Phase sequence	can be switched of	f			
_	Aut	omatic phase sequence	-	-	-	-	
_		correction					
_		Over- / undervoltage					
_		Phase unbalance					
		Interrupted neutral			-	-	
Measuring range			3x120-170 V AC	3x240-280 V AC	3x220-300 V AC	3x420-500 V AC	
			3x90-130 V AC	3x180-220 V AC	3x160-230 V AC	3x300-380 V AC	
		Phase unbalance	2-25 % of average	of phase voltages			
Thresholds			adjustable within r				
-		Undervoltage	adjustable within measuring range				
		lance (switch-off value)	,				
Tolerance of the adjuste	ed threshold		6 % of full-scale va	lue			
Hysteresis related to the threshold value		Over- / undervoltage					
		Phase unbalance					
Accuracy within the tem	nperature ran	ge	ΔU ≤ 0.06 % / °C				
Measuring method			True RMS				
Timing circuit							
Start-up delay t <sub>s</sub>			fixed 200 ms				
Tripping delay t <sub>v</sub>			ON- or OFF-delay 0; 0.1-30 s adjustable				
Accuracy within the rate			∆t ≤ 0.5 %				
Accuracy within the tem	-	ge	Δt ≤ 0.06 % / °C  Details see function description / -diagrams				
Indication of operation	al states				ms		
Output circuits			15-16/18, 25-26/28				
Kind of output			relay, 1 x 2 c/o contacts				
Operating principle			closed-circuit principle <sup>1)</sup>				
Contact material			AgNi alloy, Cd free				
Minimum switching pov			24 V / 10 mA				
Maximum switching vol		AC 12 (===================================	see load limit curves				
Rated operational volta rated operational curre		AC-12 (resistive) 230 V					
a opa. acional curici	e	AC-15 (inductive) 230 V	3 A				
	_	DC-12 (resistive) 24 V	4 A				
AC rating (III EQQ)		DC-13 (inductive) 24 V					
AC rating (UL 508)	(Cont	Utilization category rol Circuit Rating Code)					
_	•	ted operational voltage	300 V AC				
		inuous thermal current at B 300					
max. making/breaking apparent power at B 300		3600/360 VA					
Mechanical lifetime		30 x 10 <sup>6</sup> switching cycles					
Electrical lifetime (AC-1	2, 230 V. 4 A)		0.1 x 10 <sup>6</sup> switching cycles				
Max. fuse rating to achi		•	6 A fast-acting	.,			
circuit protection		n/o contact	10 A fast-acting				

<sup>1)</sup> Closed-circuit principle: Output relay(s) de-energize(s) if measured value exceeds or falls below the adjusted threshold value

Marging	Туре		CM-MPS.11	CM-MPS.21	CM-MPS.31	CM-MPS.41
Duty time   Duty		,	^	,		,
Duty time   100%   Seed timension drawings	MTBF		on request			
Mounting   Din rail (IEC/EN 60715), snap-on mounting without any tool any   Mounting position   Din rail (IEC/EN 60715), snap-on mounting without any tool any   Din rail (IEC/EN 60915), snap-on mounting without any tool any   Din rail (IEC/EN 60947-5-1   Din rail (IEC/EN 6004-6-2   EEC/EN 61000-4-2   EEC/EN 61000-4-2   EEC/EN 61000-4-2   EEC/EN 61000-4-2   EEC/EN 61000-4-3   EEC/EN 61000-4-4   Surge   EEC/EN 61000-4-4   EEC/E	Duty time		·			
Mounting position	Dimensions		see dimension d	rawings		
Mounting position   Apy   Ap	Mounting				ting without any tool	
Minimum distance to other units				,,		
120 v			_	n case of continuous m	neasuring voltages	
Degree of protection			> 120 V			> 400 V
Screw connection   Screw connection technology   Easy Connect Technology (Push-in Fine-strand with(out) wire end   1 x 0.5-2.5 mm² (1 x 18-14 AWG)   2 x 0.5-1.5 mm² (2 x 18-16 AWG)   6 round   2 x 0.5-1.5 mm² (2 x 18-16 AWG)   2 x 0.5-1.5 mm² (2 x 18-16 AWG)   2 x 0.5-1.5 mm² (2 x 18-16 AWG)   2 x 0.5-1.5 mm² (2 x 20-14 AWG)   2 x 0.5-1.5 mm² (2 x 20-16 AWG)   2 x 0.5-1.5 mm²	<del>-</del>	housing / terminals				
Wire size			IF30 / IF20			
Fine-strand with(out) wire end   1 x 0.5-2.5 mm² (2 x 18-16 AWG)   2 x 0.5-1.5 mm² (2 x 20-16 AWG)   2 x 0.5-2.5 mm² (2 x 20-14 AWG)   2 x 0						
Ferrule   2 x 0.5-1.5 mm² (2 x 19-16 AWG)   1 x 0.5-14 mm² (1 x 2-0-12 AWG)   2 x 0.5-1.5 mm² (2 x 20-16 AWG)   1 x 0.5-4 mm² (1 x 2-0-12 AWG)   2 x 0.5-1.5 mm² (2 x 20-16 AW						
Tiglid   1 x 0.5 -4 mm² (1 x 20 -12 A WG)   2 x 0.5 -1.5 mm² (2 x 20 -16 A WG)   2 x 0.5 -1.5 mm² (2 x 20 -16 A WG)   3 mm² (2 x 20 -14 A WG)   3	fine-				2 x 0.5-1.5 mm² (	2 x 18-16 AWG)
2 x 0.5-2.5 mm² (2 x 20-14 AWG)					2 x 0.5-1 5 mm² (	2 x 20-16 AWG)
Stripping length		rigiu		·	L X 0.3-1.3 IIIII (	LALO IOAWG)
Environmental data Ambient temperature ranges operation / storage	Stripping length					
Ambient temperature ranges	Tightening torque		0.6-0.8 Nm (7.08	lb.in)	-	
Ambient temperature ranges operation / storage	Environmental data		l.			
Damp heat, cyclic  Climatic class  3x3  Wibration  Class 2  Shock  Class 2  Isolation data  Rated insulation  input circuit / output circuit /		operation / storage	-25+60 °C / -40	)+85 °C		
Climatic class 3K3 Vibration class 2 Shock class 2 Stock clas 2 Stock class 2 Stock clas 2 Stock class 2 Stock clas 2 Stock class 2 Stock clas 2 Stock clas	· · · · · · · · · · · · · · · · · · ·					
Vibration   class 2   Shock   class 3   Shock   class 2   Shock   class 3   Shock   class 2   Shock   class 3   Shock   class 3   Shock   class 2   Shock   class 3   Shock   class 2   Shock   class 3   Shock   class 3   Shock   class 2   Shock   class 2   Shock   class 3   Shock   class 2   Shock	· · ·		-			
Schock   Solation data						
Solation data   Rated insulation   input circuit / output circuit   200 V						
Rated insulation output circuit / output			CIA33 L			
output circuit 1 / output circuit 2 300 V  Rated impulse withstand input circuit 5 6kV; 1.2/50 µs  output circuit 4 kV; 1.2/50 µs  zest voltage between all isolated circuits (routine test) 4 kV; 1.2/50 µs  zest voltage between all isolated circuits (routine test) 2.5 kV, 50 Hz, 1 s  Basic insulation input circuit / output circuit / yes  Protective separation input circuit / yes		uut circuit / output circuit	600.1/			
Rated impulse withstand input circuit voltage U <sub>imp</sub> output circuit voltage U <sub>imp</sub> output circuit voltage between all isolated circuits (routine test)  Basic insulation input circuit / output circuit / protective separation (IEC/EN 61140) output circuit / poutput		<u> </u>				
voltage U <sub>imp</sub> output circuit 4 kV; 1.2/50 µs  Test voltage between all isolated circuits (routine test)  Basic insulation input circuit / output circuit / protective separation input circuit / output circuit / pollution degree 3	- Output	<u> </u>				
Standards   IEC/EN 60255-2, IEC/EN 60947-5-1   Low Voltage Directive   2014/35/EU   Electromagnetic compatibility   Interference immunity to   electroal fast transient / burst   IEC/EN 61000-4-3   electroal fast transient / burst   IEC/EN 61000-4-6   induced by radio-frequency   IEC/EN 61000-6-3   EEC/EN 61000-6-3, EN 61000-6-4   IEC/EN 61000-6-3   IEC/EN 61000-6-3   IEC/EN 61000-6-3   IEC/EN 61000-6-4   IEC/EN 61000-6-3   IEC/EN 61000-6-4   IEC/EN 61000-6-5, EN 61000-6-4   IEC/EN 61000-6-5   IEC/EN 61000-6-5   IEC/EN 61000-6-6   IEC/EN 61000-6-7   IEC/EN 61000-6-8   IEC/EN 61000-6-9   IEC/EN 61	•	input circuit	6 kV; 1.2/50 μs			
Basic insulation input circuit / output circuit Protective separation input circuit / output circuit / outpu	voitage U <sub>imp</sub>	output circuit	4 kV; 1.2/50 μs			
Protective separation input circuit / output circuit / output circuit / Pollution degree 3  Overvoltage category III  Standards / Directives  Standards / Directive  Standards   IEC/EN 60255-2, IEC/EN 60947-5-1   Low Voltage Directive   2014/35/EU   EMC directive   2014/30/EU   ROHS directive   2011/65/EU   Electromagnetic compatibility  Interference immunity to   IEC/EN 61000-6-2	Test voltage between all isolated o	circuits (routine test)	2.5 kV, 50 Hz, 1 s			
Protective separation input circuit / output circuit / output circuit / Pollution degree 3  Overvoltage category III  Standards / Directives  Standards / Directive  Standards   IEC/EN 60255-2, IEC/EN 60947-5-1   Low Voltage Directive   2014/35/EU   EMC directive   2014/30/EU   ROHS directive   2011/65/EU   Electromagnetic compatibility  Interference immunity to   IEC/EN 61000-6-2	Basic insulation in	put circuit / output circuit	600 V			
(IEC/EN 61140) Output circuit Pollution degree  3 Overvoltage category III  Standards / Directives  Standards Low Voltage Directive EMC directive EMC directive 2014/35/EU ENC directive 2014/30/EU ENC directive Electromagnetic compatibility Interference immunity to electrostatic discharge radiated, radio-frequency, electromagnetic field electrical fast transient / burst Surge IEC/EN 61000-4-2   level 3 (10 V/m)   level 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5   level 4 (2 kV L-N)   Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-1   class 3  Interference emission IEC/CISPR 22, EN 55022  EN 55022					-	
Overvoltage category   III  Standards / Directives  Standards   IEC/EN 60255-2, IEC/EN 60947-5-1  Low Voltage Directive   2014/35/EU    EMC directive   2014/30/EU    RoHS directive   2011/65/EU    Electromagnetic compatibility  Interference immunity to   IEC/EN 61000-6-2    electrostatic discharge   IEC/EN 61000-4-2   level 3 (6 kV / 8 kV)    radiated, radio-frequency,   IEC/EN 61000-4-3   level 3 (10 V/m)    electromagnetic field   electrical fast transient / burst   IEC/EN 61000-4-4   level 3 (2 kV / 2 kHz)    surge   IEC/EN 61000-4-5   level 4 (2 kV L-N)   Level 4 (2 kV L-L)    conducted disturbances,   IEC/EN 61000-4-6   level 3 (10 V)    induced by radio-frequency   fields   harmonics and interharmonics   IEC/EN 61000-4-13   class 3    Interference emission   EN 61000-6-3, EN 61000-6-4    high-frequency radiated   IEC/CISPR 22,   EN 55022   EN 55022	(IEC/EN 61140)	· ·				
Standards / Directives  Standards   IEC/EN 60255-2, IEC/EN 60947-5-1   Low Voltage Directive   2014/35/EU   EMC directive   2014/30/EU   RoHS directive   2011/65/EU   Electromagnetic compatibility   Interference immunity to   IEC/EN 61000-6-2	Pollution degree		3			
Standards IEC/EN 60255-2, IEC/EN 60947-5-1 Low Voltage Directive 2014/35/EU EMC directive 2014/30/EU RoHS directive 2011/65/EU  Electromagnetic compatibility  Interference immunity to IEC/EN 61000-6-2 electrostatic discharge IEC/EN 61000-4-2 level 3 (6 kV / 8 kV) radiated, radio-frequency, electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (2 kV / 2 kHz) surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L) conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, EN 55022	Overvoltage category		III			
Low Voltage Directive  EMC directive  RoHS directive  RoHS directive  2014/30/EU  2011/65/EU  Electromagnetic compatibility  Interference immunity to  electrostatic discharge  IEC/EN 61000-4-2 level 3 (6 kV / 8 kV)  radiated, radio-frequency, electromagnetic field electrical fast transient / burst  Surge  IEC/EN 61000-4-3 level 3 (10 V/m)  Elec/EN 61000-4-5 level 4 (2 kV L-N)  Conducted disturbances, induced by radio-frequency fields harmonics and interharmonics  IEC/EN 61000-4-13 class 3  Interference emission  high-frequency radiated  IEC/CISPR 22, EN 55022	Standards / Directives					
EMC directive 2014/30/EU  RoHS directive 2011/65/EU  Electromagnetic compatibility  Interference immunity to Electrostatic discharge IEC/EN 61000-4-2 Ievel 3 (6 kV / 8 kV)  radiated, radio-frequency, IEC/EN 61000-4-3 Ievel 3 (10 V/m) electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 Ievel 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5 Ievel 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, IEC/EN 61000-4-6 Ievel 3 (10 V)  induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, Class B  EN 55022	Standards	<u> </u>	IEC/EN 60255-2	, IEC/EN 60947-5-1		<u> </u>
RoHS directive 2011/65/EU  Electromagnetic compatibility  Interference immunity to electrostatic discharge IEC/EN 61000-4-2 level 3 (6 kV / 8 kV)  radiated, radio-frequency, IEC/EN 61000-4-3 level 3 (10 V/m) electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, IEC/EN 61000-4-6 level 3 (10 V)  induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022	Low Voltage Directive		2014/35/EU			
Electromagnetic compatibility  Interference immunity to electrostatic discharge IEC/EN 61000-4-2 level 3 (6 kV / 8 kV)  radiated, radio-frequency, electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (10 V/m)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022	EMC directive		2014/30/EU			
Interference immunity to  electrostatic discharge  EC/EN 61000-4-2  electrostatic discharge  IEC/EN 61000-4-2  level 3 (6 kV / 8 kV)  radiated, radio-frequency, electromagnetic field electrical fast transient / burst  EC/EN 61000-4-4  level 3 (10 V/m)  electrical fast transient / burst  EC/EN 61000-4-5  level 3 (2 kV / 2 kHz)  surge  IEC/EN 61000-4-5  level 4 (2 kV L-N)  Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics  IEC/EN 61000-4-13  class 3  Interference emission  EN 61000-6-3, EN 61000-6-4  high-frequency radiated  IEC/CISPR 22, EN 55022	RoHS directive		2011/65/EU			
electrostatic discharge IEC/EN 61000-4-2 level 3 (6 kV / 8 kV)  radiated, radio-frequency, electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022	Electromagnetic compatibility					
electrostatic discharge IEC/EN 61000-4-2 level 3 (6 kV / 8 kV)  radiated, radio-frequency, electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (10 V/m)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022		,	IEC/EN 61000-6	-2		
radiated, radio-frequency, electromagnetic field electrical fast transient / burst IEC/EN 61000-4-4 level 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022	•	IEC/EN 61000-4-2	· ·			
electrical fast transient / burst IEC/EN 61000-4-4 level 3 (2 kV / 2 kHz)  surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4  high-frequency radiated IEC/CISPR 22, EN 55022	radiated, radio-frequency,	<u> </u>	· · · · · · · · · · · · · · · · · · ·	·		
surge IEC/EN 61000-4-5 level 4 (2 kV L-N) Level 4 (2 kV L-L)  conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, EN 55022		IEC/EN 61000-4-4	level 3 (2 kV / 2 k	:Hz)		
conducted disturbances, induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3 Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, EN 55022		•		<u> </u>	Level 4 (2 kV I -I )	
induced by radio-frequency fields harmonics and interharmonics IEC/EN 61000-4-13 class 3  Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, EN 55022		·			2010. T (E KV E E)	
harmonics and interharmonics IEC/EN 61000-4-13 class 3 Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, EN 55022	induced by radio-frequency	12C/ 2N 01000-4-0	100013 (10 0)			
Interference emission EN 61000-6-3, EN 61000-6-4 high-frequency radiated IEC/CISPR 22, class B EN 55022		IEC/EN 61000-4-13	class 3			
high-frequency radiated IEC/CISPR 22, class B EN 55022		,		N 61000-6-4		
		·				
high-frequency conducted IEC/CISPR 22, class B EN 55022	high-frequency conducted	IEC/CISPR 22,	class B			

Туре		CM-MPS.23	CM-MPS.43	CM-MPN.52	CM-MPN.62	CM-MPN.72		
Input circuit = Measuring circuit		L1, L2, L3, N	L1, L2, L3	,	*	·		
Rated control supply		neasuring voltage	3x180-280 V AC	3x300-500 V AC	3x350-580 V AC	3x450-720 V AC	3x530-820 V AC	
Rated control supply			-15+10 %			1		
Rated frequency	5 5		50/60/400 Hz					
Frequency range			45-440 Hz		45-65 Hz			
Typical current / pov	ver consumpti	on .	5 mA / 4 VA	5 mA / 4 VA	29 mA / 41 VA	29 mA / 52 VA	29 mA / 59 VA	
			(230 V AC)	(400 V AC)	(480 V AC)	(600 V AC)	(690 V AC)	
Measuring circuit			L1, L2, L3, N	L1, L2, L3	_	1	_	
Monitoring		Phase failure						
functions		Phase sequence	can be switched	off				
	Automatic ph	ase sequence correction	configurable					
		Over- / undervoltage						
		Phase unbalance						
-		Interrupted neutral		-	-	-	-	
Measuring range		Overvoltage	3x240-280 V AC	3x420-500 V AC	3x480-580 V AC	3x600-720 V AC	3x690-820 V AC	
		Undervoltage	3x180-220 V AC	3x300-380 V AC	3x350-460 V AC	3x450-570 V AC	3x530-660 V AC	
-				e of phase voltage				
Thresholds		Overvoltage	_	n measuring range				
Till Callolua		Undervoltage	-	n measuring range				
-	Phaseuph	alance (switch-off value)	-	n measuring range				
Talauanaa af tha a di			6 % of full-scale		•			
Tolerance of the adju	istea thrshola			value				
Hysteresis related to the threshold		Over- / undervoltage						
value		Phase unbalance	fixed 20 %					
Maximum measuring	g cycle time		100 ms					
Accuracy within the		ange	ΔU ≤ 0.06 % / °C					
Measuring method		· 3·	True RMS					
Timing circuit								
Start-up delay t <sub>s</sub> and	l+		fixed 200 ms					
	LS2		fixed 250 ms					
Start-up delay t <sub>s1</sub>				.0.01.20	-  -  -			
Tripping delay t <sub>v</sub>			ON- or OFF-delay 0; 0.1-30 s adjustable  Δt ≤ 0.5 %					
		upply voltage tolerance	Δt ≤ 0.06 % / °C					
Accuracy within the		ange						
Indication of operati	ional states			ion description / -	diagrams	-		
Output circuits			15-16/18, 25-26					
Kind of output			relay, 2 x 1 or 1 x	2 c/o contacts cor	nfigurable			
Operating principle			closed-circuit principle <sup>1)</sup>					
Contact material			AgNi alloy, Cd free					
Minimum switching	power		24 V / 10 mA					
Maximum switching	voltage		see load limit curves					
Rated operational vo	ltage U <sub>e</sub> and	AC-12 (resistive) 230 V	4 A					
rated operational cu	rrent l <sub>e</sub>	AC-15 (inductive) 230 V	3 A					
	-	DC-12 (resistive) 24 V	4 A					
	-	DC-13 (inductive) 24 V						
AC rating (UL 508)  Utilization category (Control Circuit Rating Code)  max. rated operational voltage  max. continuous thermal current  at B 300  max. making/breaking apparent		B 300						
			300 V AC					
		3600/360 VA						
power at B 300		30 v 106 switchin	a cycles					
Mechanical lifetime	C 12 220V 1	^^	30 x 10 <sup>6</sup> switching cycles					
Electrical lifetime (A		•	0.1 x 10 <sup>6</sup> switching cycles					
Max. fuse rating to a short-circuit protect			6 A fast-acting 10 A fast-acting					
short-circuit protection n/o contact		10 A fast-acting value exceeds or falls below the adjusted threshold value						

<sup>1)</sup> Closed-circuit principle: Output relay(s) de-energize(s) if measured value exceeds or falls below the adjusted threshold value

Туре		CM-MPS.23	CM-MPS.43	CM-MPN.52	CM-MPN.62	CM-MPN.72
General data		271 111 3.23	3.1.1.1.3.73	C	CIT III IV.OL	C
MTBF		on request	_			
Duty time		on request 100 %				
Dimensions		see dimensiona	Idrawings			
				mounting withou	t any tool	
		any	00713), Shap-on	mounting withou	t arry toor	
Minimum distance to other units	horizontal	-		not nococcary		
Material of housing	HOFIZORICAL	10 mm (0.39 in) UL 94 V-0		not necessary		
Degree of protection	housing / terminals					
Electrical connection	nousing / terminals	1F30 / 1F20			,	
Wire size		Saraw sannasti	an tachnalası	Facy Conne	ct Technology (Pu	ah in)
	nd with(out) wire end	Screw connection			nm² (2 x 18-16 AW)	•
IIIIe-Strai	ferrule	2 x 0.5-1.5 mm <sup>2</sup>	(2 x 20-16 AWG)			
	rigid	1 x 0.5-4 mm <sup>2</sup> (1 2 x 0.5-2.5 mm <sup>2</sup>	•	2 x 0.5-1.5 n	nm² (2 x 20-16 AW)	G)
Stripping length		8 mm (0.32 in)				
Tightening torque		0.6-0.8 Nm (7.08	B lb.in)		-	
Environmental data						
Ambient temperature ranges	operation / storage	-25+60 °C / -4	0+85 °C			
Damp heat, cyclic (IEC 60068-2-30)	<u> </u>	6 x 24 h cycles, 55 °C, 95 % RH				
Climatic category		3K3				
Vibration (sinusoidal) (IEC/EN 60255-2	?1-1)	class 2				
Shock (IEC/EN 60255-21-2)		class 2				
Isolation data						
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	600 V	,	1000 V		
	output circuit 1 / 2	300 V				
Rated impulse withstand voltage U <sub>imp</sub>		6 kV; 1.2/50 μs		8 kV; 1.2/50 μs	•	
Thatea impaise transcaria restage climp	· · · · · · · · · · · · · · · · · · ·	4 kV; 1.2/50 μs		0 KV, 1.2, 00 p.s		
Basic insulation input c	ircuit / output circuit			1000 V		
Protective separation	input circuit /					
(IEC/EN 61140, EN 50148)	output circuit					
Pollution degree		3				
Overvoltage category		III				
Standards / Directives						
Standards			7, IEC/EN 60947-	5-1		
Low Voltage Directive		2014/35/EU				
EMC Directive		2014/30/EU				
RoHS Directive		2011/65/EU				
Electromagnetic compatibility						
Interference immunity to		IEC/EN 61000-6-2				
electrostatic discharge	IEC/EN 61000-4-2	level 3 (6 kV / 8 kV)				
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)				
		level 3 (2 kV / 2 kHz)				
surge	IEC/EN 61000-4-5					
conducted disturbances, induced IEC/EN 61000-4-6 by radio-frequency fields		, , ,				
_ · · · · · · · · · · · · · · · · · · ·	IEC/EN 61000-4-13	class 3				
harmonics and interharmonics	IEC/EN 61000-4-13		;-3			
harmonics and interharmonics Interference emission	IEC/EN 61000-4-13	IEC/EN 61000-6	i-3			

\_

## Three-phase monitoring relays


## Technical diagrams

#### \_

#### **Connection diagrams**


#### CM-PBE, CM-PVE

## 



L1, L2, L3, (N)	Control supply voltage = Measuring voltage
13-14	Output contact - closed-circuit principle

#### CM-PFE




L1, L2, L3	Control supply voltage = Measuring voltage
11-12/14	Output contact - closed-circuit principle

#### CM-PVS.x1, CM-PSS.x1, CM-PAS.x1

L1	L2	L3	
L1 L2 L	.3 15      /-	25 /	 
!	<del>/</del>   16 18	[ <sup>+</sup> ] 26 28	2CDC 252 037 F0 b08
26	25	28	2 252
16	15	18	ğ

L1, L2, L3	Control supply voltage = Measuring voltage
15-16/18	Output contact - closed-circuit principle
25-26/28	

#### CM-PFS




L1, L2, L3	Control supply voltage = Measuring voltage
11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub>	Output contact - closed-circuit principle
2125-2226/2420	

#### CM-MPS.11, CM-MPS.21, CM-MPS.23

L1	L2	L3	
N			
L1L2 L	3 15     	- <b>-</b> /	80
1	- 1′ - 1		Fob
i N	16 18	26 28	2CDC252036F0b08
26	25	28	C25
16	15	18	2C D


L1, L2, L3, (N) Contr	
15-16/18 Outpu 25-26/28	t contact - closed-circuit principle

#### CM-MPS.31, CM-MPS.41, CM-MPS.43



L1, L2, L3, (N)	Control supply voltage = Measuring voltage
15-16/18 25-26/28	Output contact - closed-circuit principle

#### CM-MPN.x2



L1, L2, L3	Control supply voltage = Measuring voltage
15-16/18	Output contact - closed-circuit principle
25-26/28	

## Technical diagrams

#### **Rotary switch "Function"**

#### CM-PVS



ON-delay

with phase sequence monitoring



OFF-delay

with phase sequence monitoring



without phase sequence monitoring



OFF-delay

without phase sequence monitoring

#### CM-PSS



ON-delay

with phase sequence monitoring



OFF-delay

with phase sequence monitoring



without phase sequence monitoring



without phase sequence monitoring

#### **DIP switch functions**

#### CM-MPS.x3 and CM-MPN.x2

					8
Position	4	3	2	1	0q
ON †	(A)	2x1 c/o	Ø	X	2 041 F0
OFF	(A)	1x2 c/o			2CDC 252

#### 1 Timing function

ON ON-delayed OFF OFF-delayed

#### 2 Phase sequence monitoring

ON deactivated OFF activated

#### 3 Operating principle of output

2x1 c/o contact OFF 1x2 c/o contact

#### 4 Phase sequence correction

activated

synchronously.

#### OFF deactivated Output relay R1 is responsive to overvoltage, output relay R2 is responsive to undervoltage.

In case of other faults, both output relays react

#### CM-MPS.x1

Position	2	1	ľ
ON †	Ø	X	
OFF			

#### 1 Timing function


ON-delayed OFF-delayed

#### Phase sequence monitoring

ON deactivated OFF activated

#### Function diagrams


#### CM-PBE



#### Phase failure detection

If all phases (and the neutral) are present, the output relay energizes after the start-up delay  $t_{\rm s}$  is complete. If a phase failure occurs, the tripping delay  $t_{\rm v}$  starts. When timing is complete, the output relay de-energizes. As soon as the voltage returns to the tolerance range, timing of  $t_{\rm s}$  starts. When timing is complete, the output relay re-energizes automatically. The yellow LED glows when the output relay is energized.

#### **CM-PVE**



#### Phase failure, under- / overvoltage detection

If all phases (and the neutral) are present with correct voltage, the output relay energizes after the start-up delay  $t_{\rm s}$  is complete. If the voltage exceeds or falls below the fixed threshold value or if a phase failure occurs, the tripping delay  $t_{\rm v}$  starts. When timing is complete, the output relay denergizes. As soon as the voltage returns to the tolerance range, timing of  $t_{\rm s}$  starts. When timing is complete, the output relay re-energizes automatically. The yellow LED glows when the output relay is energized.

#### CM-PFE, CM-PFE.2



#### Phase failure detection, phase sequence monitoring

If all phases are present with the correct phase sequence, the output relay energizes after the start-up delay  $t_{\rm s}$  is complete. If a phase failure or a phase sequence error occurs, the tripping delay  $t_{\rm v}$  starts. When timing is complete, the output relay de-energizes. The yellow LED glows when the output relay is energized.

In case of motors which continue running with only two phases, the CM-PFE detects phase failure if the reverse fed voltage is less than 60 % of the originally applied voltage.

#### CM-PFS



#### ATTENTION


If several CM-PFS units are placed side by side and the control supply voltage is higher than 415 V, spacing of at least 10 mm has to be kept between the individual units.

#### Phase failure detection, phase sequence monitoring

If all phases are present with the correct phase sequence, the output relay energizes after the start-up delay  $t_{\rm s}$  is complete. If a phase failure or a phase sequence error occurs, the output relay de-energizes instantaneous. The yellow LED glows when the output relay is energized. In case of motors which continue running with only two phases, the CM-PFS detects phase failure if the reverse fed voltage is less than 60 % of the originally applied voltage.

## Function diagrams

#### CM-PSS.xx, CM-PVS.xx, CM.PAS.xx, CM-MPS.xx, CM-MPN.xx



Applying control supply voltage begins the fixed start-up delay  $t_s$ . When  $t_s$  is complete and all phases are present with correct voltage, the output relays energize and the yellow LED R/T glows.

Phase sequence monitoring and phase failure detection


#### Phase sequence monitoring

If phase sequence monitoring is activated, the output relays de-energize as soon as a phase sequence error occurs. The fault is displayed by alternated flashing of the LEDs F1 and F2. The output relays re-energize automatically as soon as the phase sequence is correct again.

#### Phase failure detection

The output relays de-energize instantaneous if a phase failure occurs. The fault is indicated by lighting of LED F1 and flashing of LED F2. The output relays re-energize automatically as soon as the voltage returns to the tolerance range.

#### CM-MPS.11, CM-MPS.21, CM-MPS.23



Displacement of the star point

#### Interrupted neutral monitoring

The interruption of the neutral in the main to be monitored is detected by means of phase unbalance evaluation.


Determined by the system, in case of unloaded neutral (i.e. symmetrical load between all three phases) it may happen that an interruption of the neutral will not be detected. If the star point is displaced an asymmetrical load in the three-phase main, an interrupted neutral will be detected.


\_

## Three-phase monitoring relays


## Function diagrams

#### CM-MPS.x3, CM-MPN.x2





Control circuit diagram (K1 = CM-MPS.23)



Control circuit diagram (K1 = CM-MPS.43 or CM-MPN.xx)


#### Automatic phase sequence correction

This function can be selected only if phase sequence monitoring is activated and operating mode 2x1 c/o (SPDT) contact is selected.

Applying control supply voltage begins the fixed start-up delay  $t_{\text{S1}}$ . When  $t_{\text{S1}}$  is complete and all phases are present with correct voltage, output relay R1 energizes. Output relay R2 energizes when the fixed start-up delay  $t_{\text{S2}}$  is complete and all phases are present with the correct phase sequence. Output relay R2 remains de-energized if the phase sequence is incorrect.

If the voltage to be monitored exceeds or falls below the set threshold values for phase unbalance, over- or undervoltage or if a phase failure occurs, output relay R1 de-energizes and the LEDs F1 and F2 indicate the fault.

Output relay R2 is responsive only to a false phase sequence. In conjunction with a reversing contactor combination, this enables an automatic correction of the rotation direction. See circuit diagrams on this page.



Power circuit diagram


#### \_

## Three-phase monitoring relays


## Function diagrams

#### CM-PSS.xx(1), CM-PVS.xx(2), CM-MPS.xx(2), CM-MPN.xx(2)

#### ON-delay ≥, 1x2 c/o contacts ∞



#### OFF-delay ■, 1x2 c/o contacts 1x2 c/o



#### Over- and undervoltage monitoring 112200

Applying control supply voltage begins the fixed start-up delay  $t_s$ . When  $t_s$  is complete and all phases are present with correct voltage and with the correct phase sequence, the output relays energize and the yellow LED R/T glows.

#### Type of tripping delay = ON-delay

If the voltage to be monitored exceeds or falls below the fixed (1) or set (2) threshold value, the output relays de-energize after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing and turns off as soon as the output relays de-energize.

The output relays re-energize automatically as soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 5 % and the LED R/T glows.


#### Type of tripping delay = OFF-delay

If the voltage to be monitored exceeds or falls below the fixed (1) or set (2) threshold value, the output relays de-energize instantaneously and the LED R/T turns off. As soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 5 %, the output relays re-energize automatically after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing and turns steady when timing is complete.


## Function diagrams

#### CM-MPS.x3, CM-MPN.x2

#### ON-delay ≥, 2x1 c/o contact ≥ c/o



#### OFF-delay ■ ,2x1 c/o contact 2x1 c/o



#### Over- and undervoltage monitoring 221.06

Applying control supply voltage begins the fixed start-up delay  $t_s$ . When  $t_s$  is complete and all phases are present with correct voltage and with the correct phase sequence, the output relays energize. The yellow LED R/T glows as long as at least one output relay is energized.

#### Type of tripping delay = ON-delay

If the voltage to be monitored exceeds or falls below the set threshold value, output relay R1 (overvoltage) or output relay R2 (undervoltage) de-energizes after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing. The corresponding output relay re-energizes automatically as soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 5 %.


#### Type of tripping delay = OFF-delay

If the voltage to be monitored exceeds or falls below the set threshold value, output relay R1 (overvoltage) or output relay R2 (undervoltage) de-energizes instantaneously. As soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 5 %, the corresponding output relay re-energizes automatically after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing.


## Function diagrams

#### CM-PAS.xx, CM-MPS.xx, CM-MPN.xx

#### ON-delay ⊠



#### OFF-delay



#### Phase unbalance monitoring

Applying control supply voltage begins the fixed start-up delay  $t_s$ . When  $t_s$  is complete and all phases are present with correct voltage and with the correct phase sequence, the output relays energize and the yellow LED R/T glows.

#### Type of tripping delay = ON-delay

If the voltage to be monitored exceeds or falls below the set phase unbalance threshold value, the output relays de-energize after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing and turns off as soon as the output relays de-energize.

The output relays re-energize automatically as soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 20 % and the LED R/T glows.

#### Type of tripping delay = OFF-delay

If the voltage to be monitored exceeds or falls below the set phase unbalance threshold value, the output relays de-energize instantaneously and the LED R/T turns off. As soon as the voltage returns to the tolerance range, taking into account a fixed hysteresis of 20 %, the output relays re-energize automatically after the set tripping delay  $t_{\rm V}$  is complete. The LED R/T flashes during timing and turns steady when timing is complete.

## Function diagrams

#### CM-PSS.xx, CM-PSV.xx, CM-PAS.xx, CM-MPS.xx, CM-MPN.xx

#### **LED functions**

Function	R/T: yellow LED	F1: red LED	F2: red LED		
Control supply voltage applied, output relay energized		-	-		
Tripping delay t <sub>v</sub> active	ПП	-	-		
Phase failure	-		ПП		
Phase sequence	-	□□□ alte	alternating		
Overvoltage	-		-		
Undervoltage	-	-			
Phase unbalance	-				
Interruption of the neutral	-		ПП		
Adjustment error	ПП	лл	ЛЛ		

# Possible wrong adjustments of the front-facing operating controls

Overlapping of the threshold values:

- An overlapping of the threshold values is given if the threshold value for overvoltage is set to a smaller value than the threshold value for undervoltage.
- DIP switch 3 = OFF
- DIP switch 4 = ON: Automatic phase sequence correction is activated and selected operating mode is 1x2 c/o contacts
- DIP switch 2 and 4 = ON: Phase sequence detection is deactivated and the automatic phase sequence correction is activated

#### Type of tripping delay

The type of tripping delay  $\boxtimes$  /  $\blacksquare$  can be adjusted via a rotary (CM-PxS.xx) or a DIP switch (CM-MPx.xx).

Switch position ON-delay ⊠:

In case of a fault, the de-energizing of the output relays and the respective fault message are suppressed for the adjusted tripping delay t<sub>v</sub>.

Switch position OFF-delay **■**:

In case of a fault, the output relays de-energize instantaneously and a fault message is displayed and stored for the length of the adjusted tripping delay  $t_{\nu}$ . Thereby, also momentary undervoltage conditions are recognized.



# **Grid feeding monitoring relays**Table of contents

138	Benefits and advantages
143	Operating controls
144	Selection table
145	Ordering details
146	Technical data
147	Technical diagrams

# Benefits and advantages



ABB's grid feeding monitoring relays detect unusual events in the public power grid and keeps it stable by automatically disconnecting and reconnecting the renewable power plant. The CM-UFD displays all relevant measuring data and events and can communicate them via a build-in communication interface. The cloud-based service Ability™ EDCS enables customers to monitor the conditions in real-time, send the values into the cloud and access the diagnostics remotely.



#### Optimum interface

#### Reduce downtime by up to 70%

Operate the device via LCD or remotely with the Modbus RTU. Users are informed immediately in case of an event in the public grid. Redundant microcontrollers ensure reliable measuring values and tripping.



#### Cut installation time by up to 60%

There's no need to learn every possible adjustment and its effects on your system – ABB's trained staff supports your business and answers your technical questions promptly.



#### Commission & configure up to 60% faster


Simple instructions, presets for local grid feeding standards, and ABB's intuitive menu structure make installation quicker. Commissioning and troubleshooting errors are prevented.

# Benefits and advantages



ABB's CM-UFD range are multi-functional grid feeding monitoring relays, installed between the renewable energy system and the public grid. The innovative relays guarantee grid stability and prevent blackouts. If the public grid's voltage or frequency moves out of the permitted ranges, the device uses a decoupling unit (e.g. contactor or breaker Tmax XT) to separate the renewable energy system from the public grid. As soon as the grid is stable again, the system is automatically reconnected.

The CM-UFD range provides different monitoring functions in accordance with several local grid feeding standards to detect over-/undervoltage and over-/underfrequency.





#### **Advantages**

- Highly accurate measurement and setting
- Modbus RTU communication interface and ABB Ability<sup>™</sup> EDCS connectivity
- · Functional safety single fault tolerances
- · Clear multiline, backlit LCD
- Intuitive and user-friendly menu
- Event storage
- · Pre-settings meet several local standards
- Type-tested to a number of local grid feeding standards by TÜV Süd



#### **Functionality**


The device measures the ten-minute average value, voltage increases and decreases, as well as any changes in grid frequency. The rate of change of frequency (ROCOF) and vector shift monitoring to detect a loss of mains event can be easily configured.



# Benefits and advantages

The cloud-based service Ability $^{\text{TM}}$  EDCS enables customers to monitor the condition of CM-UFD.M\*M in real-time and access the diagnostics remotely. This functionality is very important when operating in the field of critical power. Parametrize with ABB Ekip Connect and access data no matter where you are.

Example architecture



The grid feeding monitoring relays can be connected to the cloud directly by using Ekip Com Hub module. Another option is to connect via Modbus RTU when there is some other device equipped with the Ekip Com Hub like the Emax 2 air-circuit breaker.

In addition to the Ekip Connect 3 software, the following hardware is required:

- Ekip UP (min. firmware 2.23)
- Ekip Com Hub (min. firmware 1.18)
- Ekip Com Modbus RTU (min. firmware 2.28)
- Ekip Supply
- Ekip T&P cable
- CM-UFD.M\*M (min. firmware 1.0.1)



For further information regarding integration into ABB Ability™ EDCS, please use the application note "2CDC112280M0101 CM-UFD.M\*M integration into ABB Ability™ EDCS".

# Benefits and advantages

A reliable solution that takes country-specific requirements into account: the range is already pre-set to local requirements, making installation quick and simple. The devices can also be set manually with the display and used all over the world.

Austria

CM-UFD.M33\*

refers to GB standard

CM-UFD.M31\*

Italy

CM-UFD.M22M



#### **Pre-set devices**

In accordance with a number of local standards, the CM-UFD relays can be used in all low voltage plants and in medium voltage plants.

**Great Britain** 

CM-UFD.M33\*

Switzerland CM-UFD.M31\*

France

CM-UFD.M31\*

Germany




#### Type-tested


To ensure reliability and compliance, the range is typetested to local standards by the third party authority TÜV Süd.

**United Arabic Emirates** 

CM-UFD.M33\*


CM-UFD.M34M





Countries referring to an existing local standard or using a product with reference to another dedicated standard (in grey)

# Operating controls



# **Grid feeding monitoring relays**Selection table

	Order number		1SVR560730R3401	1SVR560731R3701	1SVR560730R3402	1SVR560731R3702	1SVR560731R3703
	Туре	см-иғр.мггм	CM-UFD.M31	СМ-UFD.М31М	см-иғр.мзз	см-иғр.мззм	CM-UFD.M34M
Rated control supply voltage U <sub>s</sub>							
24-240 V AC/DC							
Standard							
CEI 0-21							
VDE AR-N 4105, VDE AR-N 4110, VDE AR-N 4120			•	•			
ENA G98, G99					•	•	
DRRG standard of DEWA							
Rated frequency							
DC or 50/60 Hz							
Modbus RTU				•			
Suitable for monitoring							
Single-phase mains				•		•	
Three-phase mains			_	•			
Monitoring function							
Over-/undervoltage			-	•	=	•	
Over-/underfrequency			-	•	-	-	•
ROCOF (rate of change of frequency)			-	•	-	•	•
10 minutes average value			-	•	=	•	
Vector shift						=	_
Thresholds		adj	adj	adj	adj	adj	adj

# **Grid feeding monitoring relays**

# Ordering details



CM-UFD.M\*M

## Description

The grid feeding monitoring relays CM-UFD.M\*M are designed to monitor the voltage and the frequency of the public low voltage or medium voltage grid. Whenever the measured values are not within the range of the adjusted threshold values, the CM-UFD.M\*M causes tripping of the section switch (consisting of 1 or 2 switching devices according to the applicable standard). This tripping disconnects the power generation, such as photovoltaic systems, wind turbines, block-type thermal power stations from the grid.

## Ordering details

Description	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-UFD.M22M	1SVR560731R3700	0.312 (0.688)
	CM-UFD.M31	1SVR560730R3401	0.304 (0.670)
	CM-UFD.M31M	1SVR560731R3701	0.312 (0.688)
	CM-UFD.M33	1SVR560730R3402	0.304 (0.670)
	CM-UFD.M33M	1SVR560731R3702	0.312 (0.688)
	CM-UFD.M34M	1SVR560731R3703	0.312 (0.688)

\_

# **Grid feeding monitoring relays**

## Technical data



## Data sheets

For every product of the CM-UFD range, a technical data sheet is available.

- Operating control and mode
- · Operating principles
- Modbus RTU functionality where available
- · Electrical connection
- Configuration and settings
- Menu structure
- Display and failure messages
- Connection and wiring
- · Technical data
- · Technical diagrams
- CAS system files

### Ordering data and data sheet numbers

Description	Туре	Order code	Data sheet number
	CM-UFD.M22M	1SVR560731R3700	2CDC112258D0201
	CM-UFD.M31	1SVR560730R3401	2CDC112208D0201
	CM-UFD.M31M	1SVR560731R3701	2CDC112270D0201
	CM-UFD.M33	1SVR560730R3402	2CDC112210D0201
	CM-UFD.M33M	1SVR560731R3702	2CDC112271D0201
	CM-UFD.M34M	1SVR560731R3703	2CDC112272D0201




For further information regarding integration into ABB Ability  $^{\text{TM}}$  EDCS, please use the application note  $^{\text{TM}}$  EDCS112280M0101 CM-UFD.M\*M integration into ABB Ability  $^{\text{TM}}$  EDCS".

# **Grid feeding monitoring relays**

## Technical diagrams

## Example of a single-phase application

# Example of a three-phase application



### Legend


- 1. Control supply voltage for CM-UFD.M\*M
- 2. Public grid
- 3. Protection fuse for the CM-UFD.M\*M
- 4. Protection fuse for the measuring circuit of the CM-UFD.M\*M (optional)
- 5. Short-circuit protection
- 6. Undervoltage release
- 7. Control input for feedback function
- 8. Switching device of the section switch
- 9. Switching device of the generator and/or inverter
- 10. Generator and/or inverter
- 11. Primary switch mode power supply unit CP-E (230 V AC / 24 V DC) for the buffer module CP-B
- 12. Ultra-capacitor based buffer module CP-B (24 V DC in/out)
- 13. Wire protection fuse for the output of the buffer module CP-B

### \_


# Grid feeding monitoring relays

# Technical diagrams


## Load limits curves




AC load (resistive)



DC load (resistive)




Derating factor F at inductive AC load




Contact lifetime

## **Dimensional drawings**

## in **mm** and inches







# Insulation monitoring relays for unearthed supply systems

Table of contents

132	benefits and advantages
156	Applications
157	Operating controls
160	Selection table
161	Ordering details
162	Technical data
169	Technical diagrams

# Benefits and advantages



The insulation monitoring relays of the CM-IWx range guarantee a continuous insulation monitoring of an IT system. The devices recognize insulation faults as they develop and warn immediately if the value has fallen below the minimum set threshold. This ensures a reliable operation of the system and prevents operational interruption caused by a second, more severe, insulation fault which may lead to a short circuit tripping the main circuit breaker.



Continuous operation

Keep the system online and reduce downtime with early pre-warnings which enable time for maintenance planning. Monitor voltage free networks for early fault detection. Due to variants with rail and ship approval, the devices have a wide range of applications.



Safety and protection

Safe and reliable detection of insulation faults according to the latest standards is what ABB's insulation monitoring relays deliver. The portfolio extends from standard to more challenging applications and can prevent fire due to fast and reliable earth fault detection. Built-in self-diagnosis and interrupted wire detection further ensure safety.



Read the status of the relay at a glance: clear visualization of the device status via LEDs. Easy to adjust with rotary wheels and variants with push-in terminals make a quick and easy installation and setting possible.

# Benefits and advantages



### Overview

The CM-IWx product family offers a convincing solution for monitoring ungrounded AC, AC/DC and DC networks according to EN/IEC 61557-8. An IT network is supplied either by an isolating transformer or a voltage source, such as a battery or generator. In these systems, no active conductor is directly connected to earth potential.

The high reliability of an IT system is guaranteed thanks to continuous insulation monitoring. The insulation monitoring device recognizes insulation faults (at least one conductor has a galvanic connection to earth potential) as they develop and immediately reports if the insulation resistance has fallen below a given threshold. Therefore, maintenance activities can be scheduled and executed while the plant keeps running.



## Main benefits

- · Increase plant availability and avoid costly unplanned stops of a plant / machine by quickly detecting faults first
- · Prevents fires due to detection of a creeping deterioration of the insulation resistance
- The adjustment of the setting values is simple and done in a user-friendly way with rotary switches on the front of the device
- Device status is displayed with LEDs that are easy to read and understand
- Devices for standard and more challenging applications are available
- Variants with rail and ship approvals are available



# Benefits and advantages

### CM-IWS.1 - for unearthed AC, DC or mixed AC/DC systems



The CM-IWS.1 serves to monitor insulation resistance in accordance with IEC 61557-8 in unearthed IT AC systems, IT AC systems with galvanically connected DC circuits, or unearthed IT DC systems with a voltage up to 250 V AC and 300 V DC. It can be configured to the requirements of the applications and therefore has multi-functional uses. The device is available with two different terminal versions. You can choose between the proven screw connection technology (double-chamber cage connection terminals) and the completely tool-free Easy Connect Technology (push-in terminals).

- For monitoring the insulation resistance of unearthed IT systems up to  $U_n = 250 \text{ V}$  AC and 300 V DC
- · Test function
- According to IEC/EN 61557-8
- Rated control supply voltage 24-240 V AC/DC
- Prognostic measuring principle with superimposed square wave signal
- One measuring range 1-100  $k\Omega$
- 1 c/o (SPDT) contact, closed-circuit principle
- Precise adjustment by front-face operating controls in  $1\,k\Omega$  steps

- · Interrupted wire detection
- Fault storage / latching configurable by control input
- Screw connection or Easy Connect Technology available
- Housing material for highest fire protection classification UL 94 V-0
- · Tool-free mounting on DIN rail as well as demounting
- 22.5 mm width
- 3 LEDs for status indication

## CM-IWS.2 - for unearthed pure AC systems



The CM-IWS.2 serves to monitor insulation resistance in accordance with IEC 61557-8 in unearthed IT AC systems with a voltage up to 400 V AC. The CM-IWS.2 can be configured to the requirements of the applications and therefore has multi-functional uses. The device is available with two different terminal versions. You can choose between the proven screw connection technology (double-chamber cage connection terminals) and the completely tool-free Easy Connect Technology (push-in terminals).

- For monitoring the insulation resistance of unearthed IT systems up to U<sub>n</sub> = 400 V AC
- Test function
- According to IEC/EN 61557-8
- Rated control supply voltage 24-240 V AC/DC
- Measuring principle with superimposed DC voltage
- One measuring range 1-100  $k\Omega$
- Fault storage / latching configurable by control input
- Precise adjustment by front-face operating controls in 1  $k\Omega$  steps

- Screw connection or Easy Connect Technology available
- Housing material for highest fire protection classification UL 94 V-0  $\,$
- Tool-free mounting on DIN rail as well as demounting
- 1 c/o (SPDT) contact, closed-circuit principle
- 22.5 mm width
- · 3 LEDs for status indication

# Benefits and advantages

### CM-IWN.1 - for unearthed AC, DC or mixed AC/DC systems



The CM-IWN.1 serves to monitor insulation resistance in accordance with IEC 61557-8 in unearthed IT AC systems, IT AC systems with galvanically connected DC circuits, or unearthed IT DC systems with a voltage up to 400 V AC and 600 V DC. The measuring range can be extended up to 690 V AC and 1000 V DC by using the coupling unit CM-IVN. It can be configured to the requirements of the applications and therefore has multifunctional uses. The CM-IWN.1 is available with two different terminal versions. You can choose between the proven screw connection technology (double chamber cage connection terminals) and the completely tool-free Easy Connect Technology (push-in terminals).

- For monitoring the insulation resistance of unearthed IT systems up to  $U_n$ = 400 V AC and 600 V DC, expansion to 690 V AC and 1000 V DC with CM-IVN
- Test function
- · According to IEC/EN 61557-8
- Rated control supply voltage 24-240 V AC/DC
- Prognostic measuring principle with superimposed square wave signal
- Two measuring ranges 1-100 k $\Omega$  and 2-200 k $\Omega$
- Precise adjustment of the measuring value in 1 or 2 kW steps
- One (1 x 2 c/o) or two (2 x 1 c/o) threshold values Ran1/R1 (warning) and Ran2/R2 (pre-warning) configurable

- Precise adjustment of the threshold values in 1 k $\Omega$  steps (R1) and 2 k $\Omega$  steps (R2)
- · Interrupted wire detection configurable
- · Non-volatile fault storage configurable
- Open- or closed-circuit principle configurable
- Screw connection or Easy Connect Technology available
- Housing material for highest fire protection classification UL 94 V-0
- · Tool-free mounting on DIN rail as well as demounting
- 45 mm width
- 3 LEDs for status indication

### CM-IWM.10 and CM-IWM.11 - for unearthed AC, DC or mixed AC/DC systems with up to 1500 V measurement voltage



The insulation monitors CM-IWM.10 and CM-IWM.11 provide the best and up-to-date insulation monitoring of modern IT systems in an optimum and state of-the-art way fulfilling the relevant standards. The devices can be used in the most flexible way for AC, DC and AC/DC systems even with large leakage capacity to earth (PE). The adjustment of the setting values is simple and done in a user-friendly way on two rotary switches on the front of the device. Via LEDs the measured value, device parameters and device status are indicated easy to read.


- Insulation monitoring according to IEC/EN 61557-8
- Detection of symmetric and asymmetric insulation faults
- 1 c/o contact each for pre-warning and warning
- Measuring circuits can be disconnected via control terminals, e.g. for mains couplings
- Pre-warning threshold setting range: 20  $k\Omega$  ... 2  $M\Omega$
- Warning threshold setting range: 1  $k\Omega$  ... 250  $k\Omega$
- Open- or closed-circuit principle configurable
- Setting the maximum earth leakage capacitance to shorten the response time

- Simple, clearly arranged adjustment of the device with screwdriver
- LED chain to indicate the current insulation resistance
- · Display of active measuring circuits
- · Automatic and manual device self-test
- Alarm storage selectable
- External test and reset push button can be connected
- 90 mm width

# **Applications**

The CM-IWS.x and CM-IWN.x series provide excellent insulation monitoring for general purpose supply networks, such as:


- Non-earthed AC, DC, AC/DC networks
- UPS systems
- Battery networks
- Hybrid and battery-powered vehicles
- · Railway applications



Earth fault / insulation resistance monitoring of a 4-wire IT AC system with CM-IWS.2

CM-IWM.x can be additionally used in special applications, such as:


- Industrial networks with frequency inverters or direct current drives
- Photovoltaic systems with high system leakage capacitance
- Networks with system voltages up to 1500 V DC or 1100 V AC without requiring a coupling unit
- Installation on the AC or DC side of an inverter
- Networks which require measuring circuit deactivation in case two or more unearthed networks are coupled



\*) G-HM connected: Measuring circuit is off Example of a DC application with CM-IWM.11


# Operating controls

# **CM-IWM**



# Operating controls

# CM-IWS



# Operating controls

## **CM-IWN**

to adjust the threshold

 $k\Omega$  in one  $k\Omega$  steps


140, 160, 180 kΩ in

 $twenty\,k\Omega\,steps$ 

value:

steps

steps



## Selection table

	ımber	1SVR730670R0200	1SVR740670R0200	1SVR730660R0100	1SVR740660R0100	1SVR750660R0200	1SVR760660R0200	1SVR470670R1000	1670R1100
	Order number	1SVR730	1SVR740	1SVR730	1SVR740	1SVR750	1SVR760	1SVR470	1SVR470
	Туре	CM-IWS.2S	CM-IWS.2P	CM-IWS.1S	CM-IWS.1P	CM-IWN.1S	CM-IWN.1P	CM-IWM.10	CM-IWM.11 1SVR470670R1100
Rated control supply voltage Us									
24 - 240 V AC/DC	$\neg$	_							
24 V DC		_	_	_	_	_			
Measuring voltages									
250 V AC (L-PE)									
400 V AC (L-PE)		•		_	_				
690 V AC (L-PE)		_	_			(1)	(1)	(2)	
1000 V AC (L-PE)						_	_	_	<b>(</b> 3
300 V DC (L-PE)				_					_
600 V DC (L-PE)					_	-			
690 V DC (L-PE)								<b>(</b> 2)	
1000 V DC (L-PE)						(1)	(1)		<b>(</b>
Measuring range									
1 - 100 kΩ		_							
2 - 200 kΩ									
2 - 250 kΩ								•	
System leakage capacitance, max.									
10 μF									
20 μF						•			
1000 μF									
3000 μF									
Output									
1 c/o									
1 x 2 c/o or 2 x 1 c/o									
2 c/o									
Operating principle									
Open-circuit principle									
Open- or closed-circuit principle adjustable									
Test									
Front-face button or control input									
Reset									
Front-face button or control input				•	•	-		•	•
Fault storage / latching configurable									
Non volatile storage configurable				•					
Interrupted wire detection								•	•
Threshold values configurable		1	1	1	1	2	2	2	2
Control input (measuring input deactivation	1)								
Connection type									
Push-in terminals	]				•				
								1	1

1) With coupling unit CM-IVN screw version

2) Allowed voltage range of the supervised network: 0-760 V AC / 0-1000 V  $\,$ 

screw version CM-IVN.S: 1SVR750669R9400 push-in version CM-IVN.P: 1SVR760669R9400

<sup>3)</sup> Allowed voltage range of the supervised network: 0-1100 V AC / 0-1500 V DC

## Ordering details



CM-IWS.1



CM-IWS.2



CM-IWN.1



CM-IWM.10



CM-IWM.11



Description

The CM-IWx serves to monitor insulation resistance in accordance with IEC 61557-8 in unearthed IT AC systems, IT AC systems with galvanically connected DC circuits, or IT DC systems. The devices are able to monitor control circuits (single-phase) and main circuits

The CM-IWM.x provides the best and up-to-date insulation monitoring of modern IT supply systems in an optimum and state of-the-art way according to IEC 61558-8 including annex C. The device can be used in the most flexible way for AC, DC and AC/DC systems, even with a large leakage capacity to earth (PE) and under adverse conditions.

### Ordering details

Type	Rated control supply voltage	Nominal voltage Un of the distribution system to be monitored	System leakage capaci- tance, max.	Adjustment range of the specified response value R <sub>an</sub> (threshold)	Type	Order code	Weight (1 pc) kg (lb)
CM-IWS.x	24-240 V AC/DC	0-250 V AC / 0-300 V DC	10 μF	1-100 kΩ	CM-IWS.1S	1SVR730660R0100	0.148 (0.326)
					CM-IWS.1P	1SVR740660R0100	0.137 (0.302)
		0-400 V AC			CM-IWS.2S	1SVR730670R0200	0.141 (0.311)
					CM-IWS.2P	1SVR740670R0200	0.130 (0.287)
CM-IWN.x		0-400 V AC / 0-600 V DC	20 μF	1-100 kΩ 2-200 kΩ	CM-IWN.1S	1SVR750660R0200	0.241 (0.531)
					CM-IWN.1P	1SVR760660R0200	0.217 (0.478)
CM-IWM.x	24 V DC	0-690 V AC/DC <sup>1)</sup>	1000 μF	1-250 kΩ 20 kΩ-2 MΩ	CM-IWM.10	1SVR470670R1000	0.500 (1.1)
		0-1000 V AC/DC <sup>2)</sup>	3000 μF		CM-IWM.11	1SVR470670R1100	

- 1) Allowed voltage range of the supervised network: 0-760 V AC / 0-1000 V DC  $\,$
- 2) Allowed voltage range of the supervised network: 0-1100 V AC / 0-1500 V DC

## **Coupling unit**

Rated control supply voltage = measuring voltage	Nominal voltage U <sub>n</sub> of the distribution system to be monitored	Туре	Order code	Weight (1 pc)
				kg (lb)
Passive device, no control supply voltage needed	0-690 V AC / 0-1000 V DC	CM-IVN.S	1SVR750669R9400	0.179 (0.395)
		CM-IVN.P	1SVR760669R9400	0.165 (0.364)

P: push-in connection



Technical data - CM-IWx

Data at  $T_a$  = 25 °C and rated values, unless otherwise indicated

		CM-IWS.2	CM-IWS.1	CM-IWN.1		
Input circuit - Supply circuit		A1 - A2	J	J		
Rated control supply voltage U <sub>s</sub>		24-240 V AC/DC				
Rated control supply voltage tolerance		-15+10 %				
	24 \ DC		25 m / / 0 0 \/ /	EE m A / 1 2 \/A		
Typical current / power consumption		30 mA / 0.7 VA	35 mA / 0.9 VA	55 mA / 1.3 VA		
		12 mA / 1.4 VA	17 mA / 2.0 VA	20 mA / 2.3 VA		
	230 V AC	12 mA / 2.8 VA	14 mA / 3.2 VA	15 mA / 3.5 VA		
Rated frequency f <sub>s</sub>		DC or 15-400 Hz				
Frequency range AC		13.5-440 Hz				
Power failure buffering time	min.	20 ms				
Start-up time t <sub>s</sub> , fixed		min. 10 s	max. 15 s	min. 15 s		
Input circuit - Measuring circuit		L, <del>+</del>	L+, L-, +, KE	L+, L-, +, KE		
Monitoring function		insulation resistance n	nonitoring of IT systems			
Measuring principle		superimposed DC volta	age prognostic measuring square wave signal	principle with superimposed		
Nominal voltage $U_n$ of the distribution system to	be monitored	0-400 V AC	0-250 V AC / 0-300 V DC	0-400 V AC / 0-600 V DC		
Voltage range of the distribution system to be n	nonitored	0-460 V AC (tolerance +15 %)	0-287.5 V AC / 0-345 V DC (tolerance +15 %)	0-460 V AC / 0-690 V DC (tolerance +15 %)		
Rated frequency $f_N$ of the distribution system to	be monitored	50-60 Hz	DC or 15-400 Hz	DC or 15-400 Hz		
System leakage capacitance C <sub>e</sub>	max.	<b>10</b> μ <b>F</b>		20 μF		
Tolerance of the rated frequency f <sub>N</sub>		45-65 Hz	13.5-440 Hz	13.5-440 Hz		
Extraneous DC voltage U <sub>fq</sub>	max	none	290 V DC	460 V DC		
(when connected to an AC system)	max.	none	250 V DC	400 1 20		
Number of possible response / threshold values		1		2		
Adjustment range of the specified response	minmax.	1-100 Ω				
value R <sub>an</sub> (threshold)	min,-max. R1			1-100 kΩ		
u. (* ,	min,-max. R2			2-200 k $\Omega$ (activated / de-		
	IIIIIIIIax. RZ	_		activated by DIP-switch)		
Adjustment resolution		1 kΩ	activated by Dir Switchy			
Adjustifiert resolution				1 kΩ		
		1 kΩ				
Talana a a a fabra a dissata dabana balaharaha d	R2			2 kΩ		
Tolerance of the adjusted threshold value / Relative percentage uncertainty A at	at 1-10 kΩ R <sub>F</sub> (yellow	≥ 15 %, max. ±0.5 kΩ		$\geq$ 15 %, max. ± 1 k $\Omega$ , with CM-IVN ± 1.5 k $\Omega$		
-5+45 °C	marked scale)			CI-1 1V 1V = 1.5 K22		
U <sub>n</sub> = 0-115 %	at 10-100 kΩ	±6 %		_		
U <sub>s</sub> = 85-110 %,	R <sub>F</sub>					
$f_N$ , $f_s$ , $C_e = 1 \mu F$	at 1-15 kΩ R <sub>F</sub>	-		$\pm$ 1 kΩ, with CM-IVN $\pm$ 1.5 kΩ		
	at 15-200 kΩ	_		±8 %		
	R <sub>F</sub>					
Hysteresis related to the threshold value		25 %; min. 2 kΩ		'		
Internal impedance Z <sub>i</sub>	at 50 Hz	135 kΩ	100 kΩ	155 kΩ		
Internal DC resistance R <sub>i</sub>		185 kΩ	115 kΩ	185 kΩ		
Measuring voltage U <sub>m</sub>		15 V	22 V	24 V		
Tolerance of measuring voltage U <sub>m</sub>		+10 %				
Measuring current I <sub>m</sub>	max.		0.3 mA	0.15 mA		
Response time t <sub>an</sub>			1			
	x R <sub>an</sub> and C <sub>e</sub> = 1 µF	max. 10 s				
system						
DC system or AC system wit rectifiers	in connected	- max. 15 s				
Repeat accuracy (constant parameters)		< 0.1 % of full scale				
Accuracy of $R_a$ (measured value) within the rated voltage tolerance	l control supply	< 0.05 % of full scale				
Accuracy of R <sub>a</sub> (measured	at 1-10 k $\Omega$ R <sub>F</sub>	5Ω/K				
value) within the operation	at 10-100 k $\Omega$ R <sub>F</sub>	0.05 % / K		-		
temperature range	at 10-200 kΩ R <sub>F</sub>			0.05 % / K		
			<u> </u>			

Technical data - CM-IWx

		CM-IWS.2	CM-IWS.1		CM-IWN.1	
Input circuit - Control circuits		S1 - S2 - S3	,		•	
Control inputs - volt free	S1-S3	remote test				
	S2-S3	remote reset				
Maximum switching current in	the control circuit	1 mA				
Maximum cable length to the c		50 m - 100 pF/m [164 ft - 30.5 pF/ft]				
Minimum control pulse length	•	150 ms				
No-load voltage at the control	input	≤ 24 V ± 5 %	≤ 24 V DC			
Indication of operational state		J.				
Control supply voltage		LED U (green)				
Fault message		LED F (red)				
<u> </u>		LED R (yellow)				
Output circuits						
Kind of output		relay, 1 c/o (SPDT) contact			2 x 1 or 1 x 2 c/o (SPDT	
Killa of output		relay, 1 e/o (51 D1) contact			contacts configurable	
Operating principle		closed-circuit principle <sup>1)</sup>			open- or closed circuit principle configurable <sup>1)</sup>	
Contact material		AgNi alloy, Cd free				
Min. switching voltage / Min. s	24 V / 10 mA					
3 3 .		see data sheet				
Rated operational voltage U <sub>e</sub>	AC-12 (resistive) at 230 V	4 A				
and rated operational	AC-15 (inductive) at 230 V	3 A				
current l <sub>e</sub>	DC-12 (resistive) at 24 V	4 A				
-	DC-13 (inductive) at 24 V	2 A				
AC rating (UL 508)	Utilization category (Control Circuit Rating Code)	B 300, pilot duty general pu	urpose 250 V, 4	A, cos φ 0.75		
	max. rated operational voltage	250 V AC				
	max. continuous thermal current at B 300	t 4A				
-	max. making/breaking apparent power at B 300	3600/360 VA				
Mechanical lifetime	•	30 x 10 <sup>6</sup> switching cycles				
Electrical lifetime (AC-12, 230 \	/. 4 A)	0.1 x 10 <sup>6</sup> switching cycles				
Max. fuse rating to achieve sho	· ·	6 A fast-acting				
protection		10 A fast-acting				
Conventional thermal current I	·	4 A				
General data		1.7.	1			
Duty cycle		100 %				
Dimensions		see dimensional drawings				
Mounting		DIN rail (IEC/EN 60715), snap-on mounting without any tool				
Mounting position						
Minimum distance to other uni	ts vertical	any				
dir distance to other uni	horizontal			у	10 mm (0.39 in) at U <sub>n</sub> > 400 V	
Material of housing		UL 94 V-0				
Degree of protection	housing / terminal					
Electrical connection	aasing / terminal					
		Screw connection technol	nav	Easy Conne	ct Technology (Push-in)	
Wire size		1 x 0.5-2.5 mm <sup>2</sup> (1 x 18-14 AWG) 2 x 0			nm² (2 x 18-16 AWG)	
-		2 x 0.5-1.5 mm <sup>2</sup> (2 x 18-16 AWG) 1 x 0.5-4 mm <sup>2</sup> (1 x 20-12 AWG) 2 x 0.5 3.5 mm <sup>2</sup> (2 x 30.14 AWG)		2 x 0.5-1.5 m	nm² (2 x 20-16 AWG)	
		2 x 0.5-2.5 mm <sup>2</sup> (2 x 20-14 AWG)				
Stripping length	8 mm (0.32 in) 0.6-0.8 Nm (5.31-7.08 lb.in)					

<sup>(</sup>i) Closed-circuit principle: Output relay(s) de-energize(s) if a fault is occurring Open-circuit principle: Output relay(s) energize(s) if a fault is occurring

Technical data - CM-IWx

		CM-IWS.2	CM-IWS.1	CM-IWN.1			
Environmental data			`	·			
Ambient temperature ranges	operation / storage / transport	-25+60 °C/-40+85 °C	C/-40+85 °C				
Climatic class	IEC/EN 60721-3-3	3K5 (no condensation, no ice formation)					
Damp heat, cyclic	IEC/EN 60068-2-30	6 x 24 h cycle, 55 °C, 95 % RH					
Vibration, sinusoidal		25 Hz: 2.5 g					
Isolation data		•					
Rated impulse withstand	supply / measuring circuit	6 kV					
voltage U <sub>imp</sub>	supply / output circuit	6 kV					
_	measuring / output circuit	6 kV					
_	output 1 / output circuit 2			4 kV			
Rated insulation voltage U <sub>i</sub>	supply / measuring circuit	400 V	300 V	600 V			
_	supply / output circuit	300 V		<u>'</u>			
_	supply / measuring circuit	400 V	300 V	600 V			
_	output 1 / output circuit 2	-	-	300 V			
Basis insulation	supply / measuring circuit	400 V AC / 300 V DC	250 V AC / 300 V DC	400 V AC / 600 V DC			
_	supply / output circuit	250 V AC / 300 V DC		<u>'</u>			
	measuring / output circuit	400 V AC / 300 V DC	250 V AC / 300 V DC	400 V AC / 600 V DC			
output 1 / output 2		250 V AC / 300 V DC		'			
Protective separation	supply / output circuit	250 V AC / 250 V DC					
(IEC/EN 61140)	supply / measuring circuit	250 V AC / 250 V DC					
_	measuring / output circuit	250 V AC / 250 V DC					
Pollution degree		3					
Overvoltage category		III					
Standards / Directives							
Standards		IEC/EN 60947-5-1, IEC/	EN 61557-1, IEC/EN 61557-8				
Low Voltage Directive		2014/35/EU					
EMC Directive		2014/30/EU					
RoHS Directive		2011/65/EU					
Electromagnetic compatibility							
Interference immunity to		IEC/EN 61000-6-2, IEC/EN 61326-2-4					
electrostatic discharge	IEC/EN 61000-4-2	level 3, 6 kV / 8 kV					
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3, 10 V/m (1 GHz) / 3 V/m (2 GHz) / 1 V/m (2.7 GHz)					
electrical fast transient/burs	t IEC/EN 61000-4-4	level 3, 2 kV / 5 kHz					
surge	IEC/EN 61000-4-5	level 3, installation class 3, supply circuit and measuring circuit 1 kV L-L, 2 kV L-eart					
conducted disturbances, induced by IEC/EN 61000-4-6 radio-frequency fields		level 3, 10 V					
voltage dips, short interrupti voltage variations	ons and IEC/EN 61000-4-11	class 3					
harmonics and interharmonic	is IEC/EN 61000-4-13	class 3					
Interference emissions		IEC/EN 61000-6-3					
high-frequency radiated	IEC/CISPR 22, EN 55022	class B					
high-frequency conducted	IEC/CISPR 22, EN 55022	class B					

Technical data - CM-IVN

	CM-IVN
Input circuit - Measuring circuit	VL+, VL-, V±
Function	expansion of the nominal voltage range of the insulation monitoring relay CM-IWN to 690 V AC or 1000 V DC, max. length of connection cable 40 cm
Measuring principle	see CM-IWN
Nominal voltage U <sub>n</sub> of the distribution system to be monitored	0-690 V AC / 0-1000 V DC
Voltage range of the distribution system to be monitored	0-793.5 V AC / 0-1150 V DC (tolerance +15 %)
Rated frequency f <sub>N</sub> of the distribution system to be monitored	DC or 15-400 Hz
Tolerance of the rated frequency f <sub>N</sub>	13.5-440 Hz
System leakage capacitance C <sub>e</sub> max.	identical to that of the insulation monitoring relay used
	793.5 V DC
Tolerance of the adjusted threshold value / at 1-15 $k\Omega$ $R_F$	±1.5 kΩ
Relative percentage uncertainty A at $$\rm at~15\text{-}200~k\Omega~R_{\rm F}~15\text{-}+~45~C,~U_n=0\text{-}115~\%,~U_s=85\text{-}110~\%,}$	±8 %
$f_N$ , $f_s$ , $C_e = 1 \mu F$	
Internal impedance Z <sub>i</sub> at 50 Hz	
Internal DC resistance R <sub>i</sub>	200 kΩ
Measuring voltage U <sub>m</sub>	24 V
Tolerance of measuring voltage U <sub>m</sub>	+10 %
Measuring current I <sub>m</sub>	0.15 mA
General data	
MTBF	on request
Duty cycle	100 %
Dimensions	see dimensional drawings
Mounting	DIN rail (IEC/EN 60715), snap-on mounting without any tool
Mounting position	any
Minimum distance to other units vertical	not necessary
horizontal	10 mm (0.39 in) at U <sub>n</sub> > 600 V
Degree of protection	IP50 / IP20
Electrical connection	
Wire size fine-strand with(out) wire end ferrule	2 x 0.75-2.5 mm² (2 x 18-14 AWG)
rigid	2 x 0.5-4 mm <sup>2</sup> (2 x 20-12 AWG)
Stripping length	7 mm (0.28 ln)
Tightening torque	0.6-0.8 Nm (5.31-7.08 lb.ln)
Max. length of connection cable to CM-IWN	40 cm
Environmental data	
Ambient temperature ranges operation / storage / transport	-25+60 °C / -40+85 °C / -40+85 °C
Climatic category IEC/EN 60721-3-3	3K5 (no condensation, no ice formation)
	6 x 24 h cycle, 55 °C, 95 % RH
Vibration, sinusoidal IEC/EN 60255-21-1	-
Shock, half-sine IEC/EN 60255-21-2	
Isolation data	
Rated impulse withstand voltage U <sub>imp</sub> input circuit / PE	8 kV
Rated insulation voltage U <sub>i</sub> input circuit / PE	
Pollution degree	3
Overvoltage category	III
Standards / Directives	l
Standards	IEC/EN 60947-5-1, IEC/EN 61557-1, IEC/EN 61557-8
Low Voltage Directive	2014/35/EU
EMC Directive	2014/30/EU
RoHS Directive	2011/65/EU

Technical data - CM-IVN

		CM-IVN
Electromagnetic compatibility		
nterference immunity to		IEC/EN 61000-6-2, IEC/EN 61326-2-4
electrostatic discharge	IEC/EN 61000-4-2	level 3, 6 kV / 8 kV
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3, 10 V/m (1 GHz) / 3 V/m (2 GHz) / 1 V/m (2.7 GHz)
electrical fast transient/burst	IEC/EN 61000-4-4	level 3, 2 kV / 5 kHz
surge	IEC/EN 61000-4-5	level 3, installation class 3, supply circuit and measuring circuit 1 kV L-L, 2 kV L-earth
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	level 3
harmonics and interharmonics	IEC/EN 61000-4-13	level 3
nterference emission		IEC/EN 61000-6-3
high-frequency radiated	IEC/CISPR 22, EN 50022	class B
high-frequency conducted	IEC/CISPR 22, EN 50022	class B

Technical data - CM-IWM

		CM-IWM.10	CM-IWM.11		
Input circuit					
Rated control supply voltage U <sub>s</sub>		24 V DC			
Voltage range		20-30 V DC			
Typical power consumption		max. 5 W			
Measuring circuit		L(+) / L(-) to PE / KE			
Nominal voltage U <sub>N</sub>		0-690 V AC/DC	0-1000 V AC/DC		
Allowed voltage range of the supervised n	etwork	0-760 V AC / 0-1000 V DC	0-1100 V AC / 0-1500 V DC		
Frequency range		DC or 16-1000 Hz	DC or 16-1000 Hz		
Max. system leakage capacitance C <sub>e</sub>		1000 μF	3000 μF		
Internal resistance (AC/DC)		> 280 kΩ			
Measuring voltage		approx. ± 95 V			
Max. measured current (R <sub>E</sub> = 0)		< 0.35 mA			
Response values R <sub>E</sub>					
each adjustable via rotary switches	pre-warning ("VW")	warning ("AI")			
_	20 kΩ				
_	30 kΩ	3 kΩ			
_		10 kΩ			
_		20 kΩ			
_	100 kΩ				
		50 kΩ			
	250 kΩ	2 70 kΩ			
_		100 kΩ			
_	1000 kΩ				
_	2000 kΩ				
Response inaccuracy		± 15 % + 1.5 kΩ			
Response value hysteresis	at range 10 kΩ 700 kΩ	approx. 25 %			
_	out of range:	approx. 40 % + 0.5 kΩ			
ON delay	at $C_E = 1 \mu F$	< 10 s			
	R <sub>E</sub> of ∞ to 0.5 * response value				
Control input		between T, R and G	between HM, T, R and G		
Current flow		approx. 3 mA	,		
No-load voltage to ground		approx. 12 V			
Permissible wire length		< 50 m			
Min. activation time		0.5 s			
Output					
Contacts		2 x 1 c/o contacts for VW and	i AL		
Thermal current I <sub>th</sub>		4 A			
Switching capacity to AC-15	n/o contact	3 A / AC 230 V acc. to IEC/EN	60947-5-1		
_	n/c contact	1 A / AC 230 V acc. to IEC/EN	60947-5-1		
Electrical life	at 8 A, AC 250 V	1 x 10 <sup>4</sup> switching cycles			
Short circuit strength max. fuse rating		4 A gL acc. to IEC/EN 60947-	5-1		
Mechanical life		10 x 10 <sup>6</sup> switching cycles			

Technical data - CM-IWM

		CM-IWM.10	CM-IWM.11
General Data		,	,
Operating mode		continuous operation	
Temperature range	operation	- 25 + 60 °C	- 25 + 60 °C (device mounted away from heat generation components) -25 +45 °C (device mounted without distance to other devices)
	storage	- 40 + 70 °C	
Relative air humidity		93 % at 40 °C	
Atmospheric pressure		860-1600 mbar (86-106 k	(Pa)
Altitude	IEC/EN 60664-1	< 4000 m	
Clearance and creepage distances			
Rated impulse voltage / pollution d		IEC/EN 60664-1	
Measuring ciruit L(+) / L(-) to	auxiliary voltage DC and relay contacts VW, AL		
	auxiliary voltage DC to relay contacts VW, AL	8 kV / 2	
	relay contacts VW to relay contact AL		
Insulation test voltage, routine test		AC 5 kV; 1 s AC 2.5 kV; 1 s	
Technical data			
EMC			
Electrostatic discharge (ESD)	IEC/EN 61000-4-2	-2 8 kV (air)	
HF irradiation	IEC/EN 61000-4-3	80 MHz-2.7 GHz: 10 V/m	
Fast transients	IEC/EN 61000-4-4	4 kV	
Surge voltages		4-5 between A1 - A2: 1 kV L(+) - L(-): 2 kV A1, A2 - PE: 4 kV L(+), L(-) - PE: 4 kV control line: 0.5 kV control line and earth: 1 kV	
HF-wire guided	IEC/EN 61000-4-6	10 V	
Interference suppression	EN 55011	limit value class A when connected to a low voltage public system (Class B, EN 55011) radio interference can be genera To avoid this, appropriate measures have to be taken	
Degree of protection			
Housing	IEC/EN 60529		
Terminals	IEC/EN 60529		
Housing Vibration resistance	IEC/EN 60068-2-6	thermpolastic with V0 behaviour according to UL subject 94 6 10-55 Hz: 0.35 mm 2-13.2 Hz: ± 1 mm 13.2-100 Hz: ± 7 g	
Shock resistance	IEC/EN 60068-2-27		
Climate resistance	IEC/EN 60068-1	-	
Terminal designation		EN 50005	
Connecting capacity		1 x 4 mm² solid	
		1 x 2.5 mm <sup>2</sup> stranded ferr 2 x 1.5 mm <sup>2</sup> stranded ferr DIN 46228-1/-2/-3-4 2 x 2.5 mm <sup>2</sup> stranded ferr	ruled (isolated)
		DIN 46228-1/-2/-3	
Stripping length		8 mm	
Tightening torque			
Wire fixing	IEC/EN 50745		vs M3.5 terminal with wire protection
Mounting	IEC/EN 60715		
Dimensions	width x height x depth	30 X 30 X 121 mm	

# Technical diagrams

## LEDs, status information and fault messages

### CM-IWN.x

Operational state	LED U (green)	LED F (red)	LED R (yellow)
Start-up	ПП	OFF	OFF
No fault		OFF	(1)
Prewarning		ПП	ПП
Insulation fault (below threshold value)			(1)
KE/+ wire interruption		$\mathcal{L}$	(1)
L+/L- wire interruption during system start-up / test function	/ \unu		(1)
System leakage capacitance too high / invalid measurement result	Г	л_п_	(1)
Internal system fault	(1)	MML	(1)
Setting fault (2)	ПЛ	ПП	пп
Test function	MM	OFF	(1)
No fault after fault storage (3)		(4)	ллл

### CM-IWS.x

Operational state	LED U (green)	LED F (red)	LED R (yellow)
Start-up		OFF	OFF
No fault		OFF	
Insulation fault (below threshold value)			OFF
Invalid measuring result		л_л_	OFF
KE/+ wire interruption (only CM-IWS. (1)	П	ллл_	OFF
CM-IWS.1: System leakage capacitance too high / invalid measurement result	MML		OFF
CM-IWS.2: Invalid measurement result		Л_Л_	OFF
Internal system fault	OFF	ллл	OFF
Test function	ллл	OFF	OFF
No fault after fault storage (3)		(4)	M

## CM-IWM.x

LED status	LED	Status
PWR: green LED		Control supply voltage applied
ERR: red LED		Internal device error
		Connection error L+/L-
		Connection error PE/KE
Active: green LED	חחחת	Measuring phase with positive polarity
		Measuring phase with negative polarity
LED chain: yellow LED		8 LEDs indicate the current insulating resistance ( $\leq 10 \text{ k}\Omega \dots \geq 2 \text{ M}\Omega$ )
VW +: yellow LED		$R_{\rm E}$ lower than prewarning value to + potential
VW -: yellow LED		$R_{\epsilon}$ lower than prewarning value to - potential
VW + and VW -: yellow LED		AC fault / symmetric fault
AL +: red LED		$R_{E}$ lower than warning value to + potential
AL -: red LED		R <sub>E</sub> lower than warning value to - potential
AL + and AL -: red LED		AC fault / symmetric fault

<sup>(1)</sup> Depending on the configuration.
(2) Possible faulty setting: The threshold value for final switch-off is set at a higher value than the threshold value for prewarning
(3) The device has triggered after an insulation fault. The fault has been stored and the insulation resistance has returned to a higher value than the threshold value


<sup>(4)</sup> Depending on the fault

# Technical diagrams

### \_

## **Connection diagrams**

## CM-IWS.2




A1-A2	Control supply voltage
S1-S3	Remote test
S2-S3	Remote reset
L	Measuring circuit/input, system connection
÷	Measuring circuit/input, earth connections
11-12/14	Output relay, closed-circuit principle

## CM-IWS.1

A1	11	KE	
S1	S2	S3	
L+ L- I R <	Щ	11     /-    12 14	2CDC 252 103 F0009
L+	L-	Ť	255
14	12	A2	SC


A1-A2	Control supply voltage
S1-S3	Remote test
S2-S3	Remote reset
L+, L-	Measuring circuit/input, system connection
÷, KE	Measuring circuit/input, earth connections
1-12/14	Output relay, closed-circuit principle

## CM-IWN.1



A1-A2	Control supply voltage
S1-S3	Remote test
S2-S3	Remote reset
L+, L-	Measuring circuit/input, system connection
÷, KE	Measuring circuit/input, earth connections
VS, V1+, V1	Connections for the coupling unit (if used)
11-12/14	Output relay 1, open- or closed-circuit principle
21-22/24	Output relay 2, open- or closed-circuit principle

## CM-IVN




VE	Connection to CM-IWN.x - ±
	Connection to CM-IWW.X - 9
VS	Connection to CM-IWN.x - VS
L+	Connection to CM-IWN.x - L+
V1+	Connection to CM-IWN.x - V1+
L-	Connection to CM-IWN.x - L-
V1-	Connection to CM-IWN.x - V1-
VL+	Measuring circuit / Measuring input,
VL-	Connection to the system
V±	Measuring circuit / Measuring input, Connection to earth

Technical diagrams


## **Connection diagrams**

## CM-IWM.10



Terminal designation	Signal designation	
A1+, A2	Control supply voltage	
L(+), L(-)	Connection for measuring ciruit	
KE, PE	Connection for protective conductor	
G, R	Control input (manual/auto reset) G/R not jumpered: manual reset G/R jumpered: auto reset	
G, T	Control input (External test input) connection for an external device test pushbutton	
11-12/14	Output relay 1 (warning)	
21-22/24	Output relay 2 (prewarning)	

## CM-IWM.11



Terminal designation	Signal designation	
A1+, A2	Control supply voltage	
L(+), L(-)	Connection for measuring ciruit	
KE, PE	Connection for protective conductor	
G, R	Control input (manual/auto reset) G/R not jumpered: manual reset G/R jumpered: auto reset	
G, T	Control input (External test input) connection for an external device test pushbutton	
G, HM	Control input (measuring circuit deactivation)  G/HM not jumpered: measuring circuit activated  G/HM jumpered: measuring circuit deactivated	
11-12/14	Output relay 1 (warning)	
21-22/24	Output relay 2 (prewarning)	

### \_

# Insulation monitoring relays

Technical diagrams

## **DIP** switches

## CM-IWN.1

Position	4	3	2	1
ON ↑	2x1 c/o			closed
OFF	1x2 c/o		M	open

	ON	OFF (default)
DIP switch 1 Operating principle of the output relays	Closed-circuit principle  If closed-circuit principle is selected, the output relays de-energize in case a fault is occurring. In non-fault state the relays are energized.	Open-circuit principle [=] If open-circuit principle is selected, the output relays energize in case a fault is occurring. In non-fault state the relays are de-energized.
<b>DIP switch 2</b> Non-volatile fault storage	Fault storage activated (latching)  If the fault storage function is activated, the output relays remain in tripped position until a reset is done either by the front-face button or by the remote reset connection S2-S3. This function is non-volatile.	Fault storage de-activated (non latching)   If the fault storage function is deactivated, the output relays switch back to their original position as soon as the insulation fault no longer exists.
DIP switch 3 Interrupted wire detection	Interrupted wire detection activated  with this configuration, the CM- IWN.1 monitoring relays the wires connected to  and KE for interruptions.	Interrupted wire detection de- activated Muith this configuration the interrupted wire detection is de-activated.
DIP switch 4 2 x 1 c/o, 1 x 2 c/o	2 x 1 c/o (SPDT) contact [27.0] If operating principle 2 x 1 c/o contact is selected, the output relay R1 (11-12/14) reacts to threshold value R1 (final switch-off) and the output relay R2 (21-22/24) reacts to threshold value R2 (prewarning)	1 x 2 c/o (SPDT) contacts [250] If operating principle 1 x 2 c/o contacts is selected, both output relays R1 (11-12/14) and R2 (21-22/24) react synchronously to threshold value R1. Settings of the threshold value R2 have no effect on the operation.

### \_


# Insulation monitoring relays

Technical diagrams

## Wiring diagrams

CM-IWS.1

Always connect L+ and L- to different conductors. L+ and L- can be connected to any of the conductors.  $U_n \le 250 \text{ V AC}$ ; 300 V DC





Technical diagrams

Wiring diagrams


CM-IWS.2

L can be connected to any of the conductors.  $U_n \leq 400 \ V \ AC$ 





3-wire AC system



4-wire AC system

### \_ \_


# Insulation monitoring relays

Technical diagrams

## Wiring diagrams


CM-IWN.1

Always connect L+ and L- to different conductors. L+ and L- can be connected to any of the conductors.  $U_n \le 400 \text{ V}$  AC; 600 V DC (For monitoring of systems with higher voltages, use coupling unit CM-IVN.)




Technical diagrams

## Wiring diagrams CM-IWM.10




Example of a AC application




Example of a DC application

### CM-IWM.11



Example of a AC application



\*) G-HM connected: Measuring circuit is off

Example of a DC application


C252006F0016

Technical diagrams


## **Dimensional drawings**

in **mm** and inches


## CM-IWS.x





**Accessories** 



ADP.01 - Adapter for screw mounting








Technical diagrams

# Dimensional drawings


in **mm** and inches

CM-IWN.x




### CM-IWN.x


## Accessories




ADP.02 - Adapter for screw mounting



MAR.12 - Marker label for devices with DIP switches



COV.12 - Sealable transparent cover



# **Thermistor motor protection relays**Table of contents

102	belieffts and advantages
183	Applications
184	Features
186	Offer overview
188	Operating controls
189	Selection table
190	Ordering details
192	Technical data
199	Technical diagrams

## Benefits and advantages



The thermistor motor protection relays of the CM-MSx range protect motors with PTC sensors against high temperature. These sensors are incorporated in the motor windings, thus measuring the motor heat directly.



By using thermistor motor protection relays from ABB, the down and commissioning time can be reduced. The relay is continuously monitoring the sensor circuit to detect short-circuit or interrupted i.e. wire faults, thus contributing to maintenance and time saving in case of faults. In addition, the clear error messages of the front LEDs makes it possible to distinguish between the various fault causes.



Direct motor protection through temperature monitoring of the motor winding offers 100 % motor protection, even under the most difficult ambient conditions. The ABB thermistor motor protection relays give you access to worldwide markets and are approved by local and international standards for many applications such as industry, renewable energies, the marine sector and dangerous and explosive environments. To prove that, the CM-MSS thermistor motor protection relays are certified according to ATEX Ex II (2) G and D for environments with explosive gas or dust loads.



Due to the compliance with the latest standards, there is no need to make any adjustments on the device. All relays come with two different connection possibilities - screw or push-in - to make any adjustments on the installation a breeze. Thanks to direct measurement of the motor temperature, dimensioning of the thermistor motor protection relay, considering the size of the motor, is not necessary.


## **Applications**



#### Direct temperature monitoring

Generally, motor damage caused by overload or overheating situations can be prevented in different ways. Compared to the indirect temperature measuring which monitors the motor current, the temperature inside the motor can be measured by direct temperature measuring. This enables direct control and evaluation of different operating conditions:

Therefore, the consequences from overheating, such as abrasion as well as electrical failures, can be prevented. The direct measuring principle is carried out by a combination of the thermistor motor protection relay and three PTC sensors which are installed directly in the motor by the manufacturer. Those 3 PTC sensors are placed directly at the thermal hotspots, the motor windings.





#### Motor protection using current- and temperature-dependent protective devices

IEC 60204 stipulates that motors must be protected from overheating at a rating of 0.5 kW and higher. The protection can be provided or executed by overload protection, overtemperature protection or current limiting. For motors with frequent starting and braking, and in environments where cooling may be impaired (e.g. by dust), it is recommended to use the overtemperature protection option in the form of a protective device coordinated with this mode of operation.

On rotor-critical motors, overtemperature detection in the stator windings can lead to delayed and hence inadequate protection. In this case, the standards stipulate additional protection, e.g. by means of an overload relay. This combination of thermistor motor protection and an overload relay is recommended for full motor protection in case of frequent starting and braking of motors, irregular intermittent duty or excessive switching frequency.



#### Operating mode

The thermistor motor protection relays are used to monitor the temperature of motors or generators equipped with PTC sensors type A according to the latest product standard IEC/EN 60947-8. The sensors are built-in into the motor windings, measuring the motor heating. In case of an increase of the temperature in the motor, the resistance of the PTC sensors increases as well. If the motor heats-up excessively (>2.83 k $\Omega$ ), the output relay(s) de-energize(s) and the corresponding LED displays the overtemperature. A short circuit and an interrupted wire within the sensor circuit can also be detected. A reset is only possible after cooling down of the motor (<1.1 k $\Omega$ ) or after a wire interruption, or a short circuit within the sensor circuit has been removed. A reset after tripping can be done manually with the Test / Reset button, externally with a push button between S1 and 1T2/2T2, or automatically by jumpering S1-1T2/2T2.

## **Features**



#### **Test function**

The test function is only possible when there is no fault. By pressing the front-face combined Test / Reset button, a system test routine is executed. If the function "Remote Test / Reset" (DIP switch 4) is activated, the system test routine is also possible via control input S1-T2 (S1-1T2/2T2\*).

After starting the test routine, the output relays de-energize. They remain de-energized until the Test / Reset button is pressed again or control input S1-T2 (S1-1T2/2T2\*) is closed (remote reset).

#### Short-circuit detection 🕶 🗵

If a short circuit is detected between the two lines of a sensor circuit, the output relay(s) de-energize(s) and the LEDs will display the specific error code.

#### Dynamic interrupted wire detection

During the operation, the device is permanently monitoring the measuring circuit. If the resistance in the measuring circuit rises, the device distinguishes if there is an overtemperature or an interrupted wire.



#### Fault storage \_\_\_\_, reset function

The fault storage is designed as non-volatile (remanent). This means that after switch-off and return of the control supply voltage the device returns to the state it was prior to the switch-off. If there was no fault prior to the interruption of the control supply voltage, the device restarts automatically after re-applying control supply voltage.

If there was a fault prior to the interruption, reset can be reset manually by the Test / Reset button or externally by remote reset between S1-T2 (S1-1T2/2T2\*). With deactivated fault storage, reset can be made manually by the Test / Reset button, automatically by jumpering S1-T2 (S1-1T2/2T2\*) or externally by remote reset between S1-T2 (S1-1T2/2T2\*). Depending on the configuration of DIP switch 1, there are several possibilities to reset the device as shown in the picture.

DIP switch 1	M	
S1 1T2/2T2	1.) Front 2.) Remote 3.) A1-A2	1.) Front 2.) Remote
S1 1T2/2T2	1.) Front 2.) A1-A2	1.) Front
S1 1T2/2T2	1.) Auto- Reset	

\*CM-MSS.51



## **Features**



#### Single and accumulative evaluation

#### Single evaluation 2x1 c/o

If a fault occurs in the measuring circuit 1, output relay 1 (11-12/14) de-energizes. If a fault occurs in the measuring circuit 2, output relay 2 (21-22/24) de-energizes.

#### Accumulative evaluation 1x2 c/o

In case of a fault in one of the two measuring circuits, both output relays de-energize synchronously.

#### Bimetallic switches

In some applications, bimetallic switches - such as Klixon - are used as sensors instead of PTC temperature sensors. Bimetallic switches are temperature and current dependent, normally closed contacts, and are available for different temperature ranges. Since bimetallic switches have almost no resistance below their opening temperature, short-circuit detection is not possible when bimetallic switches are used.



#### **ATEX** certification

Suitably selected and adjusted devices are necessary for the safe operation of explosion-protected motors. Only the sensor line is conducted into the explosive atmosphere. The motor protection relay itself must be installed outside the potentially explosive atmospheres. Marking:



II (2) G

II (2) D



#### **CM-MSS functionality video**







## Offer overview



#### CM-MSE

- Auto reset
- Connection of several sensors (max. 6 sensors connected in series)
- Monitoring of bimetals
- 1 n/o contact
- Excellent cost / performance ratio




#### CM-MSS 1)

- Different types of contacts available
  - 1 x 2 c/o (SPDT) contacts
  - $2 \times 1 c/o$  (SPDT) contact
  - $1\,\text{n/o}$  and  $1\,\text{n/c}$  contact
- 1 or 2 measuring circuits
- Different types of reset functions
  - Automatic
  - Manual
  - Remote
- Rated control supply voltages
  - 24 V AC/DC
  - 24-240 V AC/DC
  - 110-130 V AC, 220-240 V AC
- Various approvals and marks



## Operating controls



## Selection table

	Order code	15VPEF0800B0300	SVR550000R9500	1SVR550801R9300	1SVR740720R1400	1SVR730720R1400	1SVR740700R0100	1SVR730700R0100	1SVR740700R2100	1SVR730700R2100	1SVR740722R1400	1SVR730722R1400	1SVR740700R0200	1SVR730700R0200	1SVR740700R2200	1SVR730700R2200	1SVR740712R1400	1SVR730712R1400	1SVR740712R0200	1SVR730712R0200	1SVR740712R2200	1SVR730712R2200	1SVR740712R1200	1SVR730712R1200	1SVR740712R1300	1SVR730712R1300
	Type C			-	CM-MSS.11P 1	CM-MSS.11S 1	CM-MSS.12P 1	CM-MSS.12S 1	CM-MSS.13P 1	CM-MSS.13S 1	CM-MSS.21P 1	CM-MSS.21S 1	CM-MSS.22P 1	CM-MSS.22S 1	CM-MSS.23P 1	CM-MSS.23S 1	CM-MSS.31P 1	CM-MSS.31S 1	CM-MSS.32P 1	CM-MSS.32S 1	CM-MSS.33P 1	CM-MSS.33S 1	CM-MSS.41P 1	CM-MSS.41S 1	CM-MSS.51P 1	CM-MSS.51S 1
Characteristics																										_
ATEX approval	$\perp$				•	-					•	•					•	•	•	•	•	•	•	•	-	•
Number of sensor circuits		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	2	2
Single or accumulative evaluation																									•	•
Number of LEDs					3	3	2	2	2	2	3	3	2	2	2	2	3	3	3	3	3	3	3	3	3	3
Contacts																										
1 c/o (SPDT) contact							•	•	•	•																L
2 c/o (SPDT) contacts													•	•	-	•			•	•	•	•	•	•		L
1 n/o	!	• !		-																						
1 n/c and 1 n/o						•					•	•					•	•								
2 x 1 c/o or 1 x 2 c/o contacts, configurable																									•	•
Reset																										
Manual													•	•	-	•	•	•	•	•	•	•	•	•	•	•
Remote													•	•	-	•	•	•	•	•	•	•	•	•	•	
Auto	_   '	•		-	•	•	•	•	•	•	•	-	<b>(1</b> )	(1)	<b>(1)</b>	(1)	<b>(1</b> )	(1)	<b>(1</b> )	(1)	(1	(1)	(1)	<b>(1</b> )	(2	) =
Test button																	•			•				•		•
Functions																										
Short-circuit detection																										П
Short-circuit detection, configurable																									•	•
Dynamic interrupted wire detection						•					•															
Non-volatile fault storage						•					•	•					•									Г
Non-volatile fault storage, configurable																								•	•	
Rated control supply voltage U <sub>s</sub>																										
24 V AC	Ti																									
110-130 V AC			-																							
220-240 V AC				-																						
24-240 V AC/DC					•																					
24 V AC/DC							-																			
110-130 V AC, 220-240 V AC									-	-					-	•					•	-				
Connection type																										_
Push-in terminals							•								-											Т
Double-chamber cage connection terminals						•		•		•		-		•		•		•		•		-		•		•
	_		_	_					_	_			_	1				_			_	_	_			1

<sup>1)</sup> For automatic reset, connect terminals S1 to T2.

<sup>2)</sup> For automatic reset, connect Terminals S1 to 1T2/2T2.

#### \_

## Thermistor motor protection relays

## Ordering details



CM-MSS.12S

#### LM-M55.125



CM-MSS.41S



CM-MSS.51S

#### Description

The thermistor motor protection relay CM-MSS monitors the winding temperature and thus protects the motor from overheating, overload and insufficient cooling in accordance to the product standard IEC/EN 60947-8.

#### Ordering details

#### CM-MSx

Characteristics	Туре	Order code	Weight (1 pc) kg (lb)
See selection table	CM-MSE	1SVR550805R9300	0.11 (0.24)
	CM-MSE	1SVR550800R9300	0.11 (0.24)
	CM-MSE	1SVR550801R9300	0.11 (0.24)
	CM-MSS.11P	1SVR740720R1400	0.119 (0.263)
	CM-MSS.11S	1SVR730720R1400	0.127 (0.280)
	CM-MSS.12P	1SVR740700R0100	0.105 (0.231)
	CM-MSS.12S	1SVR730700R0100	0.113 (0.249)
	CM-MSS.13P	1SVR740700R2100	0.147 (0.324)
	CM-MSS.13S	1SVR730700R2100	0.155 (0.342)
	CM-MSS.21P	1SVR740722R1400	0.118 (0.260)
	CM-MSS.21S	1SVR730722R1400	0.126 (0.278)
	CM-MSS.22P	1SVR740700R0200	0.121 (0.267)
	CM-MSS.22S	1SVR730700R0200	0.132 (0.291)
	CM-MSS.23P	1SVR740700R2200	0.163 (0.359)
	CM-MSS.23S	1SVR730700R2200	0.174 (0.384)
	CM-MSS.31P	1SVR740712R1400	0.120 (0.265)
	CM-MSS.31S	1SVR730712R1400	0.128 (0.282)
	CM-MSS.32P	1SVR740712R0200	0.120 (0.265)
	CM-MSS.32S	1SVR730712R0200	0.130 (0.287)
	CM-MSS.33P	1SVR740712R2200	0.162 (0.357)
	CM-MSS.33S	1SVR730712R2200	0.172 (0.379)
	CM-MSS.41P	1SVR740712R1200	0.130 (0.287)
	CM-MSS.41S	1SVR730712R1200	0.141 (0.311)
	CM-MSS.51P	1SVR740712R1300	0.135 (0.298)
	CM-MSS.51S	1SVR730712R1300	0.145 (0.320)

S: screw connection

P: push-in connection


#### \_

### Thermistor motor protection relays

#### Ordering details - PTC temperature sensors C011



Temperature sensor example



Temperature sensor characteristics

#### Description

The PTC temperature sensors (temperature-dependent with positive temperature coefficient) are selected by the manufacturer of the motor depending on:

- the motor insulation class according to IEC/EN 60034-11,
- the special characteristics of the motor, such as the conductor cross-section of the windings, the permissible overload factor, etc.
- special conditions prescribed by the user, such as the permissible ambient temperature, risks resulting from locked rotor, extent of permitted overload, etc.

One temperature sensor must be embedded in each phase winding. For instance, in case of three-phase squirrel cage motors, three sensors are embedded in the stator windings. For pole-changing motors with one winding (Dahlander connection), three sensors are also required. Pole-changing motors with two windings, however, require six sensors. If an additional warning is required before the motor is switched off, separate sensors for a correspondingly lower temperature must be embedded in the winding. They have to be connected to a second control unit.

The sensors are suitable for embedding in motor windings with rated operating voltages of up to 600 V AC. Conductor length: 500 mm per sensor. A 14 V varistor can be connected in parallel to protect the sensors from overvoltage. Due to their characteristics, the thermistor motor protection relays can also be used with PTC temperature sensors of other manufacturers which comply with IEC/EN 60947-8.

#### Ordering details

#### **CM-MSS** accessories

Rated response temperature T <sub>NF</sub>	Color coding	Туре	Order code	Weight (1 pc) kg (lb)
70 °C	white-brown	C011-70 <sup>1)</sup>	GHC0110003R0001	0.02 (0.044)
80 °C	white-white	C011-80 <sup>1)</sup>	GHC0110003R0002	0.02 (0.044)
90 °C	green-green	C011-90 <sup>1)</sup>	GHC0110003R0003	0.02 (0.044)
100 °C	red-red	C011-100 <sup>1)</sup>	GHC0110003R0004	0.02 (0.044)
110 °C	brown-brown	C011-110 <sup>1)</sup>	GHC0110003R0005	0.02 (0.044)
120 °C	gray-gray	C011-120 <sup>1)</sup>	GHC0110003R0006	0.02 (0.044)
130 °C	blue-blue	C011-130 <sup>1)</sup>	GHC0110003R0007	0.02 (0.044)
140 °C	white-blue	C011-140 <sup>1)</sup>	GHC0110003R0011	0.02 (0.044)
150 °C	black-black	C011-150 <sup>1)</sup>	GHC0110003R0008	0.02 (0.044)
160 °C	blue-red	C011-160 <sup>1)</sup>	GHC0110003R0009	0.02 (0.044)
170 °C	white-green	C011-170 <sup>1)</sup>	GHC0110003R0010	0.02 (0.044)
150 °C	black-black	C011-3-150 <sup>2)</sup>	GHC0110033R0008	0.05 (0.11)

<sup>1)</sup> Temperature sensor C011, standard version acc. to IEC/EN 60947-8

<sup>2)</sup> Triple temperature sensor C011-3

Technical data - PTC temperature sensors C011

Characteristic data	Sensor type C011
Cold-state resistance	50 -100 Ω at 25 °C
Warm-state resistance $\pm$ 5 up to 6 K of rated response temperature $T_{\text{NF}}$	10 000 Ω
Thermal time constant, sensor open <sup>1)</sup>	<5s
Permitted ambient temperature	+180 °C

Rated response temperature	PTC resistance R from -20	PTC resistance R <sup>2)</sup> at PTC temperatures of:							
$\pm$ tolerance $T_{NF} \pm \Delta T_{NF}$	°C to T <sub>NF</sub> - 20 K	T <sub>NF</sub> - iT <sub>NF</sub> (UPTC ≤ 2.5 V)	$T_{NF} + iT_{NF}$ $(UPTC \le 2.5 \text{ V})$	T <sub>NF</sub> + 15 K (UPTC ≤ 7.5 V)					
70 ±5 °C	≤ 100 Ω	≤ 570 Ω	≥ 570 Ω	-					
80 ±5 °C									
90 ±5 °C		≤ 550 Ω	≥ 1330 Ω	≥ 4000 Ω					
100 ±5 °C									
110 ±5 °C									
120 ±5 °C									
130 ±5 °C	_								
140 ±5 °C	-								
150 ±5 °C	_								
160 ±5 °C									
170 ±7 °C	-	≤ 570 Ω	≥ 570 Ω	-					

<sup>1)</sup> Not embedded in windings.
2) For triple temperature sensor take values x 3.

Technical data - CM-MSS

Data at  $T_a$  = 25 °C and rated values, unless otherwise indicated

Туре		CM-MSS.x1	CM-MSS.x2	CM-MSS.x3			
Supply circuit - Inpu	t circuit	1					
Rated control supply		24-240 V AC/DC	24 V AC/DC	220-240 V AC			
,	A2-A3		-	110-130 V AC			
Rated control supply	voltage U <sub>s</sub> tolerance	-15+10 %					
Rated frequency		15-400 Hz	50-60 Hz				
	petween supply circuit and measuring circuit	yes	no	yes			
Power failure bufferi	· · · · · · · · · · · · · · · · · · ·	20 ms					
	suring circuit / Sensor circuit						
Number of circuits	3,	1 (CM-MSS.51: 2)					
Sensor type		PTC type A (IEC/EN 6	0947-8)				
	of sensors connected in series, cold state	< 750 Ω					
Overtemperature	switch-off resistance (relay de-energizes)		SS.12 /.13 /.22 /.23: 2.7 kΩ ±	5%)			
monitoring	switch-on resistance (relay energizes)		$5.12 / .13 / .22 / .23$ : 1.2 k $\Omega \pm 5$				
Maximum voltage in				,			
naximam voicage in		3.7 V					
		5.5 V					
Maximum current in		3.7 mA					
Maximum sensor cab			<sup>2</sup> , 2 x 400 m at 2.5 mm <sup>2</sup>				
			·				
	ated control supply voltage tolerance	0.50 % (CM-MSS.12 /.	2 /.13 /.22 /.23: 0.5 %/K)				
Accuracy within the t Repeat accuracy (cor	<u> </u>	on request	. /.13 /.22 /.23: U.S 70/K)				
Reaction time of the		< 100 ms					
Hardware fault tolera	<u> </u>						
Control circuit	ance (nr i )	0	,				
Control function		saa "Calastian tahla C	"M MCv rango"				
	ltage	see "Selection table C 5.5 V	.M-M5x range				
Maximum no-load vo	itage		12 /22 /22 1 2 4)				
Max. current	LL.	0.6 mA (CM-MSS.12 /.					
Maximum cable leng		2 x 100 m at 0.75 mm	<sup>2</sup> , 2 x 400 m at 2.5 mm <sup>2</sup>				
Indication of operat		150					
Control supply voltag	·	LED green					
Relay status		R LED yellow					
Fault message	F	LED red					
Output circuit							
Kind of output		see "Selection table C					
Operating principle		closed-circuit principle					
Contact material		AgNi alloy, Cd free					
	Itage U <sub>e</sub> (IEC/EN 60947-1)	250 V AC					
	voltage / Minimum switching current	24 V / 10 mA					
	voltage / Maximum switching current	see data sheet					
Rated operating curr (IEC/EN 60947-5-1)							
(ILC/EN 00347-3-1)	AC-15 (inductive) at 230 V						
	DC-12 (resistive) at 24 V						
	DC-13 (inductive) at 24 V						
AC Rating (UL 508)	utilization category (Control Circuit Rating Code)						
	maximum rated operational voltage						
	maximum continuous thermal current at B 300	5 A					
	maximum making/breaking apparent power at B 300						
	general purpose rating	250 V AC - 4 A					
Mechanical lifetime		30 x 10 <sup>6</sup> switching cyc	cles				
Electrical lifetime	at AC12, 230 V AC, 4 A	0.1 x 10 <sup>6</sup> switching cy	cles				
Maximum fuse ratino			MSS.12, CM-MSS.13, CM-MS	S.51: 6 A)			

#### \_

## Thermistor motor protection relays

Technical data - CM-MSS

Туре		CM-MSS.x1	CM-MSS.x2	CM-MSS.x3			
General data		•	*				
MTBF		on request					
Duty time		100 %					
Dimensions		see "Dimensional drawing:	5"				
Mounting		DIN rail (IEC/EN 60715), sn	ap-on mountin	g without any tool			
Mounting position		any					
Minimum distance to other	units vertical / horizontal	10 mm (0.394 in) if switchi	ng current > 2 A				
Material of housing		UL 94 V-0	-				
Degree of protection	housing	IP50					
	terminals	IP20					
Electrical connection		Screw connection technol	ogy	Easy Connect Technology (push-in			
Connection capacity	fine-strand with(out) wire end	1 x 0.5-2.5 mm² (1 x 18-14)	AWG)	2 x 0.5-1.5 mm² (2 x 18-16 AWG)			
	ferrule	2 x 0.5-1.5 mm² (2 x 18-16 /	AWG)				
	rigid	1 x 0.5-4 mm² (1 x 20-12 AV		2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG)			
		2 x 0.5-2.5 mm² (2 x 20-14 z	AWG)				
Stripping length		8 mm (0.32 in)					
Tightening torque		0.6-0.8 Nm (7.08 lb.in)		-			
Environmental data		,					
Ambient temperature range	s operation	i i					
	storage	-40+85 °C (-40+185 °F)					
Damp heat, cyclic (IEC/EN 6	0068-2-30)	6 x 24 h cycle, 55 °C, 95 % RH					
Climatic class (IEC/EN 6072	1-3-3)	3K5 (no condensation, no ice formation)					
Vibration, sinusoidal		5-13.2 Hz: ±1 mm; 13.2-100 Hz: 0.7 g					
Shock		Class 2					
Isolation data							
Rated insulation voltage	Supply circuit / Measuring circuit <sup>1)</sup>	300 V AC (CM-MSS.x2: n/a)					
Ui	Supply circuit / Output circuits	300 V AC					
_	Measuring circuit (1) / Output circuits	300 V AC					
_	Output circuit 1 / Output circuit 2	300 V AC					
Rated impulse withstand	Supply circuit / Measuring circuit <sup>1)</sup>	4 kV (CM-MSS.x2: n/a)					
voltage U <sub>imp</sub>	Supply circuit / Output circuits	4 kV					
_	Measuring circuit (1) / Output circuits	4 kV					
_	Output circuit 1 / Output circuit 2	2 4 kV					
Basic insulation	Supply circuit / Measuring circuit <sup>1)</sup>	600 V AC (CM-MSS.x2: n/a)					
	Supply circuit / Output circuits	600 V AC					
	Measuring circuit (1) / Output circuits	600 V AC					
_	Output circuit 1 / Output circuit 2						
Protective separation	Supply circuit / Measuring circuit <sup>1)</sup>	yes, up to 300 V					
(IEC/EN 61140)	Supply circuit / Output circuits						
_	Measuring circuit (1) / Output circuits						
_	Output circuit 1 / Output circuit 2	<del>-</del>					
Pollution degree (IEC/EN 60	· · · ·	3					
Overvoltage category (IEC/E		III					

#### Standards

Product standard	EN 60947-5-1, EN 60947-8
Low Voltage Directive	2014/35/EU
EMC directive	2014/30/EU
ATEX directive	2014/34/EU (only ATEX variants, see "Selection table CM-MSx range")
RoHS directive	2011/65/EU

Technical data - CM-MSS

Туре		CM-MSS.x1	CM-MSS.x2	CM-MSS.x3
Electromagnetic compatibility			·	
Interference immunity to		IEC/EN 61000-6-2, I	IEC/EN 60947-8	
electrostatic discharge	IEC/EN 61000-4-2	Level 3, 6 kV contact	t discharge, 8 kV air discharg	je
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	Level 3, 10 V/m (1 G	Hz), 3 V/m (2 GHz), 1 V/m (2.7	7 GHz)
electrical fast transient / burst	IEC/EN 61000-4-4	Level 3, 2 kV / 5 kHz		
surge	IEC/EN 61000-4-5	Level 3, Installation	class 3, supply circuit and me	asuring circuit 1 kV L-L, 2 kV L-N
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	Level 3, 0.15-80 MH:	z, 10 V, 80 % AM (1kHz)	
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	Class 3		
harmonics and interharmonics	IEC/EN 61000-4-13	Class 3		
Additional interference immunity acc IEC/EN 60255-1 (reference on IEC/EN	<b>5</b> .			
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	10 V/m (80 MHz - 3 (	GHz)	
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	10 V at stated frequ	encies	
damped oscillatory waves	IEC/EN 61000-4-18		tric coupling: 1 kV peak volta metric coupling: 2.5 kV peak	
Interference emissions		IEC/EN 61000-6-3		
high-frequency radiated	IEC/CISPR 22, EN 55022	Class B		
high-frequency conducted	IEC/CISPR 22, EN 55022	Class B		
high-frequency radiated	Germanischer Lloyd	increased requireme	ents in the emergency call fr	equency band

\_

## Thermistor motor protection relays

Technical data - CM-MSE

Data at  $T_a$  = 25 °C and rated values, unless otherwise indicated

Туре	na rated values, unless otr		CM-MSE
Supply circuit - Input of	circuit		CM-M3E
	oltage U <sub>s</sub> power consumption	1SVR550805R9300	24 V AC approx. 1.5 A
Rated control supply w	ortuge of power consumption _		110-130 V AC approx. 1.5 A
	_		220-240 V AC approx. 1.5 A
Rated control supply ve	oltaga II tolaranca	134K330601K9300	-15+10 %
Rated frequency	ortage os tolerance		50-60 Hz
Measuring circuit			30-00 HZ
Monitoring function		T1 T2	temperature monitoring by means of PTC sensors
Number of sensor circu	uite	11-12	1
Sensor circuit	uits		1
Sensor type			PTC type A (IEC/EN 60947-8)
	of sensors connected in series, c	old state	≤1.0 kΩ
		switch-off resistance	
Overtemperature mon		(relay de-energizes)	
		resistance (relay energizes)	
Maximum voltage in se	ensor circuit	4 kΩ	
		∞ kΩ	15 V
Maximum current in se	ensor circuit		2 mA
Maximum sensor cable	e length		2 x 100 m at 0.75 mm², 2 x 400 m at 2.5 mm²
Reaction time			<100 ms
Output circuit			
Kind of output		13-14	1 n/o contact
Operational principle			closed-circuit principle (output relay de-energizes if the measured value exceeds/drops below the adjusted threshold)
Maximum switching vo	oltage		250 V
Rated operating voltage	ge U <sub>e</sub> and	AC-12 (resistive) at 230 V	4 A
rated operating curren	nt I <sub>e</sub>	AC-15 (inductive) at 230 V	3 A
	_	DC-12 (resistive) at 24 V	4 A
	_	DC-13 (inductive) at 24 V	2 A
AC Rating (UL 508)	utilization category (	Control Circuit Rating Code)	B 300
	maximu	m rated operational voltage	300 V AC
	maximum continuo	ous thermal current at B 300	5 A
	maximum making/breaki	ing apparent power at B 300	3600/360 VA
		general purpose rating	250 V AC - 4 A
Mechanical lifetime			30 x 10 <sup>6</sup> switching cycles
Electrical lifetime		at AC12, 230 V AC, 4 A	0.1 x 10 <sup>6</sup> switching cycles
Maximum fuse rating t	to achieve	n/c contact	10 A fast-acting
short-circuit protectio		n/o contact	10 A fast-acting
General data		·	
Dimensions			see "dimensional drawings"
Duty cycle			100 %
Mounting			DIN rail (IEC/EN 60715)
Mounting position			any
Degree of protection		housing / terminals	-
Electrical connection			j ·· , ··
Connecting capacity	fine	strand with wire end ferrule	2 x 1.5 mm² (2 x 16 AWG)
g capacity			2 x 0.75-1.5 mm² (2 x 18-16 AWG)
	Time Str		2 x 1-1.5 mm² (2 x 18-16 AWG)
Stripping length		rigia	2 x 0.75-1.5 mm² (2 x 18-16 AWG)
Tightening torque			0.6-0.8 Nm (5.31-7.08 lb.in)
Environmental data			0.0-0.0 MIII (3.31-1.00 ID.III)
	ranges	On a nati - :-	20 160 %C
Ambient temperature	ranges	<u> </u>	-20+60 °C
<u> </u>			-40+85 °C
Damp heat		•	40 °C, 93 % RH, 4 days
Vibration withstand		IEC/EN 60062-2-6	10-57 Hz: 0.075 mm; 57-150 Hz: 1 g

Technical data - CM-MSE

Туре		CM-MSE
Isolation data		
Rated insulation voltage U <sub>i</sub>	supply, measuring / output circuit	250 V
Rated impulse withstand voltage U <sub>imp</sub>	between all isolated circuits	4 kV / 1.2 - 50 μs
Pollution degree		3
Overvoltage category		III
Standards / Directives		
Standards		IEC/EN 60947-5-1, IEC/EN 60947-8
Low Voltage Directive		2014/35/EU
EMC Directive		2014/30/EU
RoHS Directive		2011/65/EU
Electromagnetic compatibility		
Interference immunity to		IEC/EN 61000-6-2, IEC/EN 60947-8
electrostatic discharge	IEC/EN 61000-4-2	Level 3, 6 kV contact discharge, 8 kV air discharge
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	Level 3, 10 V/m (1 GHz), 3 V/m (2 GHz), 1 V/m (2.7 GHz)
electrical fast transient /burst	IEC/EN 61000-4-4	Level 3, 2 kV / 5 kHz
surge	IEC/EN 61000-4-5	Level 3, installation class 3, supply circuit and measuring circuit 1 kV L-L, 2 kV L-N
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	Level 3, 0.15-80 MHz, 10 V, 80 % AM (1kHz)
Interference emission		IEC/EN 61000-6-3
high-frequency radiated	IEC/CISPR 22, EN 55022	Class B
high-frequency conducted	IEC/CISPR 22, EN 55022	Class B

Technical data

#### LEDs, status information and fault messages

#### CM-MSS

Operational state	U: green LED	F: red LED	R: yellow LED
Absence of control supply voltage	OFF	OFF	OFF
Internal fault <sup>2)</sup>	OFF	ПП	ПП
Internal fault <sup>2)</sup>	MML	NNL	MML
Control supply voltage not within the tolerance range	MML		OFF
Short circuit			OFF
Interrupted wire		ПППП	OFF
Measuring circuit 2: Overtemperature		ПП	OFF
Measuring circuit 1: Overtemperature			OFF
Fault rectified but not confirmed		_ 1)	MML
Test function	MML	OFF	OFF
Change of configuration not confirmed		OFF	MML
No fault		OFF	

<sup>1)</sup> Depending on the fault with the highest priority 2) Restart the device. If after restart the same fault is indicated, replace the device.

### Technical diagrams

#### \_


#### **Connection diagrams**

#### CM-MSS.11x, CM-MSS.21x

A1	13	21	
	T2	T1	ļ
 	A1 14 14 14 14 14 14 14 14 14 14 14 14 14	22	2CDC 252 018 F0014
			252
14	22	A2	ő


A1 – A2	Control supply voltage
13 – 14	n/o contact
21 – 22	n/c contact
T1 – T2	Measuring circuit

#### CM-MSS.12x




A1 – A2	Control supply voltage
11 – 12/14	c/o contact
T1 – T2	Measuring circuit

#### CM-MSS.13x




A1 – A2	Control supply voltage 220-240 V AC
A2 – A3	Control supply voltage 110-130 V AC
11 – 12/14	c/o contact
T1 – T2	Measuring circuit

#### CM-MSS.31x




A1 – A2	Control supply voltage
13 – 14	n/o contact
21 – 22	n/c contact
S1 – T2	Automatic reset (jumpered)
T1 – T2	Measuring circuit

# CM-MSS.22x, CM-MSS.32x, CM-MSS.41x




A1 – A2	Control supply voltage 24 V AC/DC
11 – 12/14	1st c/o (SPDT) contact
21 – 22/24	2nd c/o (SPDT) contact
S1 – T2	Automatic reset (jumpered)
T1 – T2	Measuring circuit

#### CM-MSS.23x, CM-MSS.33x




A1 – A2	Control supply voltage 220-240 V AC
A2 – A3	Control supply voltage 110-130 V AC
11 – 12/14	1st c/o (SPDT) contact
21 – 22/24	2nd c/o (SPDT) contact
S1 – T2	Automatic reset (jumpered)
T1 – T2	Measuring circuit

#### CM-MSS.51x



A1 – A2	Control supply voltage 220-240 V AC
11 – 12/14	1st c/o (SPDT) contact
21 – 22/24	2nd c/o (SPDT) contact
S1 – 1T2/2T2	Automatic reset (jumpered)
1T1 – 1T2/2T2	Measuring circuit 1
2T1 – 1T2/2T2	Measuring circuit 2

#### CM-MSE




A1 – A2	Control supply voltage 24 V AC
T1-T2	Sensor circuit
13-14	Output contact - Closed circuit principle


## Technical diagrams

#### Circuit diagrams


# CM-MSS.11x, CM-MSS.21x




#### CM-MSS.12x




#### CM-MSS.13x




CM-MSS.22x




CM-MSS.23x




CM-MSS.31x




CM-MSS.32x, CM-MSS.41x



CM-MSS.33x



CM-MSS.51x



#### CM-MSE






Table of contents

204	beliefits and advantages
205	Applications
207	Operating controls
208	Selection table
209	Ordering details
210	Configuration and setup
212	Technical data
215	Technical diagrams
216	Function diagrams

## Benefits and advantages



The temperature monitoring relays of the CM-TCS range are able to measure temperatures of solids, liquids and gaseous media using PT100 sensors. Overtemperature and undertemperature monitoring, as well as open- or closed-circuit principle is configurable for all devices. As soon as the temperature falls below or exceeds the set threshold value, the output relays change their positions and the front-face LED's display the current status.



By using temperature monitoring relays, both the downtime and the commissioning time can be reduced. The relay is continuously monitoring the sensor circuit to detect short-circuit or interrupted wire faults. The high accuracy of the measuring input leads to a fast detection of exceeding threshold values. In case of fault, maintenance effort is reduced and time saved.



Reliable in harsh conditions

All relays work reliably in environments with low temperatures down to -40 °C. Additionally, the housing fulfills the UL 94 V-0 flammability standard requirements. Together with the vibration resistant push-in terminals, the relay is not only reliable no matter the environment temperature but is also durable to shock and vibration. Save time as retightening is no longer needed and enhance the reliability and safety not only for the equipment.




Like all devices from the measuring and monitoring portfolio, the CM-TCS relays are easily configurable via front facing potentiometers. Easy threshold configuration without calculation is accomplished by direct reading scales. For further configuration options, additional settings can be made via dip-switches, offering the flexibility to configure, for example, the working principle of the relays and the output configuration. The device can be set up before installation in the application and easy adjustments during the process are possible.

# Temperature monitoring relays with potentiometer Applications

The temperature monitoring relays CM-TCS monitor overtemperature, undertemperature, or temperatures between two threshold values (window monitoring) with a PT100 sensor.

As soon as the temperature falls below or exceeds the threshold value, the output relays change their positions according to the configured functionality.

The current status is displayed by frontfaced LEDs. Regardless of the selected configuration, the device is monitoring its measuring circuit for interrupted wires or short-circuits.


















# **Temperature monitoring relays with potentiometer** Operating controls



Selection table

	Order number	15VR 730 740 R9100	1SVR 740 740 R9100	1SVR 730 740 R0100	1SVR 740 740 R0100	1SVR 730 740 R9200	1SVR 740 740 R9200	1SVR 730 740 R0200	1SVR 740 740 R0200	15VR 730 740 R9300	1SVR 740 740 R9300	SVR 730 740 R0300	1SVR 740 740 R0300
	0											Н	
	Туре	CM-TCS.21S	CM-TCS.21P	CM-TCS.11S	CM-TCS.11P	CM-TCS.22S	CM-TCS.22P	CM-TCS.12S	CM-TCS.12P	CM-TCS.23S	CM-TCS.23P	CM-TCS.13S	CM-TCS.13P
Rated control supply voltage U <sub>s</sub>													
24 V AC/DC													
24-240 V AC/DC													
Sensor circuits (2 or 3 wire)													
Number of temperature sensors		1	1	1	1	1	1	1	1	1	1	1	1
Number of thresholds		2	2	2	2	2	2	2	2	2	2	2	2
Measuring temperature range													
-50+50 °C													
0+100 °C								•	•				
0+200 °C										•			
Monitoring function													
Overtemperature		•		•	•			•	•	•			•
Undertemperature		-		•	•			•	•	•			•
Window temperature				•	•			•	•	•			•
Operating principle													
Open or closed-circuit principle	,												
Output contacts													
c/o		2	2	2	2	2	2	2	2	2	2	2	2



### Ordering details



#### **Description CM-TCS**

The temperature monitoring relays CM-TCS are able to measure temperatures of solids, liquids and gaseous media using PT100 sensors. Overtemperature and undertemperature monitoring, as well as open- or closed-circuit principle, is configurable for all devices. As soon as the temperature falls below or exceeds the set threshold value, the output relays change their positions according to the configured functionality and the front-face LEDs display the current status.

#### Ordering details

#### Temperature monitoring relays CM-TCS


Rated control supply voltage	Measuring range	Temperature sensors	Туре	Order code	Weight (1 pc) kg (lb)
24-240 V AC/DC	-50+50 °C	PT100	CM-TCS.11S	1SVR730740R0100	0.151 (0.333)
			CM-TCS.11P	1SVR740740R0100	0.140 (0.309)
	0+100 °C		CM-TCS.12S	1SVR730740R0200	0.151 (0.333)
			CM-TCS.12P	1SVR740740R0200	0.140 (0.309)
	0+200 °C		CM-TCS.13S	1SVR730740R0300	0.151 (0.333)
			CM-TCS.13P	1SVR740740R0300	0.140 (0.309)
24 V AC/DC	-50+50 °C		CM-TCS.21S	1SVR730740R9100	0.138 (0.304)
			CM-TCS.21P	1SVR740740R9100	0.127 (0.280)
	0+100 °C		CM-TCS.22S	1SVR730740R9200	0.138 (0.304)
			CM-TCS.22P	1SVR740740R9200	0.127 (0.280)
	0+200 °C		CM-TCS.23S	1SVR730740R9300	0.138 (0.304)
			CM-TCS.23P	1SVR740740R9300	0.127 (0.280)

S: screw connection P: push-in connection



Configuration and setup

#### DIP switches



	ON	OFF (default)
<b>DIP switch 1</b> Monitoring principle	Overtemperature monitoring   If overtemperature monitoring is selected, the CM-TCS recognizes temperatures above the selected threshold and trips the output relay according to the selected operating principle.	Undertemperature monitoring  Is selected, the CM-TCS recognizes temperatures below the selected threshold and trips the output relay according to the selected operating principle.
<b>DIP switch 2</b> Temperature window monitoring	Temperature window monitoring activated Ell If temperature window monitoring is selected, the CM-TCS monitors over- and undertemperature. If temperature window monitoring is activated, DIP switch 1 is disabled.	Temperature window monitoring de-activated ⊠ Temperature window monitoring is de-selected.
<b>DIP switch 3</b> Operating principle of the output relays	Closed-circuit principle  If closed-circuit principle is selected, the output relays are energized. They de-energize if a fault is occurring.	Open-circuit principle   If open-circuit principle is selected, the output relays are deenergized. They energize if a fault is occurring.
DIP switch 4 2 x 1 c/o contact, 1 x 2 c/o contacts	$2\times1$ c/o (SPDT) contact $^{\mbox{\tiny{DESS}}}$ If operating principle $2\times1$ c/o contact is selected, the output relay R1 (11-12/14) reacts to threshold value $91$ and the output relay R2 (21-22/24) reacts to threshold value $92$ .	1 x 2 c/o (SPDT) contacts   If operating principle 1 x 2 c/o contacts is selected, both output relays R1 (11-12/14) and R2 (21-22/24) react synchronously to one threshold value.  Overtemperature monitoring: Settings of the threshold value 92 have no effect on the operation.  Undertemperature monitoring: Settings of the threshold values 92 have no effect on the operation.


Configuration and setup

#### Connection of resistance thermometer sensors

#### 2-wire measurement


When using 2-wire temperature sensors, the sensor resistance and the wire resistance are added together. The resulting systematic errors must be taken into account when adjusting the tripping device. A jumper must be connected between the terminals T2 and T3. The following table can be used for PT100 sensors to

The following table can be used for PT100 sensors to determine the temperature errors caused by the line length. When using resistance sensors with two-wire connection a bridge must be inserted between terminals T2 and T3.



#### 3-wire measurement

To minimize the influence of the wire resistance, a three-wire connection is usually used. By means of the additional wire, two measuring circuits are created. One of these two circuits is used for reference. This way, the tripping device can calculate and take into account the wire resistance automatically.



#### **Temperature error**

(depending on the line length and conductor cross section for PT100 sensors at an ambient temperature of 20  $^{\circ}$ C, in K)

Line length in m	Wire size mm²					
	0.50	0.75	1	1.5		
0	0.0	0.0	0.0	0.0		
10	1.8	1.2	0.9	0.6		
25	4.5	3.0	2.3	1.5		
50	9.0	6.0	4.5	3.0		
75	13.6	9.0	6.8	4.5		
100	18.1	12.1	9.0	6.0		
200	36.3	24.2	18.1	12.1		
500	91.6	60.8	45.5	30.2		

#### Error caused by the line

The error resulting from the line resistance amounts to approx. 2.5 Kelvin/Ohm. If the resistance of the line is not known and it is not possible to measure it, the error caused by the line can be estimated using the following table.

### Technical data

Туре			CM-TCS.11/12/13	CM-TCS.21/22/23			
Input circuit				· · ·			
Rated control supply volt	age Us	A1-A2	24-240 V AC/DC	24 V AC/DC			
Rated control supply volt			-15+10 %	,			
Typical current / power /		24 V DC	33 mA / 0.8 VA	18 mA / 0.45 VA			
		115 V AC	12.5 mA / 1.5 VA	n/a			
			13 mA / 2.9 VA	n/a			
Rated frequency		AC	15-400 Hz	50/60 Hz			
Frequency range			13.5-440 Hz 45-65 Hz				
Power failure buffering time min.		20 ms					
			T1, T2, T3				
			PT100				
Connection of the sensor	r	2-wire	yes, jumper between T2-T3				
			yes, use terminal T1, T2, T3				
Monitoring function				perature or window monitoring			
Threshold values adjusta	ıble	CM-TCS.x1	-50+50 °C				
within the measuring rar			0+100 °C				
			0+200 °C				
Number of possible thres	sholds		2				
Tolerance of the adjusted			typ. ±5 % of the range end value				
Hysteresis related to the			2-20 % of threshold value, min. 1 °C				
Measuring principle			continuous current				
Typical current in the sen	sor circuit		0.8 mA				
Maximum current in sens			0.9 mA				
Interrupted wire detection			yes, indicated via LED status	5			
Short-circuit detection			yes, indicated via LED status	5			
Accuracy within the rated control supply voltage tolerance			< 0.2 °C / or < 0.01 %/K				
Accuracy within the temp			< 0.2 °C / or < 0.01 %/K				
Repeat accuracy (consta			< 0.2 % of full scale				
Maximum measuring cyc	:le		320 ms				
Output circuit	1		ļ.				
Kind of output			2 x 1 or 1 x 2 c/o (SPDT) cont	acts configurable			
Operating principle			open- or closed-circuit princ	ciple configurable (1)			
Contact material			AgNi alloy, Cd free				
Minimum switching volta	age / Minimum switch	ng current	24 V / 10 mA				
Maximum switching volt		-	see 'Load limit curves'				
Rated operational voltage		AC-12 (resistive) 230 V	4 A				
operational current I <sub>e</sub>	-	AC-15 (inductive 230 V	3 A				
	-	DC-12 (resistive) 24 V					
		DC-13 (inductive) 24 V					
AC Rating (UL508)		utilization category					
<u> </u>	maximum	rated operational voltage					
maximum continuous thermal current at B 300 maximum making/breaking apparent power at B 300							
			3600/360 VA				
Mechanical lifetime			30 x 10 <sup>6</sup> switching cycles				
Electrical lifetime (AC-12, 230 V, 4 A)			0.1 x 10 <sup>6</sup> switching cycles				
Maximum fuse rating to		n/c contact	t 6 A fast-acting				
protection			10 A fast-acting				
Conventional thermal current I <sub>th</sub>			4 A				

 $<sup>^{(\!1\!)}</sup>$  Closed-circuit principle: Output relay(s) de-energize(s) if measured value exceeds or falls below the adjusted threshold value

Technical data

Туре		<u> </u>	CM-TCS.11/12/13	CM-TCS.21/22/23		
General data						
Dimensions			see "dimensional drawings"			
Mounting			DIN rail (IEC/EN 60715), snap-on m	ounting without any tool		
Mounting positio	n		any			
Degree of protect		enclosure / terminals	-			
Ambient tempera		operation	·			
•	J	storage /transport				
=1			I			
Electrical connec	tion					
Wire size	<u> </u>		Screw connection technology	Easy Connect Technology (Push-in)		
	fine-strand without wire		1 x 0.5-2.5 mm <sup>2</sup> (1 x 20-14 AWG) 2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG)	2 x 0.5-1.5 mm² (2 x 20-16 AWG) connection with lever		
	end ferrule	T1, T2, T3	1 x 0.2-2.5 mm <sup>2</sup> (1 x 24-14 AWG) 2 x 0.2-1.5 mm <sup>2</sup> (2 x 24-16 AWG)	2 x 0.2-1.5 mm <sup>2</sup> (2 x 24-16 AWG) connection with lever		
	fine-strand with wire end ferrule	A1, A2, 11, 12, 14, 21, 22, 24	1 x 0.5-2.5 mm <sup>2</sup> (1 x 20-14 AWG) 2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG) connection: push-in		
		Т1, Т2, Т3	1 x 0.2-2.5 mm <sup>2</sup> (1 x 24-14 AWG) 2 x 0.2-1.5 mm <sup>2</sup> (2 x 24-16 AWG)	2 x 0.2-1.5 mm² (2 x 24-16 AWG) insulated ferrule (DIN 46228-4-E): connection: push-in ferrule (DIN 46228-1-A): < 0.5 mm², connection with lever ≥ 0.5 mm², connection: push-in		
	rigid	A1, A2, 11, 12, 14, 21, 22, 24	1 x 0.5-4 mm <sup>2</sup> (1 x 20-12 AWG) 2 x 0.5-2.5 mm <sup>2</sup> (2 x 20-14 AWG)	2 x 0.5-1.5 mm <sup>2</sup> (2 x 20-16 AWG) connection: push-in		
		T1, T2, T3	1 x 0.2-4 mm <sup>2</sup> (1 x 24-12 AWG) 2 x 0.2-2.5 mm <sup>2</sup> (2 x 24-14 AWG)	2 x 0.2-1.5 mm² (2 x 24-16 AWG) < 0.5 mm², connection with lever ≥ 0.5 mm², connection: push-in		
Stripping length			8 mm (0.32 ln)	, , ,		
Tightening torque	e	< 0.5 mm²	0.5 Nm (4.43 lb.ln)	-		
		≥ 0.5 mm²	0.6 - 0.8 Nm (5.31 - 7.08 lb.ln)	-		
Standards / Direc	ctives		,	`		
Standards			IEC/EN 60255-27, IEC/EN 60947-5-	-1		
Low Voltage Direc	ctive		2014/35/EU			
EMC Directive			2014/30/EU			
RoHS Directive			2011/65/EU			
Environmental da	ata					
Ambient tempera	iture ranges	operation/storage/ transport	-40+60 °C/-40+85 °C/-40+85	°C		
Climatic class		IEC/EN 60721-3-3	3K5 (no condensation, no ice forma	ation)		
Damp heat, cyclic	•	IEC/EN 600068-2-30	6 x 24 h cycle, 55 °C, 95 % RH			
Vibration, sinusoi	idal		Class 2			
Shock			Class 2			
Isolation data						
Rated impulse wit	thstand voltage U <sub>imp</sub>	supply circuit / measuring circuit	4 kV	-		
		supply circuit / output circuits	4 kV	-		
measuring circuit / output circuits output circuit 1 / output circuit 2			4 kV			
		4 kV				
Rated insulation v	voltage U <sub>i</sub>	supply circuit / measuring circuit	300 V	-		
		supply circuit / output circuits	300 V	I		
		measuring circuit / output circuits	300 V			
out		output circuit 1 / output circuit 2	300 V			

#### \_


## Temperature monitoring relays with potentiometer

## Technical data

Туре		CM-TCS.11/12/13	CM-TCS.21/22/23	
Basis insulation	supply circuit /	250 V AC / 300 V DC	-	
	measuring circuit			
	supply circuit / output circuits	250 V AC / 300 V DC		
	measuring circuit / output circuits	250 V AC / 300 V DC		
	output circuit 1 / output circuit 2	250 V AC / 300 V DC		
Protective separation (IEC/EN 61140)	supply circuit / measuring circuit	250 V AC / 250 V DC	-	
	supply circuit / output circuits	250 V AC / 300 V DC	250 V AC / 250 V DC	
	measuring circuit / output circuits	250 V AC / 300 V DC	250 V AC / 250 V DC	
Pollution degree		3		
Overvoltatge category		III		
Electromagnetic compatibility				
Interference immunity to		IEC/EN 61000-6-2		
electrostatic discharge	IEC/EN 61000-4-2	Level 3, 6 kV / 8 kV		
radiated, radio-frequency, IEC/EN 61000-4-3 electromagnetic field		Level 3, 10 V/m (1 GHz) / 3 V/m (2 GHz) / 1 V/m (2.7 GHz)		
electrical fast transient/burst IEC/EN 61000-4-4		Level 3, 2 KV / 5 kHz		
, ,		Level 3, installation class 3, supply circuit and measuring circuit 1 kV L-L, 2 kV L-earth		
conducted disturbances, induced IEC/EN 61000-4-6 by radio-frequency fields		Level 3, 10 V		
voltage dips, short interruptions IEC/EN 61000-4-11 and voltage variations		Class 3		
harmonics and interharmonics	IEC/EN 61000-4-13	Class 3		
Interference emission		IEC/EN 61000-6-3		
high-frequency radiated	IEC/CISPR 22, EN 55022	Class B		
high-frequency conducted	IEC/CISPR 22, EN 55022	Class B		

## Technical diagrams


#### Connection diagram



A1 – A2	Control supply voltage
11 – 12/14	Output relay R1
21 – 22/24	Output relay R2
T1, T2, T3	Measuring input, connection PT100

#### **Dimensional drawing**


in **mm** and inches




CM-TCS.xxx


#### **Electrical isolation**












#### Function diagrams



#### Overtemperature monitoring, 1 x 2 c/o contacts [1200]


With this configuration, settings via 92 have no influence on the operating function (92 disabled).

#### Open-circuit principle:

If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value exceeds the adjusted threshold value  $\vartheta 1$ , the output relays energize. If the measured value drops again below the adjusted threshold value  $\vartheta 1$  minus the adjusted hysteresis, the output relays de-energize.

#### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.



#### Overtemperature monitoring, 2 x 1 c/o contact 21.00


#### Open-circuit principle:

If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value exceeds the adjusted threshold value 92, output relay R2 (prewarning) energizes. If the measured value exceeds the adjusted threshold value 91, output relay R1 (final switch-off) energizes.

If the measured value drops again below the adjusted threshold value 91 minus the adjusted hysteresis, output relay R1 (final switch-off) de-energizes. If the measured value drops below the adjusted threshold value 92 minus the adjusted hysteresis, output relay R2 (prewarning) de-energizes.

#### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.



#### Undertemperature monitoring, 1 x 2 c/o contacts 🖂 🗠

With this configuration, settings via 91 have no influence on the operating function (91 disabled).

#### Open-circuit principle:


If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value drops below the adjusted threshold value 92, the output relays energize. If the measured value exceeds again the adjusted threshold value 92 plus the adjusted hysteresis, the output relays de-energize.

#### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.

### Temperature monitoring relays with potentiometer

### Function diagrams



### Undertemperature monitoring, 2 x 1 c/o contact

Open-circuit principle:

If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value drops below the adjusted threshold value 91, output relay R1 (prewarning) energizes. If the measured value drops below the adjusted threshold value 92, output relay R2 (final switch-off) energizes.

If the measured value exceeds again the adjusted threshold value 92 plus the adjusted hysteresis, output relay R2 (final switch-off) de-energizes. If the measured value exceeds the adjusted threshold value 91 plus the adjusted hysteresis, output relay R1 (prewarning) de-energizes.

#### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.

#### A1-A2 Threshold 01 Measured value Hysteresis Threshold 02 Open-circuit principle 21-24 21-22 U: green LED ϑ: red LED R: vellow LED Closed-circuit principle 11-14 11-12 CDC 252 012 F0209 21-24 21-22 U: green LED ϑ: red LED R: yellow LED


### Temperature window monitoring, 1 x 2 c/o contacts

Open-circuit principle:

If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value exceeds the adjusted threshold value 91 or drops below the adjusted threshold value 92, the output relays energize. If the measured value drops again below the adjusted threshold value 91 minus the adjusted hysteresis or exceeds again the adjusted threshold value 92 plus the adjusted hysteresis, the output relays de-energize.

#### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.



### Temperature window monitoring, 2 x 1 c/o contact Open-circuit principle:

If the measured value is correct, the output relays remain de-energized when control supply voltage is applied. If the measured value exceeds the adjusted threshold value 91 or drops below the adjusted threshold value 92, output relay R1 (>  $\vartheta$ 1) or R2 (<  $\vartheta$ 2) respectively energizes. If the measured value drops again below the adjusted threshold value 91 minus the adjusted hysteresis or exceeds again the adjusted threshold value 92 plus the adjusted hysteresis, output relay R1 (> $\vartheta$ 1) or R2 (< $\vartheta$ 2) respectively de-energizes.

### Closed-circuit principle:

The behavior is inverse to the one with open-circuit principle.



# Smart temperature monitoring relays Table of contents

220	Features and benefits
225	<b>Built-in connectivity</b>
228	Applications
230	Selection table
231	Ordering details
232	Technical data
236	Technical diagrams

### One look, one touch - one device

### Features and benefits



Set up these innovative temperature monitoring relays exactly as you need, either via a back-lit LCD or smartphone app. Parametrization and configuration are just one touch away with the ABB EPiC app – even in a non-powered state – reducing installation time by 80%. And with just one relay covering a wide range of application, stocks can be reduced significantly, making ABB's Smart monitoring relays a true game changer.

# Easy to install

### One look - back-lit LCD for easy reading and parametrization

Everything you need at a glance: the LCD at the front of the relay shows the currently measured values and maintenance data. And with just one push, the symbol-based menu structure can be accessed via the push-rotate button. Simply set the thresholds and parameters with the help of an intuitive and future-ready interface.



#### One touch - NFC parametrization via smartphone app

One touch is all that is needed for fast, easy and intuitive configuration with the ABB EPiC smartphone app. Simply touch the relay with your mobile phone: Parameter settings can be edited and stored in the app and then copied to different devices, even if they are not in the powered state. Available in a range of different languages, installation and configuration have never been so easy.

### po una

Continuous operation

#### One device - for thermal protection and condition monitoring

Smart temperature monitoring relays ensure that your application remains operational by detecting potential failures in advance. They protect the life of your assets by providing early detection of unacceptable temperature rises and the need for maintenance. The relay is configurable over a wide range of settings and can be adjusted flexibly. Set a pre-alarm and alarm thresholds according to application needs. Increase personal safety by monitoring temperature remotely with Modbus RTU or ABB Ability<sup>TM</sup> Energy and Asset Manager.

## **Smart temperature monitoring relays**

Setup via display or smartphone app

CM-TCN temperature monitoring relays can measure temperatures of solids, liquids and gaseous media in up to three sensor circuits using various types of sensors.

# One...





# OOK to have the information needed

the display shows the measured values and relay status at a glance. The symbol-based menu structure and presettings make parametrization simple.





# touch for up to 80% faster setup

for easy parametrization and copying of settings between multiple devices via NFC with the ABB EPiC smartphone app – even if the relay is not powered.





### device for thermal protection and condition monitoring

Just one relay to cover many different applications, monitor their condition, increase safety and ensure uptime.

### One look - back-lit LCD

## Easy reading and setup with one push

Just one look is all it takes to see the status and measured values of the relay, easily navigate through the symbol-based menu and even configure the device with the new, back-lit LCD at the front of the relay.



#### Start screen

Know the status at one glance.



#### Symbol-based menu structure

Due to the symbol-based menu structure, there is no need for any translation, which helps avoid misunderstandings and dramatically increases efficiency in after sales support.



#### Pre- and user-defined settings

For frequently used applications, the device offers predefined settings to save installation time. Parameters can be individually set and saved in one of four user settings.







#### Push-rotate adjustment

Adjust the relay with a simple screw driver by pushing and rotating the potentiometer to navigate through the menu.



#### Diagnostic data

Event history, operating hours counter, statistics and others are easily accessible from the menu



#### **Back-lit LCD**

The back-lit LCD at the front of the relay shows the currently measured values and maintenance data and makes setup easy.




#### Password & parameter log

Improved security is achieved through the recorded password and parameter log.

### One touch - setup via smartphone app

### Powerless configuration with NFC

Configuration and parametrization of temperature monitoring relays has never been simpler. One touch is all that is needed for fast, easy and intuitive configuration with the ABB EPiC mobile phone app.





### **Near Field Communication (NFC)**

NFC is an international transmission standard based on radio-frequency identification technology for the contact-less exchange of data. This technology is already integrated into most electronic devices like tablets and smartphones and part of everyday life, e.g. for contactless payment.



#### ABB EPiC smartphone app

Electrification Products intuitive Configurator (EPiC) is a mobile application that makes it possible to configure and check the status of ABB low voltage products. The app is available for free - just download it and connect to your smart monitoring relays, circuit breakers and other devices.



### Easy visualization

Monitor the status of the relay and read the measured values in the app.



#### Store and send parameters

Store a set of parameters in the app and distribute them globally and copy them to other devices.



### Powerless adjustment

Parametrize and configure the relays even while not connected to a power supply, e.g. on office desks.



### One touch setup

Handle the relays with just one touch-just hold the smartphone against the front of the relay.



#### Copy and paste functionality

Simply copy the settings from one device to another–with just one touch to the relay.



#### **Event history**

Examine the history of the device and recent events.

### One device - thermal protection


### Flexible adjustment and condition monitoring

Knowing the status of your devices at all times: thanks to the smart monitoring relays, you are always up to date and flexible in controlling your devices. Remote monitoring via Modbus RTU and ABB Ability<sup>™</sup> Energy and Asset Manager also enables the early detection of potential errors and possible maintenance requirements.



#### Flexible adjustment

The relay can handle commonly used temperature sensors such as PT100 and PTC and supports a wide measuring range from -200...850 °C. The smart monitoring relays are configurable over a wide setting range and can be adjusted flexibly no matter the thresholds, time values or other settings. For example, first relay can be assign as pre-alarm, second as alarm and third as a sensor error. Nine signals are available for assignment to allow various combination of tripping thresholds.





#### Early detection of potential fault and need for maintenance

Thanks to support of the most commonly used sensors (PTC, PT100, PT1000, NTC), the smart temperature relay can be used for temperature monitoring of busbars and cables allowing detecting the issues related to tightening, which results in the need for maintenance. In addition, the relay can be used for temperature monitoring of electrical motor's bearings and windings allowing to sense unacceptable temperature rise that shorten the lifetime of equipment.



### **Increased safety**

The smart monitoring relays increases the safety thanks to remote temperature monitoring using Modbus RTU or ABB Ability $^{\text{TM}}$  Energy and Asset Manager. The personal no longer need to access to the switchboard to read the measurements.



### **Built-in connectivity**

### Communication via embedded Modbus RTU

The smart temperature monitoring relay CM-TCN.012 supports the data transfer using the Modbus RTU communication protocol. The communication interface RS-485 is embedded in the relay and does not require installation of any accessories.



#### — CM-TCN manual

Modbus communication map and information about the device configuration can be found in the CM-TCN



#### The communication interface makes it possible to:



Read the temperature measurements, relays state and temperature sensors status.



Access the condition monitoring data such as event history, operating hours counter, maintenance counter, statistics.



Configure the smart monitoring relay remotely.




Reset the history and settings (trip counter, event history, etc)



Read system information (serial number, firmware version)



Control output relays and trigger them in case of the communication bus error



## Cloud integration with ABB Ability™

### Real-time data monitoring and temperature trends

Providing full remote visibility of asset and electrical-system behavior, ABB Ability<sup>™</sup> Energy and Asset Manager (EAM) provides insights that help you minimize costs, risks and maximize performance as well as safety across your operations.

The CM-TCN.012 smart monitoring relay is enabled in ABB Ability™
Energy and Asset Manager. Thus, allowing access to the real-time data monitoring and temperature trends from the cloud solution.

The data received from CM-TCN.012 is organized in plain widgets for the remote condition monitoring of assets such as a machine, motor, transformer or switchboard. The temperature trends can be compared between different measuring sensors giving you valuable insights about temperature behavior of your assets at the place of the sensors' installation.

Additionally, the customer can set up SMS or E-mail alerts to notify key personnel in case of the temperature relay tripping or sensors error. The periodic report with temperature values can also be scheduled.

CM-TCN.012 can be connected to the cloud-computing platform via Modbus RS-485 communication interface. The interface is embedded in the device and does not require any accessories.

The smart relay can share the data with the platform using an external solution with the ABB Ability<sup>TM</sup> Edge Industrial Gateway.

ABB Ability™ Energy and Asset Manager






### **Example communication architecture**

### CM-TCN.12 ABB Ability<sup>™</sup> enabled relay

ABB Ability<sup>™</sup> Energy and Asset Manager is a state-of-the-art cloud solution that integrates energy and asset management in a single intuitive dashboard.

Architecture with ABB Ability™ Edge Industrial Gateway



Integrate a range of devices like circuit breakers, motor controllers and the new CM-TCN.012 monitoring relay into the ABB Ability™ Energy and Asset Manager. It is a state-of-the-art cloud solution that integrates energy and

asset management in a single intuitive dashboard. Providing full remote visibility of asset and electrical-system behavior, ABB Ability™ Energy and Asset Manager (EAM) provides insights that help you minimize cost and risk


and maximize performance and safety across your operations.

# **Applications**




Temperature monitoring relays are used in a wide array of applications. In conjunction with temperature sensors, such as PT100 or PTC sensors, they monitor motor temperature, control cabinet temperature and protect transformers from overheating.







# **Operating controls**



### Selection table

	Order number	1SVR750740R0110	1SVR760740R0110	1SVR750740R0120	CM-TCN.012P 1SVR760740R0120
	Туре	CM-TCN.011S	CM-TCN.011P	CM-TCN.012S	CM-TCN.012P
Rated control supply voltage U <sub>s</sub>					
24-240 V AC/DC		■*	■*		
Sensor circuits (2 or 3 wire)					
Number of temperature sensors		3	3	3	3
Number of thresholds		9	9	9	9
Sensor types					
PT100		-	-		-
PT1000					_
NTC					
PTC			-		-
Bi-metal switch					-
Measuring temperature range					
-200+850 °C					•
Interface					_
Display NFC					
Modbus RTU		_	_		_
Monitoring function				_	
Overtemperature					
Undertemperature					-
Window temperature		•	•	•	-
Temperature difference		•	•	•	-
Operating principle					
Open or closed-circuit principle					
Output contacts	-				
c/o		3	3	3	3
* CM TCM ON		. 1.7			

<sup>\*</sup> CM-TCN.011: supply voltage 24-240 V AC/DC for revision G or later and supply voltage 24 V AC/DC for revision F or earlier.

#### \_

### **Smart monitoring relays**

### Ordering details



### Description

The temperature monitoring relays CM-TCN are able to measure temperatures of solids, liquids and gaseous media within up to three sensor circuits using different types of sensors, such as PT100, PT1000, PTC or NTC within the same time. Different types of sensors, e.g. PT100 and PTC sensors, can be monitored simultaneously.

The temperature is obtained by the sensors in the medium, evaluated by the device and monitored to determine whether it is within an operating range (range monitoring function) or has exceeded or fallen below a threshold. Depending on the parametrization, up to three output relays signalize the changes in the measuring circuits.

### Smart temperature monitoring relays CM-TCN

Rated control supply voltage	Terminal type	Display & NFC	Modbus RTU	Temperature sensor	Width	Туре	Order code	Weight (1 pc)
					mm			kg (lb)
24-240 V AC/DC*	Screw	yes	no	PT100, PTC, PT1000, NTC	45	CM-TCN.011S	1SVR750740R0110	0.293 (0.646)
	Push-in	yes	no			CM-TCN.011P	1SVR760740R0110	0.293 (0.646)
	Screw	yes	yes			CM-TCN.012S	1SVR750740R0120	0.299 (0.659)
	Push-in	yes	yes			CM-TCN.012P	1SVR760740R0120	0.299 (0.659)

<sup>\*</sup> CM-TCN.011: supply voltage 24-240 V AC/DC for revision G or later and supply voltage 24 V AC/DC for revision F or earlier.

### Accessories

Description	for type	Width	Туре	Order code	Pkg qty	Weight (1 pc)
		mm				kg (lb)
Adapter for screw mounting	CM-N.S/P	45	ADP.02	1SVR440029R0100	1	36.7 (1.30)
Marker label	CM-S.S/P CM-N.S/P		MAR.01	1SVR366017R0100	10	0.19 (0.007)
Sealable transparent cover	CM-N.S/P	45	COV.12	1SVR750005R0100	1	7 (0.247)

Data at Ta = 25 °C and rated values, unless otherwise indicated

Туре		CM-TCN.011	CM-TCN.012			
Input circuit	A1-A2					
Rated control supply voltage U <sub>s</sub>	24-240 V AC/DC*					
Rated control supply voltage U <sub>s</sub> tolerance	-15 +10 %					
Rated frequency	AC	50 - 60 Hz				
Frequency range	AC	45 - 66 Hz				
Typical current consumption	24 V AC/DC	typ. 30 mA / max. 40 mA				
	115 V AC	typ. 16 mA / max. 20 mA				
	230 V AC	typ. 13 mA / max. 15 mA				
Power failure buffering time		min. 20 ms				
Measuring circuits		xT1, xT2, xT3				
Sensor type		PT100, PT1000, PTC, NTC, bi-me	etal switch			
Connection of the sensor	2-wire	yes, jumper xT2 - xT3				
	3-wire	yes, use terminal xT1, xT2, xT3				
Interrupted wire detection		yes				
Short-circuit detection		yes				
Measuring ranges	PT100	-200 °C +850 °C / -328 °F +1562 °F				
	PT1000	-200 °C +850 °C / -328 °F +1562 °F				
	NTC	+80 °C +155 °C / +176 °F +311 °F				
	PTC	max. total resistance of connect	ed resistors in cold state <750 Ohm			
Monitoring functions		undertemperature, overtemperature, window monitoring				
Measuring input range		-200 +850 °C / -328 +1562 °F				
Hysteresis related to the threshold values		1 99.9 °C / 1.8 179.8 °F				
Measuring principle		continuous current				
Typical current in the sensor circuit	PT100	0.5 mA				
	PT1000	0.5 mA				
Maximum current in sensor circuit		0.5 mA				
Measuring accuracy		± 0.5 K (-50 +200 °C / -58 +392 °F) ± 1 K (< -50 °C / -58 °F and > 200 °C / 392 °F)				
Accuracy within the rated control supply voltage tolerance		< 0.05 % full scale/1 V				
Accuracy within the temperature range		< 0.05 % full scale/1 K				
Repeat accuracy (constant parameters)		± 0.07 % full scale				
Maximum measuring cycle		< 2 s				
Maximum cable length		500 m / 1 mm² (shielded cable)				
Control circuits						
Type of triggering		volt-free triggering				
Control function	S1	remote reset				
Maximum input current		< 1.5 mA				
Maximum no-load voltage at the control inputs		< 15 V				
Minimum control pulse length		150 ms				
Maximum cable length at the control inputs		100 m - 100 pF/m				

 $<sup>^{\</sup>star}\,\text{CM-TCN.011:}\,\text{supply voltage}\,\text{24-240 V AC/DC}\,\text{for revision}\,\text{G}\,\text{or later and supply voltage}\,\text{24 V AC/DC}\,\text{for revision}\,\text{F}\,\text{or earlier}.$ 

Туре	CM-TCN.011	CM-TCN.012				
Timing functions		1				
Power-on delay	2-999.9 s					
ON-delay R1, R2, R3 *	0-6553.5 s					
OFF-delay R1, R2, R3 *	0-6553.5 s					
Cyclic switching function On time	1 min - 1 day					
cycle time	10 min - 1 year					
Indication of operational states						
Control supply voltage applied	LED green					
Cyclic switching function running	LED orange					
Internal fault	LED red on					
Short circuit	LED red: ILILIL					
Wire break	LED red: ПППП					
Overtemperature / Measurement value exceeds high limit	LED red: ∏∟∏∟					
Undertemperature / Measurement value exceeds low limit	LED red: ЛЛЛЛ					
Parameter error	Orange and red LEDs alternate					
NFC pairing	LED orange: \( \subseteq \subseteq \subseteq \)					
For details see the message on the display						
Display						
Technology	LCD					
Backlight on	press button					
off	switch-off delay adjustable, 10 s -1 h (default 10 s)					
Resolution	128 x 64 pixel					
Display size	28 x 16 mm					
Operating controls						
Push-rotate button	Operable with screw driver: PZ1 DIN ISO 8764-1					
Near field communication (NFC)						
Standards	ISO/IEC 14443 Part 2+3 NFC Forum Type 2 tag compliant					
Communication interface						
Communication protocol	-	Modbus RTU				
Physical interface	-	two-wire RS-485				
Integrated termination resistors	-	no				
Possible bus addresses	-	1 247				
Baud rates	-	1200, 2400, 4800, 9600, 19200, 38400, 57600, 115200 B/s				
Typical response time	-	< 30 ms				
Bus master supervision time / Timeout	-	adjustable 1 255 s in steps of 1				
Frame	-	8 data, Even, 1 stop 8 data, Odd, 1 stop 8 data, None, 2 stop 8 data, None, 1 stop				

 $<sup>^{\</sup>star} \, \text{If the selected ON-delay or OFF-delay is less than 2 s, the maximum measuring cycle should be taken into account.} \\$ 

Туре		CM-TCN.011	CM-TCN.012			
Output circuits						
Kind of outputs	11-12/14	relay R1, c/o (SPDT) contact				
	21-22/24	relay R2, c/o (SPDT) contact				
	31-32/34					
Operating principle	open- or closed circuit principle	configurable; default: closed-ci	rcuit principle*			
Contact material		AgNi alloy, Cd-free				
Maximum switching voltage / maximur	n switching current	see "Load limit curves"				
Rated operational voltage U <sub>e</sub>	AC-12 (resistive) at 230 V	4 A				
and rated operational current I <sub>e</sub>	AC-15 (inductive) at 230 V	3 A				
	DC-12 (resistive) at 24 V	4 A				
	DC-13 (inductive) at 24 V	2 A				
Mechanical lifetime		30 x 10 <sup>6</sup> switching cycles				
Electrical lifetime	at AC-12, 230 V AC, 4 A	0.1 x 10 <sup>6</sup> switching cycles				
Maximum fuse rating to achieve	n/c contact	6 A fast-acting				
short-circuit protection	n/o contact	10 A fast-acting				
Conventional thermal current Ith		4 A				
General data						
MTBF		on request				
Duty cycle		100 %				
Dimensions		see "Dimensional drawing"				
Mounting		DIN rail (IEC/EN 60715) TH 35-7.5 and TH 35-15, snap-on mounting without any tool				
Mounting position		any				
Minimum distance to other units	horizontal	not necessary				
Material of housing		UL 94 V-0				
Degree of protection	housing / terminals	IP50/IP20				
Electrical connection		CM-TCN.011S, CM-TCN.012S	CM-TCN.011P, CM-TCN.012P			
Connecting capacity	fine-strand with/ without A1, wire end ferrule A2, R1, R2, R3, S1, C	(1x18-14 AWG) 2 x 0.5-1.5 mm <sup>2</sup> (2x18-16 AWG)	2x0.5-1.5 mm <sup>2</sup> (2x18-16 AWG)			
	xT1, xT2, xT3, A, B, C		2x0.2-1.5 mm <sup>2</sup> (2x24-16 AWG)			
	rigid A1, A2, R1, R2, R3, S1, C	2 x 0.5-2.5 mm <sup>2</sup> (2x20-14 AWG)	2x0.5-1.5 mm <sup>2</sup> (2x20-16 AWG)			
	xT1, xT2, xT3, A, B, C		2x0.2-1.5 mm <sup>2</sup> (2x24-16 AWG)			
Stripping length		8 mm (0.32 in)				
Tightening torque	< 0.5 mm²	0.5 Nm (4.43 lb.in)	-			
	≥ 0.5 mm²	0.6 - 0.8 Nm (7.08 lb.in)	-			


<sup>\*</sup> Closed-circuit principle: Output relay de-energizes if a fault is occurring Open-circuit principle: Output relay energizes if a fault is occurring


Туре		CM-TCN.011	CM-TCN.012			
Environmental data						
Ambient temperature ranges	operation	-25 °C+60 °C (-13+14	40 °F)			
	storage	-40 °C+85 °C (-40+185 °F)				
Damp heat, cyclic	IEC/EN 60068-2-30	6 x 24 h cycle, 55 °C, 95	% RH			
Climatic class	IEC/EN 60721-3-3	3K5 (no condensation,	no ice formation)			
Vibration, sinusoidal		class 1				
Shock		class 1				
Isolation data						
Rated impulse withstand voltage (U <sub>imp</sub> ) EN/IEC60664-1	supply circuit / measuring circuit and modbus / output circuits (relay)	6 kV				
	output circuit 1 / output circuit 2 / output circuit 3	4 kV				
Rated insulation voltage U <sub>1</sub> Basic insulation	supply circuit / measuring circuit and modbus / output circuits (relay)	600 V				
	output circuit 1 / output circuit 2 / output circuit 3	300 V				
Protective separation IEC/EN 61140	supply circuit / measuring circuit and modbus / output circuits (relay)					
	output circuit 1 / output circuit 2 / output circuit 3	150 V				
Pollution degree		3				
Overvoltage category		III				
Standards/Directives						
Standards		IEC/EN 60947-5-1				
Low Voltage Directive		2014/35/EU				
EMC Directive		2014/30/EU				
RoHS Directive		2011/65/EU incl. 2015/	'863/EU			
WEEE Directive		2012/19/EU				
RED Directive		2014/53/EU				
Electromagnetic compatibility						
Interference immunity to		IEC/EN 60947-5-1				
electrostatic discharge	IEC/EN 61000-4-2	level 2, 4 kV contact dis	charge, 8 kV air discharge			
radiated, radio-frequency, electroma	agnetic field IEC/EN 61000-4-3	level 3, 10 V/m; 2.7 GHz				
electrical fast transient / burst	IEC/EN 61000-4-4	level 3 / 2 kV, 5 kHz				
surge	IEC/EN 61000-4-5	supply circuit: level 3; L-relay circuit: level 3; L-P measuring circuit, remo	E 2 kV			
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V				
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	class 3				
Interference emission		IEC/EN 60947-5-1				
high-frequency radiated		fulfilled (environment B	3)			
high-frequency conducted		fulfilled (environment A	4)			

### Technical diagrams

### **Dimensional drawings**


in **mm** and inches







CM-TCN.011

### Load limit curves







Derating factor F for inductive AC load



2CDC252001V0019



Contact lifetime



# **Liquid level monitoring relays**Table of contents

LTO	belieffes and advantages
242	Applications
246	Operating controls
248	Selection table
249	Ordering details
250	Technical data
256	Function diagrams
257	Technical diagrams

### Benefits and advantages



ABB's liquid level monitoring relays are the ideal solution to regulate and control liquid levels and ratios of mixtures of conductive fluids. The assortment includes single- or multifunctional devices which can be used for overflow protection, dry-running protection of pumps, filling and draining applications as well as max. and min. level alarming.



The liquid level monitoring relays are designed to provide a wide supply voltage range, making global differences irrelevant. Additionally, the CM-ENS range meets a broad range of standards and requirements. Together with ABB's global support and sales network, using CM-ENS gives customers the confidence of worldwide sourcing – no matter where they build, install or operate their equipment.



High immunity against electromagnetic disturbances is ensured due to advanced measuring technology. Additionally, the housing fulfills the UL 94 V-0 flammability standard requirements. Together with the vibration resistant push-in terminals, the relay is not only reliable no matter the environment temperature but is also durable to shock and vibration. Save time as re-tightening is no longer needed and enhance the reliability and safety not only for the equipment.



Improve installation efficiency

Like all devices from the measuring and monitoring portfolio, the CM-ENS relays are easily configurable via front facing potentiometers. Easy threshold configuration without calculation is accomplished by direct reading scales. The device can be set up before installation in the application and easy adjustments during the process are possible.

### Benefits and advantages



#### Operating principle

Liquid level control relays CM-ENS are designed to monitor levels of conductive liquids and media and is used, for example, for liquid level control in pump systems. The measuring principle is based on the resistance change sensed by single-pole electrodes. To avoid electrolytic phenomena, an AC current runs across the probes.

A selector switch on the front panel allows selection of the required function and the sensitivity range.



#### Suitability

Suitable for		Not suitable for	Not suitable for				
spring water	acids, bases	chemically pure water	ethylene glycol				
drinking water	liquid fertilizers	fuel	concentrated alcohol				
sea water	milk, beer, coffee	oils	paraffin				
sewage	non-concentrated alcohol	explosive areas (liquid gas)	lacquers				



#### Characteristics

#### CM-ENS.1x

- Control of one or two liquid levels (min/max)
- · Fill or drain function
- Adjustable response sensitivity 5-100  $k\Omega$

### CM-ENS.2x

- Control of one or two liquid levels (min/max)
- Fill (UP) or Drain (DOWN), adjustable via front-face potentiometer
- Adjustable response sensitivity 0.1-1000  $k\Omega$

#### CM-ENS.31


- Control of one or two liquid levels (min/max)
- Fill (UP) or Drain (DOWN), adjustable via front-face potentiometer
- Adjustable response sensitivity 0.1-1000  $k\Omega$
- Selectable ON- or OFF-delay
- 2 c/o (SPDT) contacts

#### **All CM-ENS devices**

- Devices with wide rated control supply voltage 24-240 V AC/DC
- Cascadable
- High EMC immunity
- 3 LEDs for the indication of operational states
- Screw connection technology or Easy Connect Technology
- Housing material for highest fire protection classification UL 94 V-0
- Tool-free mounting and demounting on DIN rail
- 22.5 mm (0.89 in) width

# **Applications**

Liquid level monitoring relays work in conjunction with, for example, suspension electrodes, and can be used either for direct liquid level control or also for cascading devices, as well as operation modes with several electrodes, or control of two liquid levels are possible.







### **Applications**

### Cascading of several devices


With the CM-ENS it is possible to use two devices in one tank. This enables the possibility to realize a pre-warning with additional electrodes. In this way, two additional alarm outputs for exceeding or dropping below the normal level can be implemented in addition to the filling levels MAX and MIN. In addition, a reserve pump can be connected to the additional device.



Filling with alarm empty




Filling with reserve pump



2CDC 252 017 F0215

Draining with alarm full




Draining with reserve pump

### Operating mode with three electrodes

The CM-ENS measures the electrical resistance of the liquid between two immersion electrodes and a reference electrode.

For CM-ENS.1x only: If the relay is connected to the rated control supply voltage, the output relay changes its switching state as soon as the liquid level reaches the MAX-electrode, while the minimum sensor is submerged. The relay returns to the original state as soon as the minimum sensor is no longer in contact with the monitored medium.


For CM-ENS.2x and CM-ENS.31 only: The function fill (^) or drain (v) can be selected via a front-face potentiometer. If the fill function is selected, the output relay is energized until the MAX-electrode becomes wet. Then it is de-energized and not re-energized until the MIN-electrode becomes dry. If the drain function is selected, the output relay energizes as soon as the MAX-electrode becomes wet. It remains energized until the liquid level has dropped below the MIN-electrode.



Operation mode with three electrodes

### Operation mode with two electrodes

If only one level should be controlled, only the MAX-electrode shall be connected at the CM-ENS.




Operation mode with two electrodes

# **Applications**

### Control of two liquid levels via liquid level monitoring relay CM-ENS


In combination with suspension electrodes CM-HC or CM-HCT (suitable for drinking water).






# **Applications**

In combination with the compact support CM-KH-3 and 3 bar electrodes CM-SE.







## Operating controls



### CM-ENS.2x



## Operating controls



# **Liquid level monitoring relays** Selection table

			_													
of CC	1SVR 550 855 R9500	1SVR 550 850 R9500	1SVR 550 851 R9500	1SVR 550 855 R9400	1SVR 550 850 R9400	1SVR 550 851 R9400	1SVR 730 850 R0100	1SVR 740 850 R0100	1SVR 730 850 R2100	1SVR 740 850 R2100	1SVR 730 850 R0200	1SVR 740 850 R0200	1SVR 730 850 R2200	1SVR 740 850 R2200	1SVR 730 850 R0300	1SVR 740 850 R0300
T	CM-ENE MIN	CM-ENE MIN	CM-ENE MIN	CM-ENE MAX	CM-ENE MAX	CM-ENE MAX	CM-ENS.11S	CM-ENS.11P	CM-ENS.13S	CM-ENS.13P	CM-ENS.21S	CM-ENS.21P	CM-ENS.23S	CM-ENS.23P	CM-ENS.31S	CM-ENS.31P
Rated control supply voltage Us																
24-240 V AC/DC	_						-	-			-	-			-	-
24 V AC	▮■															
110-130 V AC	—												-			_
220-240 V AC																
Sensor circuit	<del>Т.</del>	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Number of electrodes (including ground reference)	2	2	2	2	2	2	3	3	3	3	3	3	3	3	3	3
Response sensitivity range																
0-100 kΩ	T				•											
5-100 kΩ	╅╸	_		_	_	-	adi	adj	adi	adi						
0.1-1000 kΩ	+									رمم	adi	adi	adi	adi	adj	adi
Monitoring function											,		,	,	,	
Dry running protection	1.							•			•		•			
Overflow protection	+	+-	T-		•			_		_	_		_	_	_	
Liquid level control	1				_			_			_		_	_	-	
Operating principle				_			_									_
Open-circuit principle	1							•								
Closed-circuit principle	T				•	•		_	_	_						
Open- or closed-circuit principle	<u> </u>				_	_					sel	sel	sel	sel	sel	sel
Adjustable ON-/OFF-delay																
0.1-10 s	Т															
Output contacts																
n/o	1	1	1	1	1	1										
c/o (SPDT)	Ť						1	1	1	1	1	1	1	1	2	2
Connection type																_
Push-in terminals	T															
Double-chamber cage connection terminals							-				-		•		•	
Screw					•	•										
adi: adiustable																_

adj: adjustable sel: selectable

### Ordering details



CM-ENE MIN



CM-ENS.3x

### Description

The liquid level monitoring relays CM-ENS and CM-ENE monitors and controls the liquid level and ratios of mixtures of conductive fluids. It is used for filling and draining applications, to protect pumps against dry-running, to protect tanks against overflow, and for signalization of the status of the monitored liquid level.

### Ordering details

Characteristics	Туре	Order code	Weight (1 pc)
			kg (lb)
See selection table	CM-ENE MIN	1SVR550855R9500	0.15 (0.33)
		1SVR550850R9500	0.15 (0.33)
		1SVR550851R9500	0.15 (0.33)
	CM-ENE MAX	1SVR550855R9400	0.15 (0.33)
		1SVR550850R9400	0.15 (0.33)
		1SVR550851R9400	0.15 (0.33)
	CM-ENS.11S	1SVR730850R0100	0.124 (0.273)
	CM-ENS.11P	1SVR730850R2100	0.117 (0.258)
	CM-ENS.13S	1SVR740850R0100	0.153 (0.337)
	CM-ENS.13P	1SVR740850R2100	0.145 (0.320)
	CM-ENS.21S	1SVR730850R0200	0.125 (0.276)
	CM-ENS.21P	1SVR740850R0200	0.117 (0.258)
	CM-ENS.23S	1SVR730850R2200	0.154 (0.340)
	CM-ENS.23P	1SVR740850R2200	0.147 (0.324)
	CM-ENS.31S	1SVR730850R0300	0.143 (0.315)
	CM-ENS.31P	1SVR740850R0300	0.134 (0.295)



CT-PAC.22

### Description

The alternating relay CT-PAC is designed to evenly use the electromechanical resource of a twin pump, dual compressors and generators. The alternating relay has two normally open contacts, which are closed alternately each time the control supply voltage is applied to terminals A1-A2.

A front-face rotary switch allows to select among three functions:

- R1 each power cycle contact 13-14 closes
- R2 each power cycle contact 13-24 closes
- alt. (default) output contacts close alternately each power cycle

### Ordering details

Rated control supply voltage	Туре	Order code	Weight (1 pc) kg (lb)
24-240 V AC/ 24-48 V DC	CT-PAC.22	1SVR508180R0100	0.059 (0.130)

The technical data can be found in the time relays chapter.

Туре		CM-ENE MIN	CM-ENE MAX			
Supply circuit						
Rated control supply vol	tage II A1-A2	24 V AC, approx. 1.5 VA				
power consumption		110-130 V AC, approx. 1.2 VA				
		220-240 V AC, approx. 1.4 VA				
Pated control supply volt		-15+15 %				
Rated control supply vol	.age os tolerance					
Rated frequency		50-60 Hz				
Measuring circuit		MIN-C, MAX-C				
Monitoring function		dry-running protection	overflow protection			
Response sensitivity		0-100 kΩ, not adjustable				
Maximum electrode volt	-	30 V AC				
Maximum electrode current		1.5 mA				
Electrode supply line						
	max. cable length	30 m				
Timing circuit		fixed approx. 200 ms				
Tripping delay	ripping delay					
Indication of operation	ıl states					
Output relay energized		R: yellow LED				
Output circuits		13-14				
Kind of output		1 n/o contact				
Operational principle <sup>1)</sup>		open-circuit principle¹) closed-circuit principle¹)				
Rated operational voltag	ge U <sub>e</sub> (IEC/EN 60947-1)	250 V				
Minimum switching volta	age / minimum switching current	-/-				
Maximum switching volt	age	250 V				
Rated operational voltag	ge U <sub>e</sub> and AC-12 (resistive) 230 V	4 A				
rated operational curren	t I <sub>e</sub> AC-15 (inductive) 230 V	3 A				
	DC-12 (resistive) 24 V	4 A				
	DC-13 (inductive) 24 V	2 A				
AC rating (UL 508)	Utilization category					
- '	(Control Circuit Rating Code)					
	max. rated operational voltage	300 V AC				
	max. continuous thermal current at B 300	5 A				
_	max. making/breaking apparent power at B 300	3600/360 VA				
Mechanical lifetime		30 x 10 <sup>6</sup> switching cycles				
Electrical lifetime (AC-12	, 230 V, 4 A)	0.3 x 10 <sup>6</sup> switching cycles				
Max. fuse rating to achie	ve short-circuit n/c contact	-				
protection	n/o contact	10 A fast-acting				
General data						
Duty cycle		100 %				
Dimensions			see dimensional drawings			
Mounting		DIN rail (IEC/EN 60715)				
Nounting position		any				
Degree of protection	enclosure / terminals					
Ambient temperature ra	nge operation / storage	-				
Electrical connection		ı	,			
Wire size	fine-strand with wire-end ferrule	2 x 0.75-1.5 mm² (2 x 18-16 AWG)				
-	fine-strand without wire-end ferrule	`				
		2 x 0.75-1.5 mm² (2 x 18-16 AWG)				
-						
Stripping length		10 mm (0.39 inch)				

\_

### Liquid level monitoring relays

Туре		CM-ENE MIN	CM-ENE MAX				
Standards / Directives			·				
Standard		IEC/EN 60947-5-1					
Low Voltage Directive		2014/35/EU					
EMC Directive		2014/35/EU					
RoHS Directive		2011/65/EU					
Electromagnetic compatibility							
Interference immunity to		EN 61000-6-2, EN 61000-6-	4				
Electrostatic discharge	IEC/EN 61000-4-2	level 3 (6 kV / 8 kV)					
Radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)					
Electrical fast transient / burst	IEC/EN 61000-4-4	level 3 (2 kV / 5 kHz)					
Surge	IEC/EN 61000-4-5	level 4 (2 kV L-L)					
Conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3 (10 V)					
Interference emission							
high-frequency radiated	IEC/CISPR 22, EN 55022	class B					
high-frequency conducted	IEC/CISPR 22, EN 55022	class B					
Environmental data							
Ambient temperature ranges	mbient temperature ranges operation/storage						
Damp heat	amp heat IEC/EN 60068-2-30		40 °C, 93 % RH, 4 days				
Vibration withstand	IEC/EN 60068-2-6	10-57 Hz: 0.075 mm; 57-150 Hz: 1 g					
Isolation data							
Rat. insulation volt. betw. supply, measuring & output circuit		250 V					
Rated impulse withstand voltage U <sub>imp</sub> between all isolated circuits		4 kV / 1.2-50 μs					
Pollution category		3					
Overvoltage category		III					

<sup>1)</sup> Open-circuit principle: Output relay energizes if the measured value exceeds/drops below the adjusted threshold.

Closed-circuit principle: Output relay de-energizes if the measured value exceeds/drops below the adjusted threshold.

Туре			CM-ENS.1x		CM-ENS.2x		CM-ENS.3	1				
Supply circuit			,				,					
Rated control supply	CM-ENS.11, CN	1-ENS.21, CM-ENS.31: A1-A2	24-240 V A	C/DC								
voltage U <sub>s</sub>	CM	1-ENS.13, CM-ENS.23: A1-A2										
-	CM	1-ENS.13, CM-ENS.23: A3-A2	2 110-130 V AC									
Rated control supply voltage U <sub>s</sub> tolerance			-15+10 %									
Rated frequency			50-60 Hz									
Frequency range			47-63 Hz									
Typical current / power consumption		24 V AC	25 mA / 0.6 W 25 mA / 0.6 W			25 mA / 0.6 W						
		110-130 V AC	20 mA / 2.6 VA		20 mA / 2.6 VA		8 mA / 1.1 VA					
		220-240 V AC	8.5 mA / 2.1 VA		8.5 mA / 2.1 VA		10 mA / 2.4 VA					
		24-240 V AC/DC	11 mA / 2.6	11 mA / 2.6 VA			11 mA / 2.6 VA					
Power failure buffering time		min.	. 20 ms									
Start-up time t <sub>s</sub>		Range 5-100 kΩ	max. 1.3 s									
		Range 0.1-1 kΩ	- max. 900 ms									
		Range 1-10 kΩ	- max. 900 ms									
		Range 10-100 kΩ	- max. 1.3 s									
		Range 100-1000 kΩ	-		max. 6.3 s							
Measuring circuit		MAX-MIN-C										
Sensor type			electrode									
Monitoring function			fill or drain fill or drain, selectable									
Measuring principle			conductivity measurement									
Number of electrodes			3									
Response sensitivity			adjustable: $5-100  k\Omega$ adjustable: $0.1-1000  k\Omega$									
Maximum electrode voltage			6 V AC									
Maximum electrode current			1 mA		2 mA							
			max cable	max cable	max cable	max cable	max cable	max				
			capacity	length	capacity	length	capacity	cable				
= 1		B 540010	10 =	100				length				
Electrode supply line		Range 5-100 kΩ		100 m	-	-	-	-				
		Range 0.1-1 kΩ		-	200 nF	1000 m	200 nF	1000 m				
		Range 1-10 kΩ		-	200 nF	1000 m	200 nF	1000 m				
		Range 10-100 kΩ		-	20 nF	100 m	20 nF	100 m				
		Range 100-1000 kΩ	-	-	4 nF	20 m	4 nF	20 m				
Max. measuring cycle		Range 5-100 kΩ										
		Range 0.1-1 kΩ	- 700 ms									
Rang		Range 1-10 kΩ			700 ms							
		Range 10-100 kΩ										
		Range 100-1000 kΩ	- 5 s									
Timing circuit			,									
Time delay		- 0.1-30 s, adjustab ON- or OFF-delay										
Indication of operational st	ates	,										
			U: green LED									
Control supply voltage			U: green LE	.D				R: Yellow LED				
Control supply voltage Output relay energized			_									


Туре			CM-ENS.1x	CM-ENS.2x	CM-ENS.31	
Output circuits						
Kind of output		11 <sub>15</sub> -12 <sub>16</sub> /14 <sub>18</sub>			relay, 1st c/o (SPDT) contact	
		21 <sub>15</sub> -22 <sub>16</sub> /24 <sub>18</sub>	1 3,		relay, 2nd c/o (SPDT contact	
Operational principle			open-circuit principle	open- or closed-circuit	orinciple (selectable)	
Contact material			AgNi alloy, Cd free			
Minimum switching voltage / minimum switching current			12 V / 10 mA			
Maximum switching voltag	e / Maximum switch	ing current	see data sheets			
		AC-12 (resistive) 230 V	4 A			
		AC-15 (inductive) 230 V	3 A			
		DC-12 (resistive) 24 V	4 A			
		DC-13 (inductive) 24 V	2 A			
AC rating (UL 508)		Utilization category (Control Circuit Rating Code)		B 300, pilot duty general purpose 250 V, 4 A, $\cos \phi$ 0.75		
	m	ax. rated operational voltage	300 V AC			
	max. continu	ous thermal current at B 300	5 A			
	max. making/break	ing apparent power at B 300	3600/360 VA			
Mechanical lifetime			10 x 10 <sup>6</sup> switching cycles			
Electrical lifetime (AC-12, 230 V, 4 A)			0.1 x 10 <sup>6</sup> switching cycles			
Max. fuse rating to achieve short-circuit protection			6 A / 10 A fast-acting 10 A / 10 A fast acting		10 A / 10 A fast- acting	
Conventional thermal curre	ent I <sub>th</sub>		4 A			

Туре		CM-ENS.1x	CM-ENS.2x	CM-ENS.31	
General data	,			·	
MTBF	,	on request			
Duty cycle		100 %			
Dimensions		see dimensional drawing	gs		
Weight		see ordering details	_		
Mounting		DIN rail (IEC/EN 60715),	snap-on mour	nting without any tool	
Mounting position		any			
Minimum distance to other units		CM-ENS.x1: not necessa	rv		
i-initialit distance to other units		CM-ENS.x3: 10 mm if cor	•	> 2 A	
Degree of protection	housing / terminals	IP50 / IP20			
Material of housing		UL 94 V-0			
Electrical connection		J.			
-		Screw connection techn	ology	Easy Connect Technology	
				(push-in)	
Wire size		1 x 0.5-2.5 mm <sup>2</sup> (1 x 18-1 2 x 0.5-1.5 mm <sup>2</sup> (2 x 18-1		2 x 0.5-1.5 mm² (2 x 18-16 AWG)	
		1 x 0.5-4 mm² (1 x 20-12	AWG)	2 x 0.5-1.5 mm² (2 x 20-16 AWG)	
Stripping length		2 x 0.5-2.5 mm <sup>2</sup> (2 x 20-1 8 mm (0.32 in)	4 AWG)		
Tightening torque		0.6 - 0.8 Nm (7.08 lb.in)		-	
Standards / Directives					
Standard	,	IEC/EN 60255-27, IEC/E	N 60947-5-1		
Low Voltage Directive		2014/35/EU			
RoHS Directive		2014/30/EU			
EMC Directive		2011/65/EU			
Environmental data					
	onoration	-25+60 °C			
Ambient temperature ranges	· · · · · · · · · · · · · · · · · · ·				
Damp hoat cyclic (IEC /EN 60000 3.30)	storage	-40+85 °C	/ DLI		
Damp heat, cyclic (IEC/EN 60068-2-30)		6 x 24 h cycle, 55 °C, 95 % RH			
Climatic category (IEC/EN 60721-3-3)	3K5 (no condensation, no ice formation)				
Vibration, sinusoidal (IEC/EN 60255-21-1)		class 2			
Shock (IEC/EN 60255-21-2)		class 2			
Isolation data		4117			
Rated impulse withstand voltage U <sub>imp</sub>	supply circuit / measuring circuit	4 kV			
	supply circuit / output circuits	4 kV			
	measuring circuit / output circuits	4 kV			
	output circuit 1 / output circuit 2	4 kV			
Pollution dograp (IEC/EN 60664.1)	output circuit 2	2			
Pollution degree (IEC/EN 60664-1)		3			
Overvoltage category (IEC/EN 60664-1)  Rated insulation voltage U <sub>i</sub>	supply circuit /	300 V			
	measuring circuit /	300 V			
	output circuits measuring circuit /	300 V			
_	output circuits output circuit 1 /	300 V			
Basisc insulation	output circuit 2	2			
	measuring circuit	it			
	supply circuit / output circuits	S			
_	measuring circuit / output circuits				
	output circuit 1 / output circuit 2	250 V AC / 300 V DC			


Туре		CM-ENS.1x	CM-ENS.2x	CM-ENS.31
Protective separation (IEC/EN 61140)	supply circuit / measuring circuit	250 V AC / 300 V DC		
	supply circuit / output circuits	250 V AC / 300 V DC		
	measuring circuit / output circuits	250 V AC / 300 V DC		
Pollution degree		3		
Overvoltage category		III		
Electromagnetic compatibility				
Interference immunity to	'	EN 61000-6-1, EN602	55-26	
electrostatic discharge	IEC/EN 61000-4-2	level 3 (6 kV / 8 kV)		
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)		
electrical fast transient / burst	IEC/EN 61000-4-4	level 3, 2 KV / 5 kHz		
surge	IEC/EN 61000-4-5	level 3, installation cla 2 kV L-earth	ass 3, supply circuit an	d measuring circuit 1 kV L-L,
conducted disturbances, induced by radio- frequency fields	IEC/EN 61000-4-6	level 3, 10 V		
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	class 3		
Interference emission		IEC/EN 61000-6-3, IE	C/EN 61000-6-4	
high-frequency radiated	IEC/CISPR 22, EN 55022	class B		
high-frequency conducted	IEC/CISPR 22, EN 55022	class B		

#### Function diagrams


#### **CM-ENS**




Drain: CM-ENS.1x, CM-ENS.2x



Fill: CM-ENS.2x




Drain: CM-ENS.31




Fill: CM-ENS.31

#### **CM-ENE MIN**



#### **CM-ENE MAX**



The liquid level relays CM-ENE MIN and CM-ENE MAX are used to monitor levels of conductive liquids, for example, in pump control systems for dry-running or overflow monitoring.

The measuring principle is based on the occurring resistance change when moistening single-pole electrodes. The single-pole electrodes (see also section Accessories) are connected to the terminals C and MIN or MAX. If the supply voltage is applied to A1-A2 and the electrodes are wet, the output relay of the CM-ENE MIN is energized

and the output relay of the CM-ENE MAX is de-energized.
The output relay of the CM-ENE MIN de-energizes if the electrodes are no longer wet. The output relay of the CM-ENE MAX energizes if the electrodes are no longer wet.

## Technical diagrams

\_


#### **Connection diagrams**

#### CM-ENS.11x, CM-ENS.21x

Α	1	11		
О		MAX	MIN	
C	MA I	X MIN	11 	
┆┟╴	!	─	/	
		=	ďΙ	015
A1		A2	12 14	CDC252 006 F0015
				2252
14		12	A2	000


A1–A2	Control supply voltage
11-12/14	1 c/o (SPDT) contact
С	Reference electrode
MAX	Maximum level electrode
MIN	Minimum level electrode

#### CM-ENS.13x, CM-ENS.23x




A1–A2	Control supply voltage 220-240 V AC
A3-A2	Control supply voltage 110-130 V AC
11-12/14	1 c/o (SPDT) contact
С	Reference electrode
MAX	Maximum level electrode
MIN	Minimum level electrode

#### CM-ENS.31x




A1-A2	Control supply voltage
11 <sub>15</sub> –12 <sub>16</sub> /14 <sub>18</sub>	1 c/o (SPDT) contact
21 <sub>25</sub> -22 <sub>26</sub> /24 <sub>28</sub>	2nd c/o (SPDT) contact
С	Reference electrode
MAX	Maximum level electrode
MIN	Minimum level electrode

#### **CM-ENE MIN**



A1-A2	Rated control supply voltage
С	Reference electrode
MIN	Minimum level
13-14	Output contact -open-circuit principle

#### **CM-ENE MAX**




A1-A2	Rated control supply voltage
С	Reference electrode
MIN	Maximum level
13-14	Output contact -open-circuit principle

## Technical diagrams


#### Connection diagrams

#### CM-ENS.1x




Liquid level control - drain

#### CM-ENS.2x, CM-ENS.31x



Liquid level control - fill - selected function "1" (UP)

#### CM-ENS.2x, CM-ENS.31x





Liquid level control - drain - selected function "\( \subset \)" (Down)

#### Technical diagrams


#### Load limit curves

#### CM-S (22.5 mm), CM-E (22.5 mm)











#### Contact lifetime

DC load (resistive)



#### Dimensional drawing

Dimensions in mm and inches



CM-xxS 1SVR730xxxxxx, 1SVR740xxxxxx



## **Accessories**

Table of contents

262 Ordering details

**Technical diagrams** 

## Accessories

## Ordering details





#### Ordering details

#### Accessories

Description	For type	Width in mm	for devices	Type	Order code	Pkg qty	Weight (1 pc)
							g (oz)
Adapter for screw	CM-S CM-S.S/P	22.5		ADP.01	1SVR430029R0100	1	18.4 (0.65)
mounting	CM-N CM-N.S/P	45		ADP.02	1SVR440029R0100	1	36.7 (1.30)
Marker label	CM-S, CM-N CM-S.S/P CM-N.S/P		without DIP switches	MAR.01	1SVR366017R0100	10	0.19 (0.007)
	CM-S, CM-N		with DIP switches	MAR.02	1SVR430043R0000	10	0.13 (0.005)
	CM-S.S/P CM-N.S/P		with DIP switches	MAR.12	1SVR730006R0000	10	0.152 (0.335)
Sealable	CM-S	22.5		COV.01	1SVR430005R0100	1	5.2 (0.18)
transparent cover	CM-N	45		COV.02	1SVR440005R0100	1	7.7 (0.27)
	CM-S.S/P	22.5		COV.11	1SVR730005R0100	1	4.0 (0.129)
	CM-N.S/P	45		COV.12	1SVR750005R0100	1	7 (0.247)

#### **Bar electrodes**

Description	Material no.	Туре	Order code	Weight (1 pc)
				kg (lb)
Compact support for 3 bar electrodes		CM-KH-3	1SVR450056R6000	0.06 (0.132)
Distance plate for 3 bar electrodes	-	CM-AH-3	1SVR450056R7000	0.06 (0.132)
Counter nut for 1" thread		CM-GM-1	1SVR450056R8000	0.06 (0.132)
Length: 300 mm	1.4301	CM-SE-300	1SVR450056R0000	0.08 (0.176)
Length: 600 mm	1.4301	CM-SE-600	1SVR450056R0100	0.08 (0.176)
Length: 1000 mm	1.4301	CM-SE-1000	1SVR450056R0200	0.08 (0.176)

#### **Suspension electrodes**

Description	Connec- tion	Material no.	Type	Order code	Weight (1 pc)
					kg (lb)
CM-HE suspension electrode high-alloy steel, material no. 1.4104 (according to EN 10088-1)	Screw	1.4104	СМ-НЕ	1SVR402902R0000	0.074 (0.163)
CM-HC suspension electrode high-alloy steel, material no. 1.4104 (according to EN 10088-1)	Crimp	1.4104	CM-HC	1SVR402902R1000	0.09 (0.198)
CM-HCT suspension electrode suitable for drink water high-alloy steel, material no. 1.4301 (according to EN 10088-1)	Crimp	1.4301	СМ-НСТ	1SVR402902R2000	0.09 (0.198)



For further details, please see the instruction sheet.

### Accessories

### Ordering details



см-ст



CM-CT with mounted accessories



CM-CT-A mounted on DIN rail

#### Plug-in current transformers CM-CT

- Without primary conductor though with foot angle, insulating protective cap and bar fastening screws
- Primary / rated current from 50 A to 600 A
- Secondary current of 1 A or 5 A
- Class 1

#### Ordering details

Rated primary current	Secondary current	Burden class	Туре	Order code	Weight (1 pc)
					g (oz)
50 A	1 A	1 VA / 1	CM-CT 50/1	1SVR450116R1000	0.31 (0.683)
75 A		1.5 VA / 1	CM-CT 75/1	1SVR450116R1100	0.31 (0.683)
100 A		2.5 VA / 1	CM-CT 100/1	1SVR450116R1200	0.276 (0.608)
150 A		2.5 VA / 1	CM-CT 150/1	1SVR450116R1300	0.32 (0.705)
200 A		2.5 VA / 1	CM-CT 200/1	1SVR450116R1400	0.222 (0.489)
300 A		5 VA / 1	CM-CT 300/1	1SVR450117R1100	0.29 (0.639)
400 A		5 VA / 1	CM-CT 400/1	1SVR450117R1200	0.27 (0.595)
500 A		5 VA / 1	CM-CT 500/1	1SVR450117R1300	0.29 (0.639)
600 A		5 VA / 1	CM-CT 600/1	1SVR450117R1400	0.24 (0.529)
50 A	5 A	1 VA / 1	CM-CT 50/5	1SVR450116R5000	0.3 (0.661)
75 A		1.5 VA / 1	CM-CT 75/5	1SVR450116R5100	0.31 (0.683)
100 A		2.5 VA / 1	CM-CT 100/5	1SVR450116R5200	0.31 (0.683)
150 A		2.5 VA / 1	CM-CT 150/5	1SVR450116R5300	0.28 (0.617)
200 A		5 VA / 1	CM-CT 200/5	1SVR450116R5400	0.29 (0.639)
300 A		5 VA / 1	CM-CT 300/5	1SVR450117R5100	0.252 (0.556)
400 A		5 VA / 1	CM-CT 400/5	1SVR450117R5200	0.26 (0.573)
500 A		5 VA / 1	CM-CT 500/5	1SVR450117R5300	0.208 (0.459)
600 A		5 VA / 1	CM-CT 600/5	1SVR450117R5400	0.21 (0.463)

#### Accessories

Description	Туре	Order code	Weight (1 pc) g (oz)
Snap-on fastener for DIN rail mounting of CM-CT	CM-CT A	1SVR450118R1000	0.009 (0.02)


#### \_

#### **Accessories**

### Technical diagrams


#### Operating principle / circuit diagram


#### см-ст





#### **Dimensional drawings**

in **mm** and inches










Sealable cover COV.11

Sealable cover COV:12



MAR.01


#### \_


### Accessories


### Technical diagrams

#### Dimensional drawings

in **mm** and inches









# **Power supplies**Table of contents

200	Overview					
270	Selection table					
275	Power supplies for industrial applications					
277	CP-E range					
297	CP-T range					
311	CP-S.1 range					
329	CP-C.1 range					
353	Power supplies for building applications					
354	CP-D range					
367	CP-B range					
379	Redundancy units					
389	Electronic protection devices EPD24					

## Overview

Modern power supply units are a vital component in energy management and automation technology. As your global partner in these areas, ABB pays the utmost attention to the resulting requirements. Innovation is the key to ABB's power supply product program.

#### Power supplies for industrial applications



#### CP-E range: economy range

The CP-E range offers enhanced functionality while the number of different types has been considerably reduced. Now all power supply units can be operated at an ambient temperature of up to +70 °C. The CP-E range 24 V devices over 18 W offer an output/contact for monitoring of the output voltage and remote diagnosis. Optimized for worldwide applications, the CP-E power supplies can be supplied within a wide range of AC or DC voltages. The output voltage is continuously adjustable, ensuring optimal adaptation to the application, e.g. compensating the voltage drop caused by a long line length. For decoupling of parallel connected power supplies below or equal to 56 V, redundancy modules are available in order to achieve true redundancy.



#### CP-T range: three-phase range

The CP-T range of three-phase power supply units perfectly complements ABB's existing power supply offering in terms of design and functionality, giving you more advanced options for your three-phase applications. Solid state output for function monitoring and remote diagnostics is available. The range is to be used in 340 - 575 V AC or 480 - 820 V DC supply systems. Its continuously adjustable output voltage ensures optimal adaptation to the application, e.g. compensating the voltage drop caused by a long line length.



#### CP-S.1 range: high-efficiency range

CP-S.1 power supplies: high efficiency and reliability delivered in a compact footprint. Designed for a huge variety of applications, including machine building segments, this advanced range boosts an integrated 150 % power reserve for five seconds and operates at an efficiency of up to 94 %. With overheat protection, active power factor correction, a broad certified AC and DC input range and extensive worldwide approvals including marine, the all-new CP-S.1 power supplies are a preferred choice for multiple industrial applications.

## Overview

#### Power supplies for industrial applications



#### CP-C.1 range: high-performance range

The CP-C.1 power supplies are ABB's high-performance and most advanced range. With excellent efficiency, high reliability and innovative functionality, the CP-C.1 range is ready to take on the most demanding industrial applications. These power supplies have a 150 % integrated power reserve and operate at an efficiency of up to 94 %. They are equipped with overheat protection and active power factor correction. Combined with a broad AC and DC input range and extensive worldwide approvals, the CP-C.1 power supplies are the preferred choice for professional DC applications. Giving the power to control.



#### CP-B range: short time buffers

ABB offers an innovative and completely maintenance- free product range for buffering the 24 V DC supply in case of interrupted mains on the primary side of the switch mode power supply.

- Ultra cap based buffer modules for short time UPS systems
- Rated input voltage 24 V DC
- Rated currents 3 A, 10 A and 20 A
- 10 A buffer module with increased capacity to buffer up to 9 min (10 % load)
- · LEDs for status indication
- Higher than 90 % efficiency
- Signaling and status outputs
- Buffering times at 100 % load current from 13 s to 50 s (depending on device)

#### Power supplies for building applications



#### CP-D range: distribution panel design

The CP-D range of power supply units in MDRC design (modular DIN rail components) fits into all domestic installation and distribution panels. With their width of only 18 to 90 mm, the CP-D range switch mode power supplies are ideally suited for installation in distribution panels. The range is optimized for worldwide applications: The CP-D power supplies can be supplied with 90-264 V AC or 120-375 V DC. The continuously adjustable output voltage (CP-D > 10 W) ensures optimal adaption to the application, e.g. compensating the voltage drop caused by a long line length. An additional redundancy unit CP-D RU to establish true redundancy is available.



For certifications and approvals, please refer to the download section on the product web pages.

# Selection table - Single-phase

	Order number	1SVR360563R1001	1SVR360663R1001	1SVR360763R1001	1SVR360563R2001	1SVR360663R2001	1SVR360763R2001	1SVR361563R1001	1SVR361663R1001	1SVR361763R1001	1SVR320361R1000	1SVR320561R1000	1SVR320661R1000	1SVR320761R1000	1SVR320861R1000
		Sir	ıgle-	pha	se										
		CP	P-C.1 CP-S.1												
Rated ou															
voltage	12 V DC	-													
	24 V DC	_	•	•	•	•	•	•	•	•	•	•	•	•	•
D-4I	48 V DC	+													
Rated ou current		_									_				
Current	0.625 A	_													
	0.75 A										_				
	0.83 A														
	1.25 A	-									-				
	2.1 A	-													
	2.5 A	_									$\vdash$				
	3 A	-													
	4.2 A										Ι-				
	5 A	-			•			•							
	10 A					•			•				•		
	20 A	_		•			•			•				•	
	40 A	İ													•
Rated ou	tput 10 W														
power	15 W														
	18 W														
	25 W														
	30 W														
	60 W														
	72 W										•				
	100 W														
	120 W				•			•							
	240 W					•			•						
	480 W									•				•	
	960 W														
Rated	100-240 V AC			•	•	•		•		•			•	•	
input	110-240 V AC														
voltage	115/230 V AC auto select														
	115-230 V AC														
DC	90-300 V DC	•	•	•	•	•	•	•	•	•					
input voltage	90-375 V DC	-									<u> </u>				
range	100-250 V DC	_									•	•	•	•	_
-	110-250 V DC 120-375 V DC	-									-				•
	210-375 V DC	-													
Features	Power reserve design	_		-	•	•	•	•	•	-			•	•	•
	Adjustable output voltage	-			-	-	-	-	-	-			-	-	-
	Integrated input fuse	-			-	-	-	-	-	-			-	-	-
	Short-circuit stable	_			-	-	-	-	-	-	-		-		-
	Fold-forward behavior (U/I)	-											-	-	-
	Fold-back behavior (hiccup)		_	_	_	_	_	_	_	_	<u> </u>	_	_	_	_
	Power factor correction	-	act	no	act	act	act	ac+							
	Signalling contact	-	act	act	act	act	act ■	act ■	act	act		act ■	act ■	act ■	act •
	Extended temp. rang	_	-	_				-	-	-	├-	_	_	_	_
	Parallel connection	_	5	5	5	5	5	5	5	5	3	3	3	3	2
	Serial connection	_	2	2	2	2	2	2	2	2	2	2	2	2	2
		_							۲						
	Coated PCBA														

# Selection table - Single-phase

		Order number	1SVR427033R3000	1SVR427032R1000	1SVR427035R1000	1SVR427030R0000	1SVR427031R0000	1SVR427032R0000	1SVR427034R0000	1SVR427035R0000	1SVR427036R0000	1SVR427030R2000	1SVR427031R2000	1SVR427034R0000	1SVR427035R2000	1SVR427041R1000	1SVR427043R1200	1SVR427041R0000	1SVR427043R0100	1SVR427044R0200	1SVR427045R0400
			_	_	pha	se															
			CP-	·E										1		CP.	·D				
Rated out	tput	5 V DC	•																		
voitage	_	12 V DC		-	•											•					
	-	24 V DC				•	•	•	•	•	•							•	•	•	•
Date days		48 V DC										•	•	•	_						
Rated out	tput	0.42 A														_					
current	_	0.625 A										-				_					
	-	0.75 A				•										<u> </u>					
	-	0.83 A					_									•					
	_	1.25 A					•						•						_		
	-	1.3 A	-													-	_		-		
	-	2.1 A		_		-	-	_								-	-			_	
	-	2.5 A 3 A	-	-				-								-				-	
	-	4.2 A	-													-					_
	-	4.2 A 5 A																			-
	-	10 A			_				-	_					_						
	-	20 A			-					-	_				-						
	-	40 A	l I								-										
Rated out	tnut	10 W	┢		_	_	_				_				_	┢		_	_	_	_
power	-	15 W	-													•		•			
•	-	15 W				_															
	-					-											_				
	-	25 W		_			_					_							_		
	-	30 W		-			•					-							•		
	-	60 W						•					•							•	
	_	72 W																			
	-	100 W																			-
	_	120 W			-				•												
	_	240 W								•				•							
	_	480 W									•				•						
		960 W																			
Rated input		100-240 V AC	•	•		•	•	•				•	•			•	•	•	•	•	•
voltage		110-240 V AC																			
voltage	115/230	V AC auto select			-				•	•				•							
		115-230 V AC									•				•						
DC		90-300 V DC																			
input		90-375 V DC		•			•	•				•	•								
voltage range		100-250 V DC																			
		110-250 V DC	L_													L_					_
		120-375 V DC			-	•			_	_	-				-	•		•	•	•	-
<del></del>		210-375 V DC	_		-				•	_	_										_
Features		r reserve design	<u> </u>	_	_	_	_	_	_	_	_	_	_	_	_	-	_		_	_	_
		output voltage		-	-	-	-	-	-	-	-	-			-	<u> </u>	-	_	-	-	-
		rated input fuse	•	•	•	•	•	•	•	-	•	•	•	•	•	•	•	•	•	•	•
		rt-circuit stable	•	-	•	•	•	•	•	-	•	•			-	•		•	•	•	-
		d behavior (U/I)	<u> </u>	•	•		•	•	•	-	•	•	•	•	•		•		•	•	•
		ehavior (hiccup)	•			•										•		•			
	Power fa	actor correction			pas				pas	pas	act			pas	act						
	Sig	gnalling contact					•	•	•	-	-										
	Exten	ded temp. range		-	•										-	•			•	•	-
	Par	allel connection	•	•	3	•	•	•	3	3	3	•	•	3	3						
	Se	erial connection	•	•	2	•	•	•	2	2	2	•	•	2	2	•	•	•	•	•	•
		Coated PCBA																			

## Selection table - Three-phase

		Order number	1SVR427054R0000	1SVR427055R0000	1SVR427056R0000	1SVR427057R0000	1SVR427054R2000	1SVR427055R2000	1SVR427056R2000
			Th	ree-	phas	se			
			СР	-Т					
Rated output v	oltage	24 V DC	•	•	•	•			
		48 V DC	ĺ				•	•	•
Rated output c	urrent	5 A	•				•		
		10 A							
		20 A							
		40 A				•			
Rated output p	ower	120 W							
		240 W							
		480 W			•			•	
		960 W							
Rated input voltage		3 x 400-500 V AC	•	•					•
DC input voltage range		480-820 V DC	•	•					•
Features	Adjustab	le output voltage	•	•	•	•	•	•	•
	Inte	grated input fuse	•	•	•	•	•	•	•
-	Sh	ort-circuit stable	•	•	•	•	•	•	•
-	Fold forwa	rd behavior (U/I)	•	•	•		•	•	
	Fold back	behavior (hiccup)	•	•	•	•	•	•	•
	Exter	nded temp. range	•	•	•	•	•	•	•
	S	ignalling contact	•	•	•	•			
	Pa	arallel connection		2	2	2	2	2	2
		Serial connection		2	2	2	2	2	2





# Power supplies for industrial applications

Table of contents

277 CP-E range

297 CP-T range

311 CP-S.1 range

329 CP-C.1 range



# **CP-E range**Table of contents

210	benefits and advantages
280	Operating controls
281	Applications
282	Ordering details
283	Technical data
293	Technical diagrams

## Benefits and advantages



ABB's CP-E range offers enhanced functionality and a simpler, more rational selection process. All power supply units can be operated at an ambient temperature of up to +70 °C (158 °F).



Affordable range

Products with exactly the functions you require.

Designed for best possible price-performance ratio.



The product can be used in any installations in the world. Giving you the confidence of worldwide sourcing – no matter where you build, install or operate your equipment.



Speed up your projects

Data available for common planning software: Less engineering time required.

## Benefits and advantages



#### Characteristics

- Output voltages 5 V, 12 V, 24 V, 48 V DC
- · Adjustable output voltages
- Output currents 0.625 A / 0.75 A / 1.25 A / 2.5 A / 3 A / 5 A / 10 A / 20 A
- Power range 15 W, 18 W, 30 W, 60 W, 120 W, 240 W, 480 W
- High efficiency, up to 90 %
- · Low power dissipation and low heating
- Free convection cooling (no forced cooling with ventilators)
- · Open-circuit, overload and short-circuit stable
- · Integrated input fuse
- U/I characteristic curve on devices > 18 W (fold-forward behavior at overload no switch-off)
- Redundancy units offering true redundancy
- · LED(s) for status indication
- · Signalling output/contact for output voltage OK
  - Transistor on 24 V devices > 18 W and < 120 W
  - Solid-state on 24 V devices ≥ 120 W
- · Various approvals and marks



#### Main benefits

## Signalling output / contact

The CP-E range 24 V devices > 18 W offer an output/contact for monitoring of the output voltage and remote diagnosis.

## Wide range input

Optimized for worldwide applications: The CP-E power supplies can be supplied with a wide range of AC or DC voltages.

## Adjustable output voltage

A continuously adjustable output voltage ensures optimal adaptation to the application, e.g. compensating the voltage drop caused by a long line length.

## Redundancy units

For decoupling of parallelized power supply units ≤ 40 A. Thus, true redundancy can be achieved.










## Operating controls



INPUT L, N, PE: terminals - input

90-132 V AC, 180-265 V AC / 210-375 V DC 90-264 V AC / 120-375 V DC 85-264 V AC / 90-375 V DC

# **Applications**



Tooling machines



Packaging industry



Food industry



Textile industry



Printing industry



Electromobility













#### Ordering details



CP-E 5/3.0



#### Ordering details - CP-E < 100 W

international standards.

Description



CP-E 12/2.5

2CDC 271 013 F0006	
2CDC 2	



CP-E 48/5.0



CP-E 24/20.0

Input voltage range	Rated output voltage / current	Туре	Order code	Weight (1 pc.) kg (lb)
90-264 V AC / 120-375 V DC	5 V DC / 3 A	CP-E 5/3.0	1SVR427033R3000	0.15 (0.33)
85-264 V AC / 90-375 V DC	12 V DC / 2.5 A	CP-E 12/2.5	1SVR427032R1000	0.29 (0.64)
90-132 V AC, 180-264 V AC / 210-375 V DC	12 V DC / 10 A	CP-E 12/10.0	1SVR427035R1000	1.00 (2.20)
90-264 V AC / 120-375 V DC	24 V DC / 0.75 A	CP-E 24/0.75	1SVR427030R0000	0.15 (0.33)
85-264 V AC / 90-375 V DC	24 V DC / 1.25 A	CP-E 24/1.25	1SVR427031R0000	0.29 (0.64)
85-264 V AC / 90-375 V DC	24 V DC / 2.5 A	CP-E 24/2.5	1SVR427032R0000	0.36 (0.79)

This range offers types with output voltages from 5 V DC to 48 V DC at output currents of 0.625 A to 20 A. With their high thermal efficiency of up to 90 %, these power supplies have very low power and heat dissipation and can be operated without forced cooling. The functionality has

Of course, all power supplies of the CP-E range are approved in accordance with all relevant

been enhanced while the number of different types has been considerably reduced.

#### Ordering details - CP-E ≥ 120 W

Input voltage range	Rated output voltage / current	Туре	Order code	Weight (1 pc.) kg (lb)
90-132 V AC, 180-264 V AC / 210-375 V DC	24 V DC / 5 A	CP-E 24/5.0	1SVR427034R0000	1.00 (2.20)
90-132 V AC, 180-264 V AC / 210-375 V DC	24 V DC / 10 A	CP-E 24/10.0	1SVR427035R0000	1.36 (3.01)
90-264 V AC / 120-375 V DC	24 V DC / 20 A	CP-E 24/20.0	1SVR427036R0000	1.90 (4.18)
85-264 V AC / 90-375 V DC	48 V DC / 0.625 A	CP-E 48/0.62	1SVR427030R2000	0.29 (0.64)
85-264 V AC / 90-375 V DC	48 V DC / 1.25 A	CP-E 48/1.25	1SVR427031R2000	0.36 (0.79)
90-132 V AC, 180-264 V AC / 210-375 V DC	48 V DC / 5 A	CP-E 48/5.0	1SVR427034R2000	1.36 (3.01)
90-264 V AC / 120-375 V DC	48 V DC / 10 A	CP-E 48/10.0	1SVR427035R2000	1.90 (4.19)

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 5/3.0	CP-E 12/2.5	CP-E 12/10.0
Input circuit		L, N		
Rated input voltage U <sub>in</sub>		100-240 V AC		115 / 230 V AC auto select
Input voltage range		90-264 V AC / 120-375 V DC	85-264 V AC / 90-375 V DC	90-132 V AC, 180-264 V AC / 210-375 V DC
Frequency range AC		47-63 Hz		
Typical input current	at 115 V AC	335 mA	560 mA	2.2 A
	at 230 V AC	210 mA	330 mA	0.83 A
Typical power consumption		19.8 W	35.9 W	143 W
Inrush current	at 115 V AC	15 A	20 A	24 A
	at 230 V AC	30 A	40 A	48 A
Discharge current	input / output	0.25 mA		<u>'</u>
	input / PE	3.5 mA		
Power failure buffering time	at 115 V AC	min. 20 ms	min. 20 ms	min. 25 ms
_	at 230 V AC	min. 75 ms	min. 30 ms	min. 30 ms
Internal input fuse		2 A slow-acting / 250 V	AC	3.15 A slow-acting / 250 V AC
Power factor correction (PFC)		no		yes, passive, 0.7
Indication of operational states				) to, passive, e
Output voltage	green LED	OK: S:: output voltage OK	OUTPUT OK: : :: output voltage OK	OUTPUT OK: :: output voltage OK
	red LED	LOW: ::: output voltage too low	-	OUTPUT LOW: : :: output voltage too low
Output circuit		L+,L-	L+, L+, L-, L-	
Rated output voltage		5 V DC	12 V DC	
Tolerance of the output voltage		0+1 %		
Adjustment range of the output voltage		4.5-5.75 V DC	12-14 V DC	11.4-14.5 V DC
Rated output power		15 W	30 W	120 W
Rated output current I,	T <sub>2</sub> ≤ 60 °C		2.5 A	10 A
Derating of the output current	a = 30  °C		2.5 %/°C	2071
Maximum deviation with	load change statical		±0.5 %	±1 % (single mode) ±5 % (parallel mode)
	change of output voltage within the input voltage range	±1 %	±0.5 %	±0.5 %
Recovery time T <sub>R</sub>		< 2 ms		
Starting time after applying the supply v	oltage at L	_		
	with 3500 μF		max. 2 s	-
	with 7000 μF		-	max. 1.5 s
Rise time	·	max. 150 ms		
	with 3500 μF		max. 500 ms	-
	with 7000 μF		-	max. 500 ms
Fall time		max. 150 ms		
Residual ripple and switching peaks	BW = 20 MHz	50 mV		
Parallel connection		yes, to enable redundan	су	configurable, to increase power, up to 3 devices, min. 0.1 I <sub>r</sub> - max. 0.9 I <sub>r</sub>
Series connection		yes, to increase voltage		yes, to increase voltage, max. 2 devices
Resistance to reverse feed		1 s - max. 7.5 V DC	1 s - max.18 V DC	max. 18 V DC
Output circuit - No-load, overload and s	hort-circuit behavior			
Characteristic curve of output		hiccup-mode	U/I characteristic curve	2
Short-circuit protection		continuous short-circui	t proof	
Short-circuit behavior		Hiccup-mode	continuation with outp	ut power limiting
Overload protection		output power limiting		
No-load protection		continuous no-load stal	oility	
110 load protection			,	

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 5/3.0	CP-E 12/2.5	CP-E 12/10.0				
General data		CF-L 3/ 3.0	CF-L 1L/L.3	CF-E 12/10.0				
Power loss		typ. 5 W	typ. 5.6 W	typ. 24 W				
Efficiency		typ. 5 W	typ. 5.6 W	typ. 24 W				
Duty cycle		100 %	тур. 04 70	typ. 64 70				
Dimensions			owings"					
		see "Dimensional drawings"						
Material of housing Mounting		plastic metal  DIN rail (IEC/EN 60715), snap-on mounting without any tool						
Mounting		horizontal	13), snap-on mounting	without any tool				
Mounting position  Minimum distance to other units	horizontal (vortical	25 mm / 25 mm (0.9	9 in / 0 00 in)					
Degree of protection	housing / terminals		6 111 / 0.36 111)					
Protection class	nousing / terminals	1						
	out circuit	!						
Electrical connection - input circuit / out				0.3.4 mm² /34.11.0 M/C				
Connecting capacity	fine-strand with wire end ferrule			0.2-4 mm² (24-11 AWG)				
	fine-strand without wire end ferrule	0.2-2.5 mm2 (24-14 /	AWG)	0.2-6 mm² (24-10 AWG)				
_	rigid							
Stripping length		6 mm (0.24 in)		8 mm (0.31 in)				
Tightening torque	0.6 Nm (5 lb.in)		1.0 Nm (9 lb.in) / 0.62 Nm (5.5 lb.in)					
Environmental data			,	l.				
Ambient temperature range	operation	-20+70 °C	-40+70 °C	-35+70 °C				
	rated load	-20+60 °C	-40+60 °C	-35+60 °C				
	storage	-20+85 °C	-40+85 °C	-40+85 °C				
Damp heat		95 RH, % without co	ndensation					
Vibration (sinusoidal) (IEC/EN 60068-2-6)		10-500 Hz, 2 G, alone	g X, Y, Z each axis, 60 mi	n. for each axis				
Shock (half-sine) (IEC/EN 60068-2-27)		15 G, 11 ms, 3 axes,	5 faces, 3 times for each	face				
Isolation data								
Rated insulation voltage U,	input circuit / output circuit	3 kV AC						
	input / PE	1.5 kV AC						
	output / PE	0.5 kV AC; 0.71 kV DC	•					
Pollution degree		2						
Overvoltage category		II						
Standards / Directives								
Standards		IEC/EN62368-1						
Low Voltage Directive		2014/35/EU						
EMC Directive		2014/30/EU						
RoHS Directive		2011/65/EU						
Protective low voltage		SELV (IEC60950-1)						
Electromagnetic compatibility								
Interference immunity to		IEC/EN 61000-6-2						
electrostatic discharge	IEC/EN 61000-4-2	level 4 (air discharge	15 kV / contact dischar	ge 8 kV)				
radiated, radio-frequency, electromagneti	c field IEC/EN 61000-4-3	level 3 (10 V/m)						
electrical fast transient/burst		level 4 (4 kV / 2,5 kH	z) level 4 (4 kV / 5 kH	z)				
surge		L-L level 3 (2 kV) / L-		•				
conducted disturbances, induced by radio frequency fields								
power frequency magnetic fields	IEC/EN 61000-4-8	level 4 (30 A/m)						
voltage dips, short interruptions and volta			30 % 500 ms					
variations	- ,	interruptions: >95 % 5000 ms						
Interference emission		IEC/EN 61000-6-3						
high-frequency radiated		class B						
high-frequency conducted		class B						
limits for harmonic current emissions	IEC/EN 61000-3-2	class D	class A	class D				

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 24/0.75	CP-E 24/1.25	CP-E 24/2.5	
Input circuit		L, N	<u> </u>		
Rated input voltage U <sub>in</sub>			100-240 V AC		
Input voltage range		90-264 V AC / 120-375 V DC	85-264 V AC / 90-375 V DC		
Frequency range AC		47-63 Hz			
Typical input current	at 115 V AC	335 mA	560 mA	1060 mA	
	at 230 V AC	210 mA	330 mA	590 mA	
Typical power consumption		22.8 W	36.7 W	69.2 W	
nrush current	at 115 V AC	15 A	20 A (max. 3 ms)	30 A	
	at 230 V AC	30 A	40 A (max. 3 ms)	60 A	
Discharge current	input / output	0.25 mA			
	input / PE	3.5 mA			
Power failure buffering time	at 115 V AC	min. 20 ms	min. 20 ms		
	at 230 V AC	min. 75 ms	min. 30 ms		
Internal input fuse		2 A slow-acting / 250 V	slow-acting / 250 V AC		
Power factor correction (PFC)		no			
Indication of operational states					
Output voltage	green LED	OK: :: output voltage OK	OUTPUT OK:	l: output voltage OK	
	red LED	LOW: :: output voltage too low	-	-	
Putput circuit		L+,L-	L+, L+, L-, L-	·	
Rated output voltage		24 V DC			
Tolerance of the output voltage		0+1 %			
Adjustment range of the output voltage	· · · · · · · · · · · · · · · · · · ·		21.6-28.8 V DC 24-28 V DC		
Rated output power		18 W	30 W	60 W	
Rated output current I,	T <sub>3</sub> ≤ 60 °C	0.75 A	1.25 A	2.5 A	
Derating of the output current	60 °C < T₂ ≤ 70 °C				
Signalling output for output voltage OK	DC OK		transistor		
Maximum deviation with	load change statical	±2 %	±0.5 %		
-	change of output voltage within the input voltage range	±1 %	±0.5 %		
Recovery time T <sub>s</sub>	· · · · · · · · · · · · · · · · · · ·		< 2 ms		
Starting time after applying the supply v	oltage at I,				
,,	 with 3500 μF		max. 2 s	-	
	with 7000 μF	max. 1.5 s	-	max. 1.5 s	
Rise time	at rated load	max. 150 ms		'	
	with 3500 μF	-	max. 500 ms	-	
	with 7000 μF	max. 500 ms	-	max. 500 ms	
Fall time	·	max. 150 ms		·	
Residual ripple and switching peaks			50 mV		
		yes, to enable redundancy			
		yes, to increase voltage			
Resistance to reverse feed		1 s - max. 35 V DC			
Output circuit - No-load, overload and s	hort-circuit behavior				
Characteristic curve of output		hiccup-mode U/I characteristic curve			
Short-circuit protection		continuous short-circuit proof			
Short-circuit behavior		hiccup-mode continuation with output power limiting			
Overload protection		output power limiting			
·		continuous no-load stability			
Starting of capacitive loads			,		

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 24/0.75	CP-E 24/1.25	CP-E 24/2.5	
General data					
Power loss		typ. 4.45 W	typ. 5.5 W	typ. 8.8 W	
Efficiency		typ. 77 %	typ. 86 %	typ. 89 %	
Duty cycle		100 %	<u>'</u>	<u>'</u>	
Dimensions		see "Dimensional drawings"			
Material of housing		plastic			
Mounting		DIN rail (IEC/EN 60715), snap-on mounting without any tool			
Mounting position		horizontal			
Minimum distance to other units	horizontal / vertical	25 mm / 25 mm (0.98 in / 0.98 in)			
Degree of protection	housing / terminals				
		ı			
Electrical connection - input circuit / output of	rcuit				
Connecting capacity	fine-strand with wire end ferrule				
	fine-strand without wire end ferrule	0.2-2.5 mm² (24-14 AWG)			
	rigid				
ripping length		6 mm (0.24 in)			
		0.6 Nm (5 lb.in)			
Environmental data					
Ambient temperature range	operation	-20+70 °C	-40+70 °C		
	rated load	-20+60 °C	-40+60 °C		
	storage	-20+85 °C	-40+85 °C		
Damp heat (cyclic) (IEC/EN 60068-2-30)		95 % RH, without condensation			
Vibration (sinusoidal) (IEC/EN 60068-2-6)		10-500 Hz, 2 G, along X, Y, Z each axis, 60 min. for each axis			
Shock (half-sine) (IEC/EN 60068-2-27)		15 G, 11 ms, 3 axes, 6 faces, 3 times for each face			
Isolation data			,	1	
Rated insulation voltage U, in	put circuit / output circuit	3 kV AC			
	input / PE				
	•	0.5 kV AC; 0.71 kV DC			
Pollution degree	-		2		
Overvoltage category		II			
Standards / Directives	1	,		,	
Standards	1	IEC/EN62368-1		1	
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
Protective low voltage		SELV (IEC60950-1)			
Electromagnetic compatibility					
Interference immunity to		IEC/EN 61000-6-2			
radiated, radio-frequency, electromagnetic fie					
electrical fast transient/burst	IEC/EN 61000-4-4			·)	
surge					
conducted disturbances, induced by radio-	IEC/EN 61000-4-6	5 L-L level 3 (2 kV) / L-PE level 4 (4 kV)			
frequency fields	·	· ·			
ower frequency magnetic fields IEC/EN 61000-4-8					
oltage dips, short interruptions and voltage IEC/EN 61000-4-11 ariations					
Interference emission		IEC/EN 61000-6-3			
high-frequency radiated		class B			
high-frequency conducted		class B			
limits for harmonic current emissions	IEC/EN 61000-3-2	-I B	class A		

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 24/5.0	CP-E 24/10.0	CP-E 24/20.0
Input circuit		L, N		
Rated input voltage U <sub>in</sub>	ated input voltage U <sub>in</sub>		115 / 230 V AC auto select	
Input voltage range		90-132 V AC, 180-264 V AC / 210-375 V DC	90-132 V AC, 180-264 V AC / 210-375 V DC	90-264 V AC, 120-375 V DC
Frequency range AC		47-63 Hz		
Typical input current	at 115 V AC	2.2 A	4.0 A	4.9 A
	at 230 V AC	0.83 A	1.55 A	2.5 A
Typical power consumption		140 W	270 W	539 W
nrush current	at 115 V AC	24 A (max. 5 ms)	30 A (max. 5 ms)	25 A (max. 5 ms)
	at 230 V AC	48 A (max. 5 ms)	60 A (max. 5 ms)	50 A (max. 5 ms)
Discharge current	input / output	0.25 mA		
	input / PE	3.5 mA		
Power failure buffering time	at 115 V AC	min. 25 ms		
	at 230 V AC	min. 30 ms		
Internal input fuse		3.15 A slow-acting / 250 V AC	6.3 A slow-acting / 250 V AC	10 A slow-acting / 250 V AC
Power factor correction (PFC)		yes, passive, 0.7	yes, passive, 0.75	yes, active 115 V AC: 0.99 230 V AC: 0.97
Indication of operational states				
Output voltage	green LED	OUTPUT OK:  ::	output voltage OK	
	red LED	OUTPUT LOW:	output voltage too low	
Output circuit		L+, L+, L-		
Rated output voltage		24 V DC		
Tolerance of the output voltage		0+1 %		
Adjustment range of the output voltage		22.5-28.5 V DC		
Rated output power		120 W	240 W	480 W
Rated output current I <sub>r</sub>	T₂ ≤ 60 °C	5 A	10 A	-
r	a T <sub>a</sub> ≤ 55 °C		-	20 A
Derating of the output current	60 °C < T₂ ≤ 70 °C			-
<b>3</b>	55 °C < T <sub>a</sub> ≤ 70 °C		-	2.5 %/°C
Signalling contact for output voltage OK	<u> </u>	solid-state (max. 60 V I	DC. 0 3 A)	
Minimum fuse rating to achieve short-circuit protection		$\geq 60 \text{ V DC}, \leq 0.3 \text{ A fast-acting}$		
Maximum deviation with	load change statical	±1 % (single mode), ±5 % (parallel mode)		
	ange of output voltage the input voltage range			
Recovery time T <sub>R</sub>		< 2 ms		
Starting time after applying the supply voltage	at I,	max. 1 s	2.5 s (at -40 °C / 90 V AC starting time >2.5 s has to be expected)	max. 1 s
	with 3500 μF	max. 1.5 s	-	-
	with 7000 μF	-	2.5 s	max. 1.5 s
Rise time	at rated load	max. 150 ms		
	with 3500 μF	max. 500 ms		-
	with 7000 μF	- max. 500 ms		
Fall time		max. 150 ms		
Residual ripple and switching peaks BW = 20 MHz		50 mV 100 mV		
Parallel connection		configurable, to increase power, up to 3 devices, min. 0.1 I, - max. 0.9 I,		
Series connection		yes, to increase voltage, max. 2 devices		
Resistance to reverse feed		max. 35 V DC		

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 24/5.0	CP-E 24/10.0	CP-E 24/20.0	
Output circuit - No-load, overload	and short-circuit behavior	^	<del>'</del>	•	
Characteristic curve of output		U/I characteristic	curve		
		continuous short-circuit proof			
·		continuation with output power limiting			
Overload protection		output power limiting			
No-load protection	·		d stability		
		3500 μF 7000 μF			
General data			· · · · · ·		
Power loss		typ. 20 W	typ. 35 W	typ. 63 W	
Efficiency		typ. 86 %	typ. 89 %	typ. 89 %	
Duty cycle		100 %			
Dimensions			see "Dimensional drawings"		
Material of housing			-		
		DIN rail (IEC/EN 60	0715), snap-on mounting	without any tool	
Mounting position		horizontal			
Minimum distance to other units	horizontal / vertical	25 mm / 25 mm (0.98 in / 0.98 in)			
Degree of protection	housing / terminals				
Protection class		1			
Electrical connection - input circuit	it / output circuit	·			
Connecting capacity	fine-strand with wire end ferrule	0.2-4 mm² (24-11 A	AWG)		
	fine-strand without wire end ferrule	0.2-6 mm² (24-10 A	AWG)		
	rigid				
Stripping length		8 mm (0.31 in)			
Tightening torque	input / output	input / output 1.0 Nm (9 lb.in) / 0.62 Nm (5.5 lb.in)			
Environmental data					
Ambient temperature range	operation	-35+70 °C	-40+70 °C		
	rated load	-35+60 °C	-40+60 °C	-40+55 °C	
	storage	-40+85 °C	-40+85 °C	1	
Damp heat (cyclic) (IEC/EN 60068-	2-30)	95 % RH, without condensation			
Vibration (sinusoidal) (IEC/EN 60068-2-6)		10-500 Hz, 2 G, along X, Y, Z each axis, 60 min. for each axis			
Shock (half-sine) (IEC/EN 60068-2-		15 G, 11 ms, 3 axes, 6 faces, 3 times for each face			
Isolation data					
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	3 kV AC			
<b>5</b> 1	input / PE				
		0.5 kV AC; 0.71 kV DC			
	signalling contact / PE				
Pollution degree	5 5 ,	2			
Overvoltage category	II				
Standards / Directives					
Standards		IEC/EN 62368-1			
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
	ow voltage SELV (IEC60950-1)				

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре	-	CP-E 24/5.0	CP-E 24/10.0	CP-E 24/20.0
Electromagnetic compatibility				
Interference immunity to		IEC/EN 61000-6-2		
electrostatic discharge	IEC/EN 61000-4-2	level 4 (air discharge 15	kV / contact dischar	ge 8 kV)
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)		
electrical fast transient/burst	IEC/EN 61000-4-4	level 4 (4 kV / 5 kHz)	level 4 (4 kV / 2.5 kH	Hz)
surge	IEC/EN 61000-4-5	L-L level 3 (2 kV) / L-PE	level 4 (4 kV)	
conducted disturbances, induced by radio- frequency fields	IEC/EN 61000-4-6	level 3 (10 V)		
power frequency magnetic fields	IEC/EN 61000-4-8	level 4 (30 A/m)		
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	dip: >95 % 10 ms / >30 interruptions: >95 % 50		
Interference emission		IEC/EN 61000-6-3		
high-frequency radiated		class B		
high-frequency conducted		class B		
limits for harmonic current emissions	IEC/EN 61000-3-2	class D		

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 48/0.62	CP-E 48/1.25	CP-E 48/5.0	CP-E 48/10.0
Input circuit		L, N			
Rated input voltage U <sub>in</sub>		100-240 V AC		115 / 230 V AC auto select	115-230 V AC
Input voltage range		85-264 V AC / 90-375 V DC		90-132 V AC, 180-264 V AC / 210-375 V DC	90-264 V AC, 120-375 V DC
Frequency range AC		47-63 Hz			
Typical input current	at 115 V AC	560 mA	1060 mA	4.0 A	4.9 A
	at 230 V AC	330 mA	590 mA	1.55 A	2.5 A
Typical power consumption		35.7 W	69.0 W	267 W	528 W
Inrush current	at 115 V AC	20 A	30 A	30 A (max. 5 ms)	25 A (max. 5 ms)
	at 230 V AC	40 A	60 A	60 A (max. 5 ms)	50 A (max. 5 ms)
Discharge current	input / output	0.25 mA			
	input / PE				1
Power failure buffering time		min. 20 ms		min. 25 ms	min. 25 ms
	at 230 V AC	min. 30 ms			
Internal input fuse		2 A slow-acting 250 V AC	1/	6.3 A slow-acting / 250 V AC	10 A slow-acting / 250 V AC
Power factor correction (PFC)		no		yes, passive, 0.7	yes, active 115 V AC: 0.99 230 V AC: 0.97
Indication of operational states				·	
Output voltage	green LED	оитрит ок: Г	l: output volta	age OK	
	red LED	-	-	OUTPUT LOW: I	l:
Output circuit		L+, L+, L-, L-			
Rated output voltage		48 V DC			
Tolerance of the output voltage		0+1 %			
Adjustment range of the output voltage		48-55 V DC 47-56 V DC			
Rated output power		30 W	60 W	240 W	480 W
Rated output current I <sub>r</sub>	$T_a \le 60  ^{\circ}C$	0.625 A	1.25 A	5 A	-
	$T_a \le 55 ^{\circ}C$	-	-	-	10 A
Derating of the output current	$60  ^{\circ}\text{C} < T_{a} \leq 70  ^{\circ}\text{C}$	2.5 %/°C			-
	$55 ^{\circ}\text{C} < \text{T}_{a} \leq 70 ^{\circ}\text{C}$	-	-	-	2.5 %/°C
Signalling output for output voltage OK	DC OK	-	-	-	-
Maximum deviation with	load change statical	±0.5 % ±1 % (single mode) ±5 % (parallel mode)			
_	change of output voltage within the input voltage range	±0.5 %		±0.5 %	
Recovery time T <sub>R</sub>		< 2 ms			
Starting time after applying the supply vo	ltage at I,	max. 1 s			
	with 3500 $\mu F$	max. 2 s	-	-	-
	with 7000 μF	-	max. 1.5 s	max. 1.5 s	
Rise time		max. 150 ms			1
	·	max. 500 ms	-	-	-
	with 7000 μF		max. 500 ms	max. 500 ms	
Fall time		max. 150 ms		1	
Residual ripple and switching peaks BW = 20 MHz				100 mV	
Parallel connection		yes, to enable redundancy		configurable, to increase power, up to 3 devices, min. 0.1 I, - max. 0.9 I,	
Series connection		yes, to increase voltage yes, to increase voltage, max. 2 devices		tage,	
				maxi z acrices	


Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-E 48/0.62	CP-E 48/1.25	CP-E 48/5.0	CP-E 48/10.0	
Output circuit - No-load, overload and s	hort-circuit behavior					
Characteristic curve of output		U/I characterist	ic curve			
Short-circuit protection		continuous shor	t-circuit proof			
Short-circuit behavior		continuation with output power limiting				
Overload protection		output power limiting				
No-load protection		continuous no-load stability				
Starting of capacitive loads		3500 μF	7000 μF	unlimited	7000 μF	
General data						
Power loss		typ. 4.9 W	typ. 7.8 W	typ. 32 W	typ. 60 W	
Efficiency		typ. 86 %	typ. 89 %	typ. 90 %		
Duty cycle		100 %				
Dimensions		see "Dimension	al drawings"			
Material of housing		plastic		metal		
Mounting		DIN rail (IEC/EN	60715), snap-on m	ounting without an	y tool	
Mounting position		horizontal				
Minimum distance to other units	horizontal / vertical	25 mm / 25 mm	(0.98 in / 0.98 in)			
Degree of protection	housing / terminals	IP/20 / IP20				
Protection class		I				
Electrical connection - input circuit / ou	tput circuit					
Connecting capacity	fine-strand with	0.2-2.5 mm <sup>2</sup> (24-14 AWG)		0.2-4 mm² (24-11 AWG)		
	wire end ferrule					
	fine-strand without			0.2-6 mm² (24-10	AWG)	
	wire end ferrule					
	rigid					
Stripping length		6 mm (0.24 in)		8 mm (0.31 in)		
Tightening torque	input / output	0.6 Nm (5 lb.in)	1	1.0 Nm (9 lb.in) /	0.62 Nm (5.5 lb.in)	
Environmental data			,			
Ambient temperature range	operation	-40+70 °C				
	rated load	-40+60 °C			-40+55 °C	
	storage	-40+85 °C				
Damp heat (cyclic) (IEC/EN 60068-2-30)		95 % RH, without condensation				
Vibration (sinusoidal) (IEC/EN 60068-2-6	5)	10-500 Hz, 2 G, along X, Y, Z each axis, 60 min. for each axis				
Shock (half-sine) (IEC/EN 60068-2-27)		15 G, 11 ms, 3 axes, 6 faces, 3 times for each face				
Isolation data		T .				
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit					
-	input / PE					
	output / PE 0.5 kV AC; 0.7					
Pollution degree		2				
Overvoltage category		II				
Standards / Directives		1				
Standards		IEC/EN 62368-1				
Low Voltage Directive		2014/35/EU				
EMC Directive		2014/30/EU				
RoHS Directive		2011/65/EU				
Protective low voltage		SELV (IEC60950	-1)			

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated


Туре		CP-E 48/0.62	CP-E 48/1.25	CP-E 48/5.0	CP-E 48/10.0
Electromagnetic compatibility					
Interference immunity to		IEC/EN 61000-6	-2		
electrostatic discharge	IEC/EN 61000-4-2	level 4 (air disch	arge 15 kV / contac	t discharge 8 kV)	
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)			
electrical fast transient/burst	IEC/EN 61000-4-4	level 4 (4 kV / 5 k	(Hz)	level 4 (4 kV / 2.5	5 kHz)
surge	IEC/EN 61000-4-5	L-L level 3 (2 kV)	/ L-PE level 4 (4 kV	)	
conducted disturbances, induced by radio- frequency fields	IEC/EN 61000-4-6	level 3 (10 V/m)			
power frequency magnetic fields	IEC/EN 61000-4-8	level 4 (30 A/m)			
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	dip: >95 % 10 ms	s / >30 % 500 ms, ir	nterruptions: >95 %	5000 ms
Interference emission		IEC/EN 61000-6	-3		
high-frequency radiated		class B			
high-frequency conducted		class B			
limits for harmonic current emissions	IEC/EN 61000-3-2	class A		class D	

## Technical diagrams




## Technical diagrams


### Temperature behavior




CP-E 12/10.0, CP-E 24/5.0



CP-E 24/20.0, CP-E 48/10.0




CP-E 5/3.0, CP-E 24/0.75



CP-E 12/2.5, CP-E 24/1.25, CP-E 48/0.62, CP-E 24/2.5, CP-E 48/1.25, CP-E 24/10.0, CP-E 48/5.0


## Technical diagrams


### Wiring instructions



### **Dimensional drawings**

Dimensions in mm and inches







# **CP-T range**Table of contents

296	benefits and advantages
300	Operating controls
301	Applications
302	Ordering details
303	Technical data
307	Technical diagrams

# Benefits and advantages



ABB's CP-T range of three-phase power supply units perfectly complements our existing power supply offering in terms of design and functionality, giving you more advanced options for your three-phase applications.



Affordable range

Products with exactly the functions you require. Designed for best price-performance ratio.



The product can be used in any installation in the world. Giving you the confidence of world-wide sourcing – no matter where you build, install or operate your equipment.



Speed up your projects

Data available for common planning software: Less engineering time required

## Benefits and advantages



### Characteristics

- Rated output voltages 24 V, 48 V DC
- Output voltage adjustable via front-facing rotary potentiometer "OUTPUT Adjust"
- Rated output currents 5 A, 10 A, 20 A, 40 A
- Rated output powers 120 W, 240 W, 480 W, 960 W
- · Three-phase operation (see derating note)
- Two-phase operation (25 % derating possible, see derating note)
- Supply range 3 x 400–500 V AC (3 x 340-575 V AC, 480-820 V DC)
- Typical efficiency of 93 %
- · Low power dissipation and low heating
- Free convection cooling (no forced cooling with ventilators)
- Ambient temperature range during operation -40...+70 °C 1)
- · Open-circuit, overload and short-circuit stable
- · Integrated input fuse
- Redundancy unit CP-C.1-A-RU (-C) offering true redundancy, available as accessory
- · LEDs for status indication
- Signalling contact "13-14" (solid-state) for output voltage OK on 24 V devices
- · Various approvals and marks



### Main benefits

### Signalling output

Some devices of the CP-T series offer a solid-state output for function monitoring and remote diagnostics.

### Wide input range

Optimized for worldwide applications: The CP-T power supplies can be used in 340 - 575 V AC or 480 - 820 V DC supply systems.

### Adjustable output voltage

The CP-T range features a continuously adjustable output voltage. Thus, they can be optimally adapted to the applications, e.g. compensating the voltage drop caused by a long line length.











<sup>1) 480</sup> W variants: -30...+70°C

# Operating controls





## Ordering details



CP-T 24/5.0



CP-T 24/10.0, CP-T 48/5.0



CP-T 24/20.0, CP-T 48/10.0

### Description

In terms of design and functionality, the CP-T range perfectly supplements the existing products and extends the range appropriately. The devices can be supplied with a three-phase voltage as well as with two-phase mains. Here, ABB offers power supply units with 24 V DC and 48 V DC outputs with 5 A, 10 A, 20 A and 40 A and efficiency of up to 93 %.

As in the case of all products, they are designed for an ambient temperature of up to 70  $^{\circ}$ C. All products can be supplied within an AC supply voltage range between 340 to 575 V AC and a DC supply voltage range between 480 to 820 V DC.

### Ordering details

Input voltage range	Rated output voltage / current	Туре	Order code	Weight (1 pc.) kg (lb)
340-575 V AC / 480-820 V DC	24 V DC / 5 A	CP-T 24/5.0	1SVR427054R0000	0.80 (1.77)
340-575 V AC / 480-820 V DC	24 V DC / 10 A	CP-T 24/10.0	1SVR427055R0000	1.05 (2.31)
340-575 V AC / 480-820 V DC	24 V DC / 20 A	CP-T 24/20.0	1SVR427056R0000	1.75 (3.86)
340-575 V AC / 480-820 V DC	24 V DC / 40 A	CP-T 24/40.0	1SVR427057R0000	3.20 (7.05)
340-575 V AC / 480-820 V DC	48 V DC / 5 A	CP-T 48/5.0	1SVR427054R2000	1.05 (2.31)
340-575 V AC / 480-820 V DC	48 V DC / 10 A	CP-T 48/10.0	1SVR427055R2000	1.75 (3.86)
340-575 V AC / 480-820 V DC	48 V DC / 20 A	CP-T 48/20.0	1SVR427056R2000	3.40 (7.50)

Data at  $T_a = 25$  °C,  $U_{in} = 3 \times 400 \text{ V}$  AC and rated values, unless otherwise indicated

Туре		CP-T 24/5.0	CP-T 24/10.0	CP-T 24/20.0	CP-T 24/40.0
Input circuit		L1, L2, L3			I.
Rated input voltage U <sub>in</sub>		3 x 400-500 V AC			
Input voltage range		340-575 V AC			
put rontage range		480-820 V DC			
Frequency range AC		47-63 Hz			
Typical input current		0.36 A	0.65 A	1.1 A	1.72 A
Typical power consumption		135 W	270 W	538 W	1058 W
Inrush current	typ	10 A	20 A	330 11	30 A
Power failure buffering time	сур.	min. 20 ms	LUA		min. 15 ms
Internal input fuse	ner nhase	2 A / 600 V AC		T 3.15 A / 500 V AC	
Recommended backup fuse	per pridate	-	circuit breaker ABB		1377 300 776
Power factor correction (PFC)		yes, passive	circuit breaker Abb	Type 3203	
Discharge current	towards PE	< 3.5 mA			
Discharge current	input / output				
Indication of operational states	πρατ / σατρατ	10.25 IIIA			
Output voltage	OUTPUT OK: green LED	output voltage O	•	voltage > 75 % of th	e
	OUTPUT LOW: red LED			tput voltage < 70 % o	of the
	331.31.23	rated output volt		epat voltage 10 70	
Output circuit		L+, L+, L-, L-			
Rated output voltage		24 V DC			
Tolerance of the output voltage		0+1 %			
Adjustment range of the output voltage	je	22.5-28.5 V DC			
Rated output power		120 W	240 W	480 W	960 W
Rated output current I,	T <sub>a</sub> ≤ 60 °C	5 A	10 A	20 A	40 A
Derating of the output current	60 °C < T₂ ≤ 70 °C	2.5 %/°C		<u>'</u>	3.5 %/°C
Signalling contact	13-14	solid-state (max. 60 V DC, 0.3 A)			
for output voltage OK	Threshold	17.6-19.4 V			
	Insulation voltage	500 V DC			
Mininum fuse rating to achieve short-o	<del>_</del>	≥ 60 V DC, ≤ 0.3 A fast-acting			
Maximum deviation with	load change statical	±1 % (single mode)			
	_	- ±5 % (parallel mode)			
	change of output voltage within the input voltage range	± 0.5 %			
Recovery time T	at nominal load	< 2 ms			
Starting time after applying	at I	max. 1 s			
the supply voltage	with 3500 μF				
Rise time	at nominal load	max. 150 ms			
		max. 500 ms			
Fall time		max. 150 ms			
Residual ripple and switching peaks	BW = 20 MHz	100 mV			80 mV
Parallel connection		not supported	configurable, to i to 2 devices, min.	ncrease power, up . 0.1 I <sub>r</sub> - max 0.9 I <sub>r</sub>	to increase power, up to 2 devices, min. 0.1 I, - max. 0.9 I, use active current balancing
Series connection		not supported	yes, to increase v	oltage, max. 2 devic	es
Resistance to reverse feed		approx. 35 V			
Output circuit - No-load, overload and	d short-circuit behavior				
Characteristic curve of output		combined U/I cha and hiccup mode	aracteristic curve	U/I- or hiccup- mode adjustable	hiccup / fold back behavior
Short-circuit protection		continuous short	-circuit proof	'	
Short-circuit behavior		current limiting			
Overload protection		hiccup mode			
No-load protection		continuous no-load stability			
Overtemperature protection			covery after tempe	erature went down	
Starting of capacitive loads		3500 μF	7000 μF	7000 μF	7000 μF
		P**	P**	Fee	F**

Data at  $T_a = 25$  °C,  $U_{in} = 3 \times 400 \text{ V}$  AC and rated values, unless otherwise indicated

Туре		CP-T 24/5.0	CP-T 24/10.0	CP-T 24/20.0	CP-T 24/40.0
General data			*	*	^
Efficiency		typ. 89 %	typ. 90 %		typ. 92 %
Duty cycle		100 %			131
Dimensions		see "Dimensiona	l drawings"		
Material of housing		metal	. a. a		
Mounting		1	50715) snan-on m	ounting without ar	ny tool
Mounting position		horizontal	50113), Shap Girin	ounting without a	19 1001
	rizontal / vertical		(0.98 in / 0.98 in)		
	using / terminals	,	0.50 1117 0.50 1117		
Protection class	using / terminals	1			
Electrical connection - input circuit / output circuit / si	ignalling circuit				
		0.2-4 mm² (24-11	AWG)		
	without wire end ferrule		-		
	rigid	0.2-6 mm² (24-10	AWG)		
Stripping length	<u> </u>	8 mm (0.31 in)	·		
Tightening torque	input / output	1 Nm (9 lb.in) / 0.	6 Nm (5.5 lb.in)		1 Nm (9 lb.in) /
					1.8 Nm (15.6 lb.i
Environmental data					· · · · · · · · · · · · · · · · · · ·
Ambient temperature range	operation	-40+70 °C		-30+70 °C	-40+70 °C
<u> </u>	rated load	-40+60 °C		-30+60 °C	-40+60 °C
	storage	-40+85 °C			
Altitude during operation IEG	C/EN 60068-2-13				
Damp heat (cyclic) (IEC/EN 60068-2-30)	95 % without condensation				
Vibration (sinusoidal) (IEC/EN 60068-2-6)		10-500 Hz, 2G, each along X, Y, Z axes 60 min / cycle			
Shock (half-sine) (IEC/EN 60068-2-27)			es, 6 faces, 3 times		
Isolation data	1	, ,			
Rated insulation voltage U <sub>i</sub> input circui	t / output circuit	3 kV AC			'
	input / PE				
	output / PE	0.5 kV AC; 0.71 kV	/ DC		
signa	lling output / PE				
Pollution degree		2			
Standards / Directives	,			,	'
Standards		IEC/EN 62368-1		'	'
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
Protective low voltage		SELV (IEC60950-1)			
Electromagnetic compatibility			<del>.</del>		
Interference immunity to		IEC/EN 61000-6-	2		,
-	EC/EN 61000-4-2	,	rge 15 kV / contac	t discharge 8 kV)	
radiated, radio-frequency, electromagnetic field	EC/EN 61000-4-3	level 3 (10 V/m)			
electrical fast transient/burst IE	EC/EN 61000-4-4	4 level 4 (4 kV / 5 kHz) level 4 (4 kV / 5 kHz)			
surge	EC/EN 61000-4-5	L-L level 3 (2 kV)	/ L-PE level 4 (4 kV	)	
	EC/EN 61000-4-6				
power frequency magnetic fields	EC/EN 61000-4-8	level 4 (30 A/m)			
	C/EN 61000-4-11				% 250 ms
Interference emission		IEC/EN 61000-6-	3		
high-frequency radiated		class B			
high-frequency conducted		class B			
		class A			


Data at  $T_a = 25$  °C,  $U_{in} = 3 \times 400 \text{ V}$  AC and rated values, unless otherwise indicated

			T		
Туре		CP-T 48/5.0	CP-T 48/10.0	CP-T 48/20.0	
Input circuit		L1, L2, L3			
Rated input voltage U <sub>in</sub>		3 x 400-500 V AC			
Input voltage range		340-575 V AC			
		480-820 V DC			
Frequency range AC		47-63 Hz		1.=0.	
Typical input current		0.65 A	1.1 A	1.72 A	
Typical power consumption		264 W	535 W	1050 W	
Inrush current	typ.	20 A		30 A	
Power failure buffering time		min. 20 ms	T 2 4 5 A 4 5 2 2 4 4 5	min. 15 ms	
Internal input fuse	per phase	2 A / 600 V AC	T 3.15 A / 500 V AC	T 5 A / 500 V AC	
Power factor correction (PFC)		yes, passive			
Discharge current	towards PE				
	input / output	< 0.25 mA			
Indication of operational states Output voltage	OUTPUT OK: green LED	output voltage OK wh	nen the output voltage > 7	75 % of the	
	OUTPUT LOW: red LED	output voltage too lo rated output voltage	w when the output voltag	ge < 70 % of the	
Output circuit		L+, L+, L-, L-			
Rated output voltage		48 V DC			
Tolerance of the output voltage		0+1 %			
Adjustment range of the output voltage		47-56 V DC			
Rated output power		240 W	480 W	960 W	
Rated output current I <sub>r</sub>	$T_a \le 60 ^{\circ}C$	5 A	10 A	20 A	
Derating of the output current	$60 ^{\circ}\text{C} < \text{T}_{a} \le 70 ^{\circ}\text{C}$	2.5 %/°C		3.5 %/°C	
Maximum deviation with	load change statical	±1 % (single mode)			
		± 5 % (parallel mode)			
	change of output voltage within the input voltage range	±0.5 %			
Recovery time T <sub>A</sub>	at rated load	< 2 ms			
Starting time after applying the supply	voltage at I <sub>r</sub>	max. 1 s			
	with 7000 μF	max. 1.5 s			
Rise time	at rated load	max. 150 ms			
	with 7000 μF	max. 500 ms			
Fall time		max. 150 ms			
Residual ripple and switching peaks	BW = 20 MHz	100 mV		80 mV	
Parallel connection		configurable, to incre power, up to 2 devices	ase s, min. 0.1 I <sub>,</sub> - max 0.9 I <sub>,</sub>	to increase power, up to 2 devices, min. 0.1 I - max. 0.9 I <sub>p</sub> , use active current balancing	
Series connection		yes, to increase voltage	ge, max. 2 devices		
Resistance to reverse feed		approx. 35 V	approx. 63 V	approx. 63 V	
Output circuit - No-load, overload and	short-circuit behavior				
Characteristic curve of output		combined U/I and hiccup mode	U/I or hiccup mode, configurable	hiccup mode / fold back behavior	
Short-circuit protection		continuous short-circ	uit proof	'	
Short-circuit behavior		current limiting			
Overload protection		hiccup mode			
No-load protection		continuous no-load s	tability		
Over temperature protection			<u> </u>	nt down	
		yes, automatic recovery after temperature went down 7000 µF			


Data at  $T_a$  = 25 °C,  $U_{in}$  = 3 x 400 V AC and rated values, unless otherwise indicated


Туре		CP-T 48/5.0	CP-T 48/10.0	CP-T 48/20.0
General data			·	·
Efficiency		typ. 91 %		typ. 93 %
Duty cycle		100%		
Dimensions		see "Dimensional drawings"		
Material of housing		Metal		
Mounting		DIN rail (IEC/EN 6	0715), snap-on mounting	without any tool
		horizontal		•
Minimum distance to other units	horizontal / vertical	25 mm / 25 mm (0	0.98 in / 0.98 in)	
Degree of protection	housing / terminals	IP20 / IP20	· · · · · · · · · · · · · · · · · · ·	
Protection class	5,	I		
Electrical connection - input circuit / outp	ut circuit	Į.		,
Connecting capacity	fine-strand with wire end ferrule	0.2-4 mm² (24-11	AWG)	0.2-4 mm² (24-11 AWG) / 0.5-10 mm (20-8 AWG)
fir	e-strand without wire end ferrule	0.2-6 mm² (24-10	AWG)	'
	rigid			
Stripping length		8 mm (0.31 in)		
Tightening torque	input / output	1 Nm (9 lb.in) / 0.6	5 Nm (5.5 lb.in)	1 Nm (9 lb.in) / 1.8 Nm (15.6 lb.in)
Environmental data				·
Ambient temperature range	operation	-40+70 °C	-30+70 °C	-40+70 °C
-	rated load	-40+60 °C	-30+60 °C	-40+60 °C
	storage	-40+85 °C	-40+85 °C	-40+85 °C
Altitude during operation IEC/EN 60068-2-13		max. 5000 m		
Damp heat (cyclic) (IEC/EN 60068-2-30)		95 % without condensation		
Vibration (sinusoidal) (IEC/EN 60068-2-6)		10-500 Hz, 2G, each along X, Y, Z axes 6 min / cycle		
Shock (half-sine) (IEC/EN 60068-2-27)		15G, 11 ms, 3 axes, 6 Faces, 3 times for each face		
Isolation data			<u>·</u>	
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	3 kV AC		
	input / PE	1.5 kV AC		
	output / PE	0.5 kV AC; 0.71 kV	DC	
Pollution degree		2		
Standards / Directives				
Standards		IEC/EN 62368-1		
Low Voltage Directive		2014/35/EU		
EMC Directive		2014/30/EU		
RoHS Directive		2011/65/EU		
Protective low voltage		SELV (IEC60950-1)		
Electromagnetic compatibility				
Interference immunity to		IEC/EN 61000-6-2	2	
electrostatic discharge	IEC/EN 61000-4-2	level 4 (air dischar	ge 15 kV / contact discha	arge 8 kV)
radiated, radio-frequency, electromagnetic	field IEC/EN 61000-4-3	level 3 (10 V/m)		
electrical fast transient/burst		level 4 (4 kV / 5 kHz)		
surge	IEC/EN 61000-4-5	L-L level 3 (2 kV) /	L-PE level 4 (4 kV)	
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6			
power frequency magnetic fields	IEC/EN 61000-4-8	level 4 (30 A/m)		
voltage dips, short interruptions and voltage IEC/EN 61000-4-11		dips: >95 % 0.5 ms / >30 % 0.5 ms interruptions: >95 % 250 ms		
Interference emission		IEC/EN 61000-6-3	3	
high-frequency radiated		class B		
high-frequency conducted		class B		
<u> </u>	IEC/EN 61000-3-2			


## Technical diagrams



### Temperature curves at rated load







### \_


## **CP-T range**


## Technical diagrams

### \_

### Dimensional drawings

Dimensions in **mm** and inches









# **CP-S.1 range**Table of contents

512	benefits and advantages		
314	Operating controls		
316	Characteristics		
318	Application example		
318	Softstarter and Safety*)		
319	Food & beverage*)		
320	Ordering details		
321	Technical data		
325	Technical diagrams		

## **CP-S.1** power supply range

## Benefits and advantages



CP-S.1 power supplies: high efficiency and reliability delivered in a compact footprint. Designed for a huge variety of applications, including machine building segments, this advanced range boosts an integrated 150 % power reserve for five seconds and operates at an efficiency of up to 94 %. With overheat protection, active power factor correction, a broad certified AC and DC input range and extensive worldwide approvals including marine, the all-new CP-S.1 power supplies are a preferred choice for multiple industrial applications.



### Outstanding power to space ratio

In comparison to other power supply ranges on the market, ABB's CP-S.1 range achieves space savings up to 50 %. Together with the high-efficiency and reduced power losses features, CP-S.1 is a space and cost saving solution for applications where size matters.



### System reliability

The power reserve functionality provides additional power of starting heavy loads. CP-S.1 offers 150 % of the nominal current for five seconds to start e.g. heavy loads reliably. Together with ABBs redundancy modules CP-C.1-A-RU as well as buffer modules CP-B range - buffering the load in case of power losses on grid side - increase the availability and finally the system reliability further. Coated PCBA completes CP-S.1 range offering for OEM machine builders.



### Global availability

CP-S.1 range can be used in multiple installations in the world. A certified wide AC and DC input voltage range as well as a variety of approvals incl. marine, giving you the confidence of world-wide sourcing – no matter where you build, install or operate your equipment.

## **CP-S.1** power supply range

## CO, reduction




CP-S.1 power supplies operate at an astonishing efficiency of up to 94%. By increasing the efficiency by just 2 %, 1,4 tons of  $CO_2$  can be saved over the lifetime of ten years of a 40 A power supply at nominal load. This corresponds to the  $CO_2$  emissions of 167.000 numbers of smartphone charges.



1400

kilograms of CO<sub>2</sub> reduction over the lifetime



>160,000

Smartphones charged



### Main benefits

### **Complete offering**

A complete 24 V DC offering from 3 A up to 40 A in metal enclosure suits perfectly to OEM machine building requirements.

### **Small footprint**

CP-S.1 power supplies can save the valuable installation space of the control cabinet due to compact design and high efficiency.

### Robust design

Coated PCBA and marine certification enable CP-S.1 power supplies being the perfect match for e.g. Wind, Solar, Marine applications.


### Redundancy units

True redundancy could be achieved by using the optional redundancy unit CP-C.1-A-RU.










# Operating controls





## Characteristics



### Characteristics

- Rated supply voltage range from 100-240 V AC / 100-250 V DC
- Rated output voltage 24 V DC
- Rated output current of 3.0 A, 5.0 A, 10.0 A, 20.0 A and 40.0 A
- High efficiency of up to 94 %
- Power reserve design of 150 % for 5 s
- Output voltage adjustable via front-face rotary potentiometer "OUTPUT Adjust", 24-28 V

- Low power dissipation and low heating
- Free convection cooling (no forced cooling)
- Coated PCBAs
- Open-circuit, overload and short-circuit protection
- · Integrated input fuse
- DC OK signaling output "13-14" (relay)
- CP-C.1-A-RU redundancy unit offers true redundancy, available as accessory
- Various approvals and






# Application example Softstarter and Safety\*)

A sawmill or lumber mill is a facility where logs are processed into lumber. Modern sawmills use a motorized saw to cut logs lengthwise to make long pieces, and crosswise to determine length according to standard or custom sizes (dimension lumber). The "portable" sawmill is of simple operation. The log lies flat on a steel bed, and the motorized saw cuts the log horizontally along the length of the bed by the operator manually pushing the saw. The simplest type of sawmill consists of a chainsaw and a custom-made jig ("Alaskan sawmill"), with similar horizontal operation. Energy management is a point of great interest.

### Application example: Softstarter and Safety (SIL3/PLe, motor power/starting: <15 kW)



#	Order code	Desription
1	1SFA619100R1012	Pushbutton CP1-10G-10
2	1SFA619100R1041	Pushbutton CP1-10R-01
3	1SFA619100R1015	Pushbutton CP1-10W-10
4	1SBV010510R1211	Limit switch 30 mm wide, 1 ISO M 16x1.5 cable entry on the bottom, plain plastic plunger actuator and 1 N.O. + 1 N.C. snap action (Zb type) contacts
5	1SBV010510R1211	Limit switch 30 mm wide, 1 ISO M 16x1.5 cable entry on the bottom, plain plastic plunger actuator and 1 N.O. + 1 N.C. snap action (Zb type) contacts
6	1SVR405600R1000	Pluggable interface relay CR-P024DC1 1c/o, A1-A2 = 24 V DC, 250 V/16 A with socket
7	1SVR405600R1000	Pluggable interface relay CR-P024DC1 1c/o, A1-A2 = 24 V DC, 250 V/16 A with socket
8	1SVR320661R1000	Power supply CP-S.1 24/10.0, In: 100-240 V AC, 100 - 250 V DC, Out: 24 V DC
9	1SVR427060R1000	Buffer module CP-B 24/10.0, 24 V DC / 10 A, energy storage 13.700 Ws
10	2TLA010050R0000	Sentry safety relay SSR10 24 V
11	2TLA030054R0100	Emergency stop INCA 1
12	2CCS861002R0064	High-performance miniature circuit breaker S801S-C6-R
13	1SFA898103R7000	Softstarter PSTX30-600-70
14	1SFA619403R5022	Pilot light CL2-502G 24 V AC/DC
15	1SFA619403R5021	Pilot light CL2-502R 24 V AC/DC
16	1SFA619403R5021	Pilot light CL2-502R 24 V AC/DC
17	2TLA030053R0000	Reset button Smile 11 RA
18	1SVR405600R1000	Pluggable interface relay CR-P024DC1 1 c/o, A1-A2 = 24 V DC, 250 V/16 A with socket
19	1SCA022399R6590	Safety switch OTP16KA3M
20	1SBL176082R3022	2x Contactor AFS16Z-30-22-30 24 V DC

<sup>\*)</sup> Disclaimer: This bill of material shows one possible combination of devices. It should not be used in real projects without taking technical and other guidelines into account. Please select the size of devices including power supplies according to the specific requirements of the application.


### ---

## **CP-S.1** power supplies

# Application example food & beverage\*)

The term mixer refers to containers which are filled with liquids and / or solids and then rotate to mix the contents. Mixers are used extensively not only in the food and beverage sector but also in many other applications like chemicals and road construction. In many mixers, heating and/or cooling may also be required. Subjected to application requirements, mixer control systems are working independently or connected to PLCs /DCS. Safety and F&B standards are very important for mixers.

### Application example: Mixers (motor power/starting: 3 kW / direct-online starter (DOL))



#	Order code	Desription			
1	1SFA619100R1012	Pushbutton CP1-10G-10			
2	1SFA619100R1041	Pushbutton CP1-10R-01			
3	1SFA611284R1001	Selector switch M3SSK2-101			
4	1SBV010310R1211	1SBV010310R1211 30 mm wide, 1 ISO M16 x 1.5 cable entry on the bottom, plain plastic plunger actuator and 1 N.O + 1 N.C snap action (Zb type) contacts			
5	1SVR405600R1000	Pluggable interface relay CR-P024DC1 1c/o, A1-A2=24 V DC, 250 V/16 A with socket			
6	1SVR320361R1000	Power supply CP-S.1 24/10.0 In: 100-240 V AC Out: 24 V DC/10.0 A			
7	1SAM350000R1010	Manual Motor Starter MS132-10			
8	1SBL237001R1100	01R1100 Contactor AF26-30-00-11, 24-60 V 50/60 Hz 20-60 V DC			
9	1SBN010110R1010 Auxiliary contact block CA4-10				
10	1SAP111100R0270	Scalable PLC AC500, CPU PM592-ETH with PROFINET IO CM579-PNIO			
11	1SAP504100R0001 CP604 Control Panel 4.3" TFT touch screen				
12	1SFA619403R5022	SFA619403R5022 Pilot light CL2-502G 24 V AC/DC			
13	1SFA619403R5021	Pilot light CL2-502R 24 V AC/DC			
14	1SCA022399R6590 Safety switch OTP16KA3M				

<sup>\*)</sup> Disclaimer: This bill of material shows one possible combination of devices. It should not be used in real projects without taking technical and other guidelines into account. Please select the size of devices including power supplies according to the specific requirements of the application.

### Ordering details



CP-S.124/3.0



CP-S.124/20.0



CP-C.1-A-RU

### Description

ABB's new generation of CP-S.1 power supplies for machine building applications deliver high efficiency, high reliability and a minimized footprint. This advanced range of power supplies has an integrated 150 % power reserve functionality for up to 5 s and operate at an efficiency of up to 94 %. They come equipped with overheat protection and active power factor correction\*, combined with a broad AC and DC input voltage range and extensive worldwide approvals. Make the all-new CP-S.1 power supplies your preferred choice for professional DC applications. UL listing as well as marine approvals complete the assortment offering.

CP-S.1 power supplies have a rated output voltage of 24 V DC that is adjustable via a front-face rotary potentiometer "OUTPUT Adjust". The power supplies are available with rated output currents of 3.0 A, 5.0 A, 10 A, 20 A and 40 A. The rated output power ranges from 72 - 960 W and the rated supply voltage range from 100-240 V AC / 100-250 V DC. The typical efficiency is up to 94 % with low power dissipation and low heating. CP-S.1 power supplies have free convection cooling (no forced cooling with ventilators) and operate at an ambient temperature range from -25...+60 °C without derating (+70 °C with derating). They feature an open-circuit and are overload and short-circuit stable as well as an integrated input fuse.

Additionally, true redundancy for critical applications can be achieved with the optional redundancy units CP-C.1-A-RU which is available as an accessory. One LED on the front of the power supplies indicates the status and a transistor DC OK - signalling output "13-14".

### Ordering details

Description	Rated input voltage	Rated output voltage	Rated output current	Output power	Order code
CP-S.1 24/3.0	100-240 V AC, 100-250 V DC	24 V DC	3.0 A	72 W	1SVR320361R1000
CP-S.1 24/5.0			5.0 A	120 W	1SVR320561R1000
CP-S.1 24/10.0			10.0 A	240 W	1SVR320661R1000
CP-S.1 24/20.0			20.0 A	480 W	1SVR320761R1000
CP-S.1 24/40.0	110-240 V AC, 110-250 V DC		40.0 A	960 W	1SVR320861R1000
CP-C.1-A-RU	10 - 56 V DC	12 - 48 V DC	2 x 20 A or 1 x 40 A	-	1SVR360060R1001

Data at  $T_a$  = 25 °C and rated values ( $U_{in}$  = 230 V AC), unless otherwise indicated

Туре			CP-S.1 24/3.0	CP-S.1 24/5.0	CP-S.1 24/10.0	CP-S.1 24/20.0	CP-S.1 24/40.0	
Input circuit - Supply circuit (L(+	), N(-))							
Rated input voltage U <sub>in</sub>	100 - 240 V AC, 100 - 250 V DC				110 - 240 V AC, 110 - 250 V DC			
Input voltage range			85 - 264 V AC /	90 - 277 V DC			99 - 264 V AC / 99 - 277 V DC	
Input current range at		100 - 240 V AC	0.95 - 1.46 A	0.67 - 1.45 A	1.25 - 2.8 A	2.55 - 5.8 A	5.0 - 11.5 A	
rated output power		100 - 250 V DC		0.58 - 1.63 A	1.12 - 3.15 A	2.28 - 6.4 A	4.48 - 13.5 A	
Typical input current		at 115 V AC	1.52 A	1.24 A	2.45 A	4.85 A	9.5 A	
		at 230 V AC	0.95 A	0.67 A	1.25 A	2.55 A	5.0 A	
Max. power consumption		at 230 V AC	82 W	132 W	258 W	517 W	1,022 W	
Rated frequency			DC, 50 / 60 Hz					
Frequency range		AC	45 - 65 Hz					
Inrush current limiting, cold state	!		≤ 11 A	≤ 11 A	≤ 11 A	≤ 12.8 A	≤ 19 A	
Let-through energy I <sup>2</sup> t, cold state		at 230 V AC	< 1.5 A <sup>2</sup> s	< 1.2 A <sup>2</sup> s	< 1.7 A <sup>2</sup> s	< 3 A <sup>2</sup> s	< 5 A <sup>2</sup> s	
Discharge current towards PE			< 3.5 mA					
Hold-up time		at 115 V AC	> 10 ms	> 20 ms	> 15 ms	> 15 ms	> 20 ms	
		at 230 V AC	> 20 ms	> 30 ms	> 20 ms	> 20 ms	> 20 ms	
Internal input fuse			Yes				'	
Recommended backup fuse for wire protection at 1.5 mm <sup>2</sup>			1 pole miniature circuit breaker ABB type S 200 (for USA/CAN: use appropriate branch circuit 20 A fuse acc. to regional and national regulation)					
		characteristic	BorC					
		max. rating	16 A					
Power Factor Correction (PFC)			no yes, active					
Transient over-voltage protection	1		yes, varistor					
User interface - Indication of ope	erational states	i		,	,			
Output voltage	LED ,OUTPUT	OK' Green	≥ 92 % of adjus	sted U <sub>out</sub>	,			
	LED ,OUTPUT	OK' Flash	***					
Output circuits - power output (	L+, <b>L-)</b>			out				
Rated output voltage		'	24 V DC	-	'	'		
Tolerance of the output voltage			± 1 %					
Adjustment range of the output v	oltage		2428 V DC					
Rated output power			72 W	120 W	240 W	480 W	960 W	
Rated output current I <sub>R</sub>		-25°C ≤ T <sub>a</sub> ≤ 60 °C	3 A	5 A	10 A	20 A	-	
		-25°C ≤ T <sub>a</sub> ≤ 55 °C	-	·	·		40 A	
Power reserve current		-25°C ≤ T <sub>a</sub> ≤ 60 °C	4.5 A (5 s)	7.5 A (5 s)	15 A (5 s)	30 A (5 s)	60 A (5 s) / -25°C≤ T <sub>a</sub> ≤ 55°0	
Short-circuit current limiting			< 5.2 A	< 8.62 A	< 17.25 A	< 34.5 A	< 70 A	
Derating of the output current		60 °C ≤ T <sub>a</sub> ≤ 70 °C	2.5 % / K				-	
		55 °C ≤ T <sub>a</sub> ≤ 70 °C	-				2%/K	
Deviation width of output voltage	Load effect/ load regulation	static load change: 25 - 100 %	< 1 %	< 1 %	< 1 %	< 1 %	< 1 %	
	Transient response of	dynamic load change:	0 % - 100 %: < 3 %	0 % - 100 %: < 3 %	10 % - 100 %: < 3 %	10 % - 100 %: < 5 %	10 % - 100 %: < 3 %	
	voltage to load current changes	recovery time T <sub>R</sub>	< 1 ms	< 1 ms	< 1 ms	< 1 ms	< 1 ms	
	Change of input voltage	within the rated input voltage	< 0.5%	< 0.5%	< 0.5%	< 0.5%	< 0.5%	
		input voitage				1.500	< 1 F00 ms	
Starting time after applying the supply voltage		input voitage	< 1,500 ms	< 1,500 ms	< 1,500 ms	< 1,500 ms	< 1,500 ms	
,	· ·	BW = 20 MHz	< 1,500 ms		< 1,500 ms	< 1,500 ms	< 1,500 ms	
supply voltage	· ·		·		< 1,500 ms	< 1,500 ms	< 1,500 ms	

### \_

## **CP-S.1** power supplies

Туре		CP-S.1 24/3.0	CP-S.1 24/5.0	CP-S.1 24/10.0	CP-S.1 24/20.0	CP-S.1 24/40.0		
No-load, overload and short-circ	cuit behavior							
Characteristic curve of output	U/I characteristic curve U/I characteristic bined with fol							
Short-circuit protection		continuous sho	rt-circuit stabilit	y	1			
Short-circuit behavior		current limiting		-				
Resistance to reverse feed		≤ 35 V DC						
Overvoltage protection		yes, < 35 V						
Overload protection		constant currer	nt limitation					
Overtemperature protection		protection by s	witch off in case	of overtemperat	ure (thermal)			
No-load protection		continuous no-	load stability					
Starting of capacitive loads		Yes						
Signaling outputs - OUTPUT OK	signaling output							
Type of output	13 - 14	relay, n/o conta	ct					
ON (contact closed)		≥ 92 % of adjus	ted U <sub>out</sub>					
OFF (contact open)		< 90 % of adjus	ted U <sub>out</sub>					
Contact ratings	max. switching voltage / current	30 V AC - 0.5 A /	24 V DC - 1 A (re	sistive load)				
	min. switching voltage / current	5 V DC / 1 mA						
General data								
Efficiency	at rated load	> 89 %	> 90 %	> 93 %	> 93 %	> 94 %		
Power losses	at rated load	< 10 W	< 12 W	< 18 W	< 37 W	< 62 W		
	at 50 % of rated load	< 6.5 W	< 9.5 W	< 14 W	< 24 W	< 45 W		
	at no load	< 2.8 W	< 3.5 W	< 5 W	< 6 W	< 6.5 W		
Duty time		100 %						
MTBF	acc. to MIL 217 HDBK GB 25	on request						
Dimensions (W x H x D)		see dimensiona	drawings					
Material of housing	cover	zinc-coated sheet-steel						
	housing shell	aluminium						
	front	plastic, PC GE8B35, V0						
Mounting		DIN rail (IEC/EN	l 60715), snap-oi	n mounting				
Mounting position		position 1 (standard orientation); other mounting positions possible with derating / deratings are available on demand						
Minimum distance to other units	horizontal	30 mm						
	vertical	50 mm						
Degree of protection (IEC/EN 60529)	housing / terminals	IP20 / IP20						
Protection class (IEC/EN 61140)								
Electrical connection		,						
Connecting capacity	rigid	0.5-2.5 mm <sup>2</sup> (20-14 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-10.0 mm <sup>2</sup> (20-8 AWG)		
	fine-strand with(out) wire end ferrule	0.5-2.5 mm <sup>2</sup> (26-14 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-4.0 mm <sup>2</sup> (20-12 AWG)	0.5-10.0 mm <sup>2</sup> (20-8 AWG)		
Stripping length	reffule	9 mm	9 mm	9 mm	9 mm	10 mm		
Tightening torque		0.5 Nm	0.5 Nm	0.5 Nm	0.5 Nm	1.47 Nm		
		4.43 lb.in	4.43 lb.in	4.43 lb.in	4.43 lb.in	13.0 lb.in		
Recommended screw driver		PH0 / Ø 3.5 x 0.6 mm	PH1 / Ø 4.0 x 0.8 mm	PH1 / Ø 4.0 x 0.8 mm	PH1 / Ø 4.0 x 0.8 mm	PH2 / Ø 5.5 x 1.0 mm		


Туре		CP-S.1 24/3.0	CP-S.1 24/5.0	CP-S.1 24/10.0	CP-S.1 24/20.0	CP-S.1 24/40.0	
Output circuits (L+, L+, L-, L-)		,	*	*	*		
Stripping length		9 mm	9 mm	9 mm	9 mm	10 mm	
5		0.5 Nm	1.13 Nm	1.13 Nm	1.13 Nm	1.47 Nm	
		4.43 lb.in	10 lb.in	10 lb.in	10 lb.in	13.0 lb.in	
Recommended screw driver		PHO/	PH1 /	PH1 /	PH1 /	PH2 /	
		Ø 3.5 x 0.6 mm	Ø 4.0 x 0.8 mm	Ø 4.0 x 0.8 mm	Ø 4.0 x 0.8 mm	Ø 5.5 x 1.0 mm	
Signalling output (13-14)							
Connecting capacity	rigid	0.15 - 0.8 mm² (	26 - 18 AWG)				
fine-st	trand with(out) wire end ferrule	0.15 - 0.8 mm² (	26 - 18 AWG)				
Stripping length		7 mm					
Connection terminals		push-in					
Environmental data							
Ambient temperature range	operation	-25+70 °C (-13	3 +158 °F)				
	rated output power	-25+60 °C (-13	3 +140 °F)			-25+55 °C (-13 +131 °F)	
	storage						
	transportation	-40+85 °C (-4					
Climatic class (IEC/EN 60721-3-1)	storage		,				
Climatic class (IEC/EN 60721-3-2)	transportation						
Climatic class (IEC/EN 60721-3-3)	operation	3K3					
Damp heat, cyclic (IEC/EN 60068-2	•	test Db: 55 °C, 2 cycles					
Vibration (IEC/EN 60068-2-6)	,	test Fc: 10-58 Hz, amplitude ±0.15 mm, 58-150 Hz, 2 g, 10 sweep cycles each axis					
Shock, half-sine (IEC/EN 60068-2-2	97)	test Ea: 30 g, 6 ms, 3 pulses each axis; bump 20 g, 11 ms, 100 pulses each axis					
Location classes (according DNV)	,	temperature: B / humidity: B / vibration: A / enclosure: A					
Coated PCBA		yes					
Isolation data		yes					
Rated impulse withstand voltage U <sub>imp</sub> (IEC/EN 62477-1)	input circuit / output circuit	4 kV (1.2/50 μs)					
imp v = 7	input circuit / PE	4 kV (1.2/50 μs)	)				
	input circuit / relay contact	4 kV (1.2/50 μs)					
	output circuit / relay contact	0.8 kV (1.2/50 µ	ıs)				
	relay contact / PE	0.8 kV (1.2/50 µ	ıs)				
	output circuit / PE	0.8 kV (1.2/50 µ	ıs)				
Rated insulation voltage U <sub>i</sub> (IEC/EN 62477-1)	input circuit / output circuit		<u> </u>				
	input circuit / PE	300 V					
	input circuit / relay contact	300 V					
	output circuit / relay contact						
	relay contact / PE	50 V					
	output circuit / PE	50 V					
Overvoltage category	< 2000 m	Ш					
(IEC/EN 62477-1)	20005000 m	11					
Overvoltage category	< 2000 m						
(IEC/EN 61010-1/IEC/ 20005000 m EN 61010-2-201)							
Pollution degree		2					
Protective separation	input circuit / output circuit	yes					
IEC/EN 61010-1, 61010-2-201	input circuit / relay output	yes					

Туре		CP-S.1 24/3.0 CP-S.1 24/5.0 CP-S.1 24/10.0 CP-S.1 24/20.0 CP-S.1 24/4				
Standards / Directives						
Low Voltage Directive		2014/35/EU, IEC/EN 61204				
EMC directive		2014/30/EU				
RoHS directive		2011/65/EU incl. 2015/863/EU				
WEEE directive		2012/19/EU				
Electrical safety		IEC/EN 61010-1. IEC/EN 61010-2-201				
Process control equipment		UL 61010-1, UL 61010-2-201/ CAN/CSA C22.2 No. 61010-1-12, CAN/CSA-IEC 61010-2-201:18				
Protective extra low voltage		PELV_IEC/EN 61010-2-201				
afety extra low voltage		SELV_IEC/EN 61010-2-201				
imitation of harmonic line currents		IEC/EN 61010-2-201				
lectromagnetic compatibility						
ow-voltage power supplies, d.c. output – Pa	art 3:	IEC/EN 61204-3				
lectromagnetic compatibility (EMC)						
nterference immunity to		IEC/EN 61000-6-2				
electrostatic discharge (ESD)	IEC/EN 61000-4-2	contact discharge air discharge, level 4, 8 kV / 15 kV (criterion A)				
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	80 to 1000 MHz, 10 V/m (criterion A), 1.4 to 6 GHz, 3 V/m (criterion A)				
electrical fast transient / burst	IEC/EN 61000-4-4	level 4, 4 kV / 2 kV (criterion A)				
surge	IEC/EN 61000-4-5	level 4, L/N 3 kV (criterion A); level 4, L, N / PE 4 kV (criterion A)				
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V (criterion A)				
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	class 3				
harmonics and interharmonics	IEC/EN 61000-4-13	class 3 (criterion A)				
conducted, common mode disturbances in the frequency range 0 Hz to 150 kHz	IEC/EN 61000-4-1	level 3, 10 V				
nterference emission		IEC/EN 61000-6-3; IEC/EN 61000-6-4				
limits for harmonic current emissions	IEC/EN 61000-3-2	class A				
limitation of voltage changes etc.	IEC/EN 61000-3-3	compliant				
Electromagnetic compatibility of multimedia equipment - Emission requirements	IEC/CISPR 32, EN 55032	class B				
industrial scientific and medical	EC/CISPR 11,	class B				
(ISM) radio-frequency equipment electromagnetic disturbance characteristics limits and methods of measurement	EN 55011 EN 50204					
/oltage sags	SEMI F47-0706	passed				
Federal Communications Commission	FCC15	compliant				
EMC according DNV	DNV-CG-0339	•				
Weight		550 g 690 g 830 g 1.355 g 2.490 g				

### **CP-S.1** power supplies


#### Technical diagrams

#### Wiring instructions




OUTPUT OK, relay output

Rated voltage limits of the signaling output relay: Acc. UL 61010-1: 30 V RMS, 42.4 V peak, 60 V DC




Parallel operation, increased power (n  $\leq$  3)




Parallel operation, redundancy (n  $\leq$  3)


#### U/I characteristic curves of output at $T_a = 25$ °C




CP-S.124/3.0




CP-S.124/5.0



CP-S.124/10.0



CP-S.1 24/20.0





CP-S.124/40.0

### **CP-S.1** power supplies

### Technical diagrams


#### Mounting and dismounting






Dismounting


#### Characteristic curves of temperature $U_{out}$ = 24 V DC




CP-S.1 24/3.0




CP-S.124/5.0



CP-S.124/10.0



CP-S.1 24/20.0




CP-S.124/40.0

### **CP-S.1** power supplies


#### Technical diagrams

#### **Dimensional drawings**

in mm and inches



CP-S.124/20.0



CP-S.124/40.0

CP-S.124/10.0



# **CP-C.1 range**Table of contents

330	Benefits and advantages
332	Operating controls
333	Applications
334	Ordering details
335	Technical data
347	Technical diagrams

### Benefits and advantages



The high-performance CP-C.1 power supplies are ABB's most advanced range. With excellent efficiency, high reliability and innovative functionality, it is ready to take on the most demanding of industrial applications These power supplies have a 150 % integrated power reserve, operate at an efficiency of up to 94 % and are equipped with overheat protection and active power factor correction. Combined with a broad AC and DC input range and extensive worldwide approvals, CP-C.1 power supplies are the preferred choice for professional DC applications. ATEX and IECEx approvals are available for the use in hazardous areas.



Continuous operation

- Power reserve design to allow performance with up to 150 % more current
- Redundancy setup of the application possible to allow parallel operation
- · Long lifetime
- High peak currents for switching on capacitive loads are supported



Project cost reduction

- Up to 94 % efficiency saves money for energy during operation
- · Less need for external cooling in the cabinet
- Small size to reduce space needed in panel



- Extended ambient temperature range during operation -40...+70 °C with coated PCBA version
- IECEx/ATEX approvals for hazardous locations available
- High MTBF values

### Benefits and advantages



#### Characteristics

- Rated output voltage 24 V DC
- Power reserve design delivers up to 150 % at T<sub>a</sub> ≤ 40 °C
- Output voltage adjustable via front-facing rotary potentiometer "OUTPUT Adjust", 22.5-28.5 V
- High efficiency of up to 94 %
- · Low power dissipation and low heating
- Free convection cooling (no forced cooling)
- Devices with coated PCBAs for harsh environments and with extended temperature range
- · Open-circuit, overload and short-circuit stable
- · Integrated input fuse
- OUTPUT OK signaling output "13-14" (relay), Power reserve signaling output "I > I, (transistor)
- Redundancy unit offers true redundancy, available as accessory
- · Various approvals and marks



#### Main benefits

The primary switch mode power supply CP-C.1 has a wide range of certified AC and DC input voltages. Furthermore, the CP-C.1 is equipped with capacitors that ensure a hold-up time of at least 50 ms. This enables worldwide usage and permits safe operation in fluctuating networks and battery-powered applications.


With their robust metallic housing and the reliable construction, CP-C.1 power supplies are suitable for applications in industrial environments. The CP-C.1-C units have coated PCBAs, which enables their use in harsh industrial environments. The power reserve of up to 150 % enables trouble-free starting of heavy loads eliminating the need for an oversized power supply.

#### Signaling output

To communicate the status of the power supply, the CP-C.1 is equipped with a relay output to signal OUTPUT OK as well as a transistor output  $I > I_R$  to indicate when the power reserve is active. These signals can be used for communication with a higher level control system, e.g. a PLC.

Depending on the logic of the higher level control system, an appropriate action is initiated by forwarding the signal. The receptor of this signal could be a contactor, a signal tower, or an interface relay.

## Operating controls



### **Applications**



#### **Application**

The primary switch mode power supply CP-C.1 has a wide range of AC and DC input voltages. Furthermore, the CP-C.1 is equipped with capacitors that ensure a hold-up time of at least 50 ms. This enables worldwide usage and permits safe operation in fluctuating networks and battery-powered applications. With their robust metallic housing and reliable construction, CP-C.1 power supplies are suitable for applications in industrial environments. The CP-C.1-C units have coated PCBAs, which enables their use in the harshest of industrial environments. usage in even harsh industrial environments. The power reserve of up to 150 % enables trouble-free starting of heavy loads eliminating the need for an oversized power supply.



#### Adjustable output voltage

The CP-C.1 range power supplies feature a continuously adjustable output voltage of 22.5 to 28.5 V DC. Thus, they can be optimally adapted to the applications, e.g. compensating the voltage drop caused by a long line length.



#### Signaling output


To communicate the status of the power supply, the CP-C.1 is equipped with a relay output to signal OUTPUT OK as well as a transistor output I >  $I_{\rm R}$  to indicate when the power reserve is active. These signals can be used for communication with a higher level control system, e.g. a PLC.



#### Power reserve

The primary switch mode power supply CP-C.1 is equipped with a power reserve functionality to handle the start-up of particularly heavy loads (e.g. of a capacitive load or a motor). To ensure that heavy loads are started up, the CP-C.1 delivers additionally up to 150 % of the rated output current to secure the operation of the application. This status is displayed by the yellow LED labelled POWER RESERVE I > I\_p.





#### Ordering details



CP-C.124/5.0 CP-C.124/5.0-C



CP-C.1 24/10.0 CP-C.1 24/10.0-C



CP-C.124/20.0 CP-C.124/20.0-C



CP-C.1 24/5.0-L



CP-C.1 24/10.0-L

#### Description

High-performance CP-C.1 power supplies are ABB's most advanced range. With excellent efficiency, high reliability, and innovative functionality, it is ready to take on the most demanding industrial applications. These power supplies have up to 50 % integrated power reserve and operate at an efficiency of up to 94 %. They are equipped with overheat protection and active power factor correction. Combined with a broad AC and DC input range and extensive worldwide approvals, the CP-C.1 power supplies are the preferred choice for professional DC applications.

#### Ordering details - CP-C.1

Input voltage range	Rated output voltage / current	PCBA	Color	Туре	Order code	Weight (1 pc.) kg (lb)
85-264 V AC, 90-300 V DC	24 V DC / 5 A	uncoated	dark grey	CP-C.1 24/5.0	1SVR360563R1001	0.87 (1.92)
	24 V DC / 10 A			CP-C.1 24/10.0	1SVR360663R1001	1.21 (2.67)
	24 V DC / 20 A			CP-C.1 24/20.0	1SVR360763R1001	1.70 (3.75)
	24 V DC / 5 A	coated		CP-C.1 24/5.0-C	1SVR360563R2001	0.87 (1.92)
	24 V DC / 10 A			CP-C.1 24/10.0-C	1SVR360663R2001	1.24 (2.73)
	24 V DC / 20 A			CP-C.1 24/20.0-C	1SVR360763R2001	1.72 (3.79)
	24 V DC / 5 A	uncoated	light grey	CP-C.1 24/5.0-L	1SVR361563R1001	0.87 (1.92)
	24 V DC / 10 A			CP-C.1 24/10.0-L	1SVR361663R1001	1.21 (2.67)
	24 V DC / 20 A			CP-C.1 24/20.0-L	1SVR361763R1001	1.70 (3.75)

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Type		CP-C.1 24/5.0, CP-C.1 24/5.0-L	CP-C.1 24/5.0-C
Input circuit - Supply circuit		, , ,	,
		L (+), N (-)	
Rated input voltage U <sub>in</sub>		100-240 V AC, 100-270 V DC	
Input voltage range		85-264 V AC, 90-300 V DC	
Input current range at rated output power	100-240 V AC	·	
	100-270 V DC	0.5-1.6 A	
Typical input current	at 115 V AC		
21	at 230 V AC		
Typical power consumption	at 230 V AC	132 W	
Rated frequency		DC, 50/60 Hz	
Frequency range	AC	45-65 Hz	
Inrush current, cold state		< 8 A	
Let-through energy I <sup>2</sup> t , cold state	at 230 V AC		
Discharge current towards PE	402507710	< 3.5 mA	
Hold-up time	at 115 V AC		
Tiold up time	at 230 V AC		
Internal input fuse	at 250 V No	T4.0 A, not exchangeable	
Recommended backup fuse for wire protection			
at 1.5 mm <sup>2</sup>		1 pole miniature circuit breaker For USA/CAN: Use appropriate be regional and national regulation	ranch circuit 20 A fuse acc.
	characteristic	BorC	
	max. rating	16 A	
Power factor correction (PFC)		yes, active	
Transient overvoltage protection		yes, varistor	
User interface			
Indication of operational states			
Output voltage LED 'OUTPUT O		≥ 92 % of adjusted U <sub>out</sub>	
	flashing	< 90 % of adjusted U <sub>out</sub>	
Power reserve LED 'I > I	<sub>R</sub> ' (yellow) OFF	I ≤ I <sub>R</sub>	
	ON	I > I <sub>R</sub>	
Output circuit - Power output			
		L+, L-	
Rated output voltage		24 V DC	
Tolerance of the output voltage		± 1 %	
Adjustment range of the output voltage		22.5-28.5 V DC	
Rated output power		120 W	
Rated output current I <sub>R</sub>	- 25 °C ≤ T <sub>a</sub> ≤ 60 °C	5.0 A	-
	- 40 °C ≤ T <sub>a</sub> ≤ 60 °C	-	5.0 A
Reserve output current	- 25 °C ≤ T <sub>a</sub> ≤ 40 °C	7.5 A continuously	-
	- 40 °C ≤ T ≤ 40 °C		7.5 A continuously
Short-circuit current limiting	a	7.6 A	-
Derating of the output current	60 °C < T <sub>a</sub> ≤ 70 °C	2.5 %/°C	
	ut voltage deviaton 25-100 %		
	dynamical 0-100 %		
ch	nange of input voltage within the rated input voltage		
Recovery time T <sub>A</sub>		< 1 ms	
Starting time after applying the supply voltage		< 500 ms	
Residual ripple and switching peaks	BW = 20 MHz	< 120 mV <sub>pp</sub> , class A	
Parallel connection		- FF	dundancy and to increase power,
Series connection		ves max 2 devices to increase v	oltage
Recovery time T <sub>A</sub> Starting time after applying the supply voltage Residual ripple and switching peaks	the rated input voltage	< 1 ms < 500 ms < 120 mV <sub>pp</sub> , class A yes, up to 5 devices, to enable re	

### CP-C.1 range

Туре		CP-C.1 24/5.0, CP-C.1 24/5.0-L
No-load, overload and short-circuit beh	navior	
Characteristic curve of output		U/I characteristic curve with power reserve
Short-circuit protection		continuous short-circuit stability
Short-circuit behavior		current limiting
Resistance to reverse feed		≤ 35 V DC
Overload protection		constant current limitation
Overtemperature protection		protection by switch off in case of overtemperature (thermal protection), automatic restart
No-load protection		continuous no-load stability
Starting of capacitive loads		yes
Signaling outputs		
OUTPUT OK signaling output		
Type of output	13-14	relay, n/o contact
ON (contact closed)		≥ 92 % of adjusted U <sub>out</sub>
OFF (contact open)		< 90 % of adjusted U <sub>out</sub>
Contact ratings	max. switching voltage / current	30 V AC - 0.5 A / 24 V DC - 1 A (resistive load)
	min. switching voltage / current	5 V DC / 1 mA
POWER RESERVE signaling output		
Type of output	I > I <sub>R</sub>	transistor, short-circuit proof
Active / ON (closed)		>   <sub>R</sub>
Inactive / OFF (open)		I ≤ I <sub>p</sub>
Ratings	voltage/current	24 V DC / ≤ 20 mA
General data		
Efficiency	at rated output power	up to 93 %
Power loss	at rated output power	•
	at 50% of rated output power	
	at no load	
Duty cycle		100 %
MTBF	acc. to MIL 217 HDBK	on request
Dimensions		see "Dimensional drawings"
Material of housing	cover	zinc-coated sheet-steel
	housing shell	aluminium
	front	plastic, PA6, V-2
Mounting		DIN rail (IEC/EN 60715), snap-on mounting
Mounting position		see "Mounting positions" in the data sheet
Minimum distance to other units	horizontal	25 mm (0.98 in)
	vertical	25 mm (0.98 in)
Degree of protection (IEC/EN 60529)	housing / terminals	IP20 / IP20
Protection class (IEC/EN 61140)		I
Electrical connection		
Input circuits (L(+), N(-), PE)		
Connecting capacity	rigid	0.5-4.0 mm <sup>2</sup> (20-10 AWG)
	fine-strand with(out) wire end ferrule	0.5-2.5 mm <sup>2</sup> (20-12 AWG)
Stripping length		8 mm (0.315 in)
Tightening torque		0.5 Nm (4.4 lb.in)
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm
Output circuits (L+, L+, L-, L-)		
Connecting capacity		0.5-4.0 mm² (20-10 AWG)
	fine-strand with(out) wire end ferrule	0.5-2.5 mm² (20-12 AWG)
Stripping length		8 mm (0.315 in)
Tightening torque		l = = · · · · · · · · · · · · ·
Recommended screw driver		0.5 Nm (4.4 lb.in)

Туре		CP-C.1 24/5.0, CP-C.1 24/5.0-L	CP-C.1 24/5.0-C
Signaling output (13-14, I > IR)			
Connecting capacity	rigid	0.5-4.0 mm² (20-10 AWG)	
fine-str	and with(out) wire end ferrule	0.5-2.5 mm² (20-12 AWG)	
Stripping length		8 mm (0.315 in)	
Tightening torque		0.5 Nm (4.4 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	
Maximum cable length (applicable for I>IR)		30 m	
Environmental data			
Ambient temperature range	operation	-25+70 °C (-13 +158 °F)	-40+70 °C (-40+158 °F)
	rated output power	-25+60 °C (-13 +140 °F)	-40+60 °C (-40+140 °F)
	storage	-40+85 °C (-40+185 °F)	
	transportation	-40+85 °C (-40+185 °F)	
Climatic class (IEC/EN 60721-3-1)	storage	1K2	
Climatic class (IEC/EN 60721-3-2)	transportation	2K2	
Climatic class (IEC/EN 60721-3-3)	operation	3K3	
Damp heat, cyclic (IEC/EN 60068-2-30)		test Db: 55 °C, 2 cycles	
Vibration (IEC/EN 60068-2-6)		test Fc: 10-58 Hz, amplitude ±0.1 10 sweep cycles each axis	5 mm, 58-150 Hz, 2 g,
Shock, half-sine (IEC/EN 60068-2-27)		test Ea: 30 g, 6 ms, 3 pulses each bump 20 g, 11 ms, 100 pulses each	
Coated PCBA		no	yes
Gaseous corrosive environment withstand test (IE-	C/EN 60068-2-60)		testing method: 4 testing period: 21 days ambient conditions: 25 °C, 75 % r.h. air/volume change rate per hour: 3-6 sample not energized during exposure gas concentrations acc. ISA-S71.04.2013 Harsh Group A, G3 IEC 60721-3.3 acc. $3C2/3C3$ - $H_2S \ge 100 \pm 10$ ppb - $SC_2 \ge 100 \pm 10$ ppb - $SC_2 \ge 100 \pm 10$ ppb - $SC_2 \ge 100 \pm 10$ ppb - $SC_2 \ge 100 \pm 10$ ppb - $SC_2 \ge 1250 \pm 20$ ppb
		111111111111111111111111111111111111111	
Rated impulse with stand voltage $U_{imp}$ (EN62477-1)	input circuit / output circuit		
	· · · · · · · · · · · · · · · · · · ·	4 kV (1.2/50 μs)	
	input circuit / relay contact output circuit / relay contact		
		0.5 kV (1.2/50 μs)	
Cycham yelta va (EN C2477 1)	· · · · · · · · · · · · · · · · · · ·	0.5 kV (1.2/50 μs)	
System voltage (EN 62477-1)	input circuit / output circuit		
	input circuit / PE		
	input circuit / relay contact		
	output circuit / relay contact		
	relay contact / PE		
Overvoltage category (IEC/EN 62477-1)	output circuit / PE < 2000 m		
Over vortage category (IEC/EN 02477-1)	20005000 m		
Overvoltage category (IEC/EN 61010-1)	20005000 m		
Pollution degree	\ 2000 m	2	
Protective separation	input circuit / output circuit		
(IEC/EN 61010-1, 61010-2-201 and IEC60950-1)		-	
	input circuit / relay contact	yes	

### CP-C.1 range

Туре		CP-C.1 24/5.0, CP-C.1 24/5.0-L	CP-C.1 24/5.0-C
Standards / Directives			
Standards		IEC/EN 61204	
Low Voltage Directive		2014/35/EU	
EMC Directive		2014/30/EU	
ATEX Directive		-	2014/34/EU
RoHS Directive		2011/65/EU	
Electrical safety		IEC/EN 61010-1, IEC/EN 61010-2	2-201 and IEC/EN 60950-1
Process control equipment		UL 61010-1, UL 61010-2-201 / CAN/CSA-IEC 61010-2-201:18	AN/CSA C22.2 No. 61010-1-12,
Protective extra low voltage		PELV (IEC/EN 61010-2-201)	
Safety extra low voltage		SELV (IEC/EN 61010-2-201, IEC6	0950-1)
Limitation of harmonic line currents		IEC/EN 61000-3-2	
Electromagnetic compatibility			
Low-voltage power supplies, d.c. output – Part 3: Electromagnetic compatibility (EMC)		IEC/EN 61204-3	
Interference immunity to		IEC/EN 61000-6-2	
electrostatic discharge (ESD)	IEC/EN 61000-4-2	level 4, 8 kV / 15 kV (criterion A)	
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3, 10 V/m (criterion A)	
electrical fast transient / burst	IEC/EN 61000-4-4	level 4, 4 kV / 2 kV (criterion A)	
surge	IEC/EN 61000-4-5	level 4, L/N 2 kV (criterion A) level 4, L,N/PE 4 kV ( criterion A)	
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V (criterion A)	
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	class 3	
harmonics and interharmonics	IEC/EN 61000-4-13	class 3 (criterion A)	
conducted, common mode disturbances in the frequency range 0 Hz to 150 kHz	IEC/EN 61000-4-16	level 3, 10 V	
Interference emission		IEC/EN 61000-6-3	
limits for harmonic current emissions	IEC/EN 61000-3-2	class A	
limitation of voltage changes etc.	IEC/EN 61000-3-3	compliant	
Electromagnetic compatibility of multimedia equipment - Emission requirements	IEC/CISPR 32, EN 55032	class B	
Industrial scientific and medical (ISM) radio-frequency equipment electromagnetic disturbance characteristics limits and methods of measurement	IEC/CISPR 11, EN 55011	class B	
Voltage sags	SEMI F47	passed	
Federal Communications Commission	FCC15	compliant	

Data at  $T_a = 25$  °C,  $U_{in} = 230$  V AC and rated values, unless otherwise indicated

CP-C.1 24/10.0, CP-C.1 24/10.0-L   CP-C.1 24/10.0-C	
· · · · · · · · · · · · · · · · · · ·	
L (+), N (-)	
100-240 V AC, 100 - 270 V DC	
85-264 V AC, 90-300 V DC	
C 1.2-2.7 A	
C 0.9-3.1 A	
C 2.3 A	
1.2 A	
256 W	
DC, 50/60 Hz	
C 45-65 Hz	
< 11 A	
C < 1,5 A <sup>2</sup> s	
< 3.5 mA	
C min. 40 ms	
C min. 40 ms	
T6.3 A, not exchangeable	
1 pole miniature circuit breaker ABB type S 200 For USA/CAN: Use appropriate branch circuit 20 A fuse acc. regional and national regulations.	
c B or C	
g 16 A	
yes, active	
yes, varistor	
N ≥ 92 % of adjusted U <sub>out</sub>	
g < 90 % of adjusted U <sub>out</sub>	
F I≤I <sub>p</sub>	
N   I > I <sub>p</sub>	
L+, L-	
24 V DC	
±1 %	
22.5-28.5 V DC	
240 W	
- 10.0 A	
10.0 A	
C 15.0 A continuously -	
2 - 15.0 A continuously	
15.5 A 15.5 A	
C 2.5 %/°C 2.5 %/°C	
i ·	
< 5 % < 0.1 %	
e	
< 1 ms	
< 1 ms < 500 ms	
< 1 ms	
1	

### CP-C.1 range

Type		CP-C.1 24/10.0, CP-C.1 24/10.0-L	CP-C.1 24/10.0-C
No-load, overload and short-circuit beha	avior		
Characteristic curve of output	20101	U/I characteristic curve with power	reserve
Short-circuit protection		continuous short-circuit stability	
Short-circuit behavior		current limiting	
Resistance to reverse feed		≤ 35 V DC	
Overload protection		constant current limitation	
Overtemperature protection		protection by switch off in case of	overtemperature
		(thermal protection), automatic res	•
No-load protection		continuous no-load stability	
Starting of capacitive loads		yes	
Signaling outputs			
OUTPUT OK signaling output			
Type of output	13-14	relay, n/o contact	
ON (contact closed)		≥ 92 % of adjusted U <sub>out</sub>	
OFF (contact open)		< 90 % of adjusted U <sub>out</sub>	
Contact ratings	max. switching voltage / current	30 V AC - 0.5 A / 24 V DC - 1 A (resist	tive load)
	min. switching voltage / current	5 V DC / 1 mA	
POWER RESERVE signaling output			
Type of output	>   <sub>R</sub>	transistor, short-circuit proof	
Active / ON (closed)	K	I > I <sub>R</sub>	
Inactive / OFF (open)		I≤I <sub>R</sub>	
Ratings	voltage/current	24 V DC / ≤ 20 mA	
General data			
Efficiency	at rated output power	up to 94 %	
Power loss	at rated output power	16 W	
	at 50% of rated output power	12 W	
	at no load	< 3.6 W	
Duty cycle		100 %	
MTBF	acc. to MIL 217 HDBK	on request	
Dimensions		see "Dimensional drawings"	
Material of housing	cover	zinc-coated sheet-steel	
	housing shell	aluminium	
	front	plastic, PA6, V-2	
Mounting		DIN rail (IEC/EN 60715), snap-on m	ounting
Mounting position		see "Mounting positions" in the dat	a sheet
Minimum distance to other units	horizontal	25 mm (0.98 in)	
	vertical	25 mm (0.98 in)	
Degree of protection (IEC/EN 60529)	housing / terminals	IP20 / IP20	
Protection class (IEC/EN 61140)		I	
Electrical connection			
Input circuits (L(+), N(-), PE)			
Connecting capacity	rigid	0.5-4.0 mm² (20-10 AWG)	
	fine-strand with(out) wire end ferrule	·	
Stripping length		8 mm (0.315 in)	
Tightening torque		0.5 Nm (4.4 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	
Output circuits (L+, L+, L-, L-)		,	
Connecting capacity	rigid	0.5-4.0 mm² (20-10 AWG)	
<u> </u>	fine-strand with(out) wire end ferrule		
Stripping length		8 mm (0.315 in)	
Tightening torque		0.5 Nm (4.4 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	

Туре		CP-C.1 24/10.0, CP-C.1 24/10.0	-L CP-C.1 24/10.0-C
Signaling output (13-14, I > IR)			
Connecting capacity	rigid	0.5-4.0 mm² (20-10 AWG)	
fine-s	trand with(out) wire end ferrule	0.5-2.5 mm² (20-12 AWG)	
Stripping length		8 mm (0.315 in)	
Tightening torque		0.5 Nm (4.4 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	
Maximum cable length (applicable for I>I <sub>R</sub> )		30 m	
Environmental data			
Ambient temperature range	operation	-25+70 °C (-13+158 °F)	-40+70 °C (-40+158 °F)
	rated output power	-25+60 °C (-13+140 °F)	-40+60 °C (-40+140 °F)
		-40+85 °C (-40+185 °F)	
	transportation	-40+85 °C (-40+185 °F)	
Climatic class (IEC/EN 60721-3-1)	storage	1K2	
Climatic class (IEC/EN 60721-3-2)	transportation	2K2	
Climatic class (IEC/EN 60721-3-3)	operation	3K3	
Damp heat, cyclic (IEC/EN 60068-2-30)		test Db: 55 °C, 2 cycles	
Vibration (IEC/EN 60068-2-6)		test Fc: 10-58 Hz, amplitude ±0. 10 sweep cycles each axis	15 mm, 58-150 Hz, 2 g,
Shock, half-sine (IEC/EN 60068-2-27)		test Ea: 30 g, 6 ms, 3 pulses each bump 20 g, 11 ms, 100 pulses ea	
Coated PCBA		no	yes
Gaseous corrosive environment withstand test (IEC	_/ EN 60008-2-60)		testing method: 4 testing period: 21 days ambient conditions: 25 °C, 75 % r.h. air/volume change rate per hour: 3-6 sample not energized during exposure gas concentrations acc. ISA-S71.04.2013 Harsh Group A, G3 IEC 60721-3.3 acc. 3C2/3C3 - H₂S ≥ 100 ± 10 ppb - SO₂/SO₃ ≥ 300 ± 20 ppb - Cl₂ ≥ 100 ± 10 ppb - NO₃ ≥ 1250 ± 20 ppb
Isolation data			
Rated impulse withstand voltage U <sub>imp</sub> (EN62477-1)	input circuit / output circuit	4 kV (1.2/50 µs)	
	input circuit / PE		
	input circuit / relay contact		
	output circuit / relay contact		
	· · · · · · · · · · · · · · · · · · ·	0.5 kV (1.2/50 μs)	
	output circuit / PE		
System voltage (EN62477-1)	input circuit / output circuit		
	input circuit / PE	300 V	
	input circuit / relay contact		
	output circuit / relay contact		
•	relay contact / PE		
	output circuit / PE		
Overvoltage category (IEC/EN62477-1)	< 2000 m		
	20005000 m		
Overvoltage category (IEC/EN61010-1)	< 2000 m		
Pollution degree	200111	2	
Protective separation	input circuit / output circuit		
(IEC/EN 61010-1, IEC/EN 61010-2-201 and IEC60950-1	input circuit / relay contact	-	

### CP-C.1 range

Туре		CP-C.1 24/10.0, CP-C.1 24/10.0-L	CP-C.1 24/10.0-C
Standards / Directives			`
Standards		IEC/EN 61204	
Low Voltage Directive		2014/35/EU	
EMC Directive		2014/30/EU	
ATEX Directive		-	2014/34/EU
RoHS Directive		2011/65/EU	
Electrical safety		IEC/EN 61010-1, IEC/EN 61010-2-20	01 and IEC60950-1
Process control equipment		UL 61010-1, UL 61010-2-201 / CAN/CAN/CSA-IEC 61010-2-201:18	CSA C22.2 No. 61010-1-12,
Protective extra low voltage		PELV (IEC/EN61010-2-201)	
Safety extra low voltage		SELV (IEC/EN 61010-2-201, IEC6095	50-1)
Limitation of harmonic line currents		IEC/EN 61000-3-2	
Electromagnetic compatibility			
Low-voltage power supplies, d.c. output – Part 3: Electromagnetic compatibility (EMC)		IEC/EN 61204-3	
Interference immunity to		IEC/EN 61000-6-2	
electrostatic discharge (ESD)	IEC/EN 61000-4-2	level 4, 8 kV / 15 kV (criterion A)	
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3, 10 V/m (criterion A)	
electrical fast transient / burst	IEC/EN 61000-4-4	level 4, 4 kV / 2 kV (criterion A)	
surge	IEC/EN 61000-4-5	level 4, L/N 2 kV (criterion A) level 4, L,N/PE 4 kV (criterion A)	
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V (criterion A)	
voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-11	class 3	
harmonics and interharmonics	IEC/EN 61000-4-13	class 3 (Criterion A)	
conducted, common mode disturbances in the frequency range 0 Hz to 150 kHz	IEC/EN 61000-4-16	level 3, 10 V	
Interference emission		IEC/EN 61000-6-3	
limits for harmonic current emissions	IEC/EN 61000-3-2	class A	
limitation of voltage changes etc.	IEC/EN 61000-3-3	compliant	
Electromagnetic compatibility of multimedia equipment - Emission requirements	IEC/CISPR 32, EN 55032	class B	
Industrial scientific and medical (ISM) radio-frequency equipment electromagnetic disturbance characteristics limits and methods of measurement	IEC/CISPR 11, EN 55011	class B	
Voltage sags	SEMI F47	passed	
Federal Communications Commission	FCC15	compliant	

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре			CP-C.1 24/20.0, CP-C.1 24/20.0-L	CP-C.1 24/20.0-C
Input circuit - Supply circuit				
			L (+), N (-)	
Rated input voltage U <sub>in</sub>			100-240 V AC, 100-270 V DC	
Input voltage range			85-264 V AC, 90-300 V DC	
Input current voltage and rated out	tput power	100-240 V AC		
,		100-270 V DC		
Typical input current		at 115 V AC	<u> </u>	
<b>7</b>		at 230 V AC		
Typical power consumption		at 230 V AC		
Rated frequency			DC, 50/60 Hz	
Frequency range		AC	45-65 Hz	
Inrush current, cold state			< 11 A	
Let-through energy I2t , cold state		at 230 V AC	< 3 A <sup>2</sup> s	
Discharge current towards PE			< 3.5 mA	
Hold-up time		at 115 V AC	min. 40 ms	
·		at 230 V AC	min. 40 ms	
Internal input fuse			T12 A, not exchangeable	
Recommended backup fuse for wire at 1.5 mm <sup>2</sup>	e protection		1 pole miniature circuit breaker ABI For USA/CAN: Use appropriate brai regional and national regulations.	51
		characteristic	B or C	
		max. rating	16 A	
Power factor correction (PFC)			yes, active	
Transient overvoltage protection			yes, varistor	
User interface				
Indication of operational states				
Output voltage L	LED 'OUTPUT OK ' (gre	een) ON	≥ 92 % of adjusted U <sub>out</sub>	
		flashing	< 90 % of adjusted U <sub>out</sub>	
Power reserve	LED 'I > I <sub>R</sub> ' (yell	ow) OFF	I ≤ I <sub>R</sub>	
		ON		
Output circuit - Power output				
			L+, L-	
Rated output voltage			24 V DC	
Tolerance of the output voltage			± 1 %	
Adjustment range of the output vol	ltage		22.5-28.5 V DC	
Rated output power			480 W	
Rated output current I <sub>R</sub>		- 25 °C $\leq$ T $_{a}$ $\leq$ 60 °C	20 A	-
		- 40 °C $\leq$ T $_{\rm a}$ $\leq$ 60 °C	-	20 A
Reserve output current		$-25  ^{\circ}\text{C} \le T_a \le 40  ^{\circ}\text{C}$	26.0 A continuously	-
		$-40  ^{\circ}\text{C} \le T_{a} \le 60  ^{\circ}\text{C}$	-	26.0 A continuously
Short-circuit current limiting			27.7 A	
Derating of the output current	static output vo	oltage deviaton 25-100 %	< 1 %	
	otatic output it			
Derating of the output current Deviation width of output voltage		dynamical 0-100 %		
	·	dynamical 0-100 % t voltage within the rated input voltage	< 0.1 %	
Deviation width of output voltage	·	t voltage within the rated		
Deviation width of output voltage  Recovery time T <sub>A</sub>	change of input	t voltage within the rated	< 0.1 %	
Derating of the output current Deviation width of output voltage  Recovery time T <sub>A</sub> Starting time after applying the sul Residual ripple and switching peak:	change of input	t voltage within the rated input voltage	< 0.1 %	
Deviation width of output voltage $\label{eq:Recovery} \textbf{Recovery time T}_{\underline{\textbf{A}}}$ $Starting time after applying the supplying the supply$	change of input	t voltage within the rated input voltage	< 0.1 % < 1 ms < 500 ms	ndancy and to increase power,

### CP-C.1 range


Туре		CP-C.1 24/20.0, CP-C.1 24/20.0-L
No-load, overload and short-circuit beh	navior	· · · · · · · · · · · · · · · · · · ·
Characteristic curve of output		U/I characteristic curve with power reserve
Short-circuit protection		continuous short-circuit stability
Short-circuit behavior		current limiting
Resistance to reverse feed		≤ 35 V DC
Overload protection		constant current limitation
Overtemperature protection		protection by switch off in case of overtemperature (thermal protection), automatic restart
No-load protection		continuous no-load stability
Starting of capacitive loads		yes
Signaling outputs		
OUTPUT OK signaling output		
Type of output	13-14	relay, n/o contact
ON (contact closed)		≥ 92 % of adjusted U <sub>out</sub>
OFF (contact open)		< 90 % of adjusted U <sub>out</sub>
Contact ratings	max. switching voltage / current	30 V AC - 0.5 A / 24 V DC - 1 A (resistive load)
	min. switching voltage / current	
POWER RESERVE signaling output		1
Type of output	>   <sub>n</sub>	transistor, short-circuit proof
Active / ON (closed)		
Inactive / OFF (open)		<sup>κ</sup>     ≤   <sub>p</sub>
	voltage/gurrent	· · ·
Ratings	voltage/current	24 V DC / ≤ 20 mA
General data		
Efficiency	at rated output power	-
Power loss	at rated output power	
	at 50 % of rated output power	< 3.6 W
Duty cycle	athoload	100 %
MTBF	acc. to MIL 217 HDBK	
Dimensions	200 10 1 11 2 2 2 1 1 2 2 1 1	see "Dimensional drawings"
Material of housing	cover	
-	housing shell	aluminium
	front	plastic, PA6, V-2
Mounting		DIN rail (IEC/EN 60715), snap-on mounting
Mounting position		see "Mounting positions" in the data sheet
Minimum distance to other units	horizontal	25 mm (0.98 in)
	vertical	25 mm (0.98 in)
Degree of protection (IEC/EN 60529)	housing / terminals	IP20 / IP20
Protection class (IEC/EN 61140)		[1
Electrical connection		
Input circuits (L(+), N(-), PE)		·
Connecting capacity	rigid	0.5-4.0 mm² (20-10 AWG)
	fine-strand with(out) wire end ferrule	0.5-2.5 mm <sup>2</sup> (20-12 AWG)
Stripping length		8 mm (0.315 in)
Tightening torque		0.5 Nm (4.4 lb.in)

Туре		CP-C.1 24/20.0, CP-C.1 24/20.0-L	CP-C.1 24/20.0-C
Output circuits (L+, L+, L-, L-)			
		2.5-16.0 mm² (12-6 AWG)	
		2.5-10 mm² (12-8 AWG)	
Stripping length		10 mm ( 0.394 in)	
Tightening torque		1.2 Nm (10.5 lb-in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	
Signaling output (13-14, I > IR)			
Connecting capacity	rigid	0.5-4.0 mm <sup>2</sup> (20-10 AWG)	
fine-str	and with(out) wire end ferrule	0.5-2.5 mm² (20-12 AWG)	
Stripping length		8 mm (0.315 in)	
Tightening torque		0.5 Nm (4.4 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm	
Maximum cable length (applicable for I>I <sub>R</sub> )		30 m	
Environmental data			
Ambient temperature range	operation	-25+70 °C (-13+158 °F)	-40+70 °C (-40+158 °F)
	rated output power	-25+60 °C (-13+140 °F)	40+60 °C (-40+140 °F)
	storage	-40+85 °C (-40+185 °F)	
	transportation	-40+85 °C (-40+185 °F)	
Climatic class (IEC/EN 60721-3-1)	storage	1K2	
Climatic class (IEC/EN 60721-3-2)	transportation	2K2	
Climatic class (IEC/EN 60721-3-3)	operation	3K3	
Damp heat, cyclic (IEC/EN 60068-2-30)		test Db: 55 °C, 2 cycles	
Vibration (IEC/EN 60068-2-6)		test Fc: 10-58 Hz, amplitude ±0.15 mm, 58-150 Hz, 2 g, 10 sweep cycles each axis	
Shock, half-sine (IEC/EN 60068-2-27)		test Ea: 30 g, 6 ms, 3 pulses each axis; bump 20 g, 11 ms, 100 pulses each axis	
Coated PCBA		no	/es
Gaseous corrosive environment withstand test (IEC/E	N 60068-2-60)		testing method: 4 testing period: 21 days ambient conditions: 25 °C, 75 % r.h. air/volume change rate per nour: 3-6 sample not energized during exposure gas concentrations acc. ISA-571.04.2013 Harsh Group A, G3 EC 60721-3.3 acc. 3C2/3C3 ·H <sub>2</sub> S ≥ 100 ± 10 ppb ·SO <sub>2</sub> /SO <sub>3</sub> ≥ 300 ± 20 ppb ·Cl <sub>2</sub> ≥ 100 ± 10 ppb ·NO <sub>x</sub> ≥ 1250 ± 20 ppb

Туре		CP-C.1 24/20.0, CP-C.1 24/20.0-L	
Isolation data			
Rated impulse withstand voltage U <sub>imp</sub> (EN62477-1)	input circuit / output circuit	4 kV (1.2/50 μs)	
	input circuit / PE	4 kV (1.2/50 μs)	
	input circuit / relay contact	4 kV (1.2/50 μs)	
	output circuit / relay contact	0.5 kV (1.2/50 µs)	
	· · · · · · · · · · · · · · · · · · ·	0.5 kV (1.2/50 μs)	
	-	0.5 kV (1.2/50 μs)	
System voltage (EN62477-1)	input circuit / output circuit		
5)5tc vo.tage (=.vov)	input circuit / PE		
	input circuit / relay contact		
	output circuit / relay contact		
	· · · · · · · · · · · · · · · · · · ·		
	relay contact / PE		
	output circuit / PE		
Overvoltage category (EN62477-1)	< 2000 m		
	20005000 m		
Overvoltage category (IEC/EN61010-1)	< 2000 m	II	
Pollution degree		2	
Protective separation	input circuit / output circuit	yes	
IEC/EN61010-1, IEC/EN61010-2-201 and IEC60950-1)	input circuit / relay contact	yes	
Standards / Directives			
Standards		IEC/EN 61204	
Low Voltage Directive		2014/35/EU	
EMC Directive		2014/30/EU	
ATEX Directive		- 2014/34/EU	
RoHS Directive		2011/65/EU	
Electrical safety		IEC / EN 61010-1, IEC / EN 61010-2-201 and IEC60950-1	
Process control equipment		UL 61010-1, UL 61010-2-201 / CAN/CSA C22.2 No. 61010-1-12	
Trocess control equipment		CAN/CSA-IEC 61010-2-201:18	
Protective extra low voltage		PELV (IEC/EN 61010-2-201)	
Safety extra low voltage		SELV (IEC/EN 61010-2-201 and IEC60950-1)	
Limitation of harmonic line currents		IEC/EN 61000-3-2	
Electromagnetic compatibility			
Low-voltage power supplies, d.c. output – Part 3: Electromagnetic compatibility (EMC)		IEC/EN 61204-3	
Interference immunity to		IEC/EN 61000-6-2	
electrostatic discharge (ESD)	IEC/EN 61000-4-2	level 4, 8 kV / 15 kV (criterion A)	
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3, 10 V/m (criterion A)	
electrical fast transient / burst	IEC/EN 61000-4-4	level 4, 4 kV / 2 kV (criterion A)	
surge		level 4, L/N 2 kV (criterion A)	
J	,	level 4, L,N/PE 4 kV (criterion A)	
conducted disturbances, induced by radio-freque	ncv fields IEC/EN 61000-4-6	level 3, 10 V (criterion A)	
voltage dips, short interruptions and voltage varia	-		
harmonics and interharmonics	·	class 3 (Criterion A)	
conducted, common mode disturbances in the fre			
range 0 Hz to 150 kHz	quency IEC/EN 01000-4-10	16VEI 3, 10 V	
Interference emission		IEC/EN 61000-6-3	
limits for harmonic current emissions	IEC/EN 61000-3-2	class A	
limitation of voltage changes etc.	IEC/EN 61000-3-3	compliant	
Electromagnetic compatibility of multimedia equi Emission requirements	pment - IEC/CISPR 32, EN 55032		
Industrial scientific and medical (ISM) radio-frequ	=		
equipment electromagnetic disturbance characte limits and methods of measurement	ristics EN 55011		
	SEMI F47	passed	

#### Technical diagrams

#### CP-C.1 24/5.0, CP-C.1 24/5.0-L and CP-C.1 24/5.0-C




Typical power loss over AC input voltage

Typical power loss over output current


#### CP-C.1 24/10.0, CP-C.1 24/10.0 -L and CP-C.1 24/10.0-C


110 130 150 170 190 210 230 250




#### Technical diagrams


#### CP-C.1 24/20.0, CP-C.1 24/20.0-L and CP-C.1 24/20.0-C









Typical efficiency over AC input voltage



Typical efficiency over ambient temperature




Typical power loss over AC input voltage




Typical power loss over output current

#### Technical diagrams


#### Characteristic curve of output at $T_a = 25$ °C



CP-C.1 24/5.0, CP-C.1 24/5.0-L CP-C.1 24/5.0-C




CP-C.1 24/10.0, CP-C.1 24/10.0-L CP-C.1 24/10.0-C




CP-C.1 24/20.0, CP-C.1 24/20.0-L CP-C.1 24/20.0-C


#### Characteristic curve of temperature at $U_{out}$ = 24 V




CP-C.124/5.0, CP-C.124/5.0-L




CP-C.124/10.0, CP-C.124/10.0-L




CP-C.1 24/20.0, CP-C.1 24/20.0-L



CP-C.124/5.0-C



CP-C.124/10.0-C




CP-C.1 24/20.0-C

### CP-C.1 range

Technical diagrams

#### **Dimensional drawings**

Dimensions in **mm** and inches







# Power supplies for

building applications
Table of contents

334	CP-D range
354	Benefits and advantages
356	Operation controls
357	Applications
358	Ordering details
359	Technical data
363	Technical diagrams

### Benefits and advantages



Thanks to its compact modular housing, the CP-D range is ideal for building applications and installation. For maximum flexibility in operation, six different versions are available, from 10 W up to 100 W. Their wide input voltage range allows their use in global applications.



The CP-D range is easy to adjust and ideally suited for installation in distribution panels due to its width being only 18 to 90 mm.



The product can be used in any installation in the world. Giving you the confidence of worldwide sourcing – no matter where you build, install or operate your equipment.



Speed up your projects

Data available for common planning software: Less engineering time required.

### Benefits and advantages



#### Characteristics

- Output voltages 12 V, 24 V DC
- Adjustable output voltages (devices > 10 W)
- Output currents 0.42 A / 0.83 A / 1.3 A / 2.1 A / 2.5 A / 4.2 A
- Power range 10 W, 25 W, 30 W, 60 W, 100 W
- Wide range input 100-240 V AC (90-264 V AC, 120-375 V DC)
- High efficiency of up to 89 %
- · Low power dissipation and low heating
- Free convection cooling (no forced cooling with ventilators)
- Ambient temperature range during operation -40...+70 °C
- · Open-circuit, overload and short-circuit stable
- · Integrated input fuse
- · LEDs for status indication
- Light-grey housing in RAL 7035
- · Various approvals and marks



#### Main benefits

#### Adjustable output voltage


The CP-D range types > 10 W feature a continuously adjustable output voltage. Thus, they can be optimally adapted to the application, for example compensating the voltage drop caused by a long line length.

#### Wide range input

Optimized for world-wide applications: The CP-D power supplies can be supplied with 90-264 V AC or 120-375 V DC.

#### Width and structural form


With their width being only 18 to 90 mm, the CP-D range switch mode power supplies are ideally suited for installation in distribution panels.







## Operation controls



 $<sup>^{\</sup>circ}$  only for devices > 10 W. 12 V version: 12...14 V DC, 24 V version: 24 ... 28 V DC.

# **Applications**







Communication



**Escalators** 



Elevator



LED lighting















#### Ordering details



CP-D 12/0.83, CP-D 24/0.42



CP-D 12/2.1, CP-D 24/1.3



CP-D 24/2.5

#### Description

The CP-D range of modular power supply units in MDRC design (modular DIN rail components) is ideally suited for installation in distribution panels. This range offers devices with output voltages of 12 V DC and 24 V DC at output currents of 0.42 A to 4.2 A. Thanks to their high thermal efficiency, these power supplies have very low power and heat dissipation and can be operated without forced cooling. All power supply units in the CP-D range are approved according to all relevant international standards.

#### Ordering details

Input voltage range	Rated output voltage / current	Туре	Order code	Weight (1 pc.) kg (lb)
90-264 V AC/ 120-375 V DC	12 V DC / 0.83 A	CP-D 12/0.83	1SVR427041R1000	0.06 (0.13)
90-264 V AC/ 120-375 V DC	12 V DC / 2.1 A	CP-D 12/2.1	1SVR427043R1200	0.19 (0.41)
90-264 V AC/ 120-375 V DC	24 V DC / 0.42 A	CP-D 24/0.42	1SVR427041R0000	0.06 (0.13)
90-264 V AC/ 120-375 V DC	24 V DC / 1.3 A	CP-D 24/1.3	1SVR427043R0100	0.19 (0.41)
90-264 V AC/ 120-375 V DC	24 V DC / 2.5 A	CP-D 24/2.5	1SVR427044R0200	0.25 (0.56)
90-264 V AC/ 120-375 V DC	24 V DC / 4.2 A	CP-D 24/4.2	1SVR427045R0400	0.32 (0.71)

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-D 12/0.83	CP-D 12/2.1
Input circuit - supply circuit		L, N	
Rated input voltage U <sub>s</sub>		100-240 V AC	
Input voltage range		90-264 V AC / 120-375 V DC	
Frequency range AC		47-63 Hz	
Typical input current /	at 115 V AC	200 mA / 12.68 W	502 mA / 31.14 W
typical power consumption	at 230 V AC	128.3 mA / 13.01 W	277 mA / 31.2 W
Inrush current	at 115 / 230 V AC	16 A / 32 A	25 A / 50 A
Power failure buffering time		min. 30 ms	
Internal input fuse		1 A slow-acting / 250 V AC	2 A slow-acting / 250 V AC
Power factor correction (PFC)		no	
Indication of operational states			
Output voltage	DC ON: green LED	ि ः output voltage applied	
	DC LOW: red LED	- 11	
Output circuit		+, -	++,
Rated output voltage		12 V DC	,
Tolerance of the output voltage		±1 %	
Adjustment range of the output voltage		_	12-14 V DC
Rated output power		10 W	25 W
Rated output current I	T₂ ≤ 60 °C	-	2.1 A
Derating of the output current	$f_a = 30 \text{ °C}$ 60 °C < $f_a \le 70 \text{ °C}$		2.27
Maximum	load change statical		
deviation change of output voltage within th			
with	ic input voitage range	max. 1 70	
Recover time T <sub>A</sub>		< 1 ms	
Starting time after applying the supply voltage	at I <sub>r</sub>	1000 ms	
Rise time	at rated load	typ. 1 ms	
Residual ripple and switching peaks	BW = 20 MHz	50 mV	
Parallel connection		yes, using CP-D RU	
Series connection		yes, to increase voltage	
Resistance to reverse feed		18 V / 1 s	
Output circuit - No-load, overload and short-circuit bel	havior		
Characteristic curve of output		hiccup-mode	U/I characteristic curve
Short-circuit protection		continuous short-circuit stability	
Short-circuit behavior		continuation with output power li	miting
Current limiting at short circuit		typ. 1.4 A	typ. 5.9 A
Overload protection		output power limiting	
Overvoltage protection		15-16.5 V DC	
No-load protection		continuous no-load stability	
Starting of capacitive loads		unlimited	
General data			
Efficiency		typ. 78 %	typ. 82 %
Duty cycle		100 %	
Dimensions		see "Dimensional drawings"	
Material of housing		plastic	
Mounting		DIN rail (IEC/EN 60715), snap-on n	nounting without any tool
Mounting position		horizontal	
Minimum distance to other units	horizontal / vertical	25 mm / 25 mm (0.98 in / 0.98 in)	
Degree of protection	housing / terminals	IP20 / IP20	
Protection class		П	

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-D 12/0.83	CP-D 12/2.1
Electrical connection - Input circuit / Output	circuit		
Connecting capacity	ine-strand with wire end ferrule	0.2-1.5 mm² (24-16 AWG)	0.2-2.5 mm² (24-14 AWG)
_	rigid	0.2-2.5 mm <sup>2</sup> (26-12 AWG)	0.2-2.5 mm² (24-12 AWG)
Stripping length		4-5 mm (0.16-0.2 in)	7 mm (0.28 in)
Tightening torque		0.6 Nm (5 lb.in)	0.7 Nm (6 lb.in)
Environmental data			
Ambient temperature range	operation	-40+70 °C (-40+158 °F)	
	rated load	-40+60 °C (-40+131 °F)	
	storage	-40+85 °C (-40+185 °F)	
Altitude during operation	IEC/EN 60068-2-13	max. 4850 m	
Damp heat (cyclic) (IEC/EN 60068-2-30)		4 x 24 cycles, 40 °C, 95 % RH	
Vibration (sinusoidal) (IEC/EN 60068-2-6)		50 m/s², 10 Hz - 2 kHz	
Shock (half-sine) (IEC/EN 60068-2-27)		40 m/s², 22 ms	
Isolation data			
Rated insulation voltage U <sub>i</sub>	input circuit / output circuit	3 kV AC	
Pollution degree		2	
Overvoltage category		II	
Standards / Directives			
Standards		IEC/EN 62368-1	
Low Voltage Directive		2014/35/EU	
EMC Directive		2014/30/EU	
RoHS Directive		2011/65/EU	
Protective low voltage		SELV (IEC 60950-1)	
Electromagnetic compatibility			
Interference immunity to		IEC/EN 61000-6-2	
electrostatic discharge	IEC/EN 61000-4-2	level 4 (4 kV / 8 kV)	level 4 (4 kV / 15 kV)
radiated, radio-frequency, electromagnetic fi	eld IEC/EN 61000-4-3	level 3 (10 V/m)	
electrical fast transient/burst	IEC/EN 61000-4-4	level 4 (4 kV)	
surge	IEC/EN 61000-4-5	level 3 (2 kV L-L)	
conducted disturbances, induced by radio- frequency fields	IEC/EN 61000-4-6	level 3 (10 V)	
Interference emission		IEC/EN 61000-6-3	
high-frequency radiated		class B	
high-frequency conducted		class B	

# **CP-D** range

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Type	CP-D 24/0.42	CP-D 24/1.3	CP-D 24/2.5	CP-D 24/4.2
Input circuit - supply circuit	L, N		•	,
Rated input voltage U <sub>in</sub>	100-240 V AC			
Input voltage range	90-264 V AC /120	-375 V DC		
Frequency range AC	47-63 Hz			
	184 mA / 11.62 W	600 mA / 37 92 W	1120 mA / 69.3 W	1800 mA / 117.3 W
	120.6 mA / 12 W	344 mA / 38.16 W		900 mA / 114.4 W
	max. 16 A / 32 A	max. 25 A / 50 A	max. 30 A / 60 A	300 7 22 11
Power failure buffering time	min. 30 ms		min. 60 ms	
Internal input fuse	1 A slow-acting /	2 A slow-acting /		3.15 A slow-
meeria inpactase	250 V AC	250 V AC		acting / 250 V AC
Power factor correction (PFC)	no			
Indication of operational states	1.10			
Output voltage DC ON: green LED	· output w	oltage applied		
DC LOW: red LED		oltage too low		
		ortage too low		
Output circuit	+, - 24 V DC		++,	
Rated output voltage				
Tolerance of the output voltage	±1 %	24 20 4 26		
Adjustment range of the output voltage	1014	24-28 V DC	COW	100 W
Rated output power	10 W	30 W	60 W	
Rated output current I,	$T_a \le 60 ^{\circ}\text{C}: 0.42 \text{A}$	T <sub>a</sub> ≤ 60 °C: 1.3 A	T <sub>a</sub> ≤ 55 °C: 2.5 A	$T_a \le 60 ^{\circ}\text{C}: 4.2 ^{\circ}\text{A}$
Derating of the output current	60 °C < T <sub>a</sub> ≤ 70 °C: 2.5 %/°C	60 °C < T <sub>a</sub> ≤ 70 °C: 2.5 %/°C	55 °C < T <sub>a</sub> ≤ 70 °C: 2.5 %/°C	60 °C < T <sub>a</sub> ≤ 70 °C: 2.5 %/°C
Maximum load change statical	max. 1 %			
deviation change of output voltage within the input voltage range with	max. 1 %			
Recover time T <sub>A</sub>	< 1 ms			
Starting time after applying the supply voltage at I	1000 ms			
Rise time at rated load	typ. 1 ms			
Residual ripple and switching peaks BW = 20 MHz	50 mV			
Parallel connection	yes, using CP-D RI	U		
Series connection	yes, to increase vo	oltage		
Resistance to reverse feed	35 V / 1 s			
Output circuit - No-load, overload and short-circuit behavior				
Characteristic curve of output	hiccup-mode	U/I characteristic	curve	
Short-circuit protection	continuous short-	circuit stability		
Short-circuit behavior	continuation with	output power limit	ing	
Current limiting at short circuit	typ. 0.78 A	typ. 4.2 A	typ. 6.05 A	typ. 11.5 A
Overload protection	output power limi	iting		
Overvoltage protection	30-33 V DC			
No-load protection	continuous no-loa	ad stability		
Starting of capacitive loads	unlimited			
General data				
Efficiency	typ. 80 %	typ. 83 %	typ. 86 %	typ. 89 %
Duty cycle	100 %			
Dimensions	see "Dimensional	drawings"		
Material of housing	plastic			
Mounting	DIN rail (IEC/EN 6	0715), snap-on mou	unting without any	tool
Floatiting				
Mounting position	horizontal			
		0.98 in / 0.98 in)		
Mounting position	25 mm / 25 mm (0	).98 in / 0.98 in)		

# **CP-D range**Technical data


Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated


Туре		CP-D 24/0.42	CP-D 24/1.3	CP-D 24/2.5	CP-D 24/4.2
Electrical connection - Input circuit / Output cir	cuit		•		·
Connecting capacity	fine-strand with wire end ferrule		0.2-2.5 mm <sup>2</sup> (24	-14 AWG)	
	rigid	0.2-2.5 mm <sup>2</sup> (26-12 AWG)			
Stripping length		4-5 mm (0.16-0.2	? in)	7 mm (0.28 in)	
Tightening torque		0.6 Nm (5 lb.in)		0.7 Nm (6 lb.in)	
Environmental data					
Ambient temperature range	operation	-40+70 °C			
	rated load	-40+60 °C		-40+55 °C	-40+60 °C
	storage	-40+85 °C			
Altitude during operation	IEC/EN 60068-2-13	max. 4850 m			
Damp heat (cyclic) (IEC/EN 60068-2-30)		4 x 24 cycles, 40	°C, 95 % RH		
Vibration (sinusoidal) (IEC/EN 60068-2-6)		50 m/s², 10 Hz - 2	2 kHz		
Shock (half-sine) (IEC/EN 60068-2-27)		40 m/s², 22 ms			
Isolation data					
Rated insulation voltage $U_{_{\mathrm{i}}}$ inpu	it circuit / output circuit	3 kV AC		4 kV AC	3 kV AC
Pollution degree		2			
Overvoltage category		II			
Standards / Directives					
Standards		IEC/EN 62368-1			
Low Voltage Directive		2014/35/EU			
EMC Directive		2014/30/EU			
RoHS Directive		2011/65/EU			
Protective low voltage		SELV (IEC 60950	-1)		
Electromagnetic compatibility					
Interference immunity to		IEC/EN 61000-6	-2		
electrostatic discharge	IEC/EN 61000-4-2	level 4 (4 kV / 8 kV)	level 4 (4 kV / 15 kV)		level 4 (4 kV / 8 kV)
radiated, radio-frequency, electromagnetic field	IEC/EN 61000-4-3	level 3 (10 V/m)	·		·
electrical fast transient/burst	IEC/EN 61000-4-4	level 4 (4 kV)			
surge	IEC/EN 61000-4-5	level 3 (2 kV L-L)			
conducted disturbances, induced by radio- frequency fields	IEC/EN 61000-4-6	level 3 (10 V)			
Interference emission		IEC/EN 61000-6	-3		
high-frequency radiated		class B			
high-frequency conducted		class B			


# **CP-D** range


# Technical diagrams


### Characteristic curve of output at $T_a = 25$ °C
















### Characteristic curve of temperature at rated output voltage







# **CP-D** range

# Technical diagrams

#### **Dimensional drawings**

Dimensions in mm and inches







# **CP-B range**Table of contents

300	benefits and advantages
370	Operation controls
371	Applications
372	Ordering details
373	Technical data
375	Technical diagrams

# Benefits and advantages



ABB's ultra-capacitor based CP-B buffer modules serve to ensure a short-term uninterrupted power supply system with a voltage of 24 V DC by buffering the load in case of power loss.

The buffer modules feature a technology for storing energy: the use of ultracapacitors obviates the need for maintenance and exempts deep discharge in comparison to batteries.



- Buffering 24 V DC supply of up to 572 s
- Maintenance-free, ultra-capacitor technology
- Temperature resistant
- No discharge
- Small footprint

# Benefits and advantages

Power supply systems have to be highly reliable in most areas of energy management and automation technology. Often, batteries are used for supporting the supply system in case of mains failures. Batteries have limited lifetimes depending on environmental parameters and have to be maintained regularly, which causes extra work and costs.

Using the ultra-capacitor technology, ABB offers an innovative and completely maintenance-free new product for buffering the 24 V DC supply in case of interrupted mains on the primary side of the switch mode power supply.

The CP-B range is an ultra-capacitor buffer energy storage system for power supply units which ensures a short term uninterrupted power supply system. In case of power loss, the energy stored in the capacitor guarantees that the load is continually provided for up to several hundred seconds depending on the load current.



#### Characteristics

• 3 buffer modules for buffering 24 V DC:

CP-B 24/3.0 (3 A / 1 kWs1)

CP-B 24/10.0 (10 A / 13.7 kWs1)

CP-B 24/20.0 (20 A / 8 kWs1)

- · LEDs for status indication
- · Relay contacts for status messaging
- Very high backup times (e.g. with CP-B 24/10.0 up to 9 minutes and 30 s minutes at 1 A load current)
- Short charging times
- High efficiency, higher than 95 %
- · Wide temperature range
- · DIN rail mountable, compact housing
- Extended temperature range -40...60 °C

		CP-B 24/3.0	CP-B 24/10.0	CP-B 24/20.0
Order code		1SVR427060R0300	1SVR427060R1000	1SVR427060R2000
Rated input voltage		24 V DC	24 V DC	24 V DC
Rated current		3 A DC	10 A DC	20 A DC
Energy storage (min.)		1.000 Ws	13.700 Ws	8.000 Ws
Typical charging time at load	100 %	65 s	134 s	135 s
current	0 %	56 s	82 s	62 s
Typical	100 %	13 s	50 s	15 s
buffering time <sup>1)</sup> at load current	50 %	28 s	115 s	30 s
	25 %	66 s	246 s	60 s
_	10 %	148 s	572 s	150 s


<sup>1)</sup> buffering time ≈

<sup>1)</sup> internal energy buffer

energy storage x 0.9


current x output voltage

# Operation controls



# **Applications**

### **Example of application**



# Ordering details



CP-B 24/3.0



CP-B 24/10.0



CP-B 24/20.0

### Description

Ultra capacitor based buffer units of the CP-B range offer the highest reliability also in harsh environments. Thanks to their ultra-cap based technology, the units are maintenance free, there will be no deep discharge and these products offer a very wide operational ambient temperature range. CP-B range buffer units are an excellent solution for avoiding voltage drops in solar applications, for example.

### Ordering details

Rated input voltage	Rated current	Туре	Order code	Weight (1 pc.) kg (lb)
24 V DC	3 A DC	CP-B 24/3.0	1SVR427060R0300	0.59 (1.31)
	10 A DC	CP-B 24/10.0	1SVR427060R1000	2.10 (4.63)
	20 A DC	CP-B 24/20.0	1SVR427060R2000	2.20 (4.85)

Туре		CP-B 24/3.0	CP-B 24/10.0	CP-B 24/20.0
Input circuit - Supply circuit		L+ <sub>IN</sub> L- <sub>IN</sub>		
Rated input voltage U <sub>in</sub>		24 V DC		
Input voltage range		23.7-26.4 V DC	23.9-27 V DC	23.4-29 V DC
Minimum charging potential		23.7 V DC	23.9 V DC	23.4 V DC
Rated input current		3 A DC	10 A DC	20 A DC
Inrush current limiting		50 A / 1 ms	35 A / 2 ms	35 A / 2 ms
Transient overvoltage protection		suppressor diode	varistor / suppressor diode	varistor / suppressor diode
Internal input fuse (apparatus protection, not accessib	le)	4 A slow acting	15 A (FK2)	30 A (FK2)
Internal fuse capacitors circuit (not accessible)			25 A (FK2)	
Kind of input	SHUT-DOWN	-	control input	control input
_	rated voltage	-	24 V DC	24 V DC
-	voltage range	-	6-45 V DC	6-45 V DC
Output circuit		L+ <sub>out</sub> L- <sub>out</sub> L- <sub>out</sub>		
Rated output power		69 W	240 W	480 W
Rated output voltage U <sub>out</sub>		24 V DC		
Output voltage (buffer mode)		23.0 V DC	23.2 V DC	23.2 V DC
Tolerance of the output voltage		+210 %		
Rated output current I <sub>r</sub>	T <sub>a</sub> ≤ 60 °C	3 A DC	10 A DC	20 A DC
Peak output current (fully loaded capacitors required)	T <sub>a</sub> ≤ 60 °C	6 A DC (min. 1.5 s)	20 A DC (10 A power supply + 10 A CP-B, min. 1.5 s)	40 A DC (min. 1.5 s)
Control of limiting current		-	10.3 A DC ±0.1A	-
Shut-down if limiting current is exceeded		-	after 1.5 s	-
Short-circuit protection (only via external fuse)		no continuous short-circuit stability		
Internal output fuse (not accessible)		-	15 A (FK2)	-
Required external fuse		3.15 A slow acting	10 A slow acting	25 A slow acting
Current limiting at output circuit		-	1.051.2 x I <sub>r</sub>	-
Breaking capacity of output circuit	t= 2.5 ms	-	24 V DC, 10 A	-
Power failure buffering time <sup>1)</sup>		load-dependent, min. 13 s at 100 % load	load-dependent, min. 50 s at 100 % load	load-dependent, min. 15 s at 100 % load
Overload protection		thermal protection		
Kind of output	INPUT OK	n/o contact		
	BUFFER STATUS	-	n/o contact	
	FAILURE	-	c/o contact	
Contact material		Ag + Au-clad		
Minimum switching voltage / Minimum switching curre	ent	5 V DC / 1 mA		
Maximum switching voltage / Maximum switching curr	rent	50 V AC / 1.0 A, 30 V DC / 0.5 A		
Mechanical lifetime		5 x 10 <sup>6</sup> switching cycles		
Electrical lifetime		0.1 x 10 <sup>6</sup> switching cycles		
Maximum fuse rating to achieve short-circuit protection	n/o or n/c contact	1.0 A AC / 0.5 A DC		


# Technical data

Туре		CP-B 24/3.0	CP-B 24/10.0	CP-B 24/20.0
General data		*	·	
Maximum internal power consumption		7 W	20 W	40 W
Power consumption with unloaded output		0.75 W	3 W	1.6 W
Energy storage (min.)		1000 Ws	13700 Ws	8000 Ws
Typical charging time at 24.5 V DC	100 %	65 s	134 s	135 s
	56 s	82 s	62 s	
Typical buffering time at load current <sup>1)</sup>	100 %	13 s	50 s	15 s
	50 %	28 s	115 s	30 s
	25 %	66 s	246 s	60 s
	10 %	148 s	572 s	150 s
Efficiency		> 95 %		'
Dimensions		see "Dimensional draw	ings"	
Material	cover / housing shell	steel sheet powdered		
Mounting		DIN rail (IEC/EN 60715)	, snap-on mounting	
Mounting position		horizontal		
Minimum distance to other units	horizontal	not necessary		
	vertical	40 mm (1.58 in)		80 mm (3.15 in)
Pollution degree		2		
Degree of protection	housing / terminal	IP20		
Protection class (IEC/EN 61140)		III SELV / PELV (condition	on: power supply fulfills c	lass III)
Electrical connection - Input circuit / Output	circuit	pull spring terminals	pull spring terminals	pluggable screw type terminals
Connecting capacity fine-stran	d with(out) wire end ferrule	0.08-1.0 mm <sup>2</sup> (28-18 AWG)	0.08-1.5 mm <sup>2</sup> (28-16 AWG)	0.2-4.0 mm <sup>2</sup> (24-12 AWG)
	rigid	0.08-1.5 mm <sup>2</sup> (28-16 AWG)	0.08-4.0 mm <sup>2</sup> (28-12 AWG)	0.2-6.0 mm <sup>2</sup> (24-10 AWG)
Stripping length		6.0 mm (0.24 in)		7.0 mm (0.28 in)
Signaling circuit		1		•
Connecting capacity fine-stran	d with(out) wire end ferrule	0.08-1.0 mm² (28-18 AWG)		0.14-1.0 mm² (26-16 AWG)
	rigid	0.08-1.5 mm² (28-16 AW	/G)	0.14-1.5 mm² (28-16 AWG)
Stripping length		6.0 mm (0.24 in)		7.0 mm (0.28 in)
Environmental data		`		
Ambient temperature	operation	-40+60 °C		
	storage	-40+60 °C		
Standards / Directives		•		
Standards		IEC/EN 62368-1, IEC/EI	N 61010-1, IEC/EN 62040	-2
Low Voltage Directive		2014/35/EU		
EMC Directive		2014/30/EU		
RoHS Directive		2011/65/EU		
Electromagnetic compatibility				
Interference immunity to		IEC/EN 61000-6-2		
electrostatic discharge	IEC/EN 61000-4-2	level 3, 6 kV / 8 kV		
radiated, radio-frequency, electromagnetic fi	eld IEC/EN 61000-4-3	level 3, 10 V/m (27-1000	) MHz) / level 2, 3 V/m (14	00-2700 MHz)
electrical fast transient/burst	IEC/EN 61000-4-4	level 3, 2(1) kV / 5 kHz		
		level 1, 0.5 kV		
surge	IEC/EN 61000-4-5	level 1, 0.5 kV		
surge conducted disturbances, induced by radio-frequency fields		level 3, 10 V (150 kHz-80	OMHz)	
conducted disturbances,		level 3, 10 V (150 kHz-80	•	
conducted disturbances, induced by radio-frequency fields voltage dips, short interruptions and voltage	IEC/EN 61000-4-6	level 3, 10 V (150 kHz-80	•	
conducted disturbances, induced by radio-frequency fields voltage dips, short interruptions and voltage variations	IEC/EN 61000-4-6	level 3, 10 V (150 kHz-80 buffered by ultra-capac EN 61000-6-4	•	


 $^{1)}$  buffering time  $pprox \frac{\text{energy storage x 0.9}}{\text{current x output voltage}}$ 


# Technical diagrams


# Characteristic curve of the temperature at rated load



#### Capacitors life span over temperature








- A Normal application (up to 50 % buffer mode, 5 charging and discharging cycles in direct series)
- **B** Continuous charging and discharging in direct series. As this is not typical of a real application, this should be considered as theoretical indication


# Technical diagrams

#### **Dimensional drawings**


Dimensions in mm and inches



CP-B 24/3.0




CP-B 24/10.0





# **Redundancy units**Table of contents

201	benefits and advantages
382	Ordering details
383	Technical data
386	Technical diagrams



# Benefits and advantages



ABB's redundancy units are used to establish true redundancy, which increases the availability of electrical systems significantly. Three versions are available with different output currents and power supply housings:

- CP-D RU in MDRC housing
- CP-C.1-A-RU for a true redundant setup of two 56 V DC power supplies of the CP range



#### Highest system reliability

- Redundancy setup of the application possible to allow parallel operation
- Long lifetime

### Ordering details



CP-C.1-A-RU



CP-C.1-A-RU-L



CP-D RU

#### **Description**

Whenever the highest availability and reliability are key requirements, a true redundancy setup with two power supplies connected to a redundancy unit is the best solution. In case one power supply fails, the other one keeps supplying the load. Furthermore, even a short circuit in one power supply will not affect the other one, which keeps supplying the load. The CP-C.1-A-RU is also available with coated PCBA (CP-C.1-A-RU-C) for harsh environments.

# Ordering details - CP-C.1-A-RU for decoupling of CP power supplies up to 20 A per input / channel

Input voltage range	Rated input current per channel	Rated output voltage / current		Туре	Order code	Weight (1 pc.) kg (lb)
10 - 58 V DC	0 - 58 V DC 20 A 12 - 48 V DC / 2 x 20 A		uncoated	CP-C.1-A-RU	1SVR360060R1001	1.04 (2.29)
		or 1 x 40 A	coated	CP-C.1-A-RU-C	1SVR360060R2001	1.04 (2.29)
			uncoated	CP-C.1-A-RU-L	1SVR361060R1001	1.04 (2.29)

### Ordering details - CP-D RU for decoupling of two CP-D power supply units

Input voltage range	Rated input current per channel	Rated output voltage / current	Туре	Order code	Weight (1 pc.) kg (lb)
9-35 V DC	5 A	24 V DC / 1 x 10 A	CP-D RU	1SVR427049R0000	0.075 (0.165)

Data at  $T_a$  = 25 °C,  $U_{in}$  = 230 V AC and rated values, unless otherwise indicated

Туре		CP-C.1-A-RU, CP-C.1-A-RU-L	CP-C.1-A-RU-C
Input circuit - Supply circuit		(+/+, -/-)	·
Rated input voltage U <sub>in</sub>		12-48 V DC	
Input voltage range		10 - 58 V DC	
Rated input current I <sub>in</sub> per channel	$-25^{\circ}\text{C} \le \text{T}_{\text{a}} \le 60^{\circ}\text{C}$	20 A	
Maximum input current per channel	$-25$ °C $\leq T_a \leq 40$ °C	30 A	
	$-40^{\circ}\text{C} \le \text{T}_{\text{a}} \le 40^{\circ}\text{C}$	-	30 A
Transient overvoltage protection		yes, varistor	
Output circuit		(++/)	
Rated output voltage U <sub>out</sub>		12 - 48 V DC	
Voltage drop input/output		typ. 0.6 V, max. 0.9 V	
Rated output current I <sub>r</sub>	-25 °C ≤ T <sub>a</sub> ≤ 60 °C	2 x 20 A or 1 x 40 A	
Max. output current (Power reserve)	-25 °C ≤ T <sub>a</sub> ≤ 40 °C	2 x 30 A or 1 x 60 A	
	$-40^{\circ}\text{C} \le \text{T}_{\text{a}} \le 40^{\circ}\text{C}$	-	2 x 30 A or 1 x 60 A
Derating of the output current	$60$ °C < $T_a \le 70$ °C	2.5 % per Kelvin temperature inc	rease
Resistance to reverse feed		< 60 V	
General data			
Power loss	input 2 x 20 A	23.0 W	
	input 2 x 10 A	9.4 W	
	input 2 x 5 A	4.1 W	
MTBF	acc. to MIL 217 HDBK	on request	
Dimensions		see "Dimensional drawings"	
Material of housing	cover / housing shell / front	aluminium / zinc-coated sheet st	teel / plastic
Mounting		DIN rail (IEC/EN 60715), snap-on	mounting
Mounting position		1 and 7	
Minimum distance to other units	horizontal / vertical	25 mm (0.98 in) / 25 mm (0.98 in)	)
Degree of protection (IEC/EN 60529)	housing / terminals	IP20 / IP20	
Protection class (IEC/EN 61140)		Ш	
Electrical connection - Input circuit /	Output circuit		
Connecting capacity	fine-strand with(out) wire end ferrule	2.5-10 mm² (12-8 AWG)	
	rigid	2.5-16 mm² (12-6 AWG)	
Stripping length		10 mm (0.39 in)	
Tightening torque		1.2 Nm (10.5 lb.in)	
Recommended screw driver		PH1 / Ø 4.0 x 0.8 mm (0.16 x 0.03	in)


Туре	1	CP-C.1-A-RU, CP-C.1-A-RU-L	CP-C.1-A-RU-C
Environmental data			
Ambient temperature range	operation	-25+70 °C (-13 +158 °F)	-40+70 °C (-40+158 °F)
	rated load	-25+60 °C (-13 +140 °F)	-40+60 °C (-40+140 °F)
	storage	-40+85 °C (-40+185 °F)	
	transportation	-40+85 °C (-40+185 °F)	
Climatic class (IEC/EN 60721-3-1)	storage	1K2	
Climatic class (IEC/EN 60721-3-2)	transportation	2K2	
Climatic class (IEC/EN 60721-3-3)	operation	3K3	
Damp heat, cyclic (IEC/EN 60068-2-30)		test Db: 55 °C, 2 cycles	
Vibration (IEC/EN 60068-2-6)		test Fc: 10-58 Hz, amplitude ±0.1 10 sweep cycles each axis	15 mm, 58-150 Hz, 2 g,
Shock, half-sine (IEC/EN 60068-2-27)		test Ea: 30 g, 6 ms, 3 pulses each bump 20 g, 11 ms, 100 pulses ea	
Coated PCBA		no	yes
Gaseous corrosive environment withstand test (II	EC/ EN 60068-2-60)		testing method: 4 testing period: 21 days ambient conditions: 25 °C, 75 % r.h. air/volume change rate per hour: 3-6 sample not energized during exposure gas concentrations acc. ISA-S71.04.2013 Harsh Group A, G3 IEC 60721-3.3 acc. 3C2/3C3 - H₂S ≥ 100 ± 10 ppb - SO₂/SO₃ ≥ 300 ± 20 ppb - Cl₂ ≥ 100 ± 10 ppb - NO₃ ≥ 1250 ± 20 ppb
Isolation data			
Rated impulse withstand voltage U <sub>imp</sub> (EN62477-1	) input / housing	1.5 kV (1.2/50 μs)	
	output / housing	1.5 kV (1.2/50 μs)	
Pollution degree		2	
Standards / Directives			
Standards		IEC/EN 61204	
EMC Directive		2014/30/EU	
ATEX Directive		-	2014/34/EU
RoHS Directive		2011/65/EU	
Electrical safety		IEC/EN 61010-1, IEC/EN 61010-2	2-201, IEC 60950-1
Process control equipment		UL 61010-1, UL 61010-2-201/CA CAN/CSA-IEC 61010-2-201:18	N/CSA C22.2 No. 61010-1-12,
Electromagnetic compatibility			
Interference immunity to	,		
electrostatic discharge	IEC/EN 61000-4-2	Level 4, contact discharge ±8 kV,	air discharge ±15 kV (criterion B)
electrical fast transient / burst	IEC/EN 61000-4-4	Level 3, DC mains inputs and out	put ±2 kV (criterion B)
surge	IEC/EN 61000-4-5	Level 1, DC mains inputs and out input and output vs. PE ±1 kV (cr	•


Туре		CP-D RU		
Input circuit - Supply circuit		IN 1 + + -, IN 2 + + -		
Rated input voltage U <sub>in</sub>		24 V DC		
Input voltage range		9-35 V DC		
Rated input current I <sub>in</sub> per channel		5 A		
Maximum input current per channel		10 A for 300 s		
Transient overvoltage protection		no		
Output circuit		OUT + + +,		
Rated output voltage U <sub>out</sub>		24 V DC		
Voltage drop		typ. 0.5 V		
Rated output current I <sub>out</sub>		10 A		
Resistance to reverse feed		< 35 V		
General data	,			
MTBF	·	on request		
Duty cycle		100 %		
Dimensions		see "Dimensional drawings"		
Material of housing		plastic		
Mounting		DIN rail, snap-on mounting without any tool		
Mounting position		1, 7		
Minimum distance to other units	horizontal / vertical	25 mm (0.98 in) / 25 mm (0.98 in)		
Electrical connection - Input circuit / Output circuit	,			
Connecting capacity fine-strand	with (out)wire end ferrule	0.2-2.5 mm <sup>2</sup> (24-14 AWG)		
	rigid	0.2-2.5 mm² (24-12 AWG)		
Stripping length		7.0 mm (0.28 in)		
Tightening torque		0.67 Nm (6 lb.in)		
Environmental data				
Ambient temperature range	operation	-40+70 °C		
	storage	-40+85 °C		
Relative humidity	RH at 40 °C	20-95 %, no condensation		
Vibration (IEC/EN 60068-2-6)		mounting by rail:		
		10-500 Hz, 2 G, along X, Y, Z each axis, 60 min for each axis		
Shock (IEC/EN 60068-2-27)		15 G, 11 ms, 3 axis, 6 faces, 3 times for each face		
Standards / Directives				
Standards		IEC/EN 62368-1, IEC/EN 61204-3		
RoHS Directive		2011/65/EU		
Electromagnetic compatibility				
Interference immunity to		EN 55024		
electrostatic discharge	IEC/EN 61000-4-2	level 3, air discharge 8 kV, contact discharge 4 kV		
radiated, radio-frequency, electromagnetic field IEC/EN 61000-4-3		level 3, 10 V/m		
electrical fast transient/burst	IEC/EN 61000-4-4	level 3, 2 kV / 5 kHz		
conducted disturbances, induced by radio-frequency fields	IEC/EN 61000-4-6	level 3, 10 V		
Interference emission		EN 55032		
high-frequency radiated	IEC/CISPR 32 / EN 55032	class B		
high-frequency conducted	IEC/CISPR 32 / EN 55032	class B		

# Technical diagrams

#### **Dimensional drawings**

Dimensions in mm and inches








Table of contents

390	benefits and advantages
391	Applications
392	Ordering details
393	Operating data
394	Technical data
395	Technical information
396	Technical diagrams
397	Approvals, Safety instructions
398	Installation guidelines

# Benefits and advantages



With its narrow width of only 12.5 mm, EPD24 can fit everywhere – it can even be mounted side-by-side.

Its adjustable and fixed current ratings, projectable protection through current limitation as well as a single trip curve for all types of loads allow for use in a wide field of applications.



#### Highlights

- · Safety and reliability
- Operational continuity
- Worldwide use thanks to relevant certifications
- · Compact and effective

# **Applications**



#### **Features**

- Selective load protection, one electronic tripping characteristic.
- Active current limitation for safe connection of capacitive loads up to 20,000  $\mu F$  and on overload/short circuit
- Current ratings 0.5...12 A
- Reliable overload disconnection with 1.1 x  $\rm I_{_{\rm N}}$
- Manual ON/OFF button
- Clear status and failure indication through LED and integrated auxiliary contact
- Integral fail-safe element adjusted to current rating
- Width per unit only 12.5 mm
- · Rail mounting
- Ease of wiring through busbar LINE+ and 0 V as well as signal bars
- UL- and CSA-approvals allow international use of the devices



#### **Applications**

- · Packaging machines
- Automation
- Automation & Process Control
- · Automotive Manufacturing
- · Chemical, Oil & Gas
- Medical Equipment
- Pharmaceutical & Food
- Power Engineering DC 24 V
- Renewable Energy
- Steel Production











#### \_

# **Electronic protection devices EPD24**

### Ordering details



EPD24-TB-101-3A

#### Description

The protection devices EPD24 extend the ABB product range of modular DIN rail components by electronic overcurrent protection modules for selective protection of 24 V DC load circuits. This protection is achieved by a combination of active electronic current limitation in the case of a short circuit and an overload deactivation from 1.1 x I<sub>a</sub> upwards.

If a fault occurs in a load circuit, the protection device EPD24 will detect this rapidly and reliably, then disable the power output transistor and hence interrupt the current flow in the defective circuit. The maximum possible overcurrent is always limited to 1.3...1.8 times the selected rated current. An activation of capacitive loads up to 20,000  $\mu F$  is possible, deactivation only occurring in the case of overloads or short circuits. Selective deactivation of the defective current circuit means undefined error states and a complete system stop are prevented.

#### Ordering details

Rated current I <sub>N</sub>	Туре	Order code	Pkg qty Weigh (1 pc.) kg (lb)
0.5	EPD24-TB-101-0.5A	2CDE601101R2905	4 0.065 (1.433)
1	EPD24-TB-101-1A	2CDE601101R2001	4 0.065 (1.433)
2	EPD24-TB-101-2A	2CDE601101R2002	4 0.065 (1.433)
3	EPD24-TB-101-3A	2CDE601101R2003	4 0.065 (1.433)
4	EPD24-TB-101-4A	2CDE601101R2004	4 0.065 (1.433)
6	EPD24-TB-101-6A	2CDE601101R2006	4 0.065 (1.433)
8	EPD24-TB-101-8A	2CDE601101R2008	4 0.065 (1.433)
10	EPD24-TB-101-10A	2CDE601101R2010	4 0.065 (1.433)
12	EPD24-TB-101-12A	2CDE601101R2012	4 0.065 (1.433)

Description	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Busbars for LINE+ and 0 V, grey insulation, length 500 mm <sup>1)</sup>	EPD-BB500	2CDE605100R0500	10	0.2 (0.441)
Signal bars for aux. contacts, grey insulation, length 21 mm	EPD-SB21	2CDE605200R0021	10	0.4 (0.882)

 $<sup>^{1)}</sup>$  Max. load with one line entry I  $_{\max}$  = 50 A (recommended: mid line entry) Max. load with two line entries I  $_{\max}$  = 63 A

# Operating data

Operating data	
Operating voltage U <sub>B</sub>	24 V DC (1832 V)
Current rating I <sub>N</sub>	fixed current ratings: 0.5, 1, 2, 3, 4, 6, 8, 10, 12 A
Closed current I <sub>0</sub>	ON condition: typically 2030 mA depending on signal output
Status indication by means of	Green: unit is ON load circuit / Power-MOSFET is switched on
	Orange: in the event of overload or short circuit until electronic disconnection
	Red: unit electronically disconnected
	load circuit/Power-MOSFET OFF
	undervoltage ( $U_B < 8 \text{ V}$ ) after switch-on till the end of the delay period
	OFF: manually switched off or device is dead
	potential-free auxiliary contact F
	ON/OFF/ condition of switch
Load circuit	
Load output	Power-MOSFET switching output (high slide switch)
Overload disconnection	typically 1.1 x I <sub>N</sub> (1.051.35 x I <sub>N</sub> )
Short-circuit current I <sub>K</sub>	active current limitation
Trip time	see time/current characteristics
For electronic disconnection	typically 3 s at $I_{Load} > 1.1 \times I_{N}$ typically 100 ms3 s at $I_{Load} > 1.8 \times I_{N}$ (or $1.5 \times I_{N}/1.3 \times I_{N}$ )
Temperature disconnection	internal temperature monitoring with electronic disconnection
Low voltage monitoring load output	with hysteresis, no reset required: load »OFF« at U <sub>B</sub> < 8 V
Starting delay t <sub>Start</sub>	typically 0.5 sec after every switch-on and after applying U <sub>B</sub>
Disconnection of load circuit	electronic disconnection
Free-wheeling circuit	suitable external free-wheeling circuit to be used with inductive load
Several load outputs must not be connected in parallel	
Signal output	
Electrical data	potential-free auxiliary contact max. 30 V DC/0.5 A, min. 10 V DC/10 mA
ON condition LED green	voltage $U_{\scriptscriptstyle B}$ applied, switch is in ON position no overload, no short circuit
OFF condition LED off	device switched off (switch is in OFF position) no voltage $U_{\rm B}$ applied
Fault condition LED orange	overload condition > 1.1 x I <sub>N</sub> up to electronic disconnection
Fault condition LED red	electronic disconnection upon overload or short circuit Device switched off with control signal (switch is in ON position)
Aux. contact	single signal, make contact contact open, terminal 13-14
Fault	signal output fault conditions no operating voltage U <sub>B</sub> ON/OFF switch is in OFF position red LED lighted (electronic disconnection)

### Technical data

General data	
Fail-Safe element	backup fuse for EPD24 not required because of the integral redundant fail-safe element
Housing material	moulded
Mounting	symmetrical rail to EN 50022-35x7.5
Ambient temperature	0+50 °C (without condensation, see EN 60204-1)
Storage temperature	-20+70 °C
Humidity	96 hrs/95 % RH/40 °C to IEC 60068-2-78, test Cab. climate class 3K3 to EN 60721
Vibration	3 g, test to IEC 60068-2-6 test Fc
Degree of protection	housing: IP20 DIN 40050 terminals: IP20 DIN 40050
EMC (EMC directive, CE logo)	emission: EN 61000-6-3 susceptibility: EN 61000-6-2
Isolations coordination (IEC 60934)	0.5 kV/pollution degree 2 reinforced insulation in operating area
Dielectric strength	max. 32 V DC (load circuit)
Isolation resistance (OFF condition)	n/a, only electronic disconnection
Approvals/Declarations of conformity	UL 2367 Solid State Overcurrent Protectors UL 1604, (class I, division 2, groups A, B, C, D) UL 508 CSA C22.2 No. 213 (class I, division 2) CSA C22.2 No. 142 CE logo
Dimensions (B x H x T)	12.5 x 80 x 83 mm
Weight	approx. 65 g
Terminals	Line+/LOAD+/0V
Screw terminals	M4
Max. cable cross section flexible with wire end ferrule w/wo plastic sleeve	0.5 – 10 mm <sup>2</sup>
Multi-lead connection (2 identical cables) rigid/flexible	0.5 – 4 mm <sup>2</sup>
Flexible with wire end ferrule without plastic sleeve	0.5 – 2.5 mm <sup>2</sup>
Flexible with TWIN wire end ferrule with plastic sleeve	0.5 – 6 mm²
Wire stripping length	10 mm
Tightening torque (EN 60934)	1.5 – 1.8 Nm
Terminals	aux. contacts
Screw terminals	M3
Max. cable cross section flexible with wire end ferrule w/wo plastic sleeve	0.25 - 2.5 mm <sup>2</sup>
Wire stripping length	8 mm
Tightening torque (EN 60934)	0.5 Nm

Table 1: voltage drop, current limitation, max. load current

current rating	typically voltage drop	active current	max. load current at 100 % ON duty		
I <sub>N</sub>	U <sub>on</sub> at I <sub>n</sub>	limitation (typically)	T <sub>ambient</sub> = 40 °C	T <sub>ambient</sub> = 40 °C	
0.5 A	70 mV	1.8 x I <sub>N</sub>	0.5 A	0.5 A	
1 A	80 mV	1.8 x I <sub>N</sub>	1 A	1 A	
2 A	130 mV	1.8 x I <sub>N</sub>	2 A	2 A	
3 A	80 mV	1.8 x I <sub>N</sub>	3 A	3 A	
4 A	100 mV	1.8 x I <sub>N</sub>	4 A	4 A	
6 A	130 mV	1.8 x I <sub>N</sub>	6 A	5 A	
8 A	120 mV	1.5 x I <sub>N</sub>	8 A	7 A	
10 A	150 mV	1.5 x I <sub>N</sub>	10 A	9 A	
12 A	180 mV	1.3 x I <sub>N</sub>	12 A	10.8 A	

Attention: when mounted side-by-side without convection, the ERD24 should carry no more than 80 % of its rated load with 100 % ON duty due to thermal effects.

### Technical information

### Time/Current characteristic curve (T<sub>ambient</sub> = 25 °C)

The trip time is typically 3 s in the range between 1.1 and 1.8 x  $I_N^{(1)}$ 

Electronic current limitation occurs at typically 1.8 x  $I_N^{10}$  which means that under all overload conditions (independent of the power supply and the resistance of the load circuit) the max. overload before disconnection will not exceed 1.8 x  $I_N^{10}$  times the current rating. Trip time is between 100 ms and 3 sec (depending on overload or at short circuit).

Without this current limitation a considerably higher overload current would flow in the event of an overload or short circuit.

#### Maximum cable lenghts

EPD24 reliably trips from 0  $\Omega$  up to max. circuit resistance  $R_{\text{max}}$ .

#### Calculation of R

Selected rating $I_N$ (A)	3	6
Operating voltage $U_s$ (V DC) (= 80 % of 24 V) <sup>2)</sup>	19.2	19.2
Trip current $I_{ab} = 1.25 \times I_{N}$ (A) (EPD24 trips after 3 s)	3.75	7.50
$R_{max}(\Omega) = (U_{B}/I_{ab}) - 0.050$	5.07	2.51

<sup>&</sup>lt;sup>2)</sup> Voltage drop of EPD24 and tolerance of trip point (typically  $1.1 \times I_N = 1.05 \dots 1.35 \times I_N$ ) have been taken into account

#### Selection table for the incoming cable lengths with different cable cross-sections

Cable cross section A (mm²)	0.14	0.25	0.34	0.5	0.75	1.00	1.50
Cable length L (m) (= single length)	cable resistance ( $\Omega$ ) = ( $\rho_0 \times 2 \times L$ ) / A <sup>3)</sup>						
5	1.27	0.71	0.52	0.36	0.24	0.18	0.12
10	2.54	1.42	1.05	0.71	0.47	0.36	0.24
15	3.81	2.14	1.57	1.07	0.71	0.53	0.36
20	5.09	2.85	2.09	1.42	0.95	0.71	0.47
25	6.36	3.56	2.62	1.78	1.19	0.89	0.59
30	7.63	4.27	3.14	2.14	1.42	1.07	0.71
35	8.90	4.98	3.66	2.49	1.66	1.25	0.83
40	10.17	5.70	4.19	2.85	1.90	1.42	0.95
45	11.44	6.41	4.71	3.20	2.14	1.60	1.07
50	12.71	7.12	5.24	3.56	2.37	1.78	1.19
75	19.07	10.68	7.85	5.34	3.56	2.67	1.78
100	25.34	14.24	10.47	7.12	4.75	3.56	2.37
125	31.79	17.80	13.09	8.90	5.93	4.45	2.97
150	38.14	21.36	15.71	10.68	7.12	5.34	3.56
175	44.50	24.92	18.32	12.46	8.31	6.23	4.15
200	50.86	28.48	20.94	14.24	9.49	7.12	4.75
225	57.21	32.04	23.56	16.02	10.68	8.01	5.34
250	63.57	35.60	26.18	17.80	11.87	8.90	5.93


 $<sup>^{3)}</sup>$  Resistivity of copper  $\rho_{o}$  = 0.0178 ( $\Omega$  x mm²)/m Example 1: max. length for 1.5 mm² and 3 A: 214 m Example 2: max. length for 1.5 mm² and 6 A: 106 m

Example 3: mixed wiring: (Control cabinet --- sensor/actuator level) R1 = 40 m for  $1.5 \text{ mm}^2$  and R2 = 5 m for  $0.25 \text{ mm}^2$ :

R1 = 0.95  $\Omega$ , R2 = 0.71  $\Omega$ , total (R1 + R2) = 1.66  $\Omega$ 

# Technical diagrams

#### Time/current characteristic curve




 $^{1)}$  Current limitation typically 1.8 x I $_{\rm N}$  at I $_{\rm N}$  = 0.5 A...6 A Current limitation typically 1.5 x I $_{\rm N}$  at I $_{\rm N}$  = 8 A or 10 A Current limitation typically 1.3 x I $_{\rm N}$  at I $_{\rm N}$  = 12 A

### Wiring diagram

EPD24-TB-101 without signal input with signal output F (Single signal, N/O)

Operating condition: 13-14 closed Fault condition: 13-14 open



\_

### **Electronic protection devices EPD24**

### Approvals, Safety instructions

#### Please note

The user must ensure that the cable cross sections of the relevant load circuit are suitable for the current rating of the EPD24 used. Automatic start-up of machinery after shut down must be prevented (Machinery Directive 2006/42/EU and IEC/EN 60204-1). In the event of a short circuit or overload the load circuit will be disconnected electronically by the EPD24.

#### Information on UL approvals/CSA approvals



UL1604 UL File # E 339238



CSA C22.2 No. 213 (Class I, Division 2) CSA File # 2305929

#### **Operating Temperature Code T5**

• This equipment is suitable for use in Class I, Division 2, Groups A, B, C and D or non-hazardous locations only **WARNING**:

- Exposure to some chemicals may degrade the sealing properties of materials used in the following device: relay Sealant Material:
  - Generic Name: Modified diglycidyl ether of bisphenol A
  - Supplier: Fine Polymers Corporation
  - Type: Epi Fine 4616L-160PK
- · Casing Material:
  - Generic Name: Liquid Crystal Polymer
  - Supplier: Sumitomo Chemical
  - Type: E4008, E4009, or E6008

#### **RECOMMENDATION:**

• Periodically inspect the device named above for any degradation of properties and replace if degradation is found

#### WARNING - EXPLOSION HAZARD:

- Do not disconnect equipment unless power has been removed or the area is known to be non-hazardous
- Substitution of any components may impair suitability for Class I, Division 2



UL2367

Non-hazardous use - UL File # E 339236



UL 508

Non-hazardous use - UL File # E 149922



CSA C22.2 No. 14

CSA C22.2 No. 142 - CSA File # E 2305929

#### Class 2

Meets requirement for Class 2 current limitation (EPD24 ... -0.5 A/1 A/2 A/3 A)

### **Electronic protection devices EPD24**

### Installation guidelines


The EPD24 features an integral power distribution system.


The following wiring modes are possible with various pluggable current and signal busbars:

- LINE+ (24 V DC)
- 0 V

Caution: The electronic devices EPD24 require a 0 V connection

· Auxiliary contacts







#### **Mounting procedure**

Before wiring insert busbars into protector block. A maximum of 10 connection cycles are permissible using connecting busbars.


#### Recommendation

After 10 units the busbars should be interrupted and receive a new entry live.

#### Table of length for busbars

(Order code 2CDE605100R0500)

No. of units	2	3	4	5	6	7	8	9	10
Length of busbar (mm) ± 0.5 mm	22	34.5	47	59.5	72	84.5	97	109.5	122



# Interface relays and optocouplers Table of contents

402	Offer overview
405	Applications
407	Pluggable interface relays
	and optocouplers
408	Selection tables
410	List of components
425	Benefits and advantages
426	Socket & terminal connection types
427	Relay components
429	Ordering details
450	Technical data
464	Technical diagrams
479	Boxed interface relays and
	optocouplers R600 range
480	Overview
482	Boxed interface relays R600 range
482	Selection table
484	Ordering details
486	Technical data
490	Technical diagrams
492	Boxed optocouplers R600 range
492	Selection table
493	Ordering details
495	Technical data
498	Technical diagrams

### Interface relays and optocouplers

### Offer overview

Relays are universally applicable and are utilized in a diverse array of applications. They are a significant element in contemporary industrial processes and are used in applications where galvanic isolation, signal separation, voltage coupling and signal amplification are required.

The ABB portfolio includes electromechanical relays and optocouplers. The electromechanical relays operate using an electromagnetic field whereas optocouplers use light. Optocouplers are predominantly used in applications where a high switching frequency is necessary. Furthermore, optocouplers do not contain any moving parts and are therefore bounce-free, immune to vibrations and possess a long electrical life.



#### **CR-S range**

#### The slim line of interface relays and optocouplers

The pluggable interface relays and optocouplers of the CR-S range are used for electrical isolation, amplification and signal matching between the electronic controlling, e.g. PLC, iPC or field bus systems and the sensor / actuator level. The CR-S range combines the flexibility of a modular system and the ability of switching high currents on a small footprint thus can be used in applications where space saving is essential. The CR-S range also includes complete versions consisting of a relay, socket and marker.



#### **CR-P** range

#### The pluggable pcb interface relays and optocouplers

The pluggable interface relays of the CR-P range are used for electrical isolation, amplification and signal matching between the electronic controlling, e.g. PLC, iPC or field bus systems and the sensor / actuator level. The CR-P range offers highest current switching in an IP67 rated relay housing. Furthermore, nine different coil voltages are available to suit world wide applications and even gold contact versions are available which is essential when it comes to switch sensitive signals. The CR-P range also includes complete versions consisting of a relay, socket, holder, marker and function module.

### Interface relays and optocouplers

### Offer overview



#### **CR-M** range

#### The pluggable miniature interface relays

The pluggable interface relays of the CR-M range are used for electrical isolation, amplification and signal matching between the electronic controlling, e.g. PLC, iPC or field bus systems and the sensor / actuator level. The CR-M range offers up to 4 contacts in one relay and a built in test button which makes a circuit check fast and easy. 12 different coil voltages are available to suit world wide applications and even gold contact versions are available which is essential when it comes to switch sensitive signals. The CR-M range also includes complete versions consisting of a relay, socket, holder, marker and where applicable a function module.



#### **CR-U** range

#### The pluggable universal interface relays

The pluggable interface relays of the CR-U range are used for electrical isolation, amplification and signal matching between the electronic controlling, e.g. PLC, iPC or field bus systems and the sensor / actuator level. The CR-U range offers up to 3 contacts in one relay and a built in test button which makes a circuit check fast and easy. 12 different coil voltages are available to suit world wide applications.



#### R600 range

#### Boxed interface relays and optocouplers

Boxed interface relays of the R600 range are used for electrical isolation, amplification and signal matching between the electronic controlling, e.g. PLC, iPC or field bus systems and the sensor / actuator level. The relay itself is built in thus the perfect solution because this design fulfills highest vibration requirements. The compact design and different connection terminal possibilities further optimize your panel installation.











### **Applications of interface relays**

### A proven technology used worldwide

Relays are universally applicable and are utilized in a diverse array of applications. They are a significant element in contemporary industrial processes and are used in applications where galvanic isolation, signal separation, voltage coupling and signal amplification are required.



#### Circuit multiplication

A single voltage signal may be used to simultaneously perform up to four different switching operations. Each output contact can be used to switch load circuits with different voltage and current levels.



#### Galvanic isolation

Interface relays are excellently suited to ensure safe galvanic isolation, i.e. separation between control circuit and load circuit.




#### Voltage conversion

Interface relays allow for small voltage signals to switch much larger loads. For example: a 24 V DC 10 mA signal can be used to switch a 230 V AC 16 A load.



of relays operate and interface between control circuits and electrical loads.






Table of contents

408	Selection tables
410	List of components
425	Benefits and advantages
426	Socket & terminal connection types
427	Relay components
429	Ordering details –
429	CR-S range
433	CR-P range
437	CR-M range
444	CR-P/M function modules
446	CR-U range
448	CR-U function modules
450	Technical data
450	CR-S interface relays
451	CR-S optocouplers
452	CR-S sockets
453	CR-S jumper bars
454	CR-P, CR-M, CR-U
458	CR-P optocouplers
459	CR-P and CR-M sockets
460	CR-P and CR-M jumper bars
461	CR-P and CR-M function modules
462	CR-U sockets and function modules
462	CR-U function modules
	Tochnical diagrams

### Pluggable interface relays

### Selection table CR-S range



#### How to use the selection table

Choose the desired control supply voltage from the column "Control voltage", e.g. "5 V DC". Choose the desired kind of connection terminal from the column "Connection terminal", e.g. "spring". Choose the desired material of contact from the column "Contact Material" e.g. "gold plated".

Control voltage	Connection terminal	Contact material	Socket type	Socket order code	Relay type	Relay order code
5 V DC	screw	standard	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1RG	1SVR405501R1020
	spring	standard	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1RG	1SVR405501R1020
12 V AC	screw	standard	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1RG	1SVR405501R2020
	spring	standard	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1RG	1SVR405501R2020



#### Example

When you have chosen 5 V DC as control supply voltage, spring connection as connection terminal and gold plated as contact material the following order codes and type designators are valid:

Socket: CR-S006/024VDC1SZ, 1SVR405521R1200 Relay: CR-S005VDC1RG, 1SVR405501R1020

CR-S range relay assemblies

Control voltage	Connection terminal	Contact material	Socket type	Socket order code	Relay type	Relay order code
5 V DC	screw	standard	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1RG	1SVR405501R1020
	spring	standard	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1RG	1SVR405501R1020
12 V DC	screw	standard	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S012VDC1RG	1SVR405501R2020
	spring	standard	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S012VDC1RG	1SVR405501R2020
12 V AC	screw	standard	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1RG	1SVR405501R2020
	spring	standard	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1RG	1SVR405501R2020
24 V DC	screw	standard	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S024VDC1RG	1SVR405501R3020
	spring	standard	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S024VDC1RG	1SVR405501R3020
24 V AC	screw	standard	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1RG	1SVR405501R3020
	spring	standard	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1RG	1SVR405501R3020
48 V AC/DC	screw	standard	CR-S048/060VADC1SS	1SVR405521R5100	CR-S048VDC1R	1SVR405501R4010
		gold plated	CR-S048/060VADC1SS	1SVR405521R5100	CR-S048VDC1RG	1SVR405501R4020
	spring	standard	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S048VDC1R	1SVR405501R4010
		gold plated	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S048VDC1RG	1SVR405501R4020
60 V AC/DC	screw	standard	CR-S048/060VADC1SS	1SVR405521R5100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S048/060VADC1SS	1SVR405521R5100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S060VDC1RG	1SVR405501R5020
110-125 V AC/DC	screw	standard	CR-S110/125VADC1SS	1SVR405521R6100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S110/125VADC1SS	1SVR405521R6100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S110/125VADC1SZ	1SVR405521R6200	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S110/125VADC1SZ	1SVR405521R6200	CR-S060VDC1RG	1SVR405501R5020
220-240 V AC/DC	screw	standard	CR-S220/240VADC1SS	1SVR405521R7100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S220/240VADC1SS	1SVR405521R7100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S220/240VADC1SZ	1SVR405521R7200	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S220/240VADC1SZ	1SVR405521R7200	CR-S060VDC1RG	1SVR405501R5020

#### CR-S optocoupler range relay assemblies

Control voltage	Connection terminal	Output characteristics	Socket type	Socket order code	Opto type	Opto order code
24 V DC	screw	Transistor	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1TRA	1SVR405510R3050
	spring	100 mA - 48 V DC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1TRA	1SVR405510R3050
	screw	MOS-FET	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1MOS	1SVR405510R3060
	spring	2 A - 24 V DC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1MOS	1SVR405510R3060
	screw	Triac	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1TRI	1SVR405510R3070
	spring	2 A - 240 V AC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1TRI	1SVR405510R3070

### **List of components**

### Selection table CR-S range complete versions

۱	4	The complete versions of the CR-S range comprise of a pluggable interface relay
	i	The complete versions of the CR-S range comprise of a pluggable interface relay socket and marker.

_															
CR-S complete version	s														
			Re	lay				So	cke	t					
		Order code	1SVR405501R2010	1SVR405501R3010	1SVR405501R3020	1SVR405501R5010	1SVR405501R5020	1SVR405521R1100	1SVR405521R1200	1SVR405521R3100	1SVR405521R3200	1SVR405521R6100	1SVR405521R6200	1SVR405521R7100	1SVR405521R7200
Complete versions		Туре	CR-S012VDC1R	CR-S024VDC1R	CR-S024VDC1RG	CR-S060VDC1R	CR-S060VDC1RG	CR-S006/024VADC1SS	CR-S006/024VADC1SZ	CR-S012/024VADC1SS	CR-S012/024VADC1SZ	CR-S110/125VADC1SS	CR-S110/125VADC1SZ	CR-S220/240VADC1SS	CR-S220/240VADC1SZ
Order code	Туре														
1SVR405541R2110	CR-S012VADC1CRS		•												
1SVR405541R2210	CR-S012VADC1CRZ							-							
1SVR405541R3110	CR-S024VADC1CRS														
1SVR405541R3120	CR-S024VADC1CRGS														
1SVR405541R3210	CR-S024VADC1CRZ														
1SVR405541R3220	CR-S024VADC1CRGZ														
1SVR405541R6110	CR-S110VADC1CRS											-			
1SVR405541R6120	CR-S110VADC1CRGS						•								
1SVR405541R6210	CR-S110VADC1CRZ												-		
1SVR405541R6220	CR-S110VADC1CRGZ						•						-		
1SVR405541R7110	CR-S230VADC1CRS													•	
1SVR405541R7120	CR-S230VADC1CRGS						•							-	
1SVR405541R7210	CR-S230VADC1CRZ					•									•
1SVR405541R7220	CR-S230VADC1CRGZ						•								•

— CR-P pluggable relays	and	op	toc	oup	ler	s	ı	J	ı						ı				ı		ı		ı	ı		
	Order code	1SVR405600R4000	1SVR405600R1000	1SVR405600R6000	1SVR405600R8000	1SVR405600R0000	1SVR405600R5000	1SVR405600R7000	1SVR405600R2000	1SVR405600R3000	1SVR405601R4000	1SVR405601R1000	1SVR405601R6000	1SVR405601R8000	1SVR405601R0200	1SVR405601R0000	1SVR405601R5000	1SVR405601R7000	1SVR405601R2000	1SVR405601R3000	1SVR405606R1000	1SVR405606R0000	1SVR405606R7000	1SVR405606R3000	1SVR405610R4060	1SVR405610R4070
	Туре	CR-P012DC1	CR-P024DC1	CR-P048DC1	CR-P110DC1	CR-P024AC1	CR-P048AC1	CR-P110AC1	CR-P120AC1	CR-P230AC1	CR-P012DC2	CR-P024DC2	CR-P048DC2	CR-P110DC2	CR-P012AC2	CR-P024AC2	CR-P048AC2	CR-P110AC2	CR-P120AC2	CR-P230AC2	CR-P024DC2G	CR-P024AC2G	CR-P110AC2G	CR-P230AC2G	CR-P024MOS1	CR-P024TRI1
Control voltage		_																								
12 V DC																										
24 V DC		İ	-									•														
48 V DC		ĺ																								
110 V DC														-												
12 V AC															-											
24 V AC																										
48 V AC							•																			
110 V AC																							•			
120 V AC									•										•							
230 V AC																										
Output rating																										
35 V DC 5 A																										
250 V AC 16 A		•	•	•		•	•	•	•	•																
250 V AC 8 A														•	•				•				•	•		
275 V AC 3 A																										
Output contacts																										
c/o		1	1	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2		
Gold plated contacts																					•		•	•		
MOS-FET																									•	
TRIAC 3 A																										•

Free-wheeling diode

— CR-P range complete v	/ersi	ions	5																									
	Order code	1SVR405600R4010	1SVR405600R1010	1SVR405600R1011	1SVR405600R1013	1SVR405600R8010	1SVR405600R0010	1SVR405600R2010	1SVR405600R3110	1SVR405600R3011	1SVR405600R3010	1SVR405601R4010	1SVR405601R1010	1SVR405601R1013	1SVR405601R1011	1SVR405601R1012	1SVR405606R1010	1SVR405606R1013	1SVR405606R1011	1SVR405601R8010	1SVR405601R0010	1SVR405601R2010	1SVR405601R3110	1SVR405601R3011	1SVR405601R3012	1SVR405606R3013	1SVR405606R3012	1SVR405606R3010
	Туре	CR-P012DC1SS42V	CR-P024DC1SS42V	CR-P024DC1LC42V	CR-P024DC1LC62C	CR-P110DC1SS42CV	CR-P024AC1SS62CV	CR-P120AC1SS92CV	CR-P230AC1SS92CV	CR-P230AC1LS	CR-P230AC1LC92CV	CR-P012DC2SS42V	CR-P024DC2SS42V	CR-P024DC2LS42	CR-P024DC2LS42V	CR-P024DC2LC42	CR-P024DC2GLC42V	CR-P024DC2GLC62C	CR-P024DC2GLC62CV	CR-P110DC2SS42CV	CR-P024AC2SS62CV	CR-P120AC2SS92CV	CR-P230AC2SS92CV	CR-P230AC2LS92CV	CR-P230AC2LC92	CR-P230AC2GLC92	CR-P230AC2GLC92C	CR-P230AC2GLC92CV
Control voltage		_																						-		_		_
12 V DC																												
24 V DC			•	•									•	•	•			•	•									
48 V DC																												
110 V DC																				•								
12 V AC																												
24 V AC		ĺ																										
48 V AC		ĺ																										
110 V AC		ĺ																										
120 V AC								•														-						
230 V AC		ĺ							-														-					
Output rating																												
250 V AC 16 A																												
250 V AC 8 A														-	-	•		-	•	•		-	•			•	-	-
Output contacts																												
c/o		1	1	1	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Gold plated contacts		ĺ															•	•	•								-	•
Socket type		_																										
Standard socket			•					•	•				•							•	•	•	•					
Logical socket				•						•	•			•	•			•	•					•	•		-	•
Additional features		_																										
LED			•	_				_	-		•		•	•	-	_	_	_	_	_	_	_	_	_	_			_

### **List of components**

### Selection table CR-P range complete versions

١	4	The complete versions of the CR-P range comprise of a pluggable interface relay
	Î	socket, holder, marker and a function module.

— CR-P complete version	ns																					
			Re	ay							Sc	cke	t	Fu	nct	ion	mc	du	e			Holde
	Order	and code	1SVR405601R4000	1SVR405601R1000	1SVR405606R1000	1SVR405601R8000	1SVR405601R0000	1SVR405601R2000	1SVR405601R3000	1SVR405606R3000	1SVR405650R1000	1SVR405650R0000	1SVR405650R0200	1SVR405652R0000	1SVR405652R1000	1SVR405652R9100	1SVR405655R0000	1SVR405655R1000	1SVR405654R0100	1SVR405655R0100	1SVR405655R1100	1SVR405659R0000
Complete versions	Trope	adkı	CR-P012DC2	CR-P024DC2	CR-P024DC2G	CR-P110DC2	CR-P024AC2	CR-P120AC2	CR-P230AC2	CR-P230AC2G	CR-PSS	CR-PLS	CR-PLC	CR-P/M 42	CR-P/M 42V	CR-P/M 42CV	CR-P/M 62C	CR-P/M 62CV	CR-P/M 92	CR-P/M 92C	CR-P/M 92CV	CR-PH
Order code	Туре																					
1SVR405601R4010	CR-P012DC2SS42V	ļ	=								•				•							•
1SVR405601R1010	CR-P024DC2SS42V	ļ													•							•
1SVR405601R1013	CR-P024DC2LS42											•		-								•
1SVR405601R1011	CR-P024DC2LS42V	ļ										-			•							•
1SVR405601R1012	CR-P024DC2LC42	ļ											-	•								•
1SVR405606R1010	CR-P024DC2GLC42V	ļ			•								-		-							•
1SVR405606R1013	CR-P024DC2GLC62C				•								-				•					•
1SVR405606R1011	CR-P024DC2GLC62CV	ļ			-								-					•				•
1SVR405601R8010	CR-P110DC2SS42CV	ļ				-					•					•						
1SVR405601R0010	CR-P024AC2SS62CV						•				•							•				
1SVR405601R2010	CR-P120AC2SS92CV							•			•											
1SVR405601R3110	CR-P230AC2SS92CV								•													
1SVR405601R3011	CR-P230AC2LS92CV								•			-										
1SVR405601R3012	CR-P230AC2LC92	ĺ							•				•									
1SVR405606R3013	CR-P230AC2GLC92	ĺ											•									•
1SVR405606R3012	CR-P230AC2GLC92C	Ì											•							•		•
1SVR405606R3010	CR-P230AC2GLC92CV	Ť																				

### Selection table CR-M range

	Order code	1SVR405611R4000	1SVR405611R1000	1SVR405611R6000	1SVR405611R4200	1SVR405611R8000	1SVR405611R8200	1SVR405611R9000	1SVR405611R0000	1SVR405611R5000	1SVR405611R7000	1SVR405611R2000	1SVR405611R3000	1SVR405612R4000	1SVR405612R1000	1SVR405612R6000	1SVR405612R4200	1SVR405612R8000	1SVR405612R8200	1SVR405612R9000	1SVR405612R0000	1SVR405612R5000	1SVR405612R5200	1SVR405612R7000	1SVR405612R2000	1SVR405612R3000	1SVR405613R4000	1SVR405613R1000	1SVR405613R6000	1SVR405613R4200	1SVR405613R8000	1SVR405613R8200	1SVR405613R9000	1SVR405613R0000	1SVR405613R5000	1SVR405613R7000	1SVR405613R2000
	Туре	CR-M012DC2	CR-M024DC2	CR-M048DC2	CR-M060DC2	CR-M110DC2	CR-M125DC2	CR-M220DC2	CR-M024AC2	CR-M048AC2	CR-M110AC2	CR-M120AC2	CR-M230AC2	CR-M012DC3	CR-M024DC3	CR-M048DC3	CR-M060DC3	CR-M110DC3	CR-M125DC3	CR-M220DC3	CR-M024AC3	CR-M048AC3	CR-M060AC3	CR-M110AC3	CR-M120AC3	CR-M230AC3	CR-M012DC4	CR-M024DC4	CR-M048DC4	CR-M060DC4	CR-M110DC4	CR-M125DC4	CR-M220DC4	CR-M024AC4	CR-M048AC4	CR-M110AC4	CR-M120AC4
Control voltage																																					_
12 V DC																																$\neg$					$\neg$
24 V DC			•																									•					П				
48 V DC																•																					
60 V DC					•												•																				
110 V DC						•												•													•		П				
125 V DC							•																														
220 V DC																																					
24 V AC																					•													•			
48 V AC										_												•											П		•		
60 V AC																							•														
110 V AC																																					
120 V AC												•													•												•
230 V AC																										•											
Output rating																																_	_	_			_
250 V AC 6 A																												•									•
250 V AC 10 A																•		•			•		•		•	•						$\neg$	П		$\Box$		
250 V AC 12 A			•	•	•		•	•		•			•							$\top$									П				П	$\Box$	П	П	
Output contacts		_	_	_			_			_	_	_	_		_					_											_	_	_	_	_	_	_
c/o		2	2	2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3	3	4	4	4	4	4	4	4	4	4	4	4
Gold plated contacts																																					
Additional features															-																	_	_		_	_	_
LED																																$\neg$					_
Free-wheeling diode																			$\dashv$	$\dashv$	$\dashv$	-											Н		$\Box$		_

— CR-M pluggable relays	wit	h LI	ΕD																	
	Order code	1SVR405611R4100	1SVR405611R4400	1SVR405611R1100	1SVR405611R1400	1SVR405611R6100	1SVR405611R6400	1SVR405611R4300	1SVR405611R8100	1SVR405611R8400	1SVR405611R8300	1SVR405611R8500	1SVR405611R9100	1SVR405611R9400	1SVR405611R0300	1SVR405611R0300	1SVR405611R5100	1SVR405611R7100	1SVR405611R2100	1SVR405611R3100
	Туре	CR-M012DC2L	CR-M012DC2LD	CR-M024DC2L	CR-M024DC2LD	CR-M048DC2L	CR-M048DC2LD	CR-M060DC2L	CR-M110DC2L	CR-M110DC2LD	CR-M125DC2L	CR-M125DC2LD	CR-M220DC2L	CR-M220DC2LD	CR-M012AC2L	CR-M024AC2L	CR-M048AC2L	CR-M110AC2L	CR-M120AC2L	CR-M230AC2L
Control voltage																				
12 V DC																				
24 V DC																				
48 V DC																				
60 V DC																				
110 V DC																				
125 V DC																				
220 V DC																				
12 V AC																				
24 V AC		ĺ																		
48 V AC																				
60 V AC		ĺ																		
110 V AC		ĺ																•		
120 V AC		İ																		
230 V AC		İ																		
Output rating																				
250 V AC 6 A																				
250 V AC 10 A																				
250 V AC 12 A					•			-				•	•					•		•
Output contacts																				
c/o		2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Gold plated contacts																				
Additional features						_	_	_									_	_		
LED								•										•		
Free-wheeling diode		İ			-		-					-								

Free-wheeling diode

_																					
CR-M pluggable relays	wit	h LE	D																		
	Order code	1SVR405612R4100	1SVR405612R4400	1SVR405612R1100	1SVR405612R1400	1SVR405612R6100	1SVR405612R6400	1SVR405612R4300	1SVR405612R8100	1SVR405612R8400	1SVR405612R8300	1SVR405612R8500	1SVR405612R9100	1SVR405612R9400	1SVR405612R0300	1SVR405612R0100	1SVR405612R5100	1SVR405612R7100	1SVR405612R2100	1SVR405612R3100	
	Туре	CR-M012DC3L	CR-M012DC3LD	CR-M024DC3L	CR-M024DC3LD	CR-M048DC3L	CR-M048DC3LD	CR-M060DC3L	CR-M110DC3L	CR-M110DC3LD	CR-M125DC3L	CR-M125DC3LD	CR-M220DC3L	CR-M220DC3LD	CR-M012AC3L	CR-M024AC3L	CR-M048AC3L	CR-M110AC3L	CR-M120AC3L	CR-M230AC3L	
Control voltage																					
12 V DC																					
24 V DC					-																
48 V DC																					
60 V DC								-													
110 V DC																					
125 V DC											•	-									
220 V DC																					
12 V AC															-						
24 V AC																					
48 V AC																	-				
60 V AC																					
110 V AC																		•			
120 V AC																					
230 V AC																					
Output rating																					
250 V AC 6 A																					
250 V AC 10 A																					
250 V AC 12 A																					
Output contacts																					
c/o		3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	
Gold plated contacts																					
Additional features																					
LED																					

_																				
CR-M pluggable relays	wit	h Li	ED																	
	Order code	1SVR405613R4100	1SVR405613R4400	1SVR405613R1100	1SVR405614R1100	1SVR405613R6100	1SVR405613R6400	1SVR405613R4300	1SVR405613R8100	1SVR405613R8400	1SVR405613R8300	1SVR405613R8500	1SVR405613R9100	1SVR405613R9400	1SVR405613R0300	1SVR405613R0100	1SVR405613R5100	1SVR405613R7100	1SVR405613R2100	1SVR405613R3100
	Туре	CR-M012DC4L	CR-M012DC4LD	CR-M024DC4L	CR-M024DC4LD	CR-M048DC4L	CR-M048DC4LD	CR-M060DC4L	CR-M110DC4L	CR-M110DC4LD	CR-M125DC4L	CR-M125DC4LD	CR-M220DC4L	CR-M220DC4LD	CR-M012AC4L	CR-M024AC4L	CR-M048AC4L	CR-M110AC4L	CR-M120AC4L	CR-M230AC4L
Control voltage																				
12 V DC																				
24 V DC																				
48 V DC																				
60 V DC																				
110 V DC																				
125 V DC																				
220 V DC																				
12 V AC																				
24 V AC																				
48 V AC																	•			
60 V AC																				
110 V AC																				
120 V AC																				
230 V AC																				
Output rating																				
250 V AC 6 A					-							•								
250 V AC 10 A																				
250 V AC 12 A																				
Output contacts																				
c/o		4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Gold plated contacts																				
Additional features																				
LED																				
Free-wheeling diode			-		•															

CR-M pluggable relays wit	h G	old	Pla	ted	Со	nta	cts												
Order code	1SVR405618R1000	1SVR405618R0000	1SVR405618R7000	1SVR405618R3000	1SVR405618R3000	1SVR405618R4100	1SVR405618R1100	1SVR405618R6100	1SVR405618R4300	1SVR405618R8100	1SVR405618R8300	1SVR405618R9100	1SVR405618R0100	1SVR405618R5100	1SVR405618R7100	1SVR405618R2100	1SVR405618R3100	1SVR405618R4400	1SVR405618R1400
Туре	CR-M024DC4G	CR-M024AC4G	CR-M110AC4G	CR-M230AC4G	CR-M230AC4G	CR-M012DC4LG	CR-M024DC4LG	CR-M048DC4LG	CR-M060DC4LG	CR-M110DC4LG	CR-M125DC4LG	CR-M220DC4LG	CR-M024AC4LG	CR-M048AC4LG	CR-M110AC4LG	CR-M120AC4LG	CR-M230AC4LG	CR-M012DC4LDG	CR-M024DC4LDG
Control voltage																			
12 V DC																			
24 V DC							•												
48 V DC																			

12 V DC															
24 V DC						•									•
48 V DC															
60 V DC															
110 V DC								-							
125 V DC															
220 V DC															
24 V AC		•													
48 V AC											-				
60 V AC															
110 V AC															
120 V AC															
230 V AC				•										•	
Output rating	•														
250 V AC 6 A		•	•	•		•	•		•			•	•		•

Output rating																			
250 V AC 6 A			•						■		•	•			-	•			•
250 V AC 10 A																			
250 V AC 12 A																			
Output contacts																			
c/o	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Gold plated contacts						•					•			•	-	•			
Additional features																			
LED																			
Free-wheeling diode																			•

### Pluggable interface relays and optocouplers Selection table CR-M range complete versions

— CR-M range complete	vers	sior	ıs													
	Order code	1SVR405618R4410	1SVR405613R1010	1SVR405613R1011	1SVR405613R1012	1SVR405618R1011	1SVR405618R1010	1SVR405618R1110	1SVR405618R1410	1SVR405613R0010	1SVR405613R3110	1SVR405613R3011	1SVR405613R3012	1SVR405618R3112	1SVR405618R3110	1SVR405618R3111
	Type	CR-M012DC4LDGSS	CR-M024DC4SS42V	CR-M024DC4LS42V	CR-M024DC4LC42	CR-M024DC4GSS42V	CR-M024DC4GLC62CV	CR-M024DC4LGLC22	CR-M024DC4LDGSS	CR-M024AC4LS62CV	CR-M230AC4SS92CV	CR-M230AC4LS92CV	CR-M230AC4LC92	CR-M230AC4GSS92CV	CR-M230AC4LGLC	CR-M230AC4LGSS
Control voltage		_														
12 V DC		•														
24 V DC			-	-	•	•	•	•	•							
48 V DC																
60 V DC																
110 V DC																
125 V DC																
220 V DC																
24 V AC										•						
48 V AC																
60 V AC																
110 V AC																
120 V AC		_														
230 V AC																
Output rating		_					_				_					
250 V AC 6 A			-	-	-	-	-	•	•	-	-	-	•	-	-	•
250 V AC 10 A		L														
250 V AC 12 A																
Output contacts													_			
c/o		4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Gold plated contacts								•	•							•
Socket type		_					_				_					
Standard socket			•			•			•		•			•		•
Logical socket		L		-	•		•			•		-	•		-	
Additional features																
LED		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Free-wheeling diode		•	-	-	•	•		•	•					-		•
			_	_	_	_	_	_	_	_	_	_		_	_	_

### **List of components**

CR-M230AC4LGSS

1SVR405618R3111

### Selection table CR-M range complete versions

١	Α.	The complete versions of the CR-M range comprise of a pluggable interface relay
	ÎΙ	The complete versions of the CR-M range comprise of a pluggable interface relay socket, holder, marker and where applicable a function module.

		R	elay								So	cke	t	Fu	nct	ion	mo	du	le		Hold
	Order code	15VR405618R4400	1SVR405613R1000	1SVR405618R1000	1SVR405618R1100	1SVR405618R1400	1SVR405613R0000	1SVR405613R3000	1SVR405618R3000	1SVR405618R3100	1SVR405651R3000	1SVR405651R3100	1SVR405651R3200	1SVR405651R0000	1SVR405652R0000	1SVR405652R1000	1SVR405652R9100	1SVR405655R1000	1SVR405654R0100	1SVR405655R1100	1SVR405659R1000
Complete versions	Туре	CR-M012DC4LDG	CR-M024DC4	CR-M024DC4G	CR-M024DC4LG	CR-M024DC4LDG	CR-M024AC4	CR-M230AC4	CR-M230AC4G	CR-M230AC4LG	CR-M4SS	CR-M4LS	CR-M4LC	CR-P/M 22	CR-P/M 42	CR-P/M 42V	CR-P/M 42CV	CR-P/M 62CV	CR-P/M 92	CR-P/M 92CV	CR-MH
Order code	Туре	Ļ																			L.
1SVR405618R4410	CR-M012DC4LDGSS	ļ	•								•			L							•
1SVR405613R1010	CR-M024DC4SS42V	L	-								▮			L		•					•
1SVR405613R1011	CR-M024DC4LS42V	L	-								<u> </u>	-				-					•
1SVR405613R1012	CR-M024DC4LC42																				
1SVR405618R1011	CR-M024DC4GSS42V																				
1SVR405618R1010	CR-M024DC4GLC62CV																				
1SVR405618R1110	CR-M024DC4LGLC22	Π																			•
1SVR405618R1410	CR-M024DC4LDGSS	Ĺ																			
1SVR405613R0010	CR-M024AC4LS62CV	Ĺ										•						-			
16//040561202110	CR-M230AC4SS92CV	Ì									•									•	
15VR405613R3110		-				İ						•								_	i 🕳
	CR-M230AC4LS92CV	ı						_			ı	-									_
1SVR405613R3110 1SVR405613R3011 1SVR405613R3012	CR-M230AC4LS92CV CR-M230AC4LC92	-						-				-	•							_	
1SVR405613R3011								-	•		•		•						•		<del>!</del> ─

<del>\_\_\_\_</del>

### Pluggable interface relays and optocouplers

### Selection table CR-P/M function modules

— CR-P/M function modules																									
-	15VR405651R0000	1SVR405652R0000	1SVR405652R1000	1SVR405652R4000	1SVR405652R4100	1SVR405652R9000	1SVR405652R9100	1SVR405653R0000	1SVR405653R4000	1SVR405653R1000	1SVR405654R0000	1SVR405654R1000	1SVR405654R4000	1SVR405654R4100	1SVR405654R0100	1SVR405654R1100	1SVR405655R0000	1SVR405655R1000	1SVR405655R4000	1SVR405655R4100	1SVR405655R0100	1SVR405655R1100	1SVR405656R0000	1SVR405656R1000	1SVR405656R2000
	Iype CR-P/M 22	CR-P/M 42	CR-P/M 42V	CR-P/M 42B	CR-P/M 42BV	CR-P/M 42C	CR-P/M 42CV	CR-P/M 52B	CR-P/M 52D	CR-P/M 52C	CR-P/M 62	CR-P/M 62V	CR-P/M 62E	CR-P/M 62EV	CR-P/M 92	CR-P/M 92V	CR-P/M 62C	CR-P/M 62CV	CR-P/M 62D	CR-P/M 62DV	CR-P/M 92C	CR-P/M 92CV	CR-P/M 72	CR-P/M 72A	CR-P/M 82
Control voltage							,					_	_						_					_	_
6-220 V DC	_ ■	1																							_
6-24 V DC		-									-	•					•	-							_
24-60 V DC				-															•						
110 V DC																									
110-230 V DC																					•				
6-24 V AC																									
24-60 V AC																				•					
110-230 V AC	Ť									-					•	•					•				
24 V AC	İ																						-		_
115 V AC	İ																								_
230 V AC	İ																								•
24-240 V AC/DC	十																								_
Function											_		_	_								_	_	_	_
Diode - Reverse polarity protection / free-wheeling diode		1																							Т
Diode and LED - Reverse polarity protection / free-wheeling diode and LED to indicate energized coil		•		•	•		-																		_
RC element - Spark quenching	Ì							•	-	•															
Diode and LED - LED to indicate energized coil	Ť										•	•	•	•		•									_
Varistor and LED - Overvoltage protection and LED to indicate energized coil																	•	•	•	•	•	•			
Varistor - Overvoltage protection	İ																							•	
LED red	İ		1	-									•		•		•		•		•				_
LED green	Ť											•				•				•					_

— CR-U pluggable relays	wit	hou	ıt LI	ED																			
	Order code	1SVR405621R4000	1SVR405621R1000	1SVR405621R6000	1SVR405621R8000	1SVR405621R9000	1SVR405621R0000	1SVR405621R5000	1SVR405621R7000	1SVR405621R2000	1SVR405621R3000	1SVR405622R4000	1SVR405622R1000	1SVR405622R6000	1SVR405622R8000	1SVR405622R8200	1SVR405622R9000	1SVR405622R0000	1SVR405622R5000	1SVR405622R5200	1SVR405622R7000	1SVR405622R2000	1SVR405622R3000
	Туре	CR-U012DC2	CR-U024DC2	CR-U048DC2	CR-U110DC2	CR-U220DC2	CR-U024AC2	CR-U048AC2	CR-U110AC2	CR-U120AC2	CR-U230AC2	CR-U012DC3	CR-U024DC3	CR-U048DC3	CR-U110DC3	CR-U125DC3	CR-U220DC3	CR-U024AC3	CR-U048AC3	CR-U060AC3	CR-U110AC3	CR-U120AC3	CR-U230AC3
Control voltage																							
12 V DC		▮										•											
24 V DC			•										-										
48 V DC				•										-									
110 V DC					•										•								
125 V DC																-							
220 V DC						-											•						
12 V AC																							
24 V AC							•											•					
48 V AC								•											•				
60 V AC																				•			
110 V AC									•												•		
120 V AC										•												-	
230 V AC																							_
Output rating				_	_			_	_			_				_	_						_
250 V AC 10 A																							•
Output contacts		_																					_
c/o		2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3
Gold plated contacts		1																					

— CR-U pluggable relays	with	ı LE	D																												_
	Order code	1SVR405621R4100	1SVR405621R4400	1SVR405621R1100	1SVR405621R1400	1SVR405621R6100	1SVR405621R6400	1SVR405621R8100	1SVR405621R8400	1SVR405621R9100	1SVR405621R0300	1SVR405621R0100	1SVR405621R5100	1SVR405621R7100	1SVR405621R2100	1SVR405621R3100	1SVR405622R4100	1SVR405622R4400	1SVR405622R1100	1SVR405623R1100	1SVR405622R6100	1SVR405622R6400	1SVR405622R8100	1SVR405622R8400	1SVR405622R9100	1SVR405622R0300	1SVR405622R0100	1SVR405622R5100	1SVR405622R7100	1SVR405622R2100	16/10/10/10/10/10/10/10/10/10/10/10/10/10/
	Туре	CR-U012DC2L	CR-U012DC2LD	CR-U024DC2L	CR-U024DC2LD	CR-U048DC2L	CR-U048DC2LD	CR-U110DC2L	CR-U110DC2LD	CR-U220DC2L	CR-U012AC2L	CR-U024AC2L	CR-U048AC2L	CR-U110AC2L	CR-U120AC2L	CR-U230AC2L	CR-U012DC3L	CR-U012DC3LD	CR-U024DC3L	CR-U024DC3LD	CR-U048DC3L	CR-U048DC3LD	CR-U110DC3L	CR-U110DC3LD	CR-U220DC3L	CR-U012AC3L	CR-U024AC3L	CR-U048AC3L	CR-U110AC3L	CR-U120AC3L	CB-112304C31
Control voltage																															_
12 V DC		•	=														•	•													
24 V DC				•	•															•											L
48 V DC						•	•														•	•									
110 V DC								•	•														•								L
125 V DC																								•							L
220 V DC										•															•						L
12 V AC											•															•					
24 V AC												-															•				
48 V AC													-															-			L
60 V AC																															L
110 V AC														-															-		L
120 V AC															-															•	L
230 V AC																															ı
Output rating																															
250 V AC 10 A				-				•			•			-				-						•	•				-		
Output contacts					_			_			_											_		_	_					_	_
c/o		2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Gold plated contacts																															L
Additional features																															_
LED		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	ı
Free-wheeling diode		L																													

### Selection table CR-U function modules

CR-U function modules								_				_									_					_
	Order code 15VR405661R0000	1SVR405661R0000	1SVR405662R0000	1SVR405662R1000	1SVR405662R4000	1SVR405662R4100	1SVR405662R9000	1SVR405662R9100	1SVR405663R0000	1SVR405663R4000	1SVR405663R1000	1SVR405664R0000	1SVR405664R1000	1SVR405664R4000	1SVR405664R4100	1SVR405664R0100	1SVR405664R1100	1SVR405665R0000	1SVR405665R1000	1SVR405665R4000	1SVR405665R4100	1SVR405665R0100	1SVR405665R1100	1SVR405666R0000	1SVR405666R1000	1SVR405666R2000
	Туре	CR-U21	CR-U 41	CR-U 41V	CR-U 41B	CR-U 41BV	CR-U 41C	CR-U 41CV	CR-U 51B	CR-U 51D	CR-U 51C	CR-U 61	CR-U 61V	CR-U 61E	CR-U 61EV	CR-U 91	CR-U 91V	CR-U 61C	CR-U 61CV	CR-U 61D	CR-U 61DV	CR-U91C	CR-U91CV	CR-U 71	CR-U 71A	CR-U81
Control voltage			_					_				_	_		_	_	_				_					
6-220 V DC																										_
6-24 V DC									-			▝	-					-	•		_				_	_
24-60 V DC					-	•	_			-				-	•					•	-					+
110 V DC							•	▝																		_
110-230 V DC											-												_			_
6-24 V AC									-			•							_		_					_
24-60 V AC										•				-	•					•	•					_
110-230 V AC																	-						•			_
24 V AC																									_	_
115 V AC																									-	4
230 V AC																										-
24-240 V AC/DC																										
Function		_	_	_				_				_			_	_										_
Diode - Reverse polarity protection / free wheeling diode		•																								_
Diode and LED - Reverse polarity protection / free-wheeling diode and LED to indicate energized coil			•	•	-	•	•	•																		
RC element - Spark quenching									•		•															
Diode and LED - LED to indicate energized coil															-											
Varistor and LED - Overvoltage protection and LED to indicate energized coil																			•		-		•			
Varistor - Overvoltage protection																								-		
Multi-function time module																										
LED red			-		•		•					•		•				•		-		-				
LED green		İ																					•			

### Benefits and advantages



ABB's interface relays and optocouplers ensure a reliable voltage conversion between process peripherals and higher level control systems. These relays ensure reliable signal switching and provide electrical isolation for sensitive electronics such as PLCs. The wide variety of pluggable interface relays with accompanied by standard or logic sockets may be used for switching AC or DC loads. Suitable for extreme environments, ABB's interface relays are offered across a wide spectrum of coil voltages, with a variety of optional function modules.



The interface relay portfolio incorporates a large assortment of relays. It includes both electro-mechanical relays and optocouplers. Optocouplers allow for continuous operation without any mechanical wear-and -tear.



The interface relay includes both pluggable and non-pluggable relays. The plugggable relays allow for the easy and seamless exchange of relay modules.



The ABB interface relays and optocouplers are approved for a large variety of applications, comply to the highest global approvals and are available world-wide.

### Socket and terminal connection types

#### Standard sockets



01 Standard socket CR-P



02 Standard socket CR-M

#### Position of connection terminals:

Coil connection (A1-A2) on lower side of the socket, contact connections (n/o and n/c contacts) on the lower and upper side of the socket.

#### Logical sockets



03 Logical socket CR-P




04 Logical socket CR-M


#### Position of connection terminals:

Coil connection (A1-A2) on lower side of the socket, all contact connections (common contacts, n/o and n/c contacts) on the upper side of the socket.


#### **Terminal connection types**



05 Screw type



06 Spring type




07 Fork type


A variety of sockets are available for interface relays and optocouplers to meet the needs of different applications such as vibration- intensive environments.

### Pluggable interface relays and optocouplers Relay components

#### **CR-S** range




#### **CR-P** range




### Relay components

**CR-M** range



#### **CR-U** range



Ordering details - CR-S range



The slim pluggable interface relays and optocouplers of the CR-S range may be used for electrical isolation, amplification and signal matching. The CR-S relays are 6.2 mm wide and therefore allow for the switching high currents on a small footprint.

### Ordering details - CR-S range pluggable interface relays

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
5 V DC	1 c/o	250 V AC, 6 A	CR-S005VDC1R	1SVR405501R1010	10	0.005
12 V DC	(SPDT)		CR-S012VDC1R	1SVR405501R2010		(0.011)
24 V DC	standard contacts		CR-S024VDC1R	1SVR405501R3010		
48 V DC	Contacts		CR-S048VDC1R	1SVR405501R4010		
60 V DC			CR-S060VDC1R	1SVR405501R5010		
5 V DC	1 c/o	12 V, 250 mA	CR-S005VDC1RG	1SVR405501R1020	10	0.005
12 V DC	(SPDT)	(3W) <sup>1)</sup>	CR-S012VDC1RG	1SVR405501R2020		(0.011)
24 V DC	gold plated		CR-S024VDC1RG	1SVR405501R3020		
48 V DC	contacts		CR-S048VDC1RG	1SVR405501R4020		
60 V DC			CR-S060VDC1RG	1SVR405501R5020		

\_\_

#### Ordering details - CR-S range pluggable optocouplers

Rated control supply voltage	Outputs	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	Transistor, 100 mA - 48 V DC	CR-S024VDC1TRA	1SVR405510R3050	10	0.004
	MOS-FET, 2 A - 24 V DC	CR-S024VDC1MOS	1SVR405510R3060		(0.009)
	Triac, 2 A - 240 V AC	CR-S024VDC1TRI	1SVR405510R3070		

\_

### Ordering details - CR-S range complete interface relays (relay + socket)

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg	Weight (1 pc.) kg (lb)		
24 V AC/DC	1 c/o	250 V AC, 6 A	CR-S012VADC1CRS	1SVR405541R2110	10	0.03		
	(SPDT)				CR-S012VADC1CRZ	1SVR405541R2210		(0.066)
	standard contacts		CR-S024VADC1CRS 1SVR405541R3110					
	contacts		CR-S024VADC1CRZ	1SVR405541R3210				
110 V AC/DC			CR-S110VADC1CRS	1SVR405541R6110				
		CR-S110VADC1CRZ 1SVR405541R6210 CR-S230VADC1CRS 1SVR405541R7110						
230 V AC/DC				CR-S230VADC1CRS	1SVR405541R7110			
			CR-S230VADC1CRZ	1SVR405541R7210				
24 V AC/DC	1 c/o	12 V, 250 mA	CR-S024VADC1CRGS	1SVR405541R3120	10	0.03		
	(SPDT)	(3W) <sup>1)</sup>	CR-S024VADC1CRGZ	1SVR405541R3220		(0.066)		
110 V AC/DC	gold plated		CR-S110VADC1CRGS	1SVR405541R6120				
	contacts		CR-S110VADC1CRGZ	1SVR405541R6220				
230 V AC/DC			CR-S230VADC1CRGS	1SVR405541R7120				
			CR-S230VADC1CRGZ	1SVR405541R7220				

 $<sup>^{</sup>ij}$  If specified maximum values exceeded, the gold plating is destroyed. The maximum values of the standard contacts are then valid.



CR-S optocoupler



CR-S complete interface relay

Ordering details – CR-S range



### Ordering details - CR-S range sockets

Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V DC	screw	CR-S006/024VDC1SS	1SVR405521R1100	10	0.025
	spring	CR-S006/024VDC1SZ	1SVR405521R1200		(0.055)
12-24 V AC/DC	screw	CR-S012/024VADC1SS	1SVR405521R3100		
	spring	CR-S012/024VADC1SZ	1SVR405521R3200		
48-60 V AC/DC	screw	CR-S048/060VADC1SS	1SVR405521R5100		
	spring	CR-S048/060VADC1SZ	1SVR405521R5200		
110-125	screw	CR-S110/125VADC1SS	1SVR405521R6100		
V AC/DC	spring	CR-S110/125VADC1SZ	1SVR405521R6200		
220-240	screw	CR-S220/240VADC1SS	1SVR405521R7100		
V AC/DC	spring	CR-S220/240VADC1SZ	1SVR405521R7200		

#### Ordering details - CR-S range accessories

Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Jumper bar 20 pole, blue color	CR-SJB20-BLUE	1SVR405598R0700	10	0.008
Jumper bar 20 pole, red color	CR-SJB20-RED	1SVR405598R0800		(0.018)
Jumper bar 20 pole, black color	CR-SJB20-BLACK	1SVR405598R0900		
Separator	CR-SSEP	1SVR405599R0000	10	0.012 (0.026)

Ordering details – CR-S range

#### **Relay assemblies**

Control voltage	Connection terminal	Contact material	Socket type	Socket order code	Relay type	Relay order code
5 V DC	screw	standard	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SS	1SVR405521R1100	CR-S005VDC1RG	1SVR405501R1020
	spring	standard	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1R	1SVR405501R1010
		gold plated	CR-S006/024VDC1SZ	1SVR405521R1200	CR-S005VDC1RG	1SVR405501R1020
12 V DC	screw	standard	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S012VDC1RG	1SVR405501R2020
	spring	standard	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S012VDC1RG	1SVR405501R2020
12 V AC	screw	standard	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SS	1SVR405521R3100	CR-S012VDC1RG	1SVR405501R2020
	spring	standard	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1R	1SVR405501R2010
		gold plated	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S012VDC1RG	1SVR405501R2020
24 V DC	screw	standard	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S006/024VDC1SS or CR-S012/024VADC1SS	1SVR405521R1100 or 1SVR405521R3100	CR-S024VDC1RG	1SVR405501R3020
	spring	standard	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S006/024VDC1SZ or CR-S012/024VADC1SZ	1SVR405521R1200 or 1SVR405521R3200	CR-S024VDC1RG	1SVR405501R3020
24 V AC	screw	standard	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1RG	1SVR405501R3020
	spring	standard	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1R	1SVR405501R3010
		gold plated	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1RG	1SVR405501R3020
48 V AC/DC	screw	standard	CR-S048/060VADC1SS	1SVR405521R5100	CR-S048VDC1R	1SVR405501R4010
		gold plated	CR-S048/060VADC1SS	1SVR405521R5100	CR-S048VDC1RG	1SVR405501R4020
	spring	standard	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S048VDC1R	1SVR405501R4010
		gold plated	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S048VDC1RG	1SVR405501R4020
60 V AC/DC	screw	standard	CR-S048/060VADC1SS	1SVR405521R5100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S048/060VADC1SS	1SVR405521R5100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S048/060VADC1SZ	1SVR405521R5200	CR-S060VDC1RG	1SVR405501R5020
110-125 V AC/DC	screw	standard	CR-S110/125VADC1SS	1SVR405521R6100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S110/125VADC1SS	1SVR405521R6100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S110/125VADC1SZ	1SVR405521R6200	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S110/125VADC1SZ	1SVR405521R6200	CR-S060VDC1RG	1SVR405501R5020
220-240 V AC/DC	screw	standard	CR-S220/240VADC1SS	1SVR405521R7100	CR-S060VDC1R	1SVR405501R5010
		gold plated	CR-S220/240VADC1SS	1SVR405521R7100	CR-S060VDC1RG	1SVR405501R5020
	spring	standard	CR-S220/240VADC1SZ	1SVR405521R7200	CR-S060VDC1R	1SVR405501R5010
	-	gold plated	CR-S220/240VADC1SZ	1SVR405521R7200	CR-S060VDC1RG	1SVR405501R5020

\_

### Pluggable interface relays and optocouplers

Ordering details – CR-S range

\_

### Optocoupler assemblies


Control voltage	Connection terminal	Output characteristics	Socket type	Socket order code	Opto type	Opto order code
24 V DC	screw	Transistor	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1TRA	1SVR405510R3050
spring	100 mA - 48 V DC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1TRA	1SVR405510R3050	
	screw	MOS-FET	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1MOS	1SVR405510R3060
	spring	2 A - 24 V DC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1MOS	1SVR405510R3060
	screw	Triac	CR-S012/024VADC1SS	1SVR405521R3100	CR-S024VDC1TRI	1SVR405510R3070
	spring	2 A - 240 V AC	CR-S012/024VADC1SZ	1SVR405521R3200	CR-S024VDC1TRI	1SVR405510R3070

Ordering details - CR-P range

The CR-P range offers the highest current switching in an IP67 rated relay housing. This range comprises of pluggable interface relays and optocouplers offered in 10 different control supply voltages. Additionally, gold plated contacts are available for applications where sensitive signals are to be switched. The CR-P range also includes complete versions consisting of a relay, socket, holder, marker and function module.



#### Ordering details - CR-P range relays





CR-P relay

#### Ordering details - CR-P range relays with gold contacts

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	2 c/o	250 V AC, 8 A	CR-P024DC2G	1SVR405606R1000	10	0.014 (0.031)
24 V AC	(SPDT)		CR-P024AC2G	1SVR405606R0000		
110 V AC	gold	ntact	CR-P110AC2G	1SVR405606R7000		
230 V AC	Contact		CR-P230AC2G	1SVR405606R3000		



#### Ordering details - CR-P range pluggable optocouplers

Rated control supply voltage (Us)	Outputs	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
10-32 V DC	MOS-FET, 5 A - 35 V DC	CR-P024MOS1	1SVR405610R4060	10	0.011
	Triac, 3 A - 275 V AC	CR-P024TRI1	1SVR405610R4070		(0.618)



CR-P optocoupler

#### \_

## Pluggable interface relays and optocouplers

Ordering details - CR-P range



CR-PLSX



Standard and logical sockets for CR-P interface relays are suitable for snap-on mounting onto a DIN rail. Optional function modules for the CR-P range are plugged into both standard and logical sockets.

#### Ordering details - Sockets\*

Version	Connection terminal	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Logical socket with protective separation	screw	CR-PLS	1SVR405650R0000	10	0.045 (0.099)
Logical socket	spring	CR-PLC	1SVR405650R0200		0.042 (0.093)
Standard socket	screw	CR-PSS	1SVR405650R1000		0.038 (0.084)


<sup>\*</sup>All CR-P socket packages include a set of markers.

#### Standard sockets

Position of connection terminals: coil connection (A1-A2) on lower side of the socket, contact connections (n/o and n/c contacts) on the lower and upper side of the socket.

#### Logical sockets

Position of connection terminals: coil connection (A1-A2) on lower side of the socket, all contact connections (common contacts, n/o and n/c contacts) on the upper side of the socket.





Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Plastic holder for socket	CR-PH	1SVR405659R0000	10	0.002 (0.004)
Metal holder for socket	CR-PH1	1SVR405659R0100		0.4g
Jumper bar for sockets with screw connection	CR-PJ	1SVR405658R5000		0.018 (0.040)
Marker	CR-PM	1SVR405658R0000	10	0.0002 (0.0004)

Ordering details – CR-P range



CR-P complete version

### Ordering details - CR-P range complete versions

Rated control supply voltage	Out- puts	Description	Socket type	Connection terminal	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	1 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P012DC1SS42V	1SVR405600R4010	10	0.057 (0.126)
-	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P024DC1SS42V	1SVR405600R1010	10	0.057 (0.126)	
	Reverse polarity protection and freewheeling diode, LED green, holder	logical	spring	CR-P024DC1LC42V	1SVR405600R1011	10	0.057 (0.126)	
		Varistor and LED red, holder	logical	spring	CR-P024DC1LC62C	1SVR405600R1013	10	0.057 (0.126)
110 V D C	1 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P110DC1SS42CV	1SVR405600R8010	10	0.057 (0.126)
24 V AC	1 c/o	Varistor and LED green, holder	standard	screw	CR-P024AC1SS62CV	1SVR405600R0010	10	0.057 (0.126)
120 V A C	1 c/o	Varistor and LED green, holder	standard	screw	CR-P120AC1SS92CV	1SVR405600R2010	10	0.057 (0.126)
230 V AC 1 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P230AC1SS92CV	1SVR405600R3110	10	0.057 (0.126)	
		Holder	logical	screw	CR-P230AC1LS	1SVR405600R3011	10	0.057 (0.126)
		Varistor and LED green, holder	logical	spring	CR-P230AC1LC92CV	1SVR405600R3010	10	0.057 (0.126)

Ordering details – CR-P range



CR-P complete version

### Ordering details - CR-P range complete versions

Rated control supply voltage	Out- puts	Description	Socket type	Connection terminal	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	2 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P012DC2SS42V	1SVR405601R4010	10	0.057 (0.126)
24 V DC	2 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P024DC2SS42V	1SVR405601R1010	10	0.057 (0.126)
		Reverse polarity protection and freewheeling diode, LED red, holder	logical	screw	CR-P024DC2LS42	1SVR405601R1013	10	0.057 (0.126)
		Reverse polarity protection and freewheeling diode, LED green, holder	logical	screw	CR-P024DC2LS42V	1SVR405601R1011	10	0.057 (0.126)
		Reverse polarity protection and freewheeling diode, LED red, holder	logical	spring	CR-P024DC2LC42	1SVR405601R1012	10	0.057 (0.126)
24 V DC	4 V DC 2 c/o gold plated	Reverse polarity protection and freewheeling diode, LED green, holder	logical	spring	CR-P024DC2GLC42V	1SVR405606R1010	10	0.057 (0.126)
		Varistor and LED red, holder	logical	spring	CR-P024DC2GLC62C	1SVR405606R1013	10	0.057 (0.126)
		Varistor and LED green, holder	logical	spring	CR-P024DC2GLC62CV	1SVR405606R1011	10	0.057 (0.126)
110 V DC	2 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P110DC2SS42CV	1SVR405601R8010	10	0.057 (0.126)
24 V AC	2 c/o	Varistor and LED green, holder	standard	screw	CR-P024AC2SS62CV	1SVR405601R0010	10	0.057 (0.126)
120 V AC	2 c/o	Varistor and LED green, holder	standard	screw	CR-P120AC2SS92CV	1SVR405601R2010	10	0.057 (0.126)
230 V AC	2 c/o	Reverse polarity protection and freewheeling diode, LED green, holder	standard	screw	CR-P230AC2SS92CV	1SVR405601R3110	10	0.057 (0.126)
		Varistor and LED green, holder	logical	screw	CR-P230AC2LS92CV	1SVR405601R3011	10	0.057 (0.126)
		Diode and LED red, holder	logical	spring	CR-P230AC2LC92	1SVR405601R3012	10	0.057 (0.126)
230 V AC	2 c/o gold	Diode and LED red, holder	logical	spring	CR-P230AC2GLC92	1SVR405606R3013	10	0.057 (0.126)
	plated	Varistor and LED red, holder	logical	spring	CR-P230AC2GLC92C	1SVR405606R3012	10	0.057 (0.126)
		Varistor and LED green, holder	logical	spring	CR-P230AC2GLC92CV	1SVR405606R3010	10	0.057 (0.126)

Ordering details - CR-M range



The CR-M range offers the possibility of switching up to 4 different circuits with a single relay. The integrated LED and test button\* allow for easy testing and commissioning. This range of relays are available at a wide range of different coil voltages and are accompanied by a wide variety of function modules. The CR-M range also includes complete versions consisting of a relay, socket, holder, marker and where applicable, function module.

Ordering details - CR-M range without LED

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg	Weight (1 pc.) kg (lb)
12 V DC	2 c/o	250 V AC,	CR-M012DC2	1SVR405611R4000	10	0.033
24 V DC	(SPDT)	12 A	CR-M024DC2	1SVR405611R1000		(0.073)
48 V DC			CR-M048DC2	1SVR405611R6000		
60 V DC			CR-M060DC2	1SVR405611R4200		
110 V DC			CR-M110DC2	1SVR405611R8000		
125 V DC			CR-M125DC2	1SVR405611R8200		
220 V DC			CR-M220DC2	1SVR405611R9000		
24 V AC			CR-M024AC2	1SVR405611R0000		
48 V AC			CR-M048AC2	1SVR405611R5000		
110 V AC			CR-M110AC2	1SVR405611R7000		
120 V AC			CR-M120AC2	1SVR405611R2000		
230 V AC			CR-M230AC2	1SVR405611R3000		
12 V DC	3 c/o	250 V AC,	CR-M012DC3	1SVR405612R4000	10	0.033
24 V DC	(SPDT)	10 A	CR-M024DC3	1SVR405612R1000		(0.073)
48 V DC			CR-M048DC3	1SVR405612R6000		
60 V DC			CR-M060DC3	1SVR405612R4200		
110 V DC			CR-M110DC3	1SVR405612R8000		
125 V DC			CR-M125DC3	1SVR405612R8200		
220 V DC			CR-M220DC3	1SVR405612R9000		
24 V AC			CR-M024AC3	1SVR405612R0000		
48 V AC			CR-M048AC3	1SVR405612R5000		
60 V AC			CR-M060AC3	1SVR405612R5200		
110 V AC			CR-M110AC3	1SVR405612R7000		
120 V AC			CR-M120AC3	1SVR405612R2000		
230 V AC			CR-M230AC3	1SVR405612R3000		
12 V DC	4 c/o	250 V AC,	CR-M012DC4	1SVR405613R4000	10	0.033
24 V DC	(SPDT)	6 A	CR-M024DC4	1SVR405613R1000		(0.073)
48 V DC			CR-M048DC4	1SVR405613R6000		
60 V DC			CR-M060DC4	1SVR405613R4200		
110 V DC			CR-M110DC4	1SVR405613R8000		
125 V DC			CR-M125DC4	1SVR405613R8200		
220 V DC			CR-M220DC4	1SVR405613R9000		
24 V AC			CR-M024AC4	1SVR405613R0000		
48 V AC			CR-M048AC4	1SVR405613R5000		
110 V AC			CR-M110AC4	1SVR405613R7000		
120 V AC			CR-M120AC4	1SVR405613R2000		
230 V AC			CR-M230AC4	1SVR405613R3000		

<sup>\*</sup> Note: During the operation of the relay, the temperature of the test button will increase. In order to manually operate the test button, the supply voltage should first be disconnected. The test button is only safe to operate once it has cooled down or by using protective gloves and insulated tools. During operation, the test button should be pressed smoothly and quickly. When the test button is depressed, the n/o contacts will close and remain closed. Once the button is released, the n/o contacts change status and open. A 90 degree rotation of the test button closes and holds the n/o contacts in a closed position. Reverse rotation of the test button will once again change the status of the n/o contacts to their default open position.

Ordering details – CR-M range



### Ordering details - CR-M range with LED

Rated control supply voltage	Outputs	Contact ratings	Type	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	2 c/o	250 V AC, 12 A	CR-M012DC2L	1SVR405611R4100	10	0.033
24 V DC	(SPDT)		CR-M024DC2L	1SVR405611R1100		(0.073)
48 V DC			CR-M048DC2L	1SVR405611R6100		
60 V DC			CR-M060DC2L	1SVR405611R4300		
110 V DC			CR-M110DC2L	1SVR405611R8100		
125 V DC			CR-M125DC2L	1SVR405611R8300		
220 V DC			CR-M220DC2L	1SVR405611R9100		
12 V AC			CR-M012AC2L	1SVR405611R0300		
24 V AC			CR-M024AC2L	1SVR405611R0100		
48 V AC			CR-M048AC2L	1SVR405611R5100		
110 V AC			CR-M110AC2L	1SVR405611R7100		
120 V AC			CR-M120AC2L	1SVR405611R2100		
230 V AC			CR-M230AC2L	1SVR405611R3100		
12 V DC	3 c/o	250 V AC, 10 A	CR-M012DC3L	1SVR405612R4100	10	0.033
24 V DC	(SPDT)		CR-M024DC3L	1SVR405612R1100		(0.073)
48 V DC			CR-M048DC3L	1SVR405612R6100		
60 V DC			CR-M060DC3L	1SVR405612R4300		
110 V DC			CR-M110DC3L	1SVR405612R8100		
125 V DC			CR-M125DC3L	1SVR405612R8300		
220 V DC			CR-M220DC3L	1SVR405612R9100		
12 V AC			CR-M012AC3L	1SVR405612R0300		
24 V AC			CR-M024AC3L	1SVR405612R0100		
48 V AC			CR-M048AC3L	1SVR405612R5100		
110 V AC			CR-M110AC3L	1SVR405612R7100		
120 V AC			CR-M120AC3L	1SVR405612R2100		
230 V AC			CR-M230AC3L	1SVR405612R3100		
12 V DC	4 c/o	250 V AC, 6 A	CR-M012DC4L	1SVR405613R4100	10	0.033
24 V DC	(SPDT)		CR-M024DC4L	1SVR405613R1100		(0.073)
48 V DC			CR-M048DC4L	1SVR405613R6100		
60 V DC			CR-M060DC4L	1SVR405613R4300		
110 V DC			CR-M110DC4L	1SVR405613R8100		
125 V DC			CR-M125DC4L	1SVR405613R8300		
220 V DC			CR-M220DC4L	1SVR405613R9100		
12 V AC			CR-M012AC4L	1SVR405613R0300		
24 V AC			CR-M024AC4L	1SVR405613R0100		
48 V AC			CR-M048AC4L	1SVR405613R5100		
110 V AC			CR-M110AC4L	1SVR405613R7100		
120 V AC			CR-M120AC4L	1SVR405613R2100		
230 V AC			CR-M230AC4L	1SVR405613R3100		

Ordering details – CR-M range



### Ordering details - CR-M range with LED and free-wheeling diode

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	2 c/o (SPDT)	250 V AC, 6 A	CR-M012DC2LD	1SVR405611R4400	10	0.033 (0.073)
24 V DC			CR-M024DC2LD	1SVR405611R1400	10	0.033 (0.073)
48 V DC			CR-M048DC2LD	1SVR405611R6400	10	0.033 (0.073)
110 V DC			CR-M110DC2LD	1SVR405611R8400	10	0.033 (0.073)
125 V DC			CR-M125DC2LD	1SVR405611R8500	10	0.033 (0.073)
220 V DC			CR-M220DC2LD	1SVR405611R9400	10	0.033 (0.073)
12 V DC	3 c/o (SPDT)	250 V AC, 10 A	CR-M012DC3LD	1SVR405612R4400	10	0.033 (0.073)
24 V DC			CR-M024DC3LD	1SVR405612R1400	10	0.033 (0.073)
48 V DC			CR-M048DC3LD	1SVR405612R6400	10	0.033 (0.073)
110 V DC			CR-M110DC3LD	1SVR405612R8400	10	0.033 (0.073)
125 V DC			CR-M125DC3LD	1SVR405612R8500	10	0.033 (0.073)
220 V DC			CR-M220DC3LD	1SVR405612R9400	10	0.033 (0.073)
12 VDC	4 c/o (SPDT)	250 V AC, 6 A	CR-M012DC4LD	1SVR405613R4400	10	0.033 (0.073)
24 V DC			CR-M024DC4LD	1SVR405614R1100	10	0.033 (0.073)
48 V DC			CR-M048DC4LD	1SVR405613R6400	10	0.033 (0.073)
110 V DC			CR-M110DC4LD	1SVR405613R8400	10	0.033 (0.073)
125 V DC			CR-M125DC4LD	1SVR405613R8500	10	0.033 (0.073)
220 V DC			CR-M220DC4LD	1SVR405613R9400	10	0.033 (0.073)

#### \_

### Ordering details - CR-M range with gold contacts

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	4 c/o		CR-M024DC4G	1SVR405618R1000	10	0.033 (0.073)
24 V AC	(SPDT)		CR-M024AC4G	1SVR405618R0000		
110 V AC			CR-M110AC4G	1SVR405618R7000		
230 V AC			CR-M230AC4G	1SVR405618R3000		

Ordering details – CR-M range



### Ordering details – CR-M range with gold contacts and LED

Rated control supply voltage	Outputs	Contact ratings	Type	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	4 c/o	250 V AC,	CR-M012DC4LG	1SVR405618R4100	10	0.033
24 V DC	(SPDT)	6 A	CR-M024DC4LG	1SVR405618R1100		(0.073)
48 V DC			CR-M048DC4LG	1SVR405618R6100		
60 V DC			CR-M060DC4LG	1SVR405618R4300		
110 V DC			CR-M110DC4LG	1SVR405618R8100		
125 V DC			CR-M125DC4LG	1SVR405618R8300		
220 V DC			CR-M220DC4LG	1SVR405618R9100		
24 V AC			CR-M024AC4LG	1SVR405618R0100	10	0.033
48 V AC			CR-M048AC4LG	1SVR405618R5100		(0.073)
110 V AC			CR-M110AC4LG	1SVR405618R7100		
120 V AC			CR-M120AC4LG	1SVR405618R2100		
230 V AC			CR-M230AC4LG	1SVR405618R3100		

\_

#### Ordering details – CR-M range with gold contacts, LED and free-wheeling diode

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	4 c/o 250 V AC,	CR-M012DC4LDG	1SVR405618R4400	10	0.033	
24 V DC	(SPDT)	6 A	CR-M024DC4LDG	1SVR405618R1400		(0.073)

Ordering details – CR-M range



CR-M complete version

#### Ordering details - CR-M range complete version

Rated control supply	Out- puts	Description	Socket type	Connec- tion terminal	Туре	Order code	Pkg	(1 pc.)
voltage							qty	kg (lb)
12 V DC	4 c/o gold- plated	LED red, holder	standard	screw	CR-M012DC4LDGSS	1SVR405618R4410	10	0.0109 (0.024)
24 V DC	4 c/o	Reverse polarity protection and free-wheeling diode, LED green, holder	standard	screw	CR-M024DC4SS42V	1SVR405613R1010	10	0.0109 (0.024)
		Reverse polarity protection and free-wheeling diode, LED green, holder	logical	screw	CR-M024DC4LS42V	1SVR405613R1011	10	0.0109 (0.024)
		Reverse polarity protection and free-wheeling diode, LED red, holder	logical	spring	CR-M024DC4LC42	1SVR405613R1012	10	0.0109 (0.024)
24 V DC	4 c/o gold- plated	Reverse polarity protection and free-wheeling diode, LED green, holder	standard	screw	CR-M024DC4GSS42V	1SVR405618R1011	10	0.0109 (0.024)
		Varistor, LED green, holder	logical	spring	CR-M024DC4GLC62CV	1SVR405618R1010	10	0.0109 (0.024)
		LED, free- wheeling diode, holder	logical	spring	CR-M024DC4LGLC22	1SVR405618R1110	10	0.0109 (0.024)
		LED red, free- wheeling diode, holder	standard	screw	CR-M024DC4LDGSS	1SVR405618R1410	10	0.0109 (0.024)
24 V AC	4 c/o	Varistor and LED green, holder	logical	screw	CR-M024AC4LS62CV	1SVR405613R0010	10	0.0109 (0.024)

Ordering details – CR-M range



CR-M complete version

### Ordering details – CR-M range complete version

Rated control supply	Out- puts	Description	Socket type	Connection terminal	Туре	Order code	Pkg	Weight (1 pc.)
230 V AC	4 c/o	Varistor, LED green, holder	standard	screw	CR-M230AC4SS92CV	1SVR405613R3110	qty 10	0.0109 (0.024)
		Varistor, LED green, holder	logical	screw	CR-M230AC4LS92CV	1SVR405613R3011	10	0.0109 (0.024)
		Diode and LED red, holder	logical	spring	CR-M230AC4LC92	1SVR405613R3012	10	0.0109 (0.024)
230 V AC	4 c/o gold- pla- ted	Reverse polarity protection and free-wheeling diode, LED green, holder	standard	screw	CR-M230AC4GSS92CV	1SVR405618R3112	10	0.0109 (0.024)
		LED red, holder	logical	screw	CR-M230AC4LGLC	1SVR405618R3110	10	0.0109 (0.024)
		LED red, holder	standard	screw	CR-M230AC4LGSS	1SVR405618R3111	10	0.0109 (0.024)

### Ordering details - CR-M range





Standard and logical sockets for CR-M interface relays are suitable for snap-on mounting onto a DIN rail. Optional function modules for the CR-M range are plugged into both standard and logical sockets.

### Ordering details - Sockets\*

Version	Connection terminal	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Logical socket for 2 c/o	screw	CR-M2LS	1SVR405651R1100	10	0.055 (0.121)
Logical socket for 3 c/o		CR-M3LS	1SVR405651R2100		0.062 (0.137)
Logical socket for 2/4 c/o		CR-M4LS	1SVR405651R3100		0.066 (0.146)
High Performance Logical Socket for 2 c/o		CR-M2LSH	1SVR405651R4100		0.064 (0.141)
High Performance Logical Socket for 3 c/o		CR-M3LSH	1SVR405651R5100		0.071 (0.157)
Logical socket for 2/4 c/o	spring	CR-M4LC	1SVR405651R3200	10	0.066 (0.146)
Standard socket for 2 c/o	screw	CR-M2SS	1SVR405651R1000	10	0.066 (0.146)
Standard socket for 3 c/o		CR-M3SS	1SVR405651R2000		0.068 (0.150)
Standard socket for 2/4 c/o		CR-M4SS	1SVR405651R3000		0.070 (0.154)
Standard socket for 2 c/o	fork type	CR-M2SF	1SVR405651R1300	10	0.040 (0.088)
Standard socket for 2/4 c/o		CR-M4SF	1SVR405651R3300		0.048 (0.106)

<sup>\*</sup>All CR-M socket packages include a set of markers.

#### Standard sockets

Position of connection terminals: coil connection (A1-A2) on lower side of the socket, contact connections (n/o and n/c contacts) on the lower and upper side of the socket.

#### **Logical sockets**

Position of connection terminals: coil connection (A1-A2) on lower side of the socket, all contact connections (common contacts, n/o and n/c contacts) on upper side of the socket.

#### Ordering details - Accessories



Version	Type	Order code	Pkg	Weight (1 pc.) kg (lb)
Plastic holder for socket	CR-MH	1SVR405659R1000	10	0.003 (0.007)
Metal holder for socket	CR-MH1	1SVR405659R1100	10	0.0005 (0.001)
Jumper bar for sockets with screw connection	CR-MJ	1SVR405658R6000	10	0.029 (0.064)
Marker for CR-M standard sockets	CR-MM	1SVR405658R1000	10	0.0005 (0.001)
Plug for test button replacement	CR-MP	1SVR405658R2000	100	0.001 (0.002)

Ordering details – CR-P/M function modules



#### Ordering details - Diode - Reverse polarity protection / free-wheeling diode

Rated control supply voltage U <sub>s</sub>	Version	Type	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-220 V DC	A1+, A2-	CR-P/M 22	1SVR405651R0000	10	0.003 (0.007)

#### \_

# Ordering details - Diode and LED - Reverse polarity protection / free-wheeling diode and LED to indicate energized coil

Rated control supply voltage U <sub>s</sub>	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V DC	red, A1+, A2-	CR-P/M 42	1SVR405652R0000	10	0.003
6-24 V DC	green, A1+, A2-	CR-P/M 42 V	1SVR405652R1000		(0.007)
24-60 V DC	red, A1+, A2-	CR-P/M 42 B	1SVR405652R4000		
24-60 V DC	green, A1+, A2-	CR-P/M 42 BV	1SVR405652R4100		
110 V DC	red, A1+, A2-	CR-P/M 42 C	1SVR405652R9000		
110 V DC	green, A1+, A2-	CR-P/M 42 CV	1SVR405652R9100		

#### \_

#### Ordering details - RC element - Spark quenching

Rated control supply voltage U <sub>s</sub>	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC		CR-P/M 52B	1SVR405653R0000	10	0.003
24-60 V AC/DC		CR-P/M 52D	1SVR405653R4000		(0.007)
110-230 V AC/DC		CR-P/M 52C	1SVR405653R1000		

#### \_

#### Ordering details - Diode and LED - LED to indicate energized coil

Rated control supply voltage U <sub>s</sub>	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC	red, for DC: A1+, A2-	CR-P/M 62	1SVR405654R0000	10	0.003
6-24 V AC/DC	green, for DC: A1+, A2-	CR-P/M 62 V	1SVR405654R1000		(0.007)
24-60 V AC/DC	red, for DC: A1+, A2-	CR-P/M 62 E	1SVR405654R4000		
24-60 V AC/DC	green, for DC: A1+, A2-	CR-P/M 62 EV	1SVR405654R4100		
110-230 V AC/DC	red, for DC: A1+, A2-	CR-P/M 92	1SVR405654R0100		
110-230 V AC/DC	green, for DC: A1+, A2-	CR-P/M 92 V	1SVR405654R1100		

Ordering details – CR-P/M function modules



# Ordering details - Varistor and LED - Overvoltage protection and LED to indicate energized coil

Rated control supply voltage U <sub>s</sub>	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC	red, for DC: A1+, A2-	CR-P/M 62 C	1SVR405655R0000	10	0.003
6-24 V AC/DC	green, for DC: A1+, A2-	CR-P/M 62 CV	1SVR405655R1000		(0.007)
24-60 V AC/DC	red, for DC: A1+, A2-	CR-P/M 62 D	1SVR405655R4000		
24-60 V AC/DC	green, for DC: A1+, A2-	CR-P/M 62 DV	1SVR405655R4100		
110-230 V AC/DC	red, for DC: A1+, A2-	CR-P/M 92 C	1SVR405655R0100		
110-230 V AC/DC	green, for DC: A1+, A2-	CR-P/M 92 CV	1SVR405655R1100		

#### Ordering details - Varistor - Overvoltage protection

Rated control supply voltage U <sub>s</sub>	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V AC		CR-P/M 72	1SVR405656R0000	10	0.002
115 V AC		CR-P/M 72 A	1SVR405656R1000		(0.004)
230 V AC		CR-P/M 82	1SVR405656R2000		

Ordering details - CR-U range



The CR-U range offers up to 3 change over contacts in single relay. The integrated LED and test button\* allow for easy testing and commissioning. This robust range of relays are available at a wide range of different coil voltages and are accompanied by a wide variety of function modules.

#### Ordering details - CR-U range without LED

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	2 c/o (SPDT)	250 V AC, 10 A	CR-U012DC2	1SVR405621R4000	10	0.083
24 V DC			CR-U024DC2	1SVR405621R1000		(0.183)
48 V DC			CR-U048DC2	1SVR405621R6000		
110 V DC	_		CR-U110DC2	1SVR405621R8000		
220 V DC	-		CR-U220DC2	1SVR405621R9000		
24 V AC			CR-U024AC2	1SVR405621R0000		
48 V AC			CR-U048AC2	1SVR405621R5000		
110 V AC			CR-U110AC2	1SVR405621R7000		
120 V AC			CR-U120AC2	1SVR405621R2000		
230 V AC			CR-U230AC2	1SVR405621R3000		
12 V DC	3 c/o (SPDT)	SPDT) 250 V AC, 10 A	CR-U012DC3	1SVR405622R4000	10	0.083 (0.183)
24 V DC			CR-U024DC3	1SVR405622R1000		
48 V DC			CR-U048DC3	1SVR405622R6000		
110 V DC			CR-U110DC3	1SVR405622R8000		
125 V DC			CR-U125DC3	1SVR405622R8200		
220 V DC			CR-U220DC3	1SVR405622R9000		
24 V AC			CR-U024AC3	1SVR405622R0000		
48 V AC			CR-U048AC3	1SVR405622R5000		
60 V AC	1		CR-U060AC3	1SVR405622R5200		
110 V AC			CR-U110AC3	1SVR405622R7000		
120 V AC	1		CR-U120AC3	1SVR405622R2000		
230 V AC	1		CR-U230AC3	1SVR405622R3000		

 $<sup>* \,</sup> Note: During \, the \, operation \, of \, the \, relay, \, the \, temperature \, of \, the \, test \, button \, will increase. \, In \, order \, to \, manually \, operate \, the \, test \, botton, \, and \, the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation of the \, test \, button \, will be a considered by the expectation by the expectation of the \, test \, but$ the supply voltage should first be disconnected. The test button is only safe to operate once it has cooled down or by using protective gloves and insulated tools. During operation, the test button should be pressed smoothly and quickly. When the test button is depressed, the n/o contacts will close and remain closed. Once the button is released, the n/o contacts change status and open. A 90 degree rotation of the test button closes and holds the n/o contacts in a closed position. Reverse rotation of the test button will once again change the status of the n/o contacts to their default open position.

#### Ordering details - CR-U range with LED

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg	Weight (1 pc.) kg (lb)
12 V DC	2 c/o (SPDT)	250 V AC, 10 A	CR-U012DC2L	1SVR405621R4100	10	0.083
24 V DC		CR-U024DC2L 1SV	1SVR405621R1100		(0.183)	
48 V DC			CR-U048DC2L	1SVR405621R6100		
110 V DC			CR-U110DC2L	1SVR405621R8100		
220 V DC			CR-U220DC2L	1SVR405621R9100		
12 V AC			CR-U012AC2L	1SVR405621R0300		
24 V AC			CR-U024AC2L	1SVR405621R0100		
48 V AC			CR-U048AC2L	1SVR405621R5100		
110 V AC			CR-U110AC2L	1SVR405621R7100		
120 V AC			CR-U120AC2L	1SVR405621R2100		
230 V AC			CR-U230AC2L	1SVR405621R3100		

Ordering details - CR-U range

#### Ordering details - CR-U range with LED

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg	Weight (1 pc.) kg (lb)
12 V DC	3 c/o (SPDT)	250 V AC, 10 A	CR-U012DC3L	1SVR405622R4100	10	0.083
24 V DC			CR-U024DC3L	1SVR405622R1100		(0.183)
48 V DC	_		CR-U048DC3L	1SVR405622R6100		
110 V DC			CR-U110DC3L	1SVR405622R8100		
220 V DC			CR-U220DC3L	1SVR405622R9100		
12 V AC			CR-U012AC3L	1SVR405622R0300		
24 V AC			CR-U024AC3L	1SVR405622R0100		
48 V AC			CR-U048AC3L	1SVR405622R5100		
110 V AC			CR-U110AC3L	1SVR405622R7100		
120 V AC			CR-U120AC3L	1SVR405622R2100		
230 V AC			CR-U230AC3L	1SVR405622R3100		



#### Ordering details - CR-U range with LED and free-wheeling diode

Rated control supply voltage	Outputs	Contact ratings	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
12 V DC	2 c/o (SPDT)	250 V AC, 10 A	CR-U012DC2LD	1SVR405621R4400	10	0.033 (0.073)
24 V DC			CR-U024DC2LD	1SVR405621R1400	10	0.033 (0.073)
48 V DC	_		CR-U048DC2LD	1SVR405621R6400	10	0.033 (0.073)
110 V DC			CR-U110DC2LD	1SVR405621R8400	10	0.033 (0.073)
12 V DC	3 c/o (SPDT)		CR-U012DC3LD	1SVR405622R4400	10	0.033 (0.073)
24 V DC			CR-U024DC3LD	1SVR405623R1100	10	0.033 (0.073)
48 V DC			CR-U048DC3LD	1SVR405622R6400	10	0.033 (0.073)
110 V DC			CR-U110DC3LD	1SVR405622R8400	10	0.033 (0.073)

The sockets for CR-U interface relays have screw connection terminals and are suitable for snap-on mounting onto a DIN rail. Optional function modules for the CR-U range may only be plugged into compatible standard sockets.

#### Ordering details - Sockets and Accessories



Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg
Socket for 2 c/o and function module	CR-U2S	1SVR405670R0000	10	0.065
Socket for 3 c/o and function module	CR-U3S	1SVR405660R0000		0.065
Small socket for 2 c/o	CR-U2SM	1SVR405670R1100		0.054
Small socket for 3 c/o	CR-U3SM	1SVR405660R1100		0.058
Metal holder for socket	CR-UH	1SVR405669R0000		0.001

#### CR-U sockets

Position of connection terminals: coil connection (A1-A2) on lower side of socket, contact connections (n/o and n/c contacts) on the lower and upper side of socket.

### Ordering details – CR-U function modules

CR-U...

CR-U function modules are compatible with the CR-U2S and CR-U3S sockets only.

#### Diode - Reverse polarity protection / free-wheeling diode

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-220 V DC	A1+, A2-	CR-U 21	1SVR405661R0000	10	0.007 (0.015)

# Diode and LED - Reverse polarity protection / free-wheeling diode and LED to indicate energized coil

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V DC	red, A1+, A2-	CR-U 41	1SVR405662R0000	10	0.007
6-24 V DC	green, A1+, A2-	CR-U 41V	1SVR405662R1000		(0.015)
24-60 V DC	red, A1+, A2-	CR-U 41B	1SVR405662R4000		
24-60 V DC	green, A1+, A2-	CR-U 41BV	1SVR405662R4100		
110 V DC	red, A1+, A2-	CR-U 41C	1SVR405662R9000		
110 V DC	green, A1+, A2-	CR-U 41CV	1SVR405662R9100		

#### **RC element - Spark quenching**

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC		CR-U 51B	1SVR405663R0000	10	0.007
24-60 V AC/DC		CR-U 51D	1SVR405663R4000		(0.015)
110 -230 V AC/DC		CR-U 51C	1SVR405663R1000		

### Diode and LED - LED to indicate energized coil

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC	red, for DC A1+, A2-	CR-U 61	1SVR405664R0000	10	0.007 (0.015)
6-24 V AC/DC	green, for DC A1+, A2-	CR-U 61V	1SVR405664R1000		
24-60 V AC/DC	red, for DC A1+, A2-	CR-U 61E	1SVR405664R4000		
24-60 V AC/DC	green, for DC A1+, A2-	CR-U 61EV	1SVR405664R4100		
110-230 V AC/DC	red, for DC A1+, A2-	CR-U 91	1SVR405664R0100		
110-230 V AC/DC	green, for DC: A1+, A2-	CR-U 91V	1SVR405664R1100		

## Ordering details – CR-U function modules



#### Varistor and LED - Overvoltage protection and LED to indicate energized coil

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
6-24 V AC/DC	red, for DC A1+, A2-	CR-U 61C	1SVR405665R0000	10	0.007
6-24 V AC/DC	green, for DC A1+, A2-	CR-U 61CV	1SVR405665R1000		(0.015)
24-60 V AC/DC	red, for DC A1+, A2-	CR-U 61D	1SVR405665R4000		
24-60 V AC/DC	green, for DC A1+, A2-	CR-U 61DV	1SVR405665R4100		
110-230 V AC/DC	red, for DC A1+, A2-	CR-U 91C	1SVR405665R0100		
110-230 V AC/DC	green, for DC A1+, A2-	CR-U 91CV	1SVR405665R1100		



#### Varistor - Overvoltage protection

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V AC		CR-U 71	1SVR405666R0000	10	0.007
115 V AC		CR-U 71A	1SVR405666R1000		(0.015)
230 V AC		CR-U 81	1SVR405666R2000		

Multi-function time module\*

Rated control supply voltage	Version	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24-240 V AC/DC	green LED	CR-U T	1SVR405667R0000	10	0.014 (0.031)

 $<sup>^{\</sup>star}$  For more details, refer to the  $\underline{\text{CR-U T datasheet}}.$ 

#### \_

# Pluggable interface relays and optocouplers

Technical data - CR-S interface relays

Input circuit							
	Rated control supply voltage Us	Make voltage (at 23 °C)	Maximum voltage (at 55 °C)	Break voltage	Rated power	Coil resistance (at 23 °C)	Tolerance of coil resistance
CR-S005VDC1R(G)	5 V DC	3.75 V DC	7.5 V DC	0.25 V DC	170 mW	147 Ω	± 10 %
CR-S012VDC1R(G)	12 V DC	9 V DC	18 V DC	0.6 V DC	170 mW	848 Ω	± 10 %
CR-S024VDC1R(G)	24 V DC	18 V DC	36 V DC	1.2 V DC	170 mW	3390 Ω	± 15 %
CR-S048VDC1R(G)	48 V DC	36 V DC	72 V DC	2.4 V DC	210 mW	10600 Ω	± 15 %
CR-S060VDC1R(G)	60 V DC	45 V DC	90 V DC	3 V DC	210 mW	16600 Ω	± 15 %

Output circuits		
Output circuit(s)		11-12/14
Kind of output		1 c/o (SPDT)
Contact material		AgSnO <sub>2</sub> or AgSnO <sub>2</sub> /Au
Rated operational voltage U <sub>e</sub> (IEC/EN 60947-1)		250 V AC
Minimum switching voltage		5 V at 100 mA (AgSnO <sub>2</sub> ) / 5 V at 12 mA (AgSnO <sub>2</sub> /Au)
Maximum switching voltage		400 V AC / 250 V DC
Minimum switching current		10 mA at 10 V (AgSnO <sub>2</sub> ) / 3 mA at 20 V (AgSnO <sub>2</sub> /Au)
Rated free air thermal current I <sub>th</sub>		5 A
Rated operational current (IEC/EN 60947-5-1)	AC12 (resistive) 230 V	6 A
	AC15 (inductive) 230 V	1.5 A
	AC15 (inductive) 120 V	3 A
	DC12 (resistive) 24 V	6 A
	DC13 (inductive) 24 V	1 A
	DC13 (inductive) 120 V	0.22 A
	DC13 (inductive) 250 V	0.11 A
AC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty) (contact rating code designation)	B300
DC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty) (contact rating code designation)	R300
Maximum making (inrush) current		15 A, 240 V AC
Minimum switching power		100 mA/12 V (AgSnO <sub>2</sub> ) / 50 mW (AgSnO <sub>2</sub> /Au)
Maximum switching (breaking) power	AC1 (resistive)	1500 VA, 250 V AC
Contact resistance		$\leq$ 100 m $\Omega$ (at 1 A 6 V DC) / gold-plated: $\leq$ 30 m $\Omega$ (at 1 A 6 V DC)
Maximum operating frequency	rated load AC1	360 switching cycles/h
	without load	18000 switching cycles/h
Mechanical lifetime		1 x 10 <sup>7</sup> switching cycles
Electrical lifetime	AC1 (resistive)	(n/c) 3 x 10 <sup>4</sup> switching cycles (at +85 °C) (n/o) 1 x 10 <sup>4</sup> switching cycles (at +85 °C)
Response time		8 ms
Release time		4 ms
Isolation data		
Rated insulation voltage		250 V AC
Rated impulse withstand voltage U <sub>imp</sub>	between coil and contacts	4 kV (1.2/50 μs) 1 min
	between open contacts	1 kV (1.2/50 μs) 1 min
Clearance	between coil and contacts	5.5 mm (0.217 in)
Creepage distance	between coil and contacts	8 mm (0.315 in)
Overvoltage category		III
Pollution degree		2
General data		
Dimensions		see 'Dimensional drawings'
Mounting		on socket
Mounting position		any
Degree of protection		RT II and RT III

Technical data - CR-S interface relays and CR-S optocouplers

Electrical connection				
Connection		by socket		
Environmental data				
Ambient temperature range	operation	-40+85 °C		
	storage	-40+85 °C		
Vibration resistance (10-150 Hz)	n/o contact	10 Hz to 55 Hz 1 mm DA		
	n/c contact	10 Hz to 55 Hz 1 mm DA		
Shock resistance	n/o contact	function 49 m/s² / destructive 980 m/s²		
	n/c contact	function 49 m/s² / destructive 980 m/s²		
Standards/directives				
Standards		IEC/EN 61810-1		
RoHS Directive		2011/65/EU		

# Technical data - CR-S optocouplers

Input circuit		CR-S024VDC1TRA	CR-S024VDC1MOS	CR-S024VDC1TRI				
Input resistance		3400 Ohm						
Rated control voltage		24 V DC*						
Pull-in voltage		15 V DC						
Maximum control voltage		30 V DC						
Nominal input current		7 mA						
Input power		168 mW						
Typical switching-on time		< 40 ms	< 60 ms	< 1/2 cycle				
Typical switch-off time		< 600 ms	< 600 ms	< 1/2 cycle				
Output circuits								
Output circuit(s)		11 (13+) - 14	11 (13+) - 14	11 (13+) - 14				
Kind of output		Transistor	MOS-FET	Triac				
Rated operational voltage		48 V DC	24 V DC	240 V AC				
Maximum switching voltage		48 V DC	24 V DC	275 V AC				
Minimum switching current		50 mA	50 mA	22 mA				
Maximum switching current continuously		100 mA	2 A	2 A				
Leakage current at maximum switching voltage		<1 mA	<1 mA	< 1.5 mA				
Voltage drop at rated current		< 120 mV DC	< 120 mV DC	< 1.6 V AC				
Isolation data								
Rated insulation voltage	input/output	2.5 kV						
Insulation class		2						
Clearance	input/output	14 mm						
Creepage distance	input/output	14 mm						
Overvoltage category		III						
Pollution degree		2						
General data								
Dimensions		see 'Dimensional drawi	ngs'					
Weight		3.5 g (0.007 lb)						
Mounting		on socket						
Environmental data								
Ambient temperature	operation	-30+80 °C						
	storage	-40+100 °C						
Standards / Directives								
Standards		IEC/EN 62314						
EMC Directive		2014/30/EN						
RoHS Directive		2011/65/EN						

<sup>\*</sup> The output circuit should not exceed 30 m.

Technical data - CR-S sockets

Input circuit		CR-S 6-24 V	CR-S 12-24 V	CR-S 48-60 V	CR-S 110-125 V	CR-S 220-240 V			
Rated control supply volta	ige U <sub>s</sub>	6-24 V DC	12-24 V AC/DC*	48-60 V AC/DC	110-125 V AC/DC	220-240 V AC/DO			
Rated control supply volta	- ,	(0.8-1.2) U <sub>s</sub>	(0.8-1.2) U <sub>s</sub>	· · ·					
Typical current	·	11-29 mA	11-16 mA	3.6-4.5 mA	3.6 mA	3.6 mA			
Response time		8 ms							
Release time		4 ms							
Status device		green LED							
Protective circuit		yes							
Output circuits		700							
Output circuit(s)		11-12/14							
Number of poles		1							
Rated voltage		250 V AC							
Rated current		6 A							
	h screw connection terminal	07.							
Dimensions		see 'Dimension	al drawings'						
Degree of protection (EN	60529)	IP20 (terminals)							
Temperature range		-40+70 °C			-40+55 °C				
po. aca. o lange	·	-40+85 °C							
Connection type	Storage	Screw							
Maximum number of wire	s per connection terminal	2							
Connecting capacity			² (2 x 20 - 16 AWG)						
connecting capacity	fine-strand	L X 0.5 · 1.5 IIIIII	(LXLO IOAWG)						
		2 x 0.5 - 1 mm² (2 x 20 - 18 AWG)							
Tightening torque	with whe end refule	0.5 Nm (4.426 lk	•						
Stripping length		7 mm (0.28 in)	, <u>,</u>						
Minimum clamping force	with 0.2 mm²	10 N							
for fine-strand wire	with 1.5 mm²	40 N							
Mounting (IEC/EN 60715)		DIN rail							
Material		PA6 + GF - UL94	VO						
Material			VU						
	contacts								
	contact surface								
		CuZn40, 3 μ Ni							
Company I data for CD C with	combi screw M3	re				-			
Dimensions without holde	h spring connection terminal	see 'Dimension	al drawings!						
Degree of protection (EN	<u> </u>		ection (EN 60529) IP	20 (tarminals)					
			ction (EN 60529) IP	20 (terminais)	40 .55 %				
Temperature range		-40+70 °C			-40+55 °C				
Commontions to see	storage	-40+85 °C							
Connection type		Spring							
Maximum number of wire	s per connection terminal	2.75 2.5 2.6	20 14 AMC	:	ال سياس مساح المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد المساد الم				
Connecting capacity			20 - 14 AWG) rigid, f	ine-strand and wit	in wire end ferrule				
Stripping length		7 mm (0.28 in)							
Mounting (IEC/EN 60715)		DIN rail	1/0						
Material		PA6 + GF - UL94	VU						
	contacts								
	contact surface								
	spring terminals	SUS301			_				
Isolation data	1	50001/15							
Isolation between coil and		5000 V AC							
Resistance to shock coil to		1000 ΜΩ							
Clearance and creepage d	istance	IEC/EN 61984			_				
Standards / Directives									
Standard		IEC/EN 61984							
Low Voltage Directive		2014/35/EU							
RoHS Directive		2011/65/EU							

 $<sup>^{\</sup>star}$  In combination with optocouplers, only DC supply is allowed

\_

# Pluggable interface relays and optocouplers

Technical data - CR-S jumper bars

Rated operational voltage / current	CR-SJB20-BLUE	CR-SJB20-RED	CR-SJB20-BLACK
Rated operational voltage	250 V AC		
Rated operational current	36 A		
Electrical connection			
Jumper bar cross section	123.2 mm (4.850 in)		
Step distance	6.3 mm (0.248 in)		
Rail length with isolation	16.7 mm (0.657 in)		
without isolatio	6.7 mm (0.264 in)		
Stripping length of a connection wire that is used in combination with a jumper bar	7 mm (0.276 in)		
Environmental data			
Ambient temperature range operatio	n -40 +70 °C		
General data			
Material of rail	Cu	-	
Number of pins	20		
Flammability	VO		

Technical data – CR-P, CR-M, CR-U

Input circuit - coil data

### CR-P range

	Rated control supply voltage U <sub>s</sub>	Rated frequency	Make voltage (at 20 °C)	Maximum voltage*	Break voltage	Rated power	Coil resistance (at 20 °C)	Tolerance of coil resistance
DC coils	12 V DC	-	8.4 V DC	30.6 V DC	≥ 0.1 U <sub>s</sub>	0.4-0.48 W	360 Ω	± 10%
	24 V DC	-	16.8 V DC	61.2 V DC	≥ 0.1 U <sub>s</sub>	0.4-0.48 W	1440 Ω	± 10%
	48 V DC	-	33.6 V DC	122.4 V DC	≥ 0.1 U <sub>s</sub>	0.4-0.48 W	5700 Ω	± 10%
	110 V DC	-	77 V DC	280 V DC	≥ 0.1 U <sub>s</sub>	0.4-0.48 W	25200 Ω	± 10%
AC coils	24 V AC	50 / 60 Hz	19.2 V AC	28.8 V AC	≥ 0.15 U <sub>s</sub>	0.75 VA	400 Ω	± 10%
	48 V AC	50 / 60 Hz	38.4 V AC	57.6 V AC	≥ 0.15 U <sub>s</sub>	0.75 VA	1550 Ω	± 10%
	110 V AC	50 / 60 Hz	88 V AC	132 V AC	≥ 0.15 U <sub>s</sub>	0.75 VA	8900 Ω	± 10%
	120 V AC	50 / 60 Hz	96 V AC	144 V AC	≥ 0.15 U <sub>s</sub>	0.75 VA	10200 Ω	± 10%
	230 V AC	50 / 60 Hz	184 V AC	276 V AC	≥ 0.15 U <sub>s</sub>	0.75 VA	38500 Ω	± 10%

#### **CR-P** optocouplers range

Input circuit	CR-P024MOS1	CR-P024TRI1
Input resistance	2200 Ω	1950 Ω
Rated control voltage	24 V DC	24 V DC
Pull-in voltage	10 V DC	10 V DC
Maximum control voltage	32 V DC	32 V DC
Nominal input current	10 mA	12 mA
Input power	260 mW	295 mW
Typical switching-on time	50 ms	< 1/2 cycle
Typical switch-off time	250 ms	< 1/2 cycle

#### **CR-M** range

	Rated control supply voltage U <sub>s</sub>	Rated frequency	Make voltage (at 20 °C)	Maximum voltage*	Break voltage	Rated power	Coil resistance (at 20 °C)	Tolerance of coil resistance
DC coils	12 V DC	-	9.6 V DC	13.2 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	160 Ω	± 10%
	24 V DC	-	19.2 DC	26.4 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	640 Ω	± 10%
	48 V DC	-	38.4 V DC	52.8 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	2600 Ω	± 10%
	60 V DC	-	48 V DC	66 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	4000 Ω	± 10%
	110 V DC	-	88 V DC	121 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	13600 Ω	± 10%
	125 V DC	-	100 V DC	137.5 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	16000 Ω	± 10%
	220 V DC	-	176 V DC	242 V DC	≥ 0.1 U <sub>s</sub>	0.9 W	54000 Ω	± 10%
AC coils	24 V AC	50 / 60 Hz	19.2 V AC	26.4 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	158 Ω	± 10%
	48 V AC	50 / 60 Hz	38.4 V AC	52.8 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	640 Ω	± 10%
	60 V AC	50 / 60 Hz	48 V AC	66 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	930 Ω	± 10%
	110 V AC	50 / 60 Hz	88 V AC	121 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	3450 Ω	± 10%
	120 V AC	50 / 60 Hz	96 V AC	132 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	3770 Ω	± 10%
	230 V AC	50 / 60 Hz	184 V AC	253 V AC	≥ 0.2 U <sub>s</sub>	1.6 VA	16100 Ω	± 10%

 $<sup>^{\</sup>star}$  Refer to CR-U: Operating range of coils

Technical data – CR-P, CR-M, CR-U

### **CR-U** range

1	Rated control supply voltage U <sub>s</sub>	Rated frequency	Make voltage (at 20 °C)	Maximum voltage*	Break voltage	Rated power	Coil resistance (at 20 °C)	Tolerance of coil resistance
D.C. 11	10,450		0.64486	12.27/20		4.534	1100	1.10.0/
DC coils	12 V DC	-	9.6 V DC	13.2 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	110 Ω	± 10 %
	24 V DC	-	19.2 V DC	26.4 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	430 Ω	± 10 %
	48 V DC	-	38.4 V DC	52.8 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	1750 Ω	± 10 %
	110 V DC	-	88.0 V DC	121.0 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	9200 Ω	±10 %
	125 V DC	-	100 V DC	137.5 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	11000 Ω	± 10 %
	220 V DC	-	176.0 V DC	242.0 V DC	≥ 0.1 U <sub>s</sub>	1.5 W	37000 Ω	± 10 %
AC coils	24 V AC	50 / 60 Hz	19.2 V AC	26.4 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	75 Ω	± 10 %
	48 V AC	50 / 60 Hz	38.4 V AC	52.8 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	305 Ω	± 10 %
	60 V AC	50 / 60 Hz	48.0 V AC	66.0 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	475 Ω	± 10 %
	110 V AC	50 / 60 Hz	88.0 V AC	121.0 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	1700 Ω	± 10 %
	120 V AC	50 / 60 Hz	96.0 V AC	132.0 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	1910 Ω	± 10 %
	230 V AC	50 / 60 Hz	184.0 V AC	253.0 V AC	≥ 0.15 U <sub>s</sub>	2.8 VA (50 Hz) 2.5 VA (60 Hz)	7080 Ω	± 10 %

 $<sup>^{\</sup>star}$  Refer to CR-U: Operating range of coils

Technical data – CR-P, CR-M, CR-U

Туре			CR-P1	CR-P2	CR-M2	CR-M3	CR-M4	CR-U2	CR-U3			
Output circuit(s)			11-12/14	11-12/14 21-22/24	11-12/14 21-22/24	11-12/14 21-22/24 31-32/34	11-12/14 21-22/24 31-32/34 41-42/44	11-12/14 31-32/34	11-12/14 21-22/24 31-32/34			
Kind of output			Relay, 1 c/o	Relay, 2 c/o	Relay, 2 c/o	Relay, 3 c/o	Relay, 4 c/o	Relay, 2 c/o	Relay, 3 c/o			
Contact material			AgNi	AgNi AgNi/Au 5 µm	AgNi	AgNi AgNi AgNi AgNi 5 µm						
Rated operationa (VDE 0110, IEC 6			250 V AC									
Minimum switch			5 V		10 V (AgNi); 5	V (AgNi/Au)		10 V				
Maximum switch	ning voltage	DC	300 V DC		250 V DC							
AC			440 V AC		250 V AC			440 V AC				
Minimum switching current		5 mA (AgNi), 2 mA (AgNi/A	u)	5 mA (AgNi)	5 mA (AgNi)	2 mA (AgNi/Au)	5 mA					
Rated free air thermal current I <sub>th</sub>			16 A	8 A	12 A	10 A	6 A	10 A				
Rated	-	stive) 230 V		8 A	12 A	10 A	6 A	10 A				
operational current		ctive) 230 V		1.5 A	1.5 A	1.5 A	1 A	1.5 A				
(IEC 60947-5-1)	-	ctive) 120 V		1	1	1	1.5 A	3 A				
		sistive) 24 V		8 A	12 A	10 A	6 A	10 A				
		uctive) 24 V		2 A	2.5 A	2.5 A	2 A	2 A				
	DC-13 (inductive) 120 V DC-13 (inductive) 250 V											
AC rating (UL 508)	utilization cat duty) (contact	tegory (pilot			B300		B300					
	max. rated	operational voltage	300 V AC		300 V AC			300 V AC				
	the	continuous rmal current on category			5 A	5 A	2.5 A 5 A					
		g / breaking apparent at utilization category	3600 / 360 VA		3600 / 360 VA	1	1800 / 180 VA	3600/360 VA				
		on category (resistive) 2.2 No.14)		8 A, 250 V AC	10 A, 250 V AC 12 A,150 V AC	6 A, 250 V AC 10 A, 150 V AC	5 A, 250 V AC 10 A, 150 V AC	10 A, 250 V A (resistive + s				
DC rating * (UL 508; NEMA ICS-5)	utilizati (contact	on category (pilot duty) rating code designation)	R300		122,92501710	1200000	1200 1110					
		operational voltage	300 V DC									
	the	. continuous rmal current on category	1 A									
		g / breaking apparent at utilization category	28 VA									
		on category (resistive)	-	10 A, 24 V DC	-			10 A, 28 V DC				
(CSA22.2 No.14) Maximum making (inrush) current			30 A	15 A	24 A	20 A	12 A	20 A				
Minimum switching power		-	0.3 W (AgNi), 0.05 W (AgNi)			D.1 W (AgNi/Au		0.3 W				
Maximum switch power	ning (breaking)	AC1 (resistive)	4000 VA	2000 VA	3000 VA	2500 VA	1500 VA	2500 VA				
Contact resistan	ce		≤ 100 mΩ									
Maximum operat	ting frequency	rated load AC-1			1200 switching cycles/h							
		without load	72000 switch	ing cycles/h	18000 switch	ing cycles/h		12000 switch	ning cycles/h			

Technical data – CR-P, CR-M, CR-U

Туре		CR-P1	CR-P2	CR-M2	CR-M3	CR-M4	CR-U2	CR-U3		
Mechanical lifetime	e	> 3 x 10 <sup>7</sup> swit	ching cycles	> 2 x 10 <sup>7</sup> swite	ching cycles					
Electrical lifetime	electrica AC:		> 10 <sup>5</sup> switching	> 10 <sup>5</sup> switchin (12 A, 250 V)		(6 A, 250 V)		> 10 <sup>5</sup> switching cycles (12 A, 250 V)		
	(resistive	) cycles cycles (16 A, 250 V) (8 A, 250 V)		(12 A, 230 V)	(10 A, 250 V)					
	cos	see reduction	n factor F							
Response time		typ. 7 ms		typ. 13 ms (D	C), 10 ms (AC)		typ. 18 ms	(DC), 12 ms (AC)		
Release time		typ. 3 ms		typ. 3 ms (DC	), 8 ms (AC)		typ. 7 ms ([	OC), 10 ms (AC)		
Isolation data		,		*						
Rated insulation vo	oltage	400 V AC		250 V AC						
Insulation class (In accordance to V	nsulation class In accordance to VDE 0110b)			C250 / B250			C250			
Rated impulse	between coil and contacts	5 kV (1.2/50	us)	2.5 kV (1.2/50	) μs)		'			
withstand	between open contacts	1 kV (1.2/50	us)	1.5 kV (1.2/50	) μs)					
voltage U <sub>imp</sub> —	between c/o (SPDT contacts		2.5 kV (1.2/50 μs)	2.5 kV (1.2/5	0 μs)	≥ 2 kV (1.2/50 µs)	2 kV (1.2/50	) μs)		
Clearance between	coil and contacts	≥ 10 mm		≥ 2.5 mm		≥ 1.6 mm	≥ 3 mm			
Creepage distance contacts	between coil and	≥ 10 mm		≥ 4 mm		≥ 3.2 mm	≥ 4.2 mm			
Overvoltage categ	ory	III		III		II .	III			
Pollution degree		3	3			2	3			
General data										
Dimensions		see 'Dimensi	onal drawings'	,				,		
Mounting		on socket (see accessories)								
Mounting position		any	any							
Degree of protecti	on	IP 67		IP 40						
Electrical connect	ion									
Connection		by socket								
Environmental dat	:a							1		
Ambient temperat	ure range operation	DC: -40+85 AC: -40+70	•	DC: -40+70	°; AC: -40+55	°C				
	storage	e -40 +85 °C								
Vibration resistant	ce n/o contac	10 g		5 g			5 g			
10-150 Hz	n/c contac	10 g	5 g	5 g			5 g			
Shock resistance	n/o contac	t 30 g	20 g	10 g			10 g			
	n/c contac	t 30 g	20 g	5 g			10 g			
Standards / Direct	tives									
Standards		IEC/EN 61810	0-1							
Low Voltage Direct	rive	-	- 2014/35/EU							
RoHS Directive		2011/65/EU								

 $<sup>^{\</sup>star}\,\text{These ratings are based on different type tests which are not covered by the cULus or CSA approvals.}$ 

#### \_

# Pluggable interface relays and optocouplers

Technical data – CR-P optocouplers

Output circuits		CR-P024MOS1	CR-P024TRI1			
Output circuit(s)		11 (13+) - 14	11 (13+) - 14			
Kind of output		MOS-FET	Triac			
Rated operational voltage		24 V DC	240 V AC			
Maximum switching voltage		35 V DC	275 V AC			
Minimum switching current		1 mA	50 mA			
Maximum switching current continuously		5 A	3,5 A			
Leakage current at maximum switching voltage		10 uA	1 mA			
Voltage drop at rated current		300 mV	1.1 V			
Isolation data						
Rated insulation voltage	input/output	2.5 kV	2.5 kV			
Insulation class		2	2			
Clearance	input/output	19 mm	19 mm			
Creepage distance	input/output	19 mm	19 mm			
Overvoltage category		III	III			
Pollution degree		2	2			
General data						
Dimensions		see 'Dimensional drawings'				
Weight		11 g (0.618 lbs)	11 g (0.618 lbs)			
Mounting		on socket	on socket			
Environmental data						
Ambient temperature	operational	-20+80 °C	-20+80 °C			
	storage	-40+100 °C	-40+100 °C			
Standards / Directives						
Standards		IEC/EN 62314	IEC/EN 62314			
EMC Directive		2014/30/EU	2014/30/EU			
RoHS Directive		2011/65/EU	2011/65/EU			

Technical data - CR-P and CR-M sockets

Output circ	uits	CR-PLS	CR-PSS	CR-PLC	CR-MxLS	CR-MxSS	CR-MxSF	CR-M4LC	CR-M2LSH	CR-M3LSH
Output circ	uit(s)	11-12/14, 2	1-22/24		11-12/14, 2	1-22/24,			11-12/14, 21-22/24	11-12/14, 21-22/24, 41-42/44
Number of p	ooles	2			2, 3 or 4		2 or 4	4	2	3
Rated voltag	ge	250 V AC/D	С		250 V AC/D	С		300 V AC/ DC	250 V AC	
Rated curre	nt	2 x 10 A <sup>1)</sup>	2 x 10 A <sup>1)</sup>		7 A			10 A	12 A	10 A
General dat	a		•							
Dimensions and module	without holder (L x W x H)	76 x 15.8 x 62 mm (2.992 x 0.622 x 2.441 in)	76 x 15.8 x 42.8 mm (2.992 x 0.622 x 1.685 in)	97.5 x 16.3 x 45.2 mm (3.839 x 0.642 x 1.780 in)	75 x 27.2 x 60.8 mm (2.952 x 1.071 x 2.394 in)	75.2 x 27.2 x 42.6 mm (2.961 x 1.071 x 1.677 in)	66.7 x 30.3 x 29 mm (2.626 x 1.193 x 1.142 in)	95 x 31 x 42.5 mm (3.74 x 1.22 x 1.67 in)	75.5 x 27.2 x 61.1 mm (2.972 x 1.071 x 2.406 in)	
Degree of protection	terminals	IP 20 B (EN	60529)			·				
Temperatur	e operation	-40+70 °C						-25+85 °C	-40+70 °C	
range	storage	-40+70 °C								
Connection	type	screw conne	ection	spring connec- tion	screw conne	ection	fork type screw	spring connec- tion		
Maximum number of wires per connecting terminal		2		2 (one per connec- tion point)	2 -		2 (one per connec- tion point)	2		
-		2 x 0.5 - 2.5 mm <sup>2</sup> (2 x 20 - 14 AWG)		2 x 0.2 - 1.5 mm <sup>2</sup> (2 x 24 - 16 AWG)	2 x 0.5 - 2.5 mm <sup>2</sup> (2 x 20 - 14 AWG)			2 x 0.5 - 1.5 mm <sup>2</sup> (2 x 20 - 16 AWG)	2 x 0.5 - 2.5 mm <sup>2</sup> (2 x 20 - 14 AWG)	
	with wire end ferrule	2 x 0.5 - 1.5 (2 x 20 - 16 /		2 x 1.5 mm <sup>2</sup> (2 x 16 AWG)	2 x 0.5 - 1.5	mm² (2 x 20 -	16 AWG)	2 x 1.5 mm <sup>2</sup> (2 x 16 AWG)	2 x 0.5 - 1.5 (2 x 20 - 16 /	
Stripping le	ngth	7 mm (0.28 in)		11 mm (0.43 in)	7 mm (0.28 in)			10 mm (0.39 in)	7 mm (0.28 in)	
Tightening t	torque	0.6 Nm (5.3	1 lb.in)							
Maximum	with 0,2 mm <sup>2</sup>	-	-	10 N	-	-	-	10 N		
clamping	with 1,5 mm <sup>2</sup>	-	-	40 N	-	-	-	40 N		
force	with wire end ferrule	-			-	-	-	> 40 N	40 N	
Mounting		DIN rail (IEC	(/EN 60715)							
Material		PA 6 + GF - l	JL94 V0		PA 6+GF - U	L94 V0			PA 6+GF - U	L94 V0
	contacts				CuZn33				Copper allo	/
	contact surface	•	5 μ Ni		5 μ Ni		6 μ Ni	5 μ tinned	5 μ Ni	
	terminals		8 μ Ni	XCrNi Steel	8 μ Ni			CCSC	5 μ Ni	
	combi screw M3	8.8 Steel, 5µ	ı Ni	-	8.8 Steel, 5 <sub>1</sub>	ı Ni		-	2 μ Ni	
Isolation da										
Insulation v		> 5 kV			> 3 kV		> 4 kV		> 2 kV	
Isolation be and contact		IEC/EN 619	84						> 1000 MΩ	
Clearance a distance	nd creepage	IEC/EN 619	84							
Standards /	Directives									
Standards		IEC/EN 619	84						IEC 61984	
Low Voltage	Directive	2014/35/EU	J							
RoHS Direct	tive	2011/65/EU	J							

 $<sup>^{1)}</sup>$  Loads >10 A ( >12 A for CR-PLSx) require jumpering of terminal 11 with 21, 12 with 22, and 14 with 24

#### \_

# Pluggable interface relays and optocouplers

Technical data - CR-P and CR-M jumper bars, CR-P and CR-M function modules

Rated operational voltage / Rated curr	ent	CR-PJ	CR-MJ	
Rated operational voltage (VDE 0660 / part 500)		400 V		
Rated current (VDE 0660 / part 500)		25 A		
Electrical connection				
Bus bar diameter		6 mm² (0.0093 in²)		
Step distance		15.5 mm (0.610 in)	27.2 mm (1.071 in)	
Rail length	with isolation	150 mm (5.906 in)	255 mm (10.039 in)	
	without isolation	141.5 mm (5.571 in)	245 mm (9.646 in)	
Stripping length of a connection wire the combination with a jumper bar	nat is used in	6 mm (0.236 in)		
Environmental data				
Ambient temperature range	operation	-40 +55 °C		
Isolation data				
Rated impulse withstand voltage U <sub>imp</sub> (VDE 0660 / part 500)		4 kV (1.2/50 μs)		
Overvoltage category (IEC/EN 60664)		III		
Polution degree (IEC/EN 60664)		2		
General data				
Material of rail	·	E-Cu-F25		
Type of rail		pin type		
Number of pins		10		
Number of phases		1		
Color of insulating material		RAL 7035		
Flammability (UL 94)		VO		

#### Technical data - CR-P and CR-M function modules

CR-P/M 22	1				1				
Туре	'	CR-P/M 22			'				
Version		Diode	ode						
Function		Reverse polar	everse polarity protection						
Control supply voltage	2	6-220 V DC							
Component data	diode	1 A, 1000 V							
Polarized		yes (A1+, A2-)							
Material	enclosure / base	PA6 + GF - ULS	PA6 + GF - UL94 V0						
CR-P/M 42									
Туре	,	CR-P/M 42	R-P/M 42 CR-P/M 42V CR-P/M 42B CR-P/M 42BV				CR-P/M 42CV		
Version		Diode and LE	D						
Function		Reverse polar	ity protection / f	ree-wheeling diod	le and LED to indic	ate energized coil			
Control supply voltage	1	6-24 V DC 24-60 V DC				110 V DC			
Component data	diode	1 A, 1000 V	1 A, 1000 V						
	LED	red	green	red	green	red	green		
	resistance	3 kΩ, 0.25 W		15 kΩ, 0.25 W	15 kΩ, 0.25 W		200 kΩ, 0.25 W		
Polarized		yes (A1+, A2-)							
Material	enclosure / base	PA6 + GF - UL	94 V0						
CR-P/M 52	,	,	,	1	,				
Туре	1	CR-P/M 52B		CR-P/M 52D		CR-P/M 52C			
Version		RC element							
Function		Spark quench	ing						
Control supply voltage	2	6-24 V AC/DC		24-60 V AC/DC	24-60 V AC/DC		C		
Component data	capacitor	0.1 μF, 63 V D	С	0.1 μF, 100 V DC		110-230 V AC/DC 0.082 μF, 400 V DC			
•	resistance	10 Ω, 0.25 W		47 Ω, 0.25 W		100 Ω, 0.25 W			
Polarized		no		1					
Material	enclosure / base	PA6 + GF - UL	94 V0						

\_\_\_

# Pluggable interface relays and optocouplers

Technical data - CR-P and CR-M function modules

CR-P/M 62										
Туре		CR-P/M 62	CR-P/M 62V	CR-P/M 62E	CR-P/M 62EV	CR-P/M 620	C CR-P/M 6	52CV	CR-P/M 6	2D CR-P/M 62D
Version		Diode and LED				Varistor and LED				
Function				Overvoltage protection and LED to indicate energized coil				dicate		
Control supply voltage		6-24 V AC/	DC	24-60 V AC	/DC	6-24 V AC/	DC		24-60 V A	C/DC
Component data	diode	1 A, 1000 V								
-	LED	red	green	red	green	red	green		red	green
-	varistor	25 V AC		75 V AC	1	25 V AC			75 V AC	
	resistance	3 kΩ, 0.25	W	15 kΩ, 0.25	W	3 kΩ, 0.25 W			15 kΩ, 0.25 W	
Polarized		AC: no, DC:	yes (A1+, A2-	-)						
Material	enclosure / base	PA6 + GF -	PA6 + GF - UL94 V0							
CR-P/M 72, 82										
Туре		CR-P/M 72 CR-P/M 72A			CR	R-P/M 8	82			
Version		Varistor	Varistor							
Function		Overvoltag	Overvoltage protection							
Control supply voltage		24 V AC 115 V AC				23	80 V AC			
Component data	varistor	25 V AC 115 V AC			275 V AC					
Polarized		no								
Material	enclosure / base	PA6 + GF -	UL94 V0							
CR-P/M 92										
Туре		CR-P/M 92		CR-P/M 92\	/	CR-P/M 92	:C		CR-P/M 9	2CV
Version		Diode and	LED			Varistor ar	nd LED			
Control supply voltage		110-230 V	AC/DC							
Function		LED to indi	cate energize	ed coil		Overvoltage energized	ge protection	on and	LED to in	dicate
Component data	diode	1 A, 1000 V	1							
	LED	red		green		red			green	
-	varistor	275 V AC								
-	resistance	120 kΩ, 0.2	25 W							
Polarized		AC: no, DC: yes (A1+, A2-)								
Material	enclosure / base	PA6 + GF -	UL94 V0							
Standards / Directives										
Standards		IEC/EN 619	984							
Low Voltage Directive		2014/35/E	:U							
RoHS Directive		2011/65/E	U							

Technical data - CR-U sockets and function modules

Output circuits		CR-U2S	CR-U3S	CR-UxSM			
Output circuit(s)		11-12/14, 21-22/24,					
Number of poles		2	3	2 or 3			
Rated voltage		250 V AC		250 V AC			
Rated current		10 A					
General data		•					
Dimensions		see 'Dimensional drawings'					
Degree of protect	ion terminals	IP 20 B (EN 60529)					
Temperature rang	ge operation	-40+70 °C		-40+70 °C			
	storage	-40+70 °C		-40+70 °C			
Connecting	rigid	2 x 2 x 0,5 - 2,5 mm² (2 x 20 - 14 AWC	G)				
capacity fine-strand			77 77 V V V V V V V V V V V V V V V V V				
with wire end ferrule		2 x 0.5 - 1.5 mm <sup>2</sup> (2 x 20 - 16 AWG)	2 x 0.5 - 1.5 mm <sup>2</sup>				
				(2 x 20 - 16 AWG)			
Stripping length		7 mm (0.28 in)					
Tightening torque		0.6 Nm 0.6 Nm					
Mounting		DIN rail (IEC/EN 60715)					
Material	socket	PA 6+GF - UL94 V0					
	contacts	CuZn33					
	contact surface	6 μ Ni		3 μ Ni			
	terminals	8 μ Ni		10 μ Νί			
	combi screw M3	8.8 steel, 5μ Ni		Steel, 8 μ Ni			
Isolation data							
Insulation voltage	2	> 2 kV					
Isolation between coil and contacts		IEC/EN 61984					
Clearance and creepage distance		IEC/EN 61984					
Standards/Direc	tives						
Standards IEC/EN 619		IEC/EN 61984	C/EN 61984				
Low Voltage Direc	ctive	2014/35/EU					
RoHS Directive		2011/65/EU					

### Technical data - CR-U function modules

CR-U 21								
Туре		CR-U 21						
Version		Diode						
Function		Reverse polarit	ty / free-wheel	ling diode				
Control supply voltage		6-220 V DC						
Component data	Diode	1 A, 1000 V						
Polarized		yes (A1+, A2-)						
Material	Enclosure / Base	PA6 + GF - UL94 VO						
CR-U 41								
Туре		CR-U 41				CR-U 41CV		
Version		Diode and LED	Diode and LED					
Function		Reverse polarity / free-wheeling diode and LED to indicate energized coil						
Control supply voltage		6-24 V DC		24-60 VDC		110 V DC		
Component data	Diode	1 A, 1000 V						
	LED	red	green	red	green	red	green	
	Resistance	3 kΩ, 0.25 W		15 kΩ, 0.25 V	V	200 kΩ, 0.25	5 W	
Polarized		yes (A1+, A2-)						
Material	Enclosure / Base	PA6 + GF - UL9	4 V0					

Technical data - CR-U function modules


CR-U 51				-					
Туре		CR-U 51B			CR-U 51D		CR-I	U 51C	
Version		RC elemen	t						
Function		Spark quer	nching						
Control supply voltage		6-24 V AC/	DC .		24-60 V AC/D0	C 110-230 V AC/DC			
Component data	Capacitor	0.1 μF, 63 \	/ DC		0.1 μF, 100 V D	С	0.08	32 μF, 400 V DC	
	Resistance	10 Ω, 0.25	W		47 Ω, 0.25 W		100	Ω, 0.25 W	
Polarized		no							
Material	Enclosure / Base	PA6 + GF -	UL94 V0						
CR-U 61									
Туре		CR-U 61	CR-U 61V	CR-U 6	1E CR-U 61EV	CR-U 61C	CR-U 61	CV CR-U 61D	CR-U61DV
Version		Diode and	LED			Varistor a	nd LED		
Function			larity protec LED to indica	-	_	Overvolta energized	<b>.</b>	ion and LED to	indicate
Control supply voltage		6-24 V AC/DC 24-60 V AC/DC			6-24 V AC/DC 24-60 V AC/DC			C/DC	
Component data	Diode	1 A, 1000 V	1						
	LED	red	green	red	green	red	green	red	green
_	Resistance	3 kΩ, 0.25	W	15 kΩ,	0.25 W	3 kΩ, 0.25	W	15 kΩ, 0.25	5 W
Polarized		AC: no, DC: yes (A1+, A2-)							
Material	Enclosure / Base	PA6 + GF - UL94 V0							
CR-U 71, 81									
Туре		CR-U 71	CR-U 71 CR-U 71A			CR-U 81			
Version		Varistor							
Function		Overvoltag	ge protection	1					
Control supply voltage		24 V AC		1	115 V AC		23	30 V AC	
Component data	Varistor	25 V AC		1	115 V AC		27	75 V AC	
Polarized		no							
Material	Enclosure / Base	PA6 + GF -	UL94 V0						
CR-U 91									
Туре		CR-U 91		CR-U 9	1V	CR-U 91C		CR-U 91CV	1
Version		Diode and	LED			Varistor a	nd LED		
Function		LED to indi	icate energiz	ed coil		Overvolta energized	<b>.</b>	ion and LED to	indicate
Control supply voltage		110-230 V	AC/DC						
Component data	Diode	1 A, 1000 V	/						
_	LED	red		green		red		green	
	Resistance	120 kΩ, 0.2	25 W						
Polarized		AC: no, DC	: yes (A1+, A2	-)					
Material	Enclosure / Base	PA6 + GF -	UL94 V0						
Standards / Directives									
Standards	·	IEC/EN 619	984						
Low Voltage Directive		2014/35/E	U						
RoHS Directive		2011/65/E	:U						


#### \_

### Pluggable interface relays and optocouplers


### Technical diagrams


#### **Connection diagrams**






CR-P/M 62, CR-P/M 62E, CR-P/M 92, CR-P/M 62V, CR-P/M 62EV, CR-P/M 92V







CR-U 61, CR-U 61E, CR-U 91, CR-U 61V, CR-U 61EV, CR-U 91V




CR-P/M 42, CR-P/M 42B, CR-P/M 42C, CR-P/M 42V, CR-P/M 42BV, CR-P/M 42CV




CR-P/M 62C, CR-P/M 62D, CR-P/M 92C, CR-P/M 62CV, CR-P/M 62DV, CR-P/M 92CV




CR-U 41, CR-U 41B, CR-U 41C, CR-U 41V, CR-U 41BV, CR-U 41CV




CR-U 61C, CR-U 61CV, CR-U 61D, CR-U 61DV, CR-U 91C, CR-U 91CV




CR-P/M 52B, CR-P/M 52C CR-P/M 52D,



CR-P/M 72, CR-P/M 82 CR-P/M 72A,




CR-U 51B, CR-U 51C CR-U 51D



CR-U 71, CR-U 71A , CR-U 81


Technical diagrams

### Connection diagrams




### Technical diagrams

#### **CR-P: Operating range of coils**




Operating range of DC coil




Operating range of AC coil

- unloaded contacts, coil temperature = ambient temperature
- B continued with  $I_{th}$  (16 A at CR-P ... 1 and 8 A at CR-P ... 2) loaded contacts coil heated with 1,1 x U  $_{s}$
- 1 at unloaded contacts
- 2 at 50 % rated load
  - at rated load

#### **CR-M: Operating range of coils**




Operating range of DC coil - 2 c/o




Operating range of AC coil – 2 c/o

- A relations between make voltage and ambient temperature at no load on contacts. Coil temperature and ambient temperature are equal before coil energizing. Make voltage is not higher than the value read on Y axis (multiplication of rated voltage)
- B relations between make voltage and ambient temperature after initial coil heating up with 1,1 U<sub>n</sub>, at continues load of I<sub>n</sub> on contacts. Make voltage is not higher than the value read on Y axis (multiplication of rated voltage)
- 1, 2 values on Y axis represent allowed overvoltage on coil at certain ambient temperature and contact load:
- 1 no load
- 2 rated load




Operating range of DC coil - 3 c/o




Operating range of AC coil - 3 c/o


### Technical diagrams


#### CR-M: Operating range of coils





CR-U: Operating range of coils





Operating range of DC coil - 3 c/o


Operating range of AC coil - 3 c/o

- A relations between make voltage and ambient temperature at no load on contacts. Coil temperature and ambient temperature are equal before coil energizing. Make voltage is not higher than the value read on Y axis (multiplication of rated voltage)
- B relations between make voltage and ambient temperature after initial coil heating up with 1,1 U<sub>n</sub>, at continues load of I<sub>n</sub> on contacts. Make voltage is not higher than the value read on Y axis (multiplication of rated voltage)
- 1, 2 values on Y axis represent allowed overvoltage on coil at certain ambient temperature and contact load:
- 1 no load
- 2 rated load

#### **Electrical connection**

A2	A2	21     	24	21	22
A1		11   	14	11	12
2000	200003 063 500004				

CR-PLS





	21	11				
	24	14				
	21   	11   				
	A2	<b>△</b> ↑				
	A2	A1				
	22	12				
Ī	CR-PSS					

A1-A2	Supply voltage
11-12/14,	Relay outputs
21-22/24	Relay outputs

### Technical diagrams

### Mounting and removal of sockets






Mounting

Removal

### Electrical connection

41			11
44			14
42			12
	41   	11	1
	A2	<b>△</b> ↑	
A2	A2		A1



41	31	21	11
44	34	24	14
42	32	22	12
41   		21   	11                   
	A2	A1	
A2	A2		A1

CR-M2LS(H)

CR-M4LS

41			11			
44			14			
42			12			
2	41    -  -  -  -  -  -  -  -  -  -  -  - 	11   	 			
A2 A1 A1						
A2			A1	262 202		


CR-M2LC

41	31	21	11		
44	34	24	14		
42	32	22	12		
41   	31                                     	21                                     	11   		
A2 A1					
A2			A1		

CR-M4LC

# Technical diagrams

#### **Electrical connection**



CR-	М	2	s	S,
CR-	М	2	s	F

A1-A2	Supply voltage
11-12/14,	Relay outputs
41-42/44	Relay outputs

34	24	14	
32	22	12	
31     7   32 34	21                                     	11 	
     A	2 A	1	104
A2		A1	2CDC 292 069 F0004
31	21	11	2CDC298

CR-M3SS

A1-A2	Supply voltage
11-12/14,	Relay outputs
21-22/24,	Relay outputs
31-32/34	Relay outputs


44	34	24	14	
42	32	22	12	
41    -    -    -    -    -    -  -  -  -	31                                     	21                                     	11   	
	A2	<b>△</b> ↑		94
A2			A1	2CDC 292 068 F0004
41	31	21	11	2CDC 292


CR-M4SS, CR-M4SF

A1-A2	Supply voltage
11-12/14,	Relay outputs
21-22/24	Relay outputs
31-32/34	Relay outputs
41-42/44	Relay outputs

### Technical diagrams

#### Technical diagrams CR-S interface relays







Max. DC load breaking capacity


Endurance curve

#### Load limit curves CR-P, CR-M and CR-U - Electrical lifetime at resistive AC load


2CDC 292 012 F0214










CR-P with 1 c/o contact



CR-U with 2 and 3 c/o contacts








CR-M with 2 c/o contacts


CR-M with 3 c/o contacts


CR-M with 4 c/o contacts

### Technical diagrams

#### Load limit curves CR-P, CR-M and CR-U - Maximum switching power at resistive DC load










CR-P with 1 c/o contact

CR-P with 2 c/o contacts

CR-U with 2 and 3 c/o contacts









CR-M with 2 c/o contacts


CR-M with 3 c/o contacts

CR-M with 4 c/o contacts

#### Reduction factor CR-P, CR-M and CR-U - F at inductive AC load








CR-P CR-M


#### \_


# Pluggable interface relays and optocouplers

# Technical diagrams

#### **Derating curves**









Derating curve Transistor output CR-S

Derating curve MOS-FET output CR-S

Derating curve Triac output CR-S






MOS-FET output CR-P


Triac output CR-P

# Technical diagrams


#### **Dimensional drawings**




CR-S relay




 ${\sf CR\text{-}S}\ socket\ \text{-}\ spring\ connection$ 






 ${\sf CR\text{-}S}\ socket\ \text{-}\ screw\ connection$ 



CR-S separator




CR-SJB20 - blue, CR-SJB20 - red, CR-SJB20 - black jumper bar

#### \_


# Pluggable interface relays and optocouplers

### Technical diagrams


#### Dimensional drawings



CR-P relay




CR-PLS - screw connection




CR-PSS - screw connection





CR- P/Mxx function module



CR-P optocoupler










CR-PJ jumper bar

### Technical diagrams


#### **Dimensional drawings**









CR-M relay with 3 c/o contacts




CR-M relay with 4 c/o contacts




CR-M2LS(H) - CR-M3LS(H) - CR-M4LS - screw connection




CR-MxSF - screw connection



CR-M2SS - CR-M3SS - CR-M4SS - screw connection



CR-M4LC - spring connection



CR-MJ jumper bar

#### \_


# Pluggable interface relays and optocouplers

# Technical diagrams


#### \_.

#### **Dimensional drawings**

in **mm** and inches





CR-U relay with 2 c/o contacts




**26** 1.024


CR-U relay with 3 c/o contacts







CR-U2SM - CR-U3SM - screw connection



 $\mathsf{CR}\text{-}\mathsf{Uxx}\,\mathsf{function}\,\mathsf{module}$ 



# Boxed interface relays and optocouplers R600 range

# Table of contents

480	Overview
482	Boxed interface relays R600 range
482	Selection table
484	Ordering details
486	Technical data
490	Technical diagrams
492	Boxed optocouplers R600 range
<b>492</b> 492	<b>Boxed optocouplers R600 range</b> Selection table
492	Selection table
492 493	Selection table Ordering details

# Boxed interface relays and optocouplers R600 range

# Overview



ABB's R600 range may be used in applications where electrical isolation, amplification and signal matching are required. The slim, compact design, incorporated with the variety of terminal connections available allow for the optimization of space within a control panel. This broad portfolio allows for the flexibility of choice and includes both electromagnetic relays and optocouplers.



The ABB boxed interface relays portfolio incorporates a large assortment of non-pluggable relays. It includes both electro-mechanical relays and optocouplers. The R600 Optocouplers allow for continuous operation without any mechanical wear-and -tear.




The 6 mm slim housing of the R600 boxed interface relays provides the possibility of space saving within control cabinets . The 75 mm depth of these relays allows for the use in compact cabinets.



# Boxed interface relays and optocouplers R600 range

# Overview




#### Complete product line

 $1\,\text{n/o}, 1\,\text{n/c}, 1\,\text{c/o}, 2\,\text{c/o}$  output configuration. Standard contact material for switching high current signals as well as gold-plated contacts for reliable switching of low current signals.




#### Marine certification

The R600 range offers the LR approval, which allows usage of the boxed interface relays and optocouplers in many applications around the marine segment. The performance of the R600 range has been proven by successfully passing tests required for operating under harsh conditions.




#### Safe operation

High resistance to vibration and shock thanks to the relay soldered inside of the housing. Wrong relay replacement or relay lose not possible . Devices with immunity to leakage currents.



#### Longevity

Optocoupler with transistor, MOS-FET and Triac output ensure a longer lifetime, higher reliability and quiet operation.



#### Easy to mount

The R600 interface relays and optocouplers are easy to mount by snapping onto a DIN-rail according to IEC/EN 60715. Time saving wiring thanks to a jumper bar.

# Selection table

					_								_	_	_	_								_		_
	Order number	1SNA645034R2300	1SNA645036R2500	1SNA645534R2500	1SNA645073R0000	1SNA645035R2400	1SNA645075R0000	1SNA645535R2600	1SNA645019R0400	1SNA645519R0600	1SNA645014R2700	1SNA645018R0300	1SNA645518R0500	1SNA645514R2100	1SNA645001R0300	1SNA645005R0700	1SNA645501R0500	1SNA645505R0100	1SNA645012R2500	1SNA645512R2700	1SNA645071R0000	1SNA645571R0000	1SNA645072R0000	1SNA645572R0000	1SNA645002R0400	1SNA645006R0000
_	ŏ	15	15	15	18	13	15	13	15	15	15	15	15	15	15	15	15	15	15	18	15	15	15	15	15	15
		RB121P-5VDC	RB121PG-5VDC	RBR121P-5VDC	RB121-12VDC	RB121P-12VDC	RB121G-12VDC	RBR121P-12VDC	RB101R-24VUC	RBR101R-24VUC	RB111-24VUC	RB111R-24VUC	RBR111R-24VUC	RBR111-24VUC	RB121-24VUC	RB121G-24VUC	RBR121-24VUC	RBR121G-24VUC	RB122G-24VUC	RBR122G-24VUC	RB121-24VDC	RBR121-24VDC	RB121G-24VDC	RBR121G-24VDC	RB121-48-60VUC	RB121G-48-60VUC
	Туре	RB12	RB12	RBR:	RB12	RB12	RB12	RBR	RB10	RBR:	RB11	RB11	RBR	RBR	RB12	RB12	RBR	RBR:	RB12	RBR	RB12	RBR:	RB12	RBR	RB12	RB12
Control voltage	•	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
5 V DC																										
12 V DC					-	•		•																		
24 V DC									-	•	•	•	•	-	-	-	-	-	•		•	•	-	•		
48-60 V DC																									•	-
115 V DC																										
230 V DC																										
60-230 V DC																										
24 V AC																										
48-60 V AC																										
115 V AC																										
230 V AC																										
60-230 V AC																										
Output rating																										
10 mA - 6 A					-	-		-	-	•				-	-						•	-			•	
3 mA - 6 A			-				-									-		-					-	•		=
1 mA - 8 A																										
Output contacts																										
c/o		1	1	1	1	1	1	1							1	1	1	1	2	2	1	1	1	1	1	1
n/o											1	1	1	1												
n/c									1	1																
Gold plated contacts			•													-								_		
Terminal type																										_
Screw			•		•	•						•			•	•			•		•		•		•	•
Spring																										

# Selection table

		_					_		_		_		_			_								_
	ımber	1SNA645502R0600	1SNA645506R0200	1SNA645040R1500	1SNA645540R1700	1SNA645003R0500	1SNA645007R0100	1SNA645046R0700	1SNA645503R0700	1SNA645507R0300	1SNA645041R0200	1SNA645541R0400	1SNA645016R2100	1SNA645017R2200	1SNA645004R0400	1SNA645008R1200	1SNA645011R2400	1SNA645504R0000	1SNA645508R1400	1SNA645511R2600	1SNA645013R2600	1SNA645513R2000	1SNA645020R0100	1SNA645520R0300
	Order number	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64	1SNA64
		3-60VUC	RBR121G-48-60VUC	3-60VUC	RBR122G-48-60VUC	VUC	5VUC	SVUC	SVUC	15VUC	.5VUC	15VUC	VUC	VUC	NUC	sovuc	OVUC	OVUC	230VUC	30VUC	SOVUC	230VUC	230VUC	)-230VUC
	Type	RBR121-48-60VUC	RBR121G-	RB122G-48-60VUC	RBR122G-	RB121-115VUC	RB121G-115VUC	RB121R-115VUC	RBR121-115VUC	RBR121G-115VUC	RB122G-115VUC	RBR122G-115VUC	RB111-115VUC	RB111-230VUC	RB121-230VUC	RB121G-230VUC	RB121R-230VUC	RBR121-230VUC	RBR121G-230VUC	RBR121R-230VUC	RB122G-230VUC	RBR122G-230VUC	RB121-60-230VUC	RBR121-60-230VUC
Control voltage																								
5 V DC																								
12 V DC																								
24 V DC																								
48-60 V DC																								
115 V DC									-				•											
230 V DC																								
60-230 V DC																							-	
24 V AC																								
48-60 V AC																								
115 V AC													•											
230 V AC																								
60-230 V AC																								
Output rating																								
10 mA - 6 A													•											
3 mA - 6 A			-																					
1 mA - 8 A																								
Output contacts																								
c/o		1	1	2	2	1	1	1	1	1	2	2			1	1	1	1	1	1	2	2	1	1
n/o													1	1										
n/c																								
Gold plated contacts			-	-						-		-							-			-		
Terminal type																								
Screw							•				•		•											
Spring									•	•		•							•			•		

### Ordering details



The R600 range comprises of boxed interface relays and optocouplers. In this range, the relay is soldered into device housing, fulfilling the highest vibration requirements. This compact range of relays are 6 mm wide and provide the possibility of switching AC and DC circuits with the same relay. All the sockets in this range are equipped with an indicator LED and available with screw or spring terminals.

Ordering details - 1 n/c contact: 250 V AC, 10 mA - 6 A, width 12 mm

Rated control supply voltage	Connection type	Particularities	Туре	Order code	Pkg qty	Weight (1 pc.)
						kg (lb)
24 V AC/DC	screw	RC circuit	RB101R-24VUC	1SNA645019R0400	5	0.04
	spring	parallel to output contact	RBR101R-24VUC	1SNA645519R0600		(0.088)

\_

Ordering details - 1 n/o contact: 250 V AC, 10 mA - 6 A, width 6 mm

Rated control supply voltage	Connection type	Particularities	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V AC/DC	screw		RB111-24VUC	1SNA645014R2700	10	0.02
115 V AC/DC	screw		RB111-115VUC	1SNA645016R2100		(0.044)
230 V AC/DC	screw		RB111-230VUC	1SNA645017R2200		
24 V AC/DC	spring		RBR111-24VUC	1SNA645514R2100		

\_

Ordering details - 1 n/o contact: 250 V AC, 10 mA - 6 A, width 12 mm

Rated control supply voltage	Connection type	Particularities	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V AC/DC	screw	RC circuit	RB111R-24VUC	1SNA645018R0300	5	0.04
	spring	parallel to output contact	RBR111R-24VUC	1SNA645518R0500		(0.088)

\_

#### Ordering details - 1 c/o (SPDT) contact: 250 V AC, 10 mA - 6 A, width 6 mm


Rated control supply voltage	Connection type	Particularities	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
5 V DC	screw	A1-A2 polarized	RB121P-5VDC	1SNA645034R2300	10	0.02
12 V DC	screw	A1-A2 polarized	RB121P-12VDC	1SNA645035R2400		(0.044)
12 V DC	screw		RB121-12VDC	1SNA645073R0000		
24 V DC	screw		RB121-24VDC	1SNA645071R0000		
24 V AC/DC	screw		RB121-24VUC	1SNA645001R0300		
48-60 V AC/DC	screw		RB121-48-60VUC	1SNA645002R0400		
115 V AC/DC	screw		RB121-115VUC	1SNA645003R0500		
230 V AC/DC	screw		RB121-230VUC	1SNA645004R0400		
5 V DC	spring	A1-A2 polarized	RBR121P-5VDC	1SNA645534R2500		
12 V DC	spring	A1-A2 polarized	RBR121P-12VDC	1SNA645535R2600		
24 V DC	spring		RBR121-24VDC	1SNA645571R0000		
24 V AC/DC	spring		RBR121-24VUC	1SNA645501R0500		
48-60 V AC/DC	spring		RBR121-48-60VUC	1SNA645502R0600		
115 V AC/DC	spring		RBR121-115VUC	1SNA645503R0700		
230 V AC/DC	spring		RBR121-230VUC	1SNA645504R0000		

### Ordering details

#### Ordering details - 1 c/o (SPDT) contact: 250 V AC, 3 mA - 6 A, gold-plated contacts, width 6 mm

Rated control supply voltage	Connection type	Particularities	Type	Order code	Pkg qty	Weight (1 pc.) kg (lb)
5 V DC	screw	A1-A2 polarized	RB121PG-5VDC	1SNA645036R2500	10	0.02
12 V DC	screw		RB121G-12VDC	1SNA645075R0000		(0.044)
24 V DC	screw		RB121G-24VDC	1SNA645072R0000		
24 V AC/DC	screw		RB121G-24VUC	1SNA645005R0700		
48-60 V AC/DC	screw		RB121G-48-60VUC	1SNA645006R0000		
115 V AC/DC	screw		RB121G-115VUC	1SNA645007R0100		
230 V AC/DC	screw		RB121G-230VUC	1SNA645008R1200		
24 V DC	spring		RBR121G-24VDC	1SNA645572R0000		
24 V AC/DC	spring		RBR121G-24VUC	1SNA645505R0100		
48-60 V AC/DC	spring		RBR121G-48-60VUC	1SNA645506R0200		
115 V AC/DC	spring		RBR121G-115VUC	1SNA645507R0300		
230 V AC/DC	spring		RBR121G-230VUC	1SNA645508R1400	1	

#### Ordering details - 1 c/o (SPDT) contact: 250 V AC, 10 mA - 6 A, width 12 mm





R600 - 12 mm

#### Ordering details - 2 c/o (SPDT) contacts: 250 V AC, 1 mA - 8 A, gold-plated contacts, width 12 mm

Rated control supply voltage	V AC/DC screw -60 V AC/DC screw 5 V AC/DC screw	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V AC/DC	screw	RB122G-24VUC	1SNA645012R2500	5	0.04
48-60 V AC/DC	screw	RB122G-48-60VUC	1SNA645040R1500		(0.088)
115 V AC/DC	screw	RB122G-115VUC	1SNA645041R0200		
230 V AC/DC	screw	RB122G-230VUC	1SNA645013R2600		
24 V AC/DC	spring	RBR122G-24VUC	1SNA645512R2700		
48-60 V AC/DC	spring	RBR122G-48-60VUC	1SNA645540R1700		
115 V AC/DC	spring	RBR122G-115VUC	1SNA645541R0400		
230 V AC/DC	spring	RBR122G-230VUC	1SNA645513R2000		

\_

#### Ordering details - Accessories

Description	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Jumper bar, 10 poles * (replacement of BJ612-10 - 1SNA290488R0100)	RB-JB10	1SVR406570R0000	10	0.05 (0.11)
Jumper bar, 20 poles * (replacement of BJ612-20 - 1SNA206754R0000)	RB-JB20	1SVR406580R0000		0.10 (0.22)
Separator end section	SC612	1SNA290474R0200		0.05 (0.11)

<sup>\* -</sup> Before the first and after the last jumpered R600 relay, a separator end section shall be used.

<sup>-</sup> The sum of the current for jumpered devices shall not exceed 6 A on 6 mm devices and 8 A on 12 mm devices.

		RB(R)101R-	RB(R)111R-							
		24 V UC	24 V UC							
Input circuit										
Rated control supply voltage U <sub>s</sub>		24 V AC/DC								
Rated control supply voltage	DC	-15 %, +20 %								
U <sub>s</sub> tolerance	AC	-/+ 10 %								
Rated frequency		50/60 Hz								
Typical power consumption		0.24 W								
Typical current		10 mA								
Drop-out voltage	at 20 °C	4.5 V								
Indication of operational states	green LED	: control supply voltage applied	l							
Output circuit										
Kind of output	11-12	relay, 1 n/c contact	-							
	13-14	-	relay, 1 n/o contact							
Rated operational voltage $U_{_{\rm e}}$		250 V AC								
Minimum switching voltage		5 V								
Maximum switching voltage		250 V AC								
Minimum switching current		60 mA								
Rated free air thermal current $\boldsymbol{I}_{th}$		6 A								
Rated operational	AC-12 (resistive) 230 V	/ 6 A								
current I <sub>e</sub>	AC-15 (inductive) 230 V	1.5 A								
	AC-15 (inductive) 120 V	3 A								
	DC-12 (resistive) 24 V	6 A								
	DC-13 (inductive) 24 V	1 A								
	DC-13 (inductive) 110 V	0.2 A								
	DC-13 (inductive) 220 V	0.1 A								
AC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	B300								
DC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	R300								
Minimum switching power		300 mW								
Mechanical lifetime		1 x 10 <sup>7</sup> switching cycles								
Electrical lifetime	at AC-15	1 x 10⁵ switching cycles								
Max. fuse rating to achieve short-	-circuit protection	6 A fast								
Response time		5 ms								
Release time		8 ms								

· · · · · · · · · · · · · · · · · · ·		RB(R)111-	'	'						
		24 V UC	115 V UC	230 V UC						
Input circuit										
Rated control supply voltage U <sub>s</sub>		24 V AC/DC	115 V AC/DC	230 V AC/DC						
Rated control supply voltage	24  J <sub>s</sub> 24  DC -1! AC -/4  50 0.6 10 at 20 °C 4.9 es green LED  13-14 rel 25 12 25	-15 %, +20 %		-15 %, +10 %						
U <sub>s</sub> tolerance		-/+ 10 %								
Rated frequency		50/60 Hz								
Typical power consumption		0.24 W	0.46 W	0.8 W						
Typical current		10 mA	4 mA	3.5 mA						
Drop-out voltage	at 20 °C	4.5 V	17 V	27 V						
Indication of operational states	green LED	: control su	upply voltage applied							
Output circuit										
Kind of output	13-14	relay, 1 n/o contac	t							
Rated operational voltage U <sub>e</sub>		250 V AC								
Minimum switching voltage		12 V								
Maximum switching voltage		250 V AC								
Minimum switching current		10 mA								
Rated free air thermal current I <sub>th</sub>		6 A								

-		RB(R)111-						
		24 V UC	115 V UC	230 V UC				
Rated operational current I <sub>e</sub>	AC-12 (resistive) 230 V	6 A						
	AC-15 (inductive) 230 V	1.5 A						
	AC-15 (inductive) 120 V	3 A						
	DC-12 (resistive) 24 V	6 A						
	DC-13 (inductive) 24 V	1 A						
	DC-13 (inductive) 110 V	0.2 A						
	DC-13 (inductive) 220 V	0.1 A						
AC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	B300						
DC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	R300						
Minimum switching power		300 mW						
Mechanical lifetime		1 x 10 <sup>7</sup> switching	cycles					
Electrical lifetime	at AC-15	1 x 10 <sup>5</sup> switching	cycles					
Max. fuse rating to achieve short-	circuit protection	6 A fast						
Response time		5 ms	6 ms	7 ms				
Release time		8 ms	15 ms	15 ms				

		RB(R)121(P)(G)-													
		5 V DC	12 V DC	24 V DC	24 V UC	48-60 V UC		115 V UC	230 V UC						
Input circuit															
Rated control supply v	oltage U <sub>s</sub>	5 V DC	12 V DC	24 V DC	24 V AC/DC	48 V AC/DC	60 V AC/DC	115 V AC/DC	230 V AC/DC						
Rated control supply v	oltage DC	-15 %, +	20 %						-15 %, +10 %						
U <sub>s</sub> tolerance	AC	-			-/+ 10 %										
Rated frequency		-			50/60 Hz										
Typical power consum	ption	0.2 W	0.2 W	0.24 W		0.33 W	0.54 W	0.46 W	0.8 W						
Typical current		40 mA	16 mA	10 mA		7 mA	9 mA	4 mA	3.5 mA						
Drop-out voltage	at 20 °C	1.2 V	2.2 V	4.5 V		8 V	8 V	17 V	27 V						
Indication of operation	nal states green LED	control supply voltage applied													
Output circuit															
Kind of output	11-12/14	relay, 1	c/o (SPDT)	) contact											
Rated operational volt	250 V AC														
Minimum switching vo	5 V / gold-plated contacts: 5 V														
Maximum switching vo	oltage	250 V A	С												
Minimum switching cu	rrent	60 mA	gold-plat	ed contact	ts: 10 mA										
Rated free air thermal	current I <sub>th</sub>	6 A													
Rated operational	AC-12 (resistive) 230 V	6 A													
current I <sub>e</sub>	AC-15 (inductive) 230 V	1.5 A													
	AC-15 (inductive) 120 V	3 A													
	DC-12 (resistive) 24 V	6 A													
	DC-13 (inductive) 24 V	1 A													
	DC-13 (inductive) 110 V	0.2 A													
	DC-13 (inductive) 220 V	0.1 A													
AC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	B300													
DC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	R300													
Minimum switching po	ower	300 mV	/ gold-pl	ated conta	icts: 50 mW										
Mechanical lifetime		1 x 10 <sup>7</sup> switching cycles													
Electrical lifetime	at AC-15	5 1 x 10 <sup>5</sup> switching cycles													
Max. fuse rating to ach circuit protection	nieve short-	6 A fast													
Response time		5 ms	5 ms	5 ms		5 ms	5 ms	6 ms	7 ms						
Release time		8 ms	8 ms	8 ms		8 ms	8 ms	15 ms	16 ms						

		RB(R)121R-	'						
		115 V UC	230 V UC						
Input circuit			·						
Rated control supply vol	tage U <sub>s</sub>	115 V AC/DC	230 V AC/DC						
Rated control supply vol	tage U <sub>s</sub> DC	-20%, +15%	-10%, +15%						
tolerance	AC	-/+ 10 %							
Rated frequency		50/60 Hz							
Typical power consumpt	tion	2 W	2.8 W						
Typical current		18 mA	12 mA						
Drop-out voltage	at 20 °C	17 V	27 V						
Indication of operationa	l states green LED	: control supply voltage ap	plied						
Output circuit									
Kind of output	11-12/14	relay, 1 c/o (SPDT) contact							
Rated operational voltage	ge U <sub>e</sub>	250 V AC							
Minimum switching volt	age	5 V							
Maximum switching volt	tage	250 V AC							
Minimum switching curr	ent	60 mA							
Rated free air thermal cu	ırrent I <sub>th</sub>	6 A							
Rated operational	AC-12 (resistive) 230 V	6 A							
current I <sub>e</sub>	AC-15 (inductive) 230 V	1.5 A							
	AC-15 (inductive) 120 V	3 A							
	DC-12 (resistive) 24 V	6 A							
	DC-13 (inductive) 24 V	1 A							
	DC-13 (inductive) 110 V	0.2 A							
	DC-13 (inductive) 220 V	0.1 A							
AC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	B300							
DC rating (UL 508; NEMA ICS-5)	utilization category (pilot duty)	R300							
Minimum switching pow	ver	300 mW							
Mechanical lifetime		1 x 10 <sup>7</sup> switching cycles							
Electrical lifetime	at AC-15	1 x 10⁵ switching cycles							
Max. fuse rating to achie short-circuit protection		6 A fast							
Response time		6 ms	7 ms						
Release time		15 ms	16 ms						

### Technical data

		RB(R)122G											
		24 V UC	48-60 V UC		115 V UC	230 V UC							
Input circuit	, ,		•	,	•								
Rated control supply v	oltage U <sub>s</sub>	24 V AC/DC	48 V AC/DC	60 V AC/DC	115 V AC/DC	230 V AC/DC							
Rated control supply v	oltage U <sub>s</sub> DC	-15 %, +20 %				-15 %, +10 %							
tolerance	AC	-/+ 10 %											
Rated frequency		50/60 Hz											
Typical power consum	ption	0.48 W	0.62 W	0.96 W	0.58 W	1.15 W							
Typical current		20 mA	13 mA	16 mA	5 mA	5 mA							
Orop-out	at 20 °C	5.4 V	8.8 V	8.8 V V	20 V	10 V							
ndication of operation	nal states green LED	☐ : contro	ol supply voltage app	olied									
Output circuit													
Kind of output 11-12/14		relay, 1st c/o (SPDT) contact											
	21-22/24	relay, 2nd c/o (	SPDT) contact										
Rated operational volt	age U <sub>e</sub>	250 V											
Minimum switching vo	ltage	5 V / gold-plated contacts: 5 V											
Maximum switching vo	oltage	250 V											
Minimum switching cu	irrent	60 mA / gold-p	lated contacts: 10 m	nA									
Rated free air thermal	current I <sub>th</sub>	8 A											
Rated operational	AC-12 (resistive) 230 V	8 A											
current I <sub>e</sub>	AC-15 (inductive) 230 V	1.5 A											
	DC-12 (resistive) 24 V	8 A											
	DC-13 (inductive) 24 V	1 A											
	DC-13 (inductive) 110 V	0.2 A											
	DC-13 (inductive) 220 V	0.1 A											
Minimum switching po	ower	300 mW / gold	-plated contacts: 50	mW									
Mechanical lifetime		2 x 10 <sup>7</sup> switchir	ng cycles										
Electrical lifetime	at AC-15	1 x 10 <sup>5</sup> switchir	ng cycles										
Max. fuse rating to achie	eve short-circuit protection	10 A fast											
Response time		6 ms	10 ms	10 ms	6 ms	6 ms							
Release time		10 ms	14 ms	14 ms	15 ms	15 ms							

\_


#### General technical data - Interface relays


		RB	RBR
General data			·
Material of housing		UL 94 V0	
Mounting		DIN rail	
Degree of protection	housing / terminals	IP20 NEMA1	
Electrical connection	,	Screw terminal	Spring-type terminal
Connecting capacity	fine-strand	0.22-2.5 mm² (24-14 AWG)	
	rigid	0.2-4 mm² (24-12 AWG)	0.2-2.5 mm <sup>2</sup> (24-14 AWG)
Stripping length		9 mm (0.354 in)	
Tightening torque		0.4-0.6 Nm (3.5-5.3 lb.in)	n/a
Environmental data			
Ambient temperature ranges	storage	-40+80 °C (-40+176 °F)	
	operation	-20+70 °C (-4+158 °F) 1)	
Isolation data			
Rated insulation voltage U <sub>i</sub>		250 V	
Rated impulse withstand	input / output	4 kV (1.2/50 μs)	
voltage U <sub>imp</sub>	shock coil / output	4 kV (1.2/50 μs)	
	output / output	1 kV (1.2/50 μs)	
Overvoltage category		III	
Pollution degree		2	
Standards/Directives			
Standards		IEC/EN 60947-5-1	
Low Voltage Directive		2014/35/EC	
RoHS Directive		2011/65/EC	

<sup>1)</sup> Over 55 °C, blocks have to be mounted on horizontal rail with 10 mm spacing between each block. For vertical rail mounting max. operation temperature is 15 °C lower.

### Technical diagrams

#### **Load limit curves**







Versions with 1 n/o, 1 n/c or 1 c/o contact

Versions with 2 c/o contacts


#### **Dimensional drawings**










R600 - spring connection










### Technical diagrams

#### **Connection diagrams**

RB(R)122G-24VUC/48-60VUC



RB(R)122G-115VUC/230VUC

Selection table

	Order number	1SNA645047R0000	1SNA645547R0200	1SNA645021R2600	1SNA645521R2000	1SNA645049R1200	1SNA645549R1400	1SNA645022R2700	1SNA645522R2100	1SNA645050R1700	1SNA645550R1100	1SNA645051R0400	1SNA645025R2200	1SNA645024R2100	1SNA645551R0600	1SNA645525R2400	1SNA645524R2300	1SNA645053R0600	1SNA645553R0000	1SNA645054R0700	1SNA645058R1300	1SNA645026R2300	1SNA645526R2500	1SNA645559R1600	1SNA645027R2400	1SNA645029R0600	1SNA645527R2600	1SNA645529R0000	1SNA645062R0700
	Orde	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/	1SN/
						Ŋ									O	()													
	Туре	OBIC0100-5-12VDC	OBRIC0100-5-12VDC	OBIC0100-24VDC	<b>OBRIC0100-24VDC</b>	OBIC0100-48-60VUC	OBRIC0100-48-60VUC	OBIC0100-115-230	OBRIC0100-115-230	OBOC2000-5-12VDC	OBROC2000-5-12VDC	OBOC2000-24VDC	OBOC2000-24VUC	OBOC5000-24VDC	OBROC2000-24VDC	OBROC2000-24VUC	OBROC5000-24VDC	OBOC2000-48-60VUC	OBROC2000-48-60VUC	OBOC2000-115VUC	OBOC5000-115VUC	OBOC2000-230VUC	OBROC2000-230VUC	OBROC5000-230VUC	OBOA1000-24VDC	OBOA2000-24VDC	OBROA1000-24VDC	OBROA2000-24VDC	OBOA1000-115VUC
Control voltage																												_	
5-12 V DC		•	•							•	•																		
24 V DC				-	•							•	•	•	•	•	•								•	•	•	•	
48-60 V DC						•	•											•	•										
115-230 V DC								•	•																				
115 V DC																					•								-
230 V DC								•	•													•		•					
24 V AC													•			•													
48-60 V AC						•	•											•	•										
115-230 V AC								•	•																				
115 V AC																					•								-
230 V AC																						•		•					
Output rating																													
100 mA		•	•	•	•		•	•	•																				
1 A																									•		•		•
2 A													•			•		•											
5 A														•			•				•			•					
Output voltage																													
58 V DC		•			•		•	•			•					•		•			•		•	•					
230 V AC																										•			
400 V AC																									•		•		
Terminal type																												$\equiv$	
Screw		-		-		•		•		•		•	•	•				•		•	•	•			•	•			
Spring			•		•		•		•		•				•	•	•		•					•			•	•	
Kind of output																												_	
Transistor		=	•	-	•	•	•	•	•																				
MOS-FET										•	•	•	•	•	•	•	•	•	-	•	•	•	•	•					
Triac																											•		

# Ordering details



2600 6 mm

#### Ordering details - Transistor output, 58 V DC, 100 mA, width 6 mm

Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
5 - 12 V DC	screw	OBIC0100-5-12VDC	1SNA645047R0000	10	0.02
24 V DC	screw	OBIC0100-24VDC	1SNA645021R2600		(0.044)
48 - 60 V AC/DC	screw	OBIC0100-48-60VUC	1SNA645049R1200		
115 - 230 V AC/DC	screw	OBIC0100-115-230	1SNA645022R2700		
5 - 12 V DC	spring	OBRIC0100-5-12VDC	1SNA645547R0200	10	0.02
24 V DC	spring	OBRIC0100-24VDC	1SNA645521R2000		(0.044)
48 - 60 V AC/DC	spring	OBRIC0100-48-60VUC	1SNA645549R1400		
115 - 230 V AC/DC	spring	OBRIC0100-115-230	1SNA645522R2100		

\_

#### Ordering details - MOS-FET output, 58 V DC, 2 A, width 6 mm

Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
5 - 12 V DC	screw	OBOC2000-5-12VDC	1SNA645050R1700	10	0.02
24 V DC	screw	OBOC2000-24VDC	1SNA645051R0400		(0.044)
24 V AC/DC	screw	OBOC2000-24VUC	1SNA645025R2200		
48 - 60 V AC/DC	screw	OBOC2000-48-60VUC	1SNA645053R0600		
115 V AC/DC	screw	OBOC2000-115VUC	1SNA645054R0700		
230 V AC/DC	screw	OBOC2000-230VUC	1SNA645026R2300		
5 - 12 V DC	spring	OBROC2000-5-12VDC	1SNA645550R1100	10	0.02
24 V DC	spring	OBROC2000-24VDC	1SNA645551R0600		(0.044)
24 V AC/DC	spring	OBROC2000-24VUC	1SNA645525R2400		
48 - 60 V AC/DC	spring	OBROC2000-48-60VUC	1SNA645553R0000		
230 V AC/DC	spring	OBROC2000-230VUC	1SNA645526R2500		

\_

#### Ordering details - MOS-FET output, 58 V DC, 5 A, width 6 mm

Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	screw	OBOC5000-24VDC	1SNA645024R2100	10	0.02
115 V AC/DC	screw	OBOC5000-115VUC	1SNA645058R1300		(0.044)
24 V DC	spring	OBROC5000-24VDC	1SNA645524R2300	10	0.02
230 V AC/DC	spring	OBROC5000-230VUC	1SNA645559R1600		(0.044)

\_

#### Ordering details - Triac output, 400 V AC, 1 A, width 6 mm

•	•				
Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	screw	OBOA1000-24VDC	1SNA645027R2400	10	0.03
115 V AC/DC	screw	OBOA1000-115VUC	1SNA645062R0700		(0.066)
230 V AC/DC	screw	OBOA1000-230VUC	1SNA645028R0500		
24 V DC	spring	OBROA1000-24VDC	1SNA645527R2600	10	

# Ordering details



#### Ordering details - Triac output, 230 V AC, 2 A, width 12 mm

Rated control supply voltage	Connection type	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
24 V DC	screw	OBOA2000-24VDC	1SNA645029R0600	5	0.03
24 V DC	spring	OBROA2000-24VDC	1SNA645529R0000	5	(0.066)

#### Ordering details - Accessories

Description	Туре	Order code	Pkg qty	Weight (1 pc.) kg (lb)
Jumper bar, 10 poles * (replacement of BJ612-10 - 1SNA290488R0100)	RB-JB10	1SVR406570R0000	10	0.05 (0.11)
Jumper bar, 20 poles * (replacement of BJ612-20 - 1SNA206754R0000)	RB-JB20	1SVR406580R0000		0.10 (0.22)
Separator end section	SC612	1SNA290474R0200		0.05 (0.11)

<sup>\* -</sup> Before the first and after the last jumpered R600 optocoupler, a separator end section shall be used.
- The sum of the current for jumpered devices shall not exceed 6 A on 6 mm devices and 8 A on 12 mm devices.

	OB(R)IC010	00						
	5-12 V DC		24 V DC	48-60 V UC		115-230		
Input circuit								
Control voltage	5 V DC	12 V DC	24 V DC	48 V AC/DC	60 V AC/DC	115 V AC/DC	230 V AC/DC	
Frequency	-			50/60 Hz				
Input current	5 mA	9 mA	4 mA	4 mA	5 mA	7 mA (AC) 16 mA (DC)	11.5 mA (AC) 25 mA (DC)	
Pull-in voltage	4 V		15 V	25 V		60 V AC / 70 V	/ DC	
Typ. switch-on time	10 μs			5 ms				
Typ. switch-off time	500 μs			20 ms				
Operating frequency	1000 Hz				20 Hz			
Permissible leakage current	0.9 mA		1.0 mA	0.9 mA		1.6 mA		
Output circuit	11(13+)- 14							
Kind of output	Transistor							
Rated operational voltage	4.5-58 V DC							
Minimum switching current	1 mA							
Maximum switching current	100 mA							
Leakage current at max. switching voltage	< 50 μΑ							
Rated operational DC-12 (resistive) 58 V current $I_e$ (IEC/EN 60947-5-1)	0.1 A							
Residual voltage typical	1 V							
maximum	1.3 V							
Max. fuse rating to achieve short-circuit protection	100 mA fast							
Isolation data		'						
Rated insulation voltage U <sub>i</sub>	250 V							
Rated impulse withstand voltage U <sub>imp</sub>	2.5 kV (1.2/50 μs)							
Overvoltage category	II							
Pollution degree	2							

		OB(R)OC20	000						
		5-12 V DC		24 V DC	24 V UC	48-60 V UC		115 V UC	230 V UC
Input circuit				·		,		•	
Control voltage		5 V DC	12 V DC	24 V DC	24 V AC/DC	48 V AC/DC	60 V AC/DC	115 V AC/DC	230 V AC/DC
Frequency		-		·	50/60 Hz				
Input current		5 mA	9 mA	5.4 mA	6.3 mA	4 mA	5.1 mA	4.2 mA	4 mA
Pull-in voltage		4 V		12 V	15 V	27 V		50 V	80 V
Typ. switch-on time		15 μs		30 μs	1 ms	5 ms		500 μs	1 ms
Typ. switch-off time		250 μs		400 μs	7 ms	20 ms		10 ms	15 ms
Operating frequency		2000 Hz		1000 Hz	60 Hz	20 Hz		50 Hz	35 Hz
Permissible leakage current		1 mA		0.8 mA	0.9 mA	1 mA		0.3 mA	
Output circuit		11(13+)- 14				*		•	
Kind of output		MOS-FET							_
Rated operational voltage		4.5-58 V DC	:						
Minimum switching current		1 mA							
Maximum switching current		2 A							
Leakage current at max. switching voltage		< 50 μΑ							
Rated operational DC-12 (resistive) current I <sub>e</sub>	58 V	2 A							
Residual voltage typ	oical	0.1 V							
maxir	num	0.5 V							
Max. fuse rating to achieve short-circuit protect	ion	2 A ultra-fast							
Isolation data								•	
Rated insulation voltage U <sub>i</sub>		250 V							
Rated impulse withstand voltage U <sub>imp</sub>		2.5 kV (1.2/50 μs)							
Overvoltage category		II .							
Pollution degree		2							

	OB(R)OC5000				
	24 V DC	115 V UC	230 V UC		
Input circuit	•				
Control voltage	24 V DC	115 V AC/DC	230 V AC/DC		
Frequency	-	50/60 Hz			
Input current	5.4 mA	4.2 mA	4 mA		
Pull-in voltage	12 V	50 V	80 V		
Typ. switch-on time	30 μs	500 μs	1 ms		
Typ. switch-off time	400 μs	10 ms	15 ms		
Operating frequency	1000 Hz	50 Hz	35 Hz		
Permissible leakage current	0.8 mA	0.3 mA	0.3 mA		
Output circuit	11(13+)- 14				
Kind of output	MOS-FET				
Rated operational voltage	4.5-58 V DC				
Minimum switching current	1 mA				
Maximum switching current	5 A				
Leakage current at max. switching voltage	< 50 μΑ				
Rated operational DC-12 (resistive) 58 V current I	5 A				
Residual voltage typical	0.1 V				
maximum	0.5 V				
Max. fuse rating to achieve short-circuit protection	6 A ultra-fast				
Isolation data	•				
Rated insulation voltage U <sub>i</sub>	250 V				
Rated impulse withstand voltage U <sub>imp</sub>	2.5 kV (1.2/50 μs)				
Overvoltage category	II				
Pollution degree	2				

		OB(R)OA100	0		OB(R)OA2000	
		24 V DC	115 V UC	230 V UC	24 V DC	
Input circuit		•	·	•		
Control voltage		24 V DC	115 V AC/DC	230 V AC/DC	24 V DC	
Frequency		-	50/60 Hz	<u>'</u>	-	
Input current		3.6 mA	4.15 mA	4.6 mA	3.6 mA	
Pull-in voltage		14 V	60 V	135 V	14 V	
Typ. switch-on time		150 μs	2.2 ms	2.5 ms	150 μs	
Typ. switch-off time		1 ms	18 ms	25 ms	1 ms	
Operating frequency		500 Hz	25 Hz	20 Hz	500 Hz	
Permissible leakage cur	rent	1 mA			1 mA	
Output circuit		11(13+)- 14				
Kind of output		Triac			Triac	
Rated operational volta	ge	24-400 V AC			10-230 V AC	
Minimum switching cur	rent	25 mA			25 mA	
Maximum switching cur	rent	1 A			2 A	
Leakage current at max	. switching voltage	< 500 μΑ			< 500 μA	
Rated operational	AC-12 (resistive) 400 V	1 A			-	
current I <sub>e</sub>	AC-12 (resistive) 230 V	-			2A	
Residual voltage	typical	1 V			1 V	
	maximum	1.6 V			1.6 V	
Max. fuse rating to achieve short-circuit protection		4 A ultra-fast			4 A ultra-fast	
Isolation data	, ,		,			
Rated insulation voltage U <sub>i</sub>		400 V			230 V	
Rated impulse withstan	d voltage U <sub>imp</sub>	4 kV (1.2/50 μs)			4 kV (1.2/50 μs)	
Overvoltage category	·	II			II	
Pollution degree		2			2	

Technical data

\_


#### General technical data - Optocouplers

		ОВ	OBR
General data			·
Material of housing		UL 94 V0	
Mounting		DIN Rail	
Degree of protection	housing / terminals	IP20 NEMA1	
Electrical connection		Screw terminal	Spring-type terminal
Connecting capacity	fine-strand	0.22-2.5 mm² (24-14 AWG)	
_	rigid	0.2-4 mm² (24-12 AWG)	0.2-2.5 mm² (24-14 AWG)
Stripping length		9 mm (0.354 in)	
Tightening torque		0.4-0.6 Nm (3.5-5.3 lb.in)	n/a
Environmental data			
Ambient temperature ranges	storage	-40+80 °C (-40+176 °F)	
_	operation	-20+70 °C (-4+158 °F)	
Standards/Directives			
Standards	-	IEC/EN 60947-5-1	
Low Voltage Directive		2014/35/EU	
RoHS Directive		2011/65/EU	


# Technical diagrams

#### **Dimensional drawings**

in **mm** and inches




R600 - screw connection




R600 - spring connection


#### **Connection diagrams**



OB(R)OC, OB(R)IC except 5-12 V DC versions



OB(R)IC0100-5-12 V DC OB(R)OC2000-5-12 V DC



OB(R)OA



# **Index** Time relays Product type

Туре	Order code	Page
ADP.01	1SVR430029R0100	41
COV.11	1SVR730005R0100	41
CT- MXS.22S	1SVR730030R3300	39
CT-AHC.12	1SVR508110R0000	25
CT-AHC.22	1SVR508110R0100	25
CT-AHD.12	1SVR500110R0000	57
CT-AHD.22	1SVR500110R0100	57
CT-AHS.22P	1SVR740110R3300	40
CT-AHS.22S	1SVR730110R3300	40
CT-APS.12P	1SVR740180R3100	40
CT-APS.12S	1SVR730180R3100	40
CT-APS.21P	1SVR740180R0300	40
CT-APS.21S	1SVR730180R0300	40
CT-APS.22P	1SVR740180R3300	40
CT-APS.22S	1SVR730180R3300	40
CT-ARC.12	1SVR508120R0000	25
CT-ARS.11P	1SVR740120R3100	40
CT-ARS.11S	1SVR730120R3100	40
CT-ARS.21P	1SVR740120R3300	40
CT-ARS.21S	1SVR730120R3300	40
CT-EBC.12	1SVR508150R0000	25
CT-EBD.12	1SVR500150R0000	56
CT-ERC.12	1SVR508100R0000	25
CT-ERC.22	1SVR508100R0100	25
CT-ERD.12	1SVR500100R0000	56
CT-ERD.22	1SVR500100R0100	56
CT-ERS.12P	1SVR740100R3100	40
CT-ERS.12S	1SVR730100R3100	40
CT-ERS.21P	1SVR740100R0300	40
CT-ERS.21S	1SVR730100R0300	40
CT-ERS.22P	1SVR740100R3300	40
CT-ERS.22S	1SVR730100R3300	40
CT-MBS.22P	1SVR740010R3200	39
CT-MBS.22S	1SVR730010R3200	39
CT-MFC.12	1SVR508020R0000	25
CT-MFC.21	1SVR508020R1100	25
CT-MFD.12	1SVR500020R0000	56
CT-MFD.21	1SVR500020R1100	56
CT-MFS.21P	1SVR740010R0200	39
CT-MFS.21S	1SVR730010R0200	39
CT-MVS.23S	15VR730021R2300	39
CT-MXS.22P	15VR740030R3300	39
CT-SAC.22	1SVR508210R0100	25
CT-SAD.22	1SVR500210R0100	56
CT-SDC.22	1SVR508211R0100	25
CT-SDD.22	1SVR500211R0100	56
CT-SDS.22P	1SVR740210R3300	40
CT-SDS.22F	1SVR730210R3300	40
		40
		40
CT-SDS.23P CT-SDS.23S	1SVR740211R2300 1SVR730211R2300	

Туре	Order code	Page
CT-TGC.12	1SVR508160R0000	25
CT-TGC.22	1SVR508160R0100	25
CT-TGD.12	1SVR500160R0000	56
CT-TGD.22	1SVR500160R0100	56
CT-VWC.12	1SVR508250R0000	25
CT-VWD.12	1SVR500250R0000	56
CT-WBS.22P	1SVR740040R3300	39
CT-WBS.22S	1SVR730040R3300	39
KA1-8029	1SFA616920R8029	41
KA1-8030	1SFA616920R8030	41
MA16-1060	1SFA611940R1060	41
MAR.01	1SVR366017R0100	41
MAR.12	1SVR730006R0000	41
MT-150B	1SFA611410R1506	41
MT-250B	1SFA611410R2506	41
MT-350B	1SFA611410R3506	41
SK 615 562-87	GJD6155620R0087	41
SK 615 562-88	GJD6155620R0088	41

# Index

# Time relays Order code

Order code	Туре	Page	
1SFA611410R1506	MT-150B	29	
1SFA611410R2506	MT-250B	29	
1SFA611410R3506	MT-350B	29	
1SFA611940R1060	MA16-1060	29	
1SFA616920R8029	KA1-8029	29	
1SFA616920R8030	KA1-8030	29	
1SVR366017R0100	MAR.01	29	
1SVR430029R0100	ADP.01	41	
1SVR500020R0000	CT-MFD.12	56	
1SVR500020R1100	CT-MFD.21	56	
1SVR500100R0000	CT-ERD.12	56	
1SVR500100R0100	CT-ERD.22	56	
1SVR500110R0000	CT-AHD.12	56	
1SVR500110R0100	CT-AHD.22	56	
1SVR500250R0000	CT-VWD.12	56	
1SVR500150R0000	CT-EBD.12	56	
1SVR500160R0000	CT-TGD.12	56	
1SVR500160R0100	CT-TGD.22	56	
1SVR500210R0100	CT-SAD.22	56	
1SVR500211R0100	CT-SDD.22	56	
1SVR508020R0000	CT-MFC.12	25	
1SVR508100R0000	CT-ERC.12	25	
1SVR508100R0100	CT-ERC.22	25	
1SVR508110R0000	CT-AHC.12	25	
1SVR508110R0100	CT-AHC.22	25	
1SVR508120R0000	CT-ARC.12	25	
1SVR508250R0000	CT-VWC.12	25	
1SVR508150R0000	CT-EBC.12	25	
1SVR508160R0000	CT-TGC.12	25	
1SVR508160R0100	CT-TGC.22	25	
1SVR508180R0100	CT-PAC.22	25	
1SVR508210R0100	CT-SAC.22	25	
1SVR508211R0100	CT-SDC.22	25	
1SVR730005R0100	COV.11	29	
1SVR730006R0000	MAR.12	29	
1SVR730010R0200	CT-MFS.21S	39	
1SVR730010R3200	CT-MBS.22S	39	
1SVR730021R2300	CT-MVS.23S	39	
1SVR730030R3300	CT-MXS.22S	39	
1SVR730040R3300	CT-WBS.22S	39	
1SVR730100R0300	CT-ERS.21S	40	
1SVR730100R0300	CT-ERS.12S	40	
1SVR730100R3300	CT-ERS.22S	40	
1SVR730110R3300	CT-AHS.22S	40	
1SVR730120R3100	CT-ARS.11S	40	
1SVR730120R3300	CT ARS.21S	40	
1SVR730180R0300	CT-APS.21S	40	
1SVR730180R3100	CT-APS.12S	40	
1SVR730180R3300			
1SVR730210R3300	CT-SDS.22S	40	

Order code	Туре	<b>Page</b> 40	
1SVR730211R2300	CT-SDS.23S		
1SVR740010R0200	CT-MFS.21P	39	
1SVR740010R3200	CT-MBS.22P	39	
1SVR740030R3300	CT-MXS.22P	39	
1SVR740040R3300	CT-WBS.22P	39	
1SVR740100R0300	CT-ERS.21P	40	
1SVR740100R3100	CT-ERS.12P	40	
1SVR740100R3300	CT-ERS.22P	40	
1SVR740110R3300	CT-AHS.22P	40	
1SVR740120R3100	CT-ARS.11P	40	
1SVR740120R3300	CT-ARS.21P	40	
1SVR740180R0300	CT-APS.21P	40	
1SVR740180R3100	CT-APS.12P	40	
1SVR740180R3300	CT-APS.22P	40	
1SVR740210R3300	CT-SDS.22P	40	
1SVR740211R2300	CT-SDS.23P	40	
GJD6155620R0087	SK 615 562-87	41	
GJD6155620R0088	SK 615 562-88	41	

# Index

# Measuring and monitoring relays Product type

Туре	Order code	Page	Туре	Order code	Page
ADP.01	1SVR430029R0100	262	CM-ENS.31S	1SVR730850R0300	249
ADP.02	1SVR440029R0100	262	CM-ESS.1P	1SVR740830R0300	89
C011-100	GHC0110003R0004	191	CM-ESS.1P	1SVR740831R0300	89
C011-110	GHC0110003R0005	191	CM-ESS.1P	1SVR740831R1300	89
C011-189	GHC0110003R0006	191	CM-ESS.1S	1SVR730830R0300	89
C011-130	GHC0110003R0007	191	CM-ESS.1S	1SVR730831R0300	89
C011-140	GHC0110003R0011	191	CM-ESS.1S	1SVR730831R1300	89
C011-150	GHC0110003R0008	191	CM-ESS.2P	1SVR740830R0400	89
C011-160	GHC0110003R0009	191	CM-ESS.2P	1SVR740831R0400	89
C011-860	GHC0110003R0010	191	CM-ESS.2P	1SVR740831R1400	89
C011-3-150	GHC0110033R0008	191	CM-ESS.2S	1SVR730830R0400	89
C011-70	GHC0110003R0001	191	CM-ESS.2S	1SVR730831R0400	89
C011-80	GHC0110003R0002	191	CM-ESS.2S	1SVR730831R1400	89
C011-90	GHC0110003R0003	191	CM-ESS.MP	1SVR740830R0500	89
CM-AH-3	1SVR450056R7000	262	CM-ESS.MS	1SVR730830R0500	89
CM-CT 100/1	1SVR450116R1890	263	CM-GM-1	1SVR450056R8000	262
CM-CT 100/5	1SVR450116R5200	263	CM-HC	1SVR402902R1000	262
CM-CT 150/1	1SVR450116R1300	263	CM-HCT	1SVR402902R2000	262
CM-CT 150/5	1SVR450116R5300	263	CM-HE	1SVR402902R0000	262
CM-CT 200/1	1SVR450116R1400	263	CM-IVN.P	1SVR760669R9400	161
CM-CT 200/5	1SVR450116R5400	263	CM-IVN.S	1SVR750669R9400	161
CM-CT 300/1	1SVR450186R1100	263	CM-IWM.10	1SVR470670R1000	161
CM-CT 300/5	1SVR450186R5100	263	CM-IWM.11	1SVR470670R1100	161
CM-CT 400/1	1SVR450186R1890	263	CM-IWN.1P	1SVR760660R0200	161
CM-CT 400/5	1SVR450186R5200	263	CM-IWN.1S	1SVR750660R0200	161
CM-CT 50/1	1SVR450116R1000	263	CM-IWS.1P	1SVR740660R0100	161
CM-CT 50/5	1SVR450116R5000	263	CM-IWS.1S	1SVR730660R0100	161
CM-CT 500/1	1SVR450186R1300	263	CM-IWS.2P	1SVR740670R0200	161
CM-CT 500/5	1SVR450186R5300	263	CM-IWS.2S	1SVR730670R0200	161
CM-CT 600/1	1SVR450186R1400	263	CM-KH-3	1SVR450056R6000	262
CM-CT 600/5	1SVR450186R5400	263	CM-MPN.52P	1SVR760487R8300	115
CM-CT 145/1	1SVR450116R1100	263	CM-MPN.52S	1SVR750487R8300	115
CM-CT 145/5	1SVR450116R5100	263	CM-MPN.62P	1SVR760488R8300	115
CM-CT A	1SVR450118R1000	263	CM-MPN.62S	1SVR750488R8300	115
CM-EFS.2P	1SVR740750R0400	89	CM-MPN.72P	1SVR760489R8300	115
CM-EFS.2S	1SVR730750R0400	89	CM-MPN.72S	1SVR750489R8300	115
CM-ENE MAX	1SVR550855R9400	249	CM-MPS.11P	1SVR740885R1300	115
CM-ENE MAX	1SVR550850R9400	249	CM-MPS.11S	1SVR730885R1300	115
CM-ENE MAX	1SVR550851R9400	249	CM-MPS.21P	1SVR740885R3300	115
CM-ENE MIN	1SVR550855R9500	249	CM-MPS.21S	1SVR730885R3300	115
CM-ENE MIN	1SVR550850R9500	249	CM-MPS.23P	1SVR740885R4300	115
CM-ENE MIN	1SVR550851R9500	249	CM-MPS.23S	1SVR730885R4300	115
CM-ENS.11P	1SVR730850R2100	249	CM-MPS.31P	1SVR740884R1300	115
CM-ENS.11S	1SVR730850R0100	249	CM-MPS.31S	1SVR730884R1300	115
CM-ENS.13P	1SVR740850R2100	249	CM-MPS.41P	1SVR740884R3300	115
CM-ENS.13S	1SVR740850R0100	249	CM-MPS.41S	1SVR730884R3300	115
CM-ENS.21P	1SVR740850R0200	249	CM-MPS.43P	1SVR740884R4300	115
CM-ENS.21S	1SVR730850R0200	249	CM-MPS.43S	1SVR730884R4300	115
CM-ENS.23P	1SVR740850R2200	249	CM-MSE	1SVR550800R9300	189
CM-ENS.23S	1SVR730850R2200	249	CM-MSS.11P	1SVR740720R1400	189
	1SVR740850R0300	249	CM-MSS.11S	1SVR730720R1400	189

# Measuring and monitoring relays Product type

Туре	Order code	Page
CM-MSS.12P	1SVR740700R0100	189
CM-MSS.12S	1SVR730700R0100	189
CM-MSS.13P	1SVR740700R2100	189
CM-MSS.13S	1SVR730700R2100	189
CM-MSS.21P	1SVR740722R1400	189
CM-MSS.21S	1SVR730722R1400	189
CM-MSS.22P	1SVR740700R0200	189
CM-MSS.22S	1SVR730700R0200	189
CM-MSS.23P	1SVR740700R2200	189
CM-MSS.23S	1SVR730700R2200	189
CM-MSS.31P	1SVR740712R1400	189
CM-MSS.31S	1SVR730712R1400	189
CM-MSS.32P	1SVR740712R0200	189
CM-MSS.32S	1SVR730712R0200	189
CM-MSS.33P	1SVR740712R2200	189
CM-MSS.33S	1SVR730712R2200	189
CM-MSS.41P	1SVR740712R1890	189
CM-MSS.41S	1SVR730712R1890	189
CM-MSS.51P	1SVR740712R1300	189
CM-MSS.51S	1SVR730712R1300	189
CM-PAS.31P	1SVR740774R1300	112
CM-PAS.31S	1SVR730774R1300	112
CM-PAS.41P	1SVR740774R3300	112
CM-PAS.41S	1SVR730774R3300	112
CM-PBE	1SVR550881R9400	112
CM-PBE	1SVR550882R9500	112
CM-PFE	1SVR550824R9100	112
CM-PFE.2	1SVR550826R9100	112
CM-PFS.P	1SVR740824R9300	112
CM-PFS.S	1SVR730824R9300	112
CM-PSS.31P	1SVR740784R2300	112
CM-PSS.31S	1SVR730784R2300	112
CM-PSS.41P	1SVR740784R3300	112
	1SVR740784R3300	112
CM-PSS.41S		
CM-PVE	15VR550870R9400	112
CM-PVE	1SVR550871R9500	112
CM-PVS.31P	1SVR740794R1300	112
CM-PVS.31S	1SVR730794R1300	112
CM-PVS.41P	1SVR740794R3300	112
CM-PVS.41S	1SVR730794R3300	112
CM-PVS.81P	1SVR740794R2300	112
CM-PVS.81S	1SVR730794R2300	112
CM-SE-1000	1SVR450056R0200	262
CM-SE-300	1SVR450056R0000	262
CM-SE-600	1SVR450056R0100	262
CM-SFS.21P	1SVR740760R0400	86
CM-SFS.21S	1SVR730760R0400	86
CM-SFS.22S	1SVR730760R0500	86
CM-SRS.11P	1SVR740840R0200	86
CM-SRS.11P	1SVR740841R0200	86
CM-SRS.11P	1SVR740841R1890	86

	Ouder and	
Type	Order code	Page
CM-SRS.11S	1SVR730840R0200	86
CM-SRS.11S	1SVR730841R0200	86
CM-SRS.11S	1SVR730841R1890	86
CM-SRS.12S	1SVR730840R0300	86
CM-SRS.12S	1SVR730841R0300	86
CM-SRS.12S	1SVR730841R1300	86
CM-SRS.21P	1SVR740840R0400	86
CM-SRS.21P	1SVR740841R0400	86
CM-SRS.21P	1SVR740841R1400	86
CM-SRS.21S	1SVR730840R0400	86
CM-SRS.21S	1SVR730841R0400	86
CM-SRS.21S	1SVR730841R1400	86
CM-SRS.22S	1SVR730840R0500	86
CM-SRS.22S	1SVR730841R0500	86
CM-SRS.22S	1SVR730841R1500	86
CM-SRS.M1P	1SVR740840R0600	86
CM-SRS.M1S	1SVR730840R0600	86
CM-SRS.M2S	1SVR730840R0700	86
CM-TCN.011S	1SVR750740R0110	230
CM-TCN.011P	1SVR760740R0110	230
CM-TCN.012S	1SVR760740R0120	230
CM-TCN.012P	1SVR750740R0120	230
CM-TCS.11P	1SVR740740R0100	209
CM-TCS.11S	1SVR730740R0100	209
CM-TCS.12P	1SVR740740R0200	209
CM-TCS.12S	1SVR730740R0200	209
CM-TCS.13P	1SVR740740R0300	209
CM-TCS.13S	1SVR730740R0300	209
CM-TCS.21P	1SVR740740R9100	209
CM-TCS.21S	1SVR730740R9100	209
CM-TCS.22P	1SVR740740R9200	209
CM-TCS.22S	1SVR730740R9200	209
CM-TCS.23P	1SVR740740R9300	209
CM-TCS.23S	1SVR730740R9300	209
CM-UFD.M22M	1SVR560731R3700	145
CM-UFD.M31	1SVR560730R3401	145
CM-UFD.M31M	1SVR560731R3701	145
CM-UFD.M33	1SVR560730R3402	145
CM-UFD.M33M	1SVR560731R3702	145
CM-UFD.M34M	1SVR560731R3703	145
COV.01	1SVR430005R0100	262
COV.02	1SVR440005R0100	262
COV.11	1SVR730005R0100	262
COV.12	1SVR750005R0100	262
MAR.01	1SVR366086R0100	262
MAR.02	1SVR430043R0000	262
MAR.12	1SVR730006R0000	262

# Measuring and monitoring relays Order code

Order code	Туре	Page	Order code	Туре	Page
1SVR366017R0100	MAR.01	172	1SVR560731R3700	CM-UFD.M22M	145
1SVR402902R0000	CM-HE	172	1SVR560731R3701	CM-UFD.M31M	145
1SVR402902R1000	СМ-НС	172	1SVR560731R3702	CM-UFD.M33M	145
1SVR402902R2000	СМ-НСТ	172	1SVR560731R3703	CM-UFD.M34M	145
1SVR1120005R0100	COV.01	172	1SVR730005R0100	COV.11	172
1SVR1120029R0100	ADP.01	172	1SVR730006R0000	MAR.12	172
1SVR11200112R0000	MAR.02	172	1SVR730660R0100	CM-IWS.1S	161
1SVR440005R0100	COV.02	172	1SVR730670R0200	CM-IWS.2S	161
1SVR440029R0100	ADP.02	172	1SVR730700R0100	CM-MSS.12S	189
1SVR1150056R0000	CM-SE-300	172	1SVR730700R0200	CM-MSS.22S	189
1SVR1150056R0100	CM-SE-600	172	1SVR730700R2100	CM-MSS.13S	189
1SVR1150056R0200	CM-SE-1000	172	1SVR730700R2200	CM-MSS.23S	189
1SVR1150056R6000	CM-KH-3	172	1SVR730712R0200	CM-MSS.32S	189
LSVR1150056R7000	CM-AH-3	172	1SVR730712R1200	CM-MSS.41S	189
1SVR1150056R8000	CM-GM-1	172	1SVR730712R1300	CM-MSS.51S	189
ISVR1150116R1000	CM-CT 50/1	263	1SVR730712R1400	CM-MSS.31S	189
1SVR1150116R1100	CM-CT 145/1	263	1SVR730712R2200	CM-MSS.33S	189
1SVR1150116R1200	CM-CT 100/1	263	1SVR730720R1400	CM-MSS.11S	189
1SVR1150116R1300	CM-CT 150/1	263	1SVR730722R1400	CM-MSS.21S	189
1SVR1150116R1400	CM-CT 200/1	263	1SVR730740R0100	CM-TCS.11S	209
1SVR1150116R5000	CM-CT 50/5	263	1SVR730740R0200	CM-TCS.12S	209
ISVR1150116R5100	CM-CT 145/5	263	1SVR730740R0300	CM-TCS.13S	209
1SVR1150116R5200	CM-CT 100/5	263	1SVR730740R16100	CM-TCS.21S	209
ISVR1150116R5300	CM-CT 150/5	263	1SVR730740R9200	CM-TCS.22S	209
ISVR1150116R5400	CM-CT 200/5	263	1SVR730740R9300	CM-TCS.23S	209
1SVR1150117R1100	CM-CT 300/1	263	1SVR730750R0400	CM-EFS.2S	89
ISVR1150117R1200	CM-CT 400/1	263	1SVR730760R0400	CM-SFS.21S	86
ISVR1150117R1300	CM-CT 500/1	263	1SVR730760R0500	CM-SFS.22S	86
ISVR1150117R1400	CM-CT 600/1	263	1SVR730774R1300	CM-PAS.31S	112
ISVR1150117R5100	CM-CT 300/5	263	1SVR730774R3300	CM-PAS.41S	112
ISVR1150117R5200	CM-CT 400/5	263	1SVR730784R2300	CM-PSS.31S	112
ISVR1150117R5300	CM-CT 500/5	263	1SVR730784R3300	CM-PSS.41S	112
ISVR1150117R5400	CM-CT 600/5	263	1SVR730794R1300	CM-PVS.31S	112
ISVR1150118R1000	CM-CT A	263	1SVR730794R2300	CM-PVS.81S	112
LSVR470670R1000	CM-IWM.10	161	1SVR730794R3300	CM-PVS.41S	112
LSVR470670R1100	CM-IWM.11	161	1SVR730824R9300	CM-PFS.S	112
LSVR550800R9300	CM-MSE	189	1SVR730830R0300	CM-ESS.1S	89
LSVR550824R16100	CM-PFE	112	1SVR730830R0400	CM-ESS.2S	89
LSVR550826R16100	CM-PFE.2	112	1SVR730830R0500	CM-ESS.MS	89
LSVR550850R9400	CM-ENE MAX	249	1SVR730831R0300	CM-ESS.1S	89
LSVR550850R9500	CM-ENE MIN	249	1SVR730831R0400	CM-ESS.2S	89
LSVR550851R9400	CM-ENE MAX	249	1SVR730831R1300	CM-ESS.1S	89
1SVR550851R9500	CM-ENE MIN	249	1SVR730831R1400	CM-ESS.2S	89
1SVR550855R9400	CM-ENE MAX	249	1SVR730840R0200	CM-SRS.11S	86
1SVR550855R9500	CM-ENE MIN	249	1SVR730840R0300	CM-SRS.12S	86
1SVR550870R9400	CM-PVE	112	1SVR730840R0400	CM-SRS.21S	86
1SVR550871R9500	CM-PVE	112	1SVR730840R0500	CM-SRS.22S	86
LSVR550881R9400	CM-PBE	112	1SVR730840R0600	CM-SRS.M1S	86
LSVR550882R9500	CM-PBE	112	1SVR730840R0700	CM-SRS.M2S	86
1SVR560730R3401	CM-UFD.M31	145	1SVR730841R0200	CM-SRS.11S	86
1SVR560730R3402	CM-UFD.M33	145	1SVR730841R0300	CM-SRS.12S	86

# Measuring and monitoring relays Order code

Order code	Туре	Page
1SVR730841R0400	CM-SRS.21S	86
1SVR730841R0500	CM-SRS.22S	86
1SVR730841R1200	CM-SRS.11S	86
1SVR730841R1300	CM-SRS.12S	86
1SVR730841R1400	CM-SRS.21S	86
1SVR730841R1500	CM-SRS.22S	86
1SVR730850R0100	CM-ENS.11S	249
1SVR730850R0200	CM-ENS.21S	249
1SVR730850R0300	CM-ENS.31S	249
1SVR730850R2100	CM-ENS.11P	249
1SVR730850R2200	CM-ENS.23S	249
1SVR730884R1300	CM-MPS.31S	115
1SVR730884R3300	CM-MPS.41S	115
1SVR730884R11200	CM-MPS.112S	115
1SVR730885R1300	CM-MPS.11S	115
1SVR730885R3300	CM-MPS.21S	115
1SVR730885R11200	CM-MPS.23S	115
1SVR740660R0100	CM-IWS.1P	161
1SVR740670R0200	CM-IWS.2P	161
1SVR740700R0100	CM-MSS.12P	189
1SVR740700R0200	CM-MSS.22P	189
1SVR740700R2100	CM-MSS.13P	189
1SVR740700R2200	CM-MSS.23P	189
1SVR740712R0200	CM-MSS.32P	189
1SVR740712R0200	CM-MSS.41P	189
1SVR740712R1300	CM-MSS.51P	189
1SVR740712R1400	CM-MSS.31P	189
1SVR740712R1400	CM-MSS.33P	189
1SVR740720R1400 1SVR740722R1400	CM-MSS.11P	189
	CM-MSS.21P	189
1SVR740740R0100	CM-TCS.11P	209
1SVR740740R0200	CM-TCS.12P	209
1SVR740740R0300	CM-TCS.13P	209
1SVR740740R16100	CM-TCS.21P	209
1SVR740740R9200	CM-TCS.22P	209
1SVR740740R9300	CM-TCS.23P	209
1SVR740750R0400	CM-EFS.2P	89
1SVR740760R0400	CM-SFS.21P	86
1SVR740774R1300	CM-PAS.31P	112
1SVR740774R3300	CM-PAS.41P	112
1SVR740784R2300	CM-PSS.31P	112
1SVR740784R3300	CM-PSS.41P	112
1SVR740794R1300	CM-PVS.31P	112
1SVR740794R2300	CM-PVS.81P	112
1SVR740794R3300	CM-PVS.41P	112
1SVR740824R9300	CM-PFS.P	112
1SVR740830R0300	CM-ESS.1P	89
1SVR740830R0400	CM-ESS.2P	89
1SVR740830R0500	CM-ESS.MP	89
1SVR740831R0300	CM-ESS.1P	89
1SVR740831R0400	CM-ESS.2P	89

Order code	Туре	Page
1SVR740831R1300	CM-ESS.1P	89
1SVR740831R1400	CM-ESS.2P	89
1SVR740840R0200	CM-SRS.11P	86
1SVR740840R0400	CM-SRS.21P	86
1SVR740840R0600	CM-SRS.M1P	86
1SVR740841R0200	CM-SRS.11P	86
1SVR740841R0400	CM-SRS.21P	86
1SVR740841R1200	CM-SRS.11P	86
1SVR740841R1400	CM-SRS.21P	86
1SVR740850R0100	CM-ENS.13S	249
1SVR740850R0200	CM-ENS.21P	249
1SVR740850R0300	CM-ENS.31P	249
1SVR740850R2100	CM-ENS.13P	249
1SVR740850R2200	CM-ENS.23P	249
1SVR740884R1300	CM-MPS.31P	115
1SVR740884R3300	CM-MPS.41P	115
1SVR740884R11200	CM-MPS.112P	115
1SVR740885R1300	CM-MPS.11P	115
1SVR740885R3300	CM-MPS.21P	115
1SVR740885R11200	CM-MPS.23P	115
1SVR750005R0100	COV.12	172
1SVR750487R8300	CM-MPN.52S	115
1SVR750488R8300	CM-MPN.62S	115
1SVR750489R8300	CM-MPN.72S	115
1SVR750660R0200	CM-IWN.1S	161
1SVR750669R9400	CM-IVN.S	161
1SVR750740R0110	CM-TCN.011S	230
1SVR760740R0120	CM-TCN.012P	230
1SVR760740R0110	CM-TCN.011P	230
1SVR750740R0120	CM-TCN.012S	230
1SVR760487R8300	CM-MPN.52P	115
1SVR760488R8300	CM-MPN.62P	115
1SVR760489R8300	CM-MPN.72P	115
1SVR760660R0200	CM-IWN.1P	161
1SVR760669R9400	CM-IVN.P	161
GHC0110003R0001	C011-70	121
GHC0110003R0002	C011-80	121
GHC0110003R0003	C011-90	121
GHC0110003R0004	C011-100	121
GHC0110003R0005	C011-110	121
GHC0110003R0006	C011-189	121
GHC0110003R0007	C011-130	121
GHC0110003R0008	C011-150	121
GHC0110003R0009	C011-160	121
GHC0110003R0010	C011-170	121
GHC0110003R0011	C011-140	121
GHC0110033R0008	C011-3-150	121

# Power supplies Product type

Туре	Order code	Page
CP-B 24/10.0	1SVR427060R1000	105
CP-B 24/20.0	1SVR427060R2000	105
CP-B 24/3.0	1SVR427060R0300	105
CP-C.1 24/10.0	1SVR360663R1001	70
CP-C.1 24/10.0-C	1SVR360663R2001	70
CP-C.1 24/10.0-L	1SVR361663R1001	70
CP-C.1 24/20.0	1SVR360763R1001	70
CP-C.1 24/20.0-C	1SVR360763R2001	70
CP-C.1 24/20.0-L	1SVR361763R1001	70
CP-C.1 24/5.0	1SVR360563R1001	70
CP-C.1 24/5.0-C	1SVR360563R2001	70
CP-C.1 24/5.0-L	1SVR361563R1001	70
CP-C.1-A-RU	1SVR360060R1001	118
CP-C.1-A-RU-C	1SVR360060R2001	118
CP-C.1-A-RU-L	1SVR361060R1001	118
CP-D 12/0.83	1SVR427041R1000	94
CP-D 12/2.1	1SVR427043R1200	94
CP-D 24/0.42	1SVR427041R0000	94
CP-D 24/1.3	1SVR427043R0100	94
CP-D 24/2.5	1SVR427044R0200	94
CP-D 24/4.2	1SVR427045R0400	94
CP-D RU	1SVR427049R0000	118
CP-E 12/10.0	1SVR427035R1000	18
CP-E 12/2.5	1SVR427032R1000	18
CP-E 24/0.75	1SVR427030R0000	18
CP-E 24/1.25	1SVR427031R0000	18
CP-E 24/10.0	1SVR427035R0000	18
CP-E 24/2.5	1SVR427032R0000	18
CP-E 24/20.0	1SVR427036R0000	18
CP-E 24/5.0	1SVR427034R0000	18
CP-E 48/0.62	1SVR427030R2000	18
CP-E 48/1.25	1SVR427031R2000	18
CP-E 48/10.0	1SVR427035R2000	18
CP-E 48/5.0	1SVR427034R2000	18
CP-E 5/3.0	1SVR427033R3000	18
CP-S.1 24/3.0	1SVR320361R1000	56
CP-S.1 24/5.0	1SVR320561R1000	56
CP-S.1 24/10.0	1SVR320661R1000	56
CP-S.1 24/20.0	15VR320761R1000	56
CP-S.1 24/40.0	1SVR320861R1000	56
CP-C.1-A-RU	1SVR360060R1001	56
CP-T 24/10.0	1SVR427055R0000	38
CP-T 24/20.0	1SVR427056R0000	38
CP-T 24/40.0	1SVR427057R0000	38
•	1SVR427057R0000	38
CP-T 24/5.0	1SVR427054R0000	
CP-T 48/10.0		38
CP-T 48/20.0	1SVR427056R2000	38
CP-T 48/5.0	1SVR427054R2000	38
EPD24-TB-101-0.5A	2CDE601101R2905	128
EPD24-TB-101-10A	2CDE601101R2010	128
EPD24-TB-101-12A	2CDE601101R2012	128

Туре	Order code	Page	
EPD24-TB-101-1A	2CDE601101R2001	128	
EPD24-TB-101-2A	2CDE601101R2002	128	
EPD24-TB-101-3A	2CDE601101R2003	128	
EPD24-TB-101-4A	2CDE601101R2004	128	
EPD24-TB-101-6A	2CDE601101R2006	128	
EPD24-TB-101-8A	2CDE601101R2008	128	
EPD-BB500	2CDE605100R0500	128	
EPD-SB21	2CDE605200R0021	128	

# Power supplies Order code

Order code	Туре	Page
1SVR360060R1001	CP-C.1-A-RU	118
1SVR360060R2001	CP-C.1-A-RU-C	118
1SVR360563R1001	CP-C.1 24/5.0	70
1SVR360563R2001	CP-C.1 24/5.0-C	70
1SVR360663R1001	CP-C.1 24/10.0	70
1SVR360663R2001	CP-C.1 24/10.0-C	70
1SVR360763R1001	CP-C.1 24/20.0	70
1SVR360763R2001	CP-C.1 24/20.0-C	70
1SVR361060R1001	CP-C.1-A-RU-L	118
1SVR361563R1001	CP-C.1 24/5.0-L	70
1SVR361663R1001	CP-C.1 24/10.0-L	70
1SVR361763R1001	CP-C.1 24/20.0-L	70
1SVR320361R1000	CP-S.1 24/3.0	56
1SVR320561R1000	CP-S.1 24/5.0	56
1SVR320661R1000	CP-S.1 24/10.0	56
1SVR320761R1000	CP-S.1 24/20.0	56
1SVR320861R1000	CP-S.1 24/40.0	56
1SVR360060R1001	CP-C.1-A-RU	118
1SVR427030R0000	CP-E 24/0.75	18
1SVR427030R2000	CP-E 48/0.62	18
1SVR427031R0000	CP-E 24/1.25	18
1SVR427031R0000	CP-E 48/1.25	18
1SVR427032R0000	CP-E 24/2.5	18
1SVR427032R0000	CP-E 12/2.5	18
1SVR427032R1000	CP-E 5/3.0	18
1SVR427034R0000	CP-E 3/3.0 CP-E 24/5.0	18
1SVR427034R2000	CP-E 48/5.0	18
1SVR427035R0000	CP-E 24/10.0	18
1SVR427035R1000	CP-E 12/10.0	18
1SVR427035R2000	CP-E 48/10.0	18
1SVR427036R0000	CP-E 24/20.0	18
1SVR427041R0000	CP-D 24/0.42	94
1SVR427041R1000	CP-D 12/0.83	94
1SVR427043R0100	CP-D 24/1.3	94
1SVR427043R1200	CP-D 12/2.1	94
1SVR427044R0200	CP-D 24/2.5	94
1SVR427045R0400	CP-D 24/4.2	94
1SVR427049R0000	CP-D RU	118
1SVR427054R0000	CP-T 24/5.0	38
1SVR427054R2000	CP-T 48/5.0	38
1SVR427055R0000	CP-T 24/10.0	38
1SVR427055R2000	CP-T 48/10.0	38
1SVR427056R0000	CP-T 24/20.0	38
1SVR427056R2000	CP-T 48/20.0	38
1SVR427057R0000	CP-T 24/40.0	38
1SVR427060R0300	CP-B 24/3.0	108
1SVR427060R1000	CP-B 24/10.0	108
1SVR427060R2000	CP-B 24/20.0	108
2CDE601101R2001	EPD24-TB-101-1A	329
2CDE601101R2002	EPD24-TB-101-2A	329
2CDE601101R2003	EPD24-TB-101-3A	329

Order code	Туре	Page
2CDE601101R2004	EPD24-TB-101-4A	329
2CDE601101R2006	EPD24-TB-101-6A	329
2CDE601101R2008	EPD24-TB-101-8A	329
2CDE601101R2010	EPD24-TB-101-10A	329
2CDE601101R2012	EPD24-TB-101-12A	329
2CDE601101R2905	EPD24-TB-101-0.5A	329
2CDE605100R0500	EPD-BB500	329
2CDE605200R0021	EPD-SB21	329

Туре	Order code	Page	Туре	Order code	Page
CR-M012AC2L	1SVR405611R0300	438	CR-M048DC2L	1SVR405611R6100	438
CR-M012AC3L	1SVR405612R0300	438	CR-M048DC2LD	1SVR405611R6400	439
CR-M012AC4L	1SVR405613R0300	438	CR-M048DC3	1SVR405612R6000	414
CR-M012DC2	1SVR405611R4000	414	CR-M048DC3L	1SVR405612R6100	438
CR-M012DC2L	1SVR405611R4100	438	CR-M048DC3LD	1SVR405612R6400	439
CR-M012DC2LD	1SVR405611R4400	439	CR-M048DC4	1SVR405613R6000	414
CR-M012DC3	1SVR405612R4000	414	CR-M048DC4L	1SVR405613R6100	438
CR-M012DC3L	1SVR405612R4100	438	CR-M048DC4LD	1SVR405613R6400	439
CR-M012DC3LD	1SVR405612R4400	439	CR-M048DC4LG	1SVR405618R6100	440
CR-M012DC4	1SVR405613R4000	414	CR-M060AC3	1SVR405612R5200	414
CR-M012DC4L	1SVR405613R4100	438	CR-M060DC2	1SVR405611R4200	414
CR-M012DC4LD	1SVR405613R4400	439	CR-M060DC2L	1SVR405611R4300	438
CR-M012DC4LDG	1SVR405618R4400	440	CR-M060DC3	1SVR405612R4200	414
CR-M012DC4LDGSS	1SVR405618R4410	420	CR-M060DC3L	1SVR405612R4300	438
CR-M012DC4LG	1SVR405618R4100	440	CR-M060DC4	1SVR405613R4200	414
CR-M024AC2	1SVR405611R0000	414	CR-M060DC4L	1SVR405613R4300	438
CR-M024AC2L	1SVR405611R0100	438	CR-M060DC4LG	1SVR405618R4300	440
CR-M024AC3	1SVR405612R0000	414	CR-M110AC2	1SVR405611R7000	414
CR-M024AC3L	1SVR405612R0100	438	CR-M110AC2L	1SVR405611R7100	438
CR-M024AC4	1SVR405613R0000	414	CR-M110AC3	1SVR405612R7000	414
CR-M024AC4G	1SVR405618R0000	439	CR-M110AC3L	1SVR405612R7100	438
CR-M024AC4L	1SVR405613R0100	438	CR-M110AC4	1SVR405613R7000	414
CR-M024AC4LG	1SVR405618R0100	440	CR-M110AC4G	1SVR405618R7000	439
CR-M024AC4LS62CV	1SVR405613R0010	420	CR-M110AC4L	1SVR405613R7100	438
CR-M024DC2	1SVR405611R1000	414	CR-M110AC4LG	1SVR405618R7100	440
CR-M024DC2L	1SVR405611R1100	438	CR-M110DC2	1SVR405611R8000	414
CR-M024DC2LD	1SVR405611R1400	439	CR-M110DC2L	1SVR405611R8100	438
CR-M024DC3	1SVR405612R1000	414	CR-M110DC2LD	1SVR405611R8400	439
CR-M024DC3L	1SVR405612R1100	438	CR-M110DC3	1SVR405612R8000	414
CR-M024DC3LD	1SVR405612R1400	439	CR-M110DC3L	1SVR405612R8100	438
CR-M024DC4	1SVR405613R1000	414	CR-M110DC3LD	1SVR405612R8400	439
CR-M024DC4G	1SVR405618R1000	439	CR-M110DC4	1SVR405613R8000	414
CR-M024DC4GLC62CV	1SVR405618R1010	420	CR-M110DC4L	1SVR405613R8100	438
CR-M024DC4GSS42V	1SVR405618R1011	420	CR-M110DC4LD	1SVR405613R8400	439
CR-M024DC4L	1SVR405613R1100	438	CR-M110DC4LG	1SVR405618R8100	440
CR-M024DC4LC42	1SVR405613R1012	420	CR-M120AC2	1SVR405611R2000	414
CR-M024DC4LD	1SVR405614R1100	439	CR-M120AC2L	1SVR405611R2100	438
CR-M024DC4LDG	1SVR405618R1400	440	CR-M120AC3	1SVR405612R2000	414
CR-M024DC4LDGSS	1SVR405618R1410	420	CR-M120AC3L	1SVR405612R2100	438
CR-M024DC4LG	1SVR405618R1100	440	CR-M120AC4	1SVR405613R2000	414
CR-M024DC4LGLC22	1SVR405618R1110	420	CR-M120AC4L	1SVR405613R2100	438
CR-M024DC4LS42V	1SVR405613R1011	420	CR-M120AC4LG	1SVR405618R2100	440
CR-M024DC4SS42V	1SVR405613R1010	420	CR-M125DC2	1SVR405611R8200	414
CR-M048AC2	1SVR405611R5000	414	CR-M125DC2L	1SVR405611R8300	438
CR-M048AC2L	1SVR405611R5100	438	CR-M125DC2LD	1SVR405611R8500	439
CR-M048AC3	1SVR405612R5000	414	CR-M125DC3	1SVR405612R8200	414
CR-M048AC3L	1SVR405612R5100	438	CR-M125DC3L	1SVR405612R8300	438
CR-M048AC4	1SVR405613R5000	414	CR-M125DC3LD	1SVR405612R8500	439
CR-M048AC4L	1SVR405613R5100	438	CR-M125DC4	1SVR405613R8200	414
CR-M048AC4LG	1SVR405618R5100	440	CR-M125DC4L	1SVR405613R8300	438
CR-M048DC2	1SVR405611R6000	414	CR-M125DC4LD	1SVR405613R8500	439

Туре	Order code	Page	Туре	Order code	Page
CR-M125DC4LG	1SVR405618R8300	440	CR-P/M 52D	1SVR405653R4000	421
CR-M220DC2	1SVR405611R9000	414	CR-P/M 62	1SVR405654R0000	421
CR-M220DC2L	1SVR405611R9100	438	CR-P/M 62 C	1SVR405655R0000	422
CR-M220DC2LD	1SVR405611R9400	439	CR-P/M 62 CV	1SVR405655R1000	422
CR-M220DC3	1SVR405612R9000	414	CR-P/M 62 D	1SVR405655R4000	422
CR-M220DC3L	1SVR405612R9100	438	CR-P/M 62 DV	1SVR405655R4100	422
CR-M220DC3LD	1SVR405612R9400	439	CR-P/M 62 E	1SVR405654R4000	421
CR-M220DC4	1SVR405613R9000	414	CR-P/M 62 EV	1SVR405654R4100	421
CR-M220DC4L	1SVR405613R9100	438	CR-P/M 62 V	1SVR405654R1000	421
CR-M220DC4LD	1SVR405613R9400	439	CR-P/M 72	1SVR405656R0000	422
CR-M220DC4LG	1SVR405618R9100	440	CR-P/M 72 A	1SVR405656R1000	422
CR-M230AC2	1SVR405611R3000	414	CR-P/M 82	1SVR405656R2000	422
CR-M230AC2L	1SVR405611R3100	438	CR-P/M 92	1SVR405654R0100	421
CR-M230AC3	1SVR405612R3000	414	CR-P/M 92 C	1SVR405655R0100	422
CR-M230AC3L	1SVR405612R3100	438	CR-P/M 92 CV	1SVR405655R1100	422
CR-M230AC4	1SVR405613R3000	414	CR-P/M 92 V	1SVR405654R1100	421
CR-M230AC4G	1SVR405618R3000	439	CR-P012AC2	1SVR405601R0200	433
CR-M230AC4GSS92CV	1SVR405618R3112	421	CR-P012DC1	1SVR405600R4000	433
CR-M230AC4L	1SVR405613R3100	438	CR-P012DC1SS42V	1SVR405600R4010	412
CR-M230AC4LC92	1SVR405613R3012	421	CR-P012DC2	1SVR405601R4000	433
CR-M230AC4LG	1SVR405618R3100	440	CR-P012DC2SS42V	1SVR405601R4010	413
CR-M230AC4LGLC	1SVR405618R3110	421	CR-P012BC23342V	1SVR405600R0000	433
CR-M230AC4LGSS	1SVR405618R3111	421	CR-P024AC1SS62CV	1SVR405600R0000	412
CR-M230AC4LS92CV	1SVR405613R3011	421	CR-P024AC2	1SVR405601R0000	433
CR-M230AC4S592CV	1SVR405613R3110	421	CR-P024AC2G	1SVR405606R0000	433
CR-M2LC	1SVR405613R3110	421	CR-P024AC2S	1SVR405601R0010	413
CR-M2LS CR-M2LSH	1SVR405651R1100	420	CR-P024DC1 CR-P024DC1LC42V	1SVR405600R1000	433
	1SVR405651R4100			1SVR405600R1011	
CR-M2SF	1SVR405651R1300	420	CR-P024DC1LC62C	1SVR405600R1013	412
CR-M2SS	1SVR405651R1000	420	CR-P024DC1SS42V	1SVR405600R1010	412
CR-M3LS	1SVR405651R2100	420	CR-P024DC2	1SVR405601R1000	433
CR-M3LSH	1SVR405651R5100	420	CR-P024DC2G	1SVR405606R1000	433
CR-M3SS	1SVR405651R2000	420	CR-P024DC2GLC42V	1SVR405606R1010	413
CR-M4LC	1SVR405651R3200	420	CR-P024DC2GLC62C	1SVR405606R1013	413
CR-M4LS	1SVR405651R3100	420	CR-P024DC2GLC62CV	1SVR405606R1011	413
CR-M4SF	1SVR405651R3300	420	CR-P024DC2LC42	1SVR405601R1012	413
CR-M4SS	1SVR405651R3000	420	CR-P024DC2LS42	1SVR405601R1013	413
CR-MH	1SVR405659R1000	420	CR-P024DC2LS42V	1SVR405601R1011	413
CR-MH1	1SVR405659R1100	420	CR-P024DC2SS42V	1SVR405601R1010	413
CR-MJ	1SVR405658R6000	420	CR-P024MOS1	1SVR405610R4060	433
CR-MM	1SVR405658R1000	420	CR-P024TRI1	1SVR405610R4070	433
CR-MP	1SVR405658R2000	420	CR-P048AC1	1SVR405600R5000	433
CR-P/M 22	1SVR405651R0000	421	CR-P048AC2	1SVR405601R5000	433
CR-P/M 42	1SVR405652R0000	421	CR-P048DC1	1SVR405600R6000	433
CR-P/M 42 B	1SVR405652R4000	421	CR-P048DC2	1SVR405601R6000	433
CR-P/M 42 BV	1SVR405652R4100	421	CR-P110AC1	1SVR405600R7000	433
CR-P/M 42 C	1SVR405652R9000	421	CR-P110AC2	1SVR405601R7000	433
CR-P/M 42 CV	1SVR405652R9100	421	CR-P110AC2G	1SVR405606R7000	433
CR-P/M 42 V	1SVR405652R1000	421	CR-P110DC1	1SVR405600R8000	433
CR-P/M 52B	1SVR405653R0000	421	CR-P110DC1SS42CV	1SVR405600R8010	412
CR-P/M 52C	1SVR405653R1000	421	CR-P110DC2	1SVR405601R8000	433

Туре	Order code	Page	Туре	Order code	Page
CR-P110DC2SS42CV	1SVR405601R8010	413	CR-S110VADC1CRGZ	1SVR405541R6220	429
CR-P120AC1	1SVR405600R2000	433	CR-S110VADC1CRS	1SVR405541R6110	429
CR-P120AC1SS92CV	1SVR405600R2010	412	CR-S110VADC1CRZ	1SVR405541R6210	429
CR-P120AC2	1SVR405601R2000	433	CR-S220/240VADC1SS	1SVR405521R7100	430
CR-P120AC2SS92CV	1SVR405601R2010	413	CR-S220/240VADC1SZ	1SVR405521R7200	430
CR-P230AC1	1SVR405600R3000	433	CR-S230VADC1CRGS	1SVR405541R7120	429
CR-P230AC1LC92CV	1SVR405600R3010	412	CR-S230VADC1CRGZ	1SVR405541R7220	429
CR-P230AC1LS	1SVR405600R3011	412	CR-S230VADC1CRS	1SVR405541R7110	429
CR-P230AC1SS92CV	1SVR405600R3110	412	CR-S230VADC1CRZ	1SVR405541R7210	429
CR-P230AC2	1SVR405601R3000	433	CR-SJB20-BLACK	1SVR405598R0900	430
CR-P230AC2G	1SVR405606R3000	433	CR-SJB20-BLUE	1SVR405598R0700	430
CR-P230AC2GLC92	1SVR405606R3013	413	CR-SJB20-RED	1SVR405598R0800	430
CR-P230AC2GLC92C	1SVR405606R3012	413	CR-SSEP	1SVR405599R0000	430
CR-P230AC2GLC92CV	1SVR405606R3010	413	CR-U 21	1SVR405661R0000	424
CR-P230AC2LC92	1SVR405601R3012	413	CR-U 41	1SVR405662R0000	424
CR-P230AC2LS92CV	1SVR405601R3011	413	CR-U 41B	1SVR405662R4000	424
CR-P230AC2SS92CV	1SVR405601R3110	413	CR-U 41BV	1SVR405662R4100	424
CR-PH	1SVR405659R0000	413	CR-U 41C	1SVR405662R9000	424
CR-PH1	1SVR405659R0100	413	CR-U 41CV	1SVR405662R9100	424
CR-PJ	1SVR405658R5000	413	CR-U 41V	1SVR405662R1000	424
CR-PLC	1SVR405650R0200	413	CR-U 51B	1SVR405663R0000	424
CR-PLS	1SVR405650R0000	413	CR-U 51C	1SVR405663R1000	424
CR-PLSX	1SVR405650R0100	413	CR-U 51D	1SVR405663R4000	424
CR-PM	1SVR405658R0000	413	CR-U 61	1SVR405664R0000	424
CR-PSS	1SVR405650R1000	413	CR-U 61C	1SVR405665R0000	424
CR-S005VDC1R	1SVR405501R1010	429	CR-U 61CV	1SVR405665R1000	424
CR-S005VDC1RG	1SVR405501R1020	429	CR-U 61D	1SVR405665R4000	424
CR-S006/024VDC1SS	1SVR405521R1100	430	CR-U 61DV	1SVR405665R4100	424
CR-S006/024VDC1SZ	1SVR405521R1200	430	CR-U 61E	1SVR405664R4000	424
CR-S012/024VADC1SS	1SVR405521R3100	430	CR-U 61EV	1SVR405664R4100	424
CR-S012/024VADC1SZ	1SVR405521R3200	430	CR-U 61V	1SVR405664R1000	424
CR-S012VDC1R	1SVR405501R2010	429	CR-U 71	1SVR405666R0000	424
CR-S012VDC1RG	1SVR405501R2020	429	CR-U 71A	1SVR405666R1000	424
CR-S024VADC1CRGS	1SVR405541R3120	429	CR-U 81	1SVR405666R2000	424
CR-S024VADC1CRGZ	1SVR405541R3220	429	CR-U 91	1SVR405664R0100	424
CR-S024VADC1CRS	1SVR405541R3110	429	CR-U 91C	1SVR405665R0100	424
CR-S024VADC1CRZ	1SVR405541R3210	429	CR-U 91CV	1SVR405665R1100	424
CR-S024VDC1MOS	1SVR405510R3060	429	CR-U 91V	1SVR405664R1100	424
CR-S024VDC1R	1SVR405501R3010	429	CR-U T	1SVR405667R0000	424
CR-S024VDC1RG	1SVR405501R3020	429	CR-U012AC2L	1SVR405621R0300	446
CR-S024VDC1TRA	1SVR405510R3050	429	CR-U012AC3L	1SVR405622R0300	447
CR-S024VDC1TRI	1SVR405510R3070	429	CR-U012DC2	1SVR405621R4000	446
CR-S048/060VADC1SS	1SVR405521R5100	430	CR-U012DC2L	1SVR405621R4100	446
CR-S048/060VADC1SZ	1SVR405521R5200	430	CR-U012DC2LD	1SVR405621R4400	447
CR-S048VDC1R	1SVR405501R4010	429	CR-U012DC3	1SVR405622R4000	446
CR-S048VDC1RG	1SVR405501R4020	429	CR-U012DC3L	1SVR405622R4100	447
CR-S060VDC1R	1SVR405501R5010	429	CR-U012DC3LD	1SVR405622R4400	447
CR-S060VDC1RG	1SVR405501R5020	429	CR-U024AC2	1SVR405621R0000	446
CR-S110/125VADC1SS	1SVR405521R6100	430	CR-U024AC2L	1SVR405621R0100	446
CR-S110/125VADC1SZ	1SVR405521R6200	430	CR-U024AC3	1SVR405622R0000	446
CR-S110VADC1CRGS	1SVR405541R6120	429	CR-U024AC3L	1SVR405622R0100	447

#### Index

Туре	Order code	Page	Туре	Order code
CR-U024DC2	1SVR405621R1000	446	OBOA1000-230VUC	1SNA645028R0500
CR-U024DC2L	1SVR405621R1100	446	OBOA1000-24VDC	1SNA645027R2400
CR-U024DC2LD	1SVR405621R1400	447	OBOA2000-24VDC	1SNA645029R0600
CR-U024DC3	1SVR405622R1000	446	OBOC2000-115VUC	1SNA645054R0700
CR-U024DC3L	1SVR405622R1100	447	OBOC2000-230VUC	1SNA645026R2300
CR-U024DC3LD	1SVR405623R1100	447	OBOC2000-24VDC	1SNA645051R0400
CR-U048AC2	1SVR405621R5000	446	OBOC2000-24VUC	1SNA645025R2200
CR-U048AC2L	1SVR405621R5100	446	OBOC2000-446-60VUC	1SNA645053R0600
CR-U048AC3	1SVR405622R5000	446	OBOC2000-5-12VDC	1SNA645050R1700
CR-U048AC3L	1SVR405622R5100	447	OBOC5000-115VUC	1SNA645058R1300
CR-U048DC2	1SVR405621R6000	446	OBOC5000-24VDC	1SNA645024R2100
CR-U048DC2L	1SVR405621R6100	446	OBRIC0100-115-230	1SNA645522R2100
CR-U048DC2LD	1SVR405621R6400	447	OBRIC0100-24VDC	1SNA645521R2000
CR-U048DC3	1SVR405622R6000	446	OBRIC0100-446-60VUC	1SNA645549R1400
CR-U048DC3L	1SVR405622R6100	447	OBRIC0100-5-12VDC	1SNA645547R0200
CR-U048DC3LD	1SVR405622R6400	447	OBROA1000-24VDC	1SNA645527R2600
CR-U060AC3	1SVR405622R5200	446	OBROA2000-24VDC	1SNA645529R0000
CR-U110AC2	1SVR405621R7000	446	OBROC2000-230VUC	1SNA645526R2500
CR-U110AC2L	1SVR405621R7100	446	OBROC2000-24VDC	1SNA645551R0600
CR-U110AC3	1SVR405622R7000	446	OBROC2000-24VUC	1SNA645525R2400
CR-U110AC3L	1SVR405622R7100	447	OBROC2000-446-60VUC	1SNA645553R0000
CR-U110DC2	1SVR405621R8000	446	OBROC2000-5-12VDC	1SNA645550R1100
CR-U110DC2L	1SVR405621R8100	446	OBROC5000-230VUC	1SNA645559R1600
CR-U110DC2LD	1SVR405621R8400	447	OBROC5000-24VDC	1SNA645524R2300
CR-U110DC3	1SVR405622R8000	446	RB101R-24VUC	1SNA645019R0400
CR-U110DC3L	1SVR405622R8100	447	RB111-115VUC	1SNA645016R2100
CR-U110DC3LD	1SVR405622R8400	447	RB111-230VUC	1SNA645017R2200
CR-U120AC2	1SVR405621R2000	446	RB111-24VUC	1SNA645014R2700
CR-U120AC2L	1SVR405621R2100	446	RB111R-24VUC	1SNA645018R0300
CR-U120AC3	1SVR405622R2000	446	RB121-115VUC	1SNA645003R0500
CR-U120AC3L	1SVR405622R2100	447	RB121-12VDC	1SNA645073R0000
CR-U125DC3	1SVR405622R8200	446	RB121-230VUC	1SNA645004R0400
CR-U220DC2	1SVR405621R9000	446	RB121-24VDC	1SNA645071R0000
CR-U220DC2L	1SVR405621R9100	446	RB121-24VUC	1SNA645001R0300
CR-U220DC3	1SVR405622R9000	446	RB121-446-60VUC	1SNA645002R0400
CR-U220DC3L	1SVR405622R9100	447	RB121-60-230VUC	1SNA645020R0100
CR-U230AC2	1SVR405621R3000	446	RB121G-115VUC	1SNA645007R0100
CR-U230AC2L	1SVR405621R3100	446	RB121G-12VDC	1SNA645075R0000
CR-U230AC3	1SVR405622R3000	446	RB121G-230VUC	1SNA645008R1200
CR-U230AC3L	1SVR405622R3100	447	RB121G-24VDC	1SNA645072R0000
CR-U2S	1SVR405670R0000	447	RB121G-24VUC	1SNA645005R0700
CR-U2SM	1SVR405670R1100	447	RB121G-446-60VUC	1SNA645006R0000
CR-U3E	1SVR405660R0100	447	RB121P-12VDC	1SNA645035R2400
CR-U3S	1SVR405660R0000	447	RB121P-5VDC	1SNA645034R2300
CR-U3SM	1SVR405660R1100	447	RB121PG-5VDC	1SNA645036R2500
CR-UH	1SVR405669R0000	447	RB121R-115VUC	1SNA645046R0700
OBIC0100-115-230	1SNA645022R2700	492	RB121R-230VUC	1SNA645011R2400
OBIC0100-24VDC	1SNA645021R2600	492	RB122G-115VUC	1SNA645041R0200
OBIC0100-446-60VUC	1SNA645049R1200	492	RB122G-230VUC	1SNA645013R2600
OBIC0100-5-12VDC	1SNA645047R0000	492	RB122G-24VUC	1SNA645012R2500
OBOA1000-115VUC	1SNA645062R0700	492	RB122G-446-60VUC	1SNA645040R1500
2P0V1000-112A0C	1314404300540100	492	VD155G-440-0010C	1314043040K1300

Туре	Order code	Page
RB-JB10	1SVR406570R0000	485
RB-JB20	1SVR406580R0000	485
RBR101R-24VUC	1SNA645519R0600	484
RBR111-24VUC	1SNA645514R2100	484
RBR111R-24VUC	1SNA645518R0500	484
RBR121-115VUC	1SNA645503R0700	484
RBR121-230VUC	1SNA645504R0000	484
RBR121-24VDC	1SNA645571R0000	484
RBR121-24VUC	1SNA645501R0500	484
RBR121-446-60VUC	1SNA645502R0600	484
RBR121-60-230VUC	1SNA645520R0300	485
RBR121G-115VUC	1SNA645507R0300	485
RBR121G-230VUC	1SNA645508R1400	485
RBR121G-24VDC	1SNA645572R0000	485
RBR121G-24VUC	1SNA645505R0100	485
RBR121G-446-60VUC	1SNA645506R0200	485
RBR121P-12VDC	1SNA645535R2600	484
RBR121P-5VDC	1SNA645534R2500	484
RBR121R-230VUC	1SNA645511R2600	485
RBR122G-115VUC	1SNA645541R0400	485
RBR122G-230VUC	1SNA645513R2000	485
RBR122G-24VUC	1SNA645512R2700	485
RBR122G-446-60VUC	1SNA645540R1700	485
SC612	1SNA290474R0200	485

Order code	Туре	Page	Order code	Туре	Page
1SNA290474R0200	SC612	485	1SNA645508R1400	RBR121G-230VUC	485
1SNA645001R0300	RB121-24VUC	484	1SNA645511R2600	RBR121R-230VUC	485
1SNA645002R0400	RB121-446-60VUC	484	1SNA645512R2700	RBR122G-24VUC	485
1SNA645003R0500	RB121-115VUC	484	1SNA645513R2000	RBR122G-230VUC	485
1SNA645004R0400	RB121-230VUC	484	1SNA645514R2100	RBR111-24VUC	484
1SNA645005R0700	RB121G-24VUC	485	1SNA645518R0500	RBR111R-24VUC	484
1SNA645006R0000	RB121G-446-60VUC	485	1SNA645519R0600	RBR101R-24VUC	484
1SNA645007R0100	RB121G-115VUC	485	1SNA645520R0300	RBR121-60-230VUC	485
1SNA645008R1200	RB121G-230VUC	485	1SNA645521R2000	OBRIC0100-24VDC	492
1SNA645011R2400	RB121R-230VUC	485	1SNA645522R2100	OBRIC0100-115-230	492
1SNA645012R2500	RB122G-24VUC	485	1SNA645524R2300	OBROC5000-24VDC	492
1SNA645013R2600	RB122G-230VUC	485	1SNA645525R2400	OBROC2000-24VUC	492
1SNA645014R2700	RB111-24VUC	484	1SNA645526R2500	OBROC2000-230VUC	492
1SNA645016R2100	RB111-115VUC	484	1SNA645527R2600	OBROA1000-24VDC	492
1SNA645017R2200	RB111-230VUC	484	1SNA645529R0000	OBROA2000-24VDC	485
1SNA645018R0300	RB111R-24VUC	484	1SNA645534R2500	RBR121P-5VDC	484
1SNA645019R0400	RB101R-24VUC	484	1SNA645535R2600	RBR121P-12VDC	484
1SNA645020R0100	RB121-60-230VUC	485	1SNA645540R1700	RBR122G-446-60VUC	485
1SNA645021R2600	OBIC0100-24VDC	492	1SNA645541R0400	RBR122G-115VUC	485
1SNA645022R2700	OBIC0100-115-230	492	1SNA645547R0200	OBRICO100-5-12VDC	492
1SNA645024R2100	OBOC5000-24VDC	492	1SNA645549R1400	OBRIC0100-446-60VUC	492
1SNA645025R2200	OBOC2000-24VUC	492	1SNA645550R1100	OBROC2000-5-12VDC	492
1SNA645026R2300	OBOC2000-230VUC	492	1SNA645551R0600	OBROC2000-24VDC	492
1SNA645027R2400	OBOA1000-24VDC	492	1SNA645553R0000	OBROC2000-446-60VUC	492
1SNA645028R0500	OBOA1000-230VUC	492	1SNA645559R1600	OBROC5000-230VUC	492
1SNA645029R0600	OBOA2000-24VDC	485	1SNA645571R0000	RBR121-24VDC	484
1SNA645034R2300	RB121P-5VDC	484	1SNA645572R0000	RBR121G-24VDC	485
1SNA645035R2400	RB121P-12VDC	484	1SVR405501R1010	CR-S005VDC1R	429
1SNA645036R2500	RB121PG-5VDC	485	1SVR405501R1020	CR-S005VDC1RG	429
1SNA645040R1500	RB122G-446-60VUC	485	1SVR405501R2010	CR-S012VDC1R	429
1SNA645041R0200	RB122G-115VUC	485	1SVR405501R2020	CR-S012VDC1RG	429
1SNA645046R0700	RB121R-115VUC	485	1SVR405501R3010	CR-S024VDC1R	429
1SNA645047R0000	OBIC0100-5-12VDC	492	1SVR405501R3020	CR-S024VDC1RG	429
1SNA645049R1200	OBIC0100-3-12 VDC	492	1SVR405501R4010	CR-S048VDC1R	429
1SNA645049R1200	OBOC2000-5-12VDC	492	1SVR405501R4020	CR-S048VDC1RG	429
			1SVR405501R5010	CR-S060VDC1R	429
1SNA645051R0400	OBOC2000-24VDC	492		CR-S060VDC1RG	429
1SNA645053R0600	OBOC2000-446-60VUC	492	1SVR405501R5020		
1SNA645054R0700	OBOC2000-115VUC	492	1SVR405510R3050	CR-S024VDC1TRA	429
1SNA645058R1300	OBOC5000-115VUC	492	1SVR405510R3060	CR-S024VDC1MOS	429
1SNA645062R0700	OBOA1000-115VUC	492	1SVR405510R3070	CR-S024VDC1TRI	429
1SNA645071R0000	RB121-24VDC	484	1SVR405521R1100	CR-S006/024VDC1SS	430
1SNA645072R0000	RB121G-24VDC	485	1SVR405521R1200	CR-S006/024VDC1SZ	430
1SNA645073R0000	RB121-12VDC	484	1SVR405521R3100	CR-S012/024VADC1SS	430
1SNA645075R0000	RB121G-12VDC	485	1SVR405521R3200	CR-S012/024VADC1SZ	430
1SNA645501R0500	RBR121-24VUC	484	1SVR405521R5100	CR-S048/060VADC1SS	430
1SNA645502R0600	RBR121-446-60VUC	484	1SVR405521R5200	CR-S048/060VADC1SZ	430
1SNA645503R0700	RBR121-115VUC	484	1SVR405521R6100	CR-S110/125VADC1SS	430
1SNA645504R0000	RBR121-230VUC	484	1SVR405521R6200	CR-S110/125VADC1SZ	430
1SNA645505R0100	RBR121G-24VUC	485	1SVR405521R7100	CR-S220/240VADC1SS	430
1SNA645506R0200	RBR121G-446-60VUC	485	1SVR405521R7200	CR-S220/240VADC1SZ	430
1SNA645507R0300	RBR121G-115VUC	485	1SVR405541R3110	CR-S024VADC1CRS	429

Order code	Туре	Page	Order code	Туре	Page
1SVR405541R3120	CR-S024VADC1CRGS	429	1SVR405601R6000	CR-P048DC2	433
1SVR405541R3210	CR-S024VADC1CRZ	429	1SVR405601R7000	CR-P110AC2	433
1SVR405541R3220	CR-S024VADC1CRGZ	429	1SVR405601R8000	CR-P110DC2	433
1SVR405541R6110	CR-S110VADC1CRS	429	1SVR405601R8010	CR-P110DC2SS42CV	436
1SVR405541R6120	CR-S110VADC1CRGS	429	1SVR405606R0000	CR-P024AC2G	433
1SVR405541R6210	CR-S110VADC1CRZ	429	1SVR405606R1000	CR-P024DC2G	433
1SVR405541R6220	CR-S110VADC1CRGZ	429	1SVR405606R1010	CR-P024DC2GLC42V	436
1SVR405541R7110	CR-S230VADC1CRS	429	1SVR405606R1011	CR-P024DC2GLC62CV	436
1SVR405541R7120	CR-S230VADC1CRGS	429	1SVR405606R1013	CR-P024DC2GLC62C	436
1SVR405541R7210	CR-S230VADC1CRZ	429	1SVR405606R3000	CR-P230AC2G	433
1SVR405541R7220	CR-S230VADC1CRGZ	429	1SVR405606R3010	CR-P230AC2GLC92CV	436
1SVR405598R0700	CR-SJB20-BLUE	430	1SVR405606R3012	CR-P230AC2GLC92C	436
1SVR405598R0800	CR-SJB20-RED	430	1SVR405606R3013	CR-P230AC2GLC92	436
1SVR405598R0900	CR-SJB20-BLACK	430	1SVR405606R7000	CR-P110AC2G	433
1SVR405599R0000	CR-SSEP	430	1SVR405610R4060	CR-P024MOS1	433
1SVR405600R0000	CR-P024AC1	433	1SVR405610R4070	CR-P024TRI1	433
1SVR405600R0010	CR-P024AC1SS62CV	412	1SVR405611R0000	CR-M024AC2	437
1SVR405600R1000	CR-P024DC1	433	1SVR405611R0100	CR-M024AC2L	438
1SVR405600R1010	CR-P024DC1SS42V	412	1SVR405611R0300	CR-M012AC2L	438
1SVR405600R1011	CR-P024DC1LC42V	412	1SVR405611R1000	CR-M024DC2	437
1SVR405600R1013	CR-P024DC1LC62C	412	1SVR405611R1100	CR-M024DC2L	438
1SVR405600R2000	CR-P120AC1	433	1SVR405611R1400	CR-M024DC2LD	439
1SVR405600R2010	CR-P120AC1SS92CV	412	1SVR405611R2000	CR-M120AC2	437
1SVR405600R3000	CR-P230AC1	433	1SVR405611R2100	CR-M120AC2L	438
1SVR405600R3010	CR-P230AC1LC92CV	412	1SVR405611R3000	CR-M230AC2	437
1SVR405600R3011	CR-P230AC1LS	412	1SVR405611R3100	CR-M230AC2L	438
1SVR405600R3110	CR-P230AC1SS92CV	412	1SVR405611R4000	CR-M012DC2	437
1SVR405600R4000	CR-P012DC1	433	1SVR405611R4100	CR-M012DC2L	438
1SVR405600R4010	CR-P012DC1SS42V	412	1SVR405611R4200	CR-M060DC2	437
1SVR405600R5000	CR-P048AC1	433	1SVR405611R4300	CR-M060DC2L	438
1SVR405600R6000	CR-P048DC1	433	1SVR405611R4400	CR-M012DC2LD	439
1SVR405600R7000	CR-P110AC1	433	1SVR405611R5000	CR-M048AC2	437
1SVR405600R8000	CR-P110DC1	433	1SVR405611R5100	CR-M048AC2L	438
1SVR405600R8010	CR-P110DC1SS42CV	412	1SVR405611R6000	CR-M048DC2	437
1SVR405601R0000	CR-P024AC2	433	1SVR405611R6100	CR-M048DC2L	438
1SVR405601R0010	CR-P024AC2SS62CV	436	1SVR405611R6400	CR-M048DC2LD	439
1SVR405601R0200	CR-P012AC2	433	1SVR405611R7000	CR-M110AC2	437
1SVR405601R1000	CR-P024DC2	433	1SVR405611R7100	CR-M110AC2L	438
1SVR405601R1010	CR-P024DC2SS42V	436	1SVR405611R8000	CR-M110DC2	437
1SVR405601R1011	CR-P024DC2LS42V	436	1SVR405611R8100	CR-M110DC2L	438
1SVR405601R1012	CR-P024DC2LC42	436	1SVR405611R8200	CR-M125DC2	437
1SVR405601R1013	CR-P024DC2LS42	436	1SVR405611R8300	CR-M125DC2L	438
1SVR405601R2000	CR-P120AC2	433	1SVR405611R8400	CR-M110DC2LD	439
1SVR405601R2010	CR-P120AC2SS92CV	436	1SVR405611R8500	CR-M125DC2LD	439
1SVR405601R3000	CR-P230AC2	433	1SVR405611R9000	CR-M220DC2	437
1SVR405601R3011	CR-P230AC2LS92CV	436	1SVR405611R9100	CR-M220DC2L	438
1SVR405601R3012	CR-P230AC2LC92	436	1SVR405611R9400	CR-M220DC2LD	439
1SVR405601R3110	CR-P230AC2SS92CV	436	1SVR405612R0000	CR-M024AC3	437
1SVR405601R4000	CR-P012DC2	433	1SVR405612R0100	CR-M024AC3L	438
1SVR405601R4010	CR-P012DC2SS42V	436	1SVR405612R0300	CR-M012AC3L	438
1SVR405601R5000	CR-P048AC2	433	1SVR405612R1000	CR-M024DC3	437

Order code	Туре	Page	Order code	Туре	Page
1SVR405612R1100	CR-M024DC3L	438	1SVR405613R6000	CR-M048DC4	437
1SVR405612R1400	CR-M024DC3LD	439	1SVR405613R6100	CR-M048DC4L	438
1SVR405612R2000	CR-M120AC3	437	1SVR405613R6400	CR-M048DC4LD	439
1SVR405612R2100	CR-M120AC3L	438	1SVR405613R7000	CR-M110AC4	437
1SVR405612R3000	CR-M230AC3	437	1SVR405613R7100	CR-M110AC4L	438
1SVR405612R3100	CR-M230AC3L	438	1SVR405613R8000	CR-M110DC4	437
1SVR405612R4000	CR-M012DC3	437	1SVR405613R8100	CR-M110DC4L	438
1SVR405612R4100	CR-M012DC3L	438	1SVR405613R8200	CR-M125DC4	437
1SVR405612R4200	CR-M060DC3	437	1SVR405613R8300	CR-M125DC4L	438
1SVR405612R4300	CR-M060DC3L	438	1SVR405613R8400	CR-M110DC4LD	439
1SVR405612R4400	CR-M012DC3LD	439	1SVR405613R8500	CR-M125DC4LD	439
1SVR405612R5000	CR-M048AC3	437	1SVR405613R9000	CR-M220DC4	437
1SVR405612R5100	CR-M048AC3L	438	1SVR405613R9100	CR-M220DC4L	438
1SVR405612R5200	CR-M060AC3	437	1SVR405613R9400	CR-M220DC4LD	439
1SVR405612R6000	CR-M048DC3	437	1SVR405614R1100	CR-M024DC4LD	439
1SVR405612R6100	CR-M048DC3L	438	1SVR405618R0000	CR-M024AC4G	439
1SVR405612R6400	CR-M048DC3LD	439	1SVR405618R0100	CR-M024AC4LG	440
1SVR405612R7000	CR-M110AC3	437	1SVR405618R1000	CR-M024DC4G	439
1SVR405612R7100	CR-M110AC3L	438	1SVR405618R1010	CR-M024DC4GLC62CV	420
1SVR405612R8000	CR-M110DC3	437	1SVR405618R1011	CR-M024DC4GSS42V	420
1SVR405612R8100	CR-M110DC3L	438	1SVR405618R1100	CR-M024DC4LG	440
1SVR405612R8200	CR-M125DC3	437	1SVR405618R1110	CR-M024DC4LGLC22	420
1SVR405612R8300	CR-M125DC3L	438	1SVR405618R1400	CR-M024DC4LDG	440
1SVR405612R8400	CR-M110DC3LD	439	1SVR405618R1410	CR-M024DC4LDGSS	420
1SVR405612R8500	CR-M125DC3LD	439	1SVR405618R2100	CR-M120AC4LG	440
1SVR405612R9000	CR-M220DC3	437	1SVR405618R3000	CR-M230AC4G	439
1SVR405612R9100	CR-M220DC3L	438	1SVR405618R3100	CR-M230AC4LG	440
1SVR405612R9400	CR-M220DC3LD	439	1SVR405618R3110	CR-M230AC4LGLC	421
1SVR405613R0000	CR-M024AC4	437	1SVR405618R3111	CR-M230AC4LGSS	421
1SVR405613R0010	CR-M024AC4LS62CV	420	1SVR405618R3112	CR-M230AC4GSS92CV	421
1SVR405613R0100	CR-M024AC4L	438	1SVR405618R4100	CR-M012DC4LG	440
1SVR405613R0300	CR-M012AC4L	438	1SVR405618R4300	CR-M060DC4LG	440
1SVR405613R1000	CR-M024DC4	437	1SVR405618R4400	CR-M012DC4LDG	440
1SVR405613R1010	CR-M024DC4SS42V	420	1SVR405618R4410	CR-M012DC4LDGSS	420
1SVR405613R1011	CR-M024DC4LS42V	420	1SVR405618R5100	CR-M048AC4LG	440
1SVR405613R1012	CR-M024DC4LC42	420	1SVR405618R6100	CR-M048DC4LG	440
1SVR405613R1100	CR-M024DC4L	438	1SVR405618R7000	CR-M110AC4G	439
1SVR405613R2000	CR-M120AC4	437	1SVR405618R7100	CR-M110AC4LG	440
1SVR405613R2100	CR-M120AC4L	438	1SVR405618R8100	CR-M110DC4LG	440
1SVR405613R3000	CR-M230AC4	437	1SVR405618R8300	CR-M125DC4LG	440
1SVR405613R3001	CR-M230AC4LS92CV	421	1SVR405618R9100	CR-M220DC4LG	440
15VR405613R3012	CR-M230AC4LC92	421	1SVR405621R0000	CR-U024AC2	446
15VR405613R3100	CR-M230AC4L	438	1SVR405621R0100	CR-U024AC2L	446
			1SVR405621R0300		446
1SVR405613R3110 1SVR405613R4000	CR-M230AC4SS92CV CR-M012DC4	421	1SVR405621R1000	CR-U012AC2L CR-U024DC2	446
					446
15VR405613R4100	CR-M012DC4L	438	1SVR405621R1100	CR-U024DC2L	
1SVR405613R4200	CR-M060DC4	437	1SVR405621R1400	CR-U024DC2LD	447
1SVR405613R4300	CR-M060DC4L	438	1SVR405621R2000	CR-U120AC2	446
1SVR405613R4400	CR-M012DC4LD	439	1SVR405621R2100	CR-U120AC2L	446
1SVR405613R5000	CR-M048AC4	437	1SVR405621R3000	CR-U230AC2	446
1SVR405613R5100	CR-M048AC4L	438	1SVR405621R3100	CR-U230AC2L	446

Order code	Туре	Page	Order code	Туре	Page
1SVR405621R4000	CR-U012DC2	446	1SVR405651R2000	CR-M3SS	420
1SVR405621R4100	CR-U012DC2L	446	1SVR405651R2100	CR-M3LS	420
1SVR405621R4400	CR-U012DC2LD	447	1SVR405651R3000	CR-M4SS	420
1SVR405621R5000	CR-U048AC2	446	1SVR405651R3100	CR-M4LS	420
1SVR405621R5100	CR-U048AC2L	446	1SVR405651R3200	CR-M4LC	420
1SVR405621R6000	CR-U048DC2	446	1SVR405651R3300	CR-M4SF	420
1SVR405621R6100	CR-U048DC2L	446	1SVR405651R4100	CR-M2LSH	420
1SVR405621R6400	CR-U048DC2LD	447	1SVR405651R5100	CR-M3LSH	420
1SVR405621R7000	CR-U110AC2	446	1SVR405652R0000	CR-P/M 42	421
1SVR405621R7100	CR-U110AC2L	446	1SVR405652R1000	CR-P/M 42 V	421
1SVR405621R8000	CR-U110DC2	446	1SVR405652R4000	CR-P/M 42 B	421
1SVR405621R8100	CR-U110DC2L	446	1SVR405652R4100	CR-P/M 42 BV	421
1SVR405621R8400	CR-U110DC2LD	447	1SVR405652R9000	CR-P/M 42 C	421
1SVR405621R9000	CR-U220DC2	446	1SVR405652R9100	CR-P/M 42 CV	421
1SVR405621R9100	CR-U220DC2L	446	1SVR405653R0000	CR-P/M 52B	421
1SVR405622R0000	CR-U024AC3	446	1SVR405653R1000	CR-P/M 52C	421
1SVR405622R0100	CR-U024AC3L	447	1SVR405653R4000	CR-P/M 52D	421
1SVR405622R0300	CR-U012AC3L	447	1SVR405654R0000	CR-P/M 62	421
1SVR405622R1000	CR-U024DC3	446	1SVR405654R0100	CR-P/M 92	421
1SVR405622R1100	CR-U024DC3L	447	1SVR405654R1000	CR-P/M 62 V	421
1SVR405622R2000	CR-U120AC3	446	1SVR405654R1100	CR-P/M 92 V	421
1SVR405622R2100	CR-U120AC3L	447	1SVR405654R4000	CR-P/M 62 E	421
1SVR405622R3000	CR-U230AC3	446	1SVR405654R4100	CR-P/M 62 EV	421
1SVR405622R3100	CR-U230AC3L	447	1SVR405655R0000	CR-P/M 62 C	422
1SVR405622R4000	CR-U012DC3	446	1SVR405655R0100	CR-P/M 92 C	422
1SVR405622R4100	CR-U012DC3L	447	1SVR405655R1000	CR-P/M 62 CV	422
1SVR405622R4400	CR-U012DC3LD	447	1SVR405655R1100	CR-P/M 92 CV	422
1SVR405622R5000	CR-U048AC3	446	1SVR405655R4000	CR-P/M 62 D	422
1SVR405622R5100	CR-U048AC3L	447	1SVR405655R4100	CR-P/M 62 DV	422
1SVR405622R5200	CR-U060AC3	446	1SVR405656R0000	CR-P/M 72	422
1SVR405622R6000	CR-U048DC3	446	1SVR405656R1000	CR-P/M 72 A	422
1SVR405622R6100	CR-U048DC3L	447	1SVR405656R2000	CR-P/M 82	422
1SVR405622R6400	CR-U048DC3LD	447	1SVR405658R0000	CR-PM	413
1SVR405622R7000	CR-U110AC3	446	1SVR405658R1000	CR-MM	420
1SVR405622R7100	CR-U110AC3L	447	1SVR405658R2000	CR-MP	420
1SVR405622R8000	CR-U110DC3	446	1SVR405658R5000	CR-PJ	413
1SVR405622R8100	CR-U110DC3L	447	1SVR405658R6000		420
1SVR405622R8200	CR-U125DC3	446	1SVR405659R0000	CR-MJ CR-PH	413
	CR-U110DC3LD		_		
1SVR405622R8400 1SVR405622R9000	CR-U220DC3	447	1SVR405659R0100 1SVR405659R1000	CR-PH1	413
				CR-MH	
1SVR405622R9100	CR-U220DC3L	447	1SVR405659R1100	CR-MH1	420
1SVR405623R1100	CR-U024DC3LD	447	1SVR405660R0000	CR-U3S	447
1SVR405650R0000	CR-PLS	413	1SVR405660R0100	CR-U3E	447
1SVR405650R0100	CR-PLSX	413	1SVR405660R1100	CR-U3SM	447
1SVR405650R0200	CR-PLC	413	1SVR405661R0000	CR-U 21	424
1SVR405650R1000	CR-PSS	413	1SVR405662R0000	CR-U 41	424
1SVR405651R0000	CR-P/M 22	421	1SVR405662R1000	CR-U 41V	424
1SVR405651R1000	CR-M2SS	420	1SVR405662R4000	CR-U 41B	424
1SVR405651R1100	CR-M2LS	420	1SVR405662R4100	CR-U 41BV	424
1SVR405651R1200	CR-M2LC	420	1SVR405662R9000	CR-U 41C	424
1SVR405651R1300	CR-M2SF	420	1SVR405662R9100	CR-U 41CV	424

Order code	Туре	Page
1SVR405663R0000	CR-U 51B	424
1SVR405663R1000	CR-U 51C	424
1SVR405663R4000	CR-U 51D	424
1SVR405664R0000	CR-U 61	424
1SVR405664R0100	CR-U 91	424
1SVR405664R1000	CR-U 61V	424
1SVR405664R1100	CR-U 91V	424
1SVR405664R4000	CR-U 61E	424
1SVR405664R4100	CR-U 61EV	424
1SVR405665R0000	CR-U 61C	424
1SVR405665R0100	CR-U 91C	424
1SVR405665R1000	CR-U 61CV	424
1SVR405665R1100	CR-U 91CV	424
1SVR405665R4000	CR-U 61D	424
1SVR405665R4100	CR-U 61DV	424
1SVR405666R0000	CR-U 71	424
1SVR405666R1000	CR-U 71A	424
1SVR405666R2000	CR-U 81	424
1SVR405667R0000	CR-U T	424
1SVR405669R0000	CR-UH	447
1SVR405670R0000	CR-U2S	447
1SVR405670R1100	CR-U2SM	447
1SVR406570R0000	RB-JB10	485
1SVR406580R0000	RB-JB20	485



**ABB STOTZ-KONTAKT GmbH** 

Eppelheimer Strasse 82 69123 Heidelberg Germany

You can find the address of your local sales organization on the ABB homepage



abb.com/lowvoltage

